



**भारत सरकार**  
**Government of India**

**विद्युत मंत्रालय**  
**Ministry of Power**

**केन्द्रीय विद्युत प्राधिकरण**  
**Central Electricity Authority**

# **जल विद्युत गृहों के निष्पादन का पुनर्विलोकन-2021-22**

## **REVIEW OF PERFORMANCE OF HYDRO POWER STATIONS 2021-22**

**नई दिल्ली**  
**NEW DELHI**  
**सितम्बर, 2023**  
**SEPTEMBER, 2023**

विद्युत अधिनियम, 2003 की धारा 73 (आई) व (जे) के तहत के0वि0प्रा0 के सांविधिक दायित्व का निर्वहन करते हुए प्रकाशित

(PUBLISHED IN FULFILMENT OF CEA'S STATUTORY OBLIGATION UNDER SECTION 73 (i) & (j) OF THE ELECTRICITY ACT, 2003)

## **FUNCTIONS AND DUTIES OF CEA AS PER SECTION-73 OF ELECTRICITY ACT-2003**

The Authority shall perform such functions and duties as the Central Government may prescribe or direct, and in particular to –

- a) Advise the Central Government on the matters relating to the national electricity policy, formulate short-term and perspective plans for development of the electricity system and coordinate the activities of the planning agencies for the optimal utilization of resources to sub serve the interests of the national economy and to provide reliable and affordable electricity to all consumers;
- b) Specify the technical standards for construction of electrical plants, electric lines and connectivity to the grid;
- c) Specify the safety requirements for construction, operation and maintenance of electrical plants and electric lines;
- d) Specify the Grid Standards for operation and maintenance of transmission lines;
- e) Specify the conditions for installation of meters for transmission and supply of electricity;
- f) Promote and assist in the timely completion of schemes and projects for improving and augmenting the electricity system;
- g) Promote measures for advancing the skills of persons engaged in electricity industry;
- h) Advise the Central Government on any matter on which its advice is sought or make recommendation to that Government on any matter if, in the opinion of the Authority, the recommendation would help in improving the generation, transmission, trading, distribution and utilization of electricity;
- i) Collect and record the data concerning the generation, transmission, trading, distribution and utilization of electricity and carry out studies relating to cost, efficiency, competitiveness and such like matters;
- j) Make public from time to time the information secured under this Act, and provide for the publication of reports and investigations;
- k) Promote research in matters affecting the generation, transmission, distribution and trading of electricity;
- l) Carry out, or cause to be carried out, any investigation for the purpose of generating or transmitting or distributing electricity;
- m) Advise any State Government, licensees or the generating companies on such matters which shall enable them to operate and maintain the electricity system under their ownership or control in an improved manner and where necessary, in coordination with any other Government, licensee or the generating company owning or having the control of another electricity system;
- n) Advise the Appropriate Government and the Appropriate Commission on all technical matters relating to generation, transmission and distribution of electricity; and
- o) Discharge such other functions as may be provided under this Act.



**भारत सरकार**  
**Government of India**  
**विद्युत मंत्रालय**  
**Ministry of Power**  
**केन्द्रीय विद्युत प्राधिकरण**  
**Central Electricity Authority**

**जल विद्युत गृहों के निष्पादन का**  
**पुनर्विलोकन 2021-22**

**REVIEW OF PERFORMANCE OF**  
**HYDRO POWER STATIONS 2021-22**

**जल परियोजना आयोजन तथा अन्वेषण प्रभाग**  
**HYDRO PROJECT PLANNING & INVESTIGATION DIVISION**

**नई दिल्ली**  
**NEW DELHI**  
**सितम्बर, 2023**  
**September, 2023**

(विद्युत अधिनियम, 2003 की धारा 73 (आई) व (जे) के तहत के0वि0प्रा0 के सांविधिक दायित्व का निर्वहन करते हुए प्रकाशित)

(PUBLISHED IN FULFILMENT OF CEA'S STATUTORY OBLIGATION UNDER SECTION 73(i) & (j) OF THE ELECTRICITY ACT, 2003)

## CONTENTS

| <b>Sl. No.</b> | <b>Chapter No.</b>                | <b>Particulars</b>                                          | <b>Page No.</b> |
|----------------|-----------------------------------|-------------------------------------------------------------|-----------------|
| 1              |                                   | Summary                                                     | 1               |
| 2              | Chapter 1<br>Exhibits<br>Annexure | Hydro Electric Potential and Development                    | 13              |
| 3              | Chapter 2<br>Exhibits<br>Annexure | Generation Performance                                      | 43              |
| 4              | Chapter 3<br>Exhibits<br>Annexure | Major Reservoir Based HE Stations                           | 62              |
| 5              | Chapter 4<br>Exhibits<br>Annexure | Planned Maintenance of HE Units                             | 83              |
| 6              | Chapter 5<br>Exhibits<br>Annexure | Forced Outage of HE Units                                   | 103             |
| 7              | Chapter 6<br>Exhibits<br>Annexure | Operating Availability of HE Units                          | 121             |
| 8              | Chapter 7<br>Annexure             | Miscellaneous Outage of HE Units                            | 194             |
| 9              | Chapter 8<br>Annexure             | Generation Programme for the year 2021-22                   | 245             |
| 10             | Chapter 9<br>Annexure             | Renovation & Modernization of Hydro Electric Power Projects | 250             |
| 11             | Chapter 10                        | Definitions and Abbreviations                               | 272             |

## LIST OF EXHIBITS

| <b>Exhibit No.</b> | <b>Description</b>                                                                       | <b>Page No.</b> |
|--------------------|------------------------------------------------------------------------------------------|-----------------|
| 1.1                | Region-wise Hydro Electric Capacity as on 31.03.2022                                     | 15              |
| 1.2                | Basin-wise Hydro Potential Development as on 31.03.2022                                  | 16              |
| 1.3                | Growth of Installed Capacity since 1947                                                  | 19              |
| 1.4                | Growth of Hydro Generation vis-a-vis other Sources since 1947                            | 20              |
| 1.5                | Trend of Hydro Capacity and Generation since 1947                                        | 21              |
| 1.6                | Contribution of Hydro Capacity as on 31.03.2022                                          | 24              |
| 1.7                | Contribution of Hydro Generation as on 31.03.2022                                        | 24              |
| 1.8                | Sector-wise Hydro Capacity as on 31.03.2022                                              | 24              |
| 1.9                | Sector-wise Hydro Generation during 2021-22                                              | 24              |
| 2.1                | Monthly All India Hydro Generation vs. Targets during 2021-22                            | 44              |
| 2.2                | Region-wise Actual Generation vs. Targets during 2021-22                                 | 49              |
| 2.3                | Utility-wise Excess/ Shortfall in Generation during 2021-22                              | 53              |
| 3.1                | Inflows into Major Reservoirs during 2021-22 vis-à-vis 2020-21                           | 65              |
| 3.2 to 3.11        | Month-wise Maximum Levels of Important Reservoirs                                        | 66              |
| 3.12               | Generation from Reservoirs Based Hydroelectric Stations during 2021-22 vis-à-vis 2020-21 | 80              |
| 4.1                | Duration Pattern of Planned Maintenance during 2021-22                                   | 92              |
| 5.1                | Duration Pattern of Forced Outages during 2021-22                                        | 113             |
| 6.1                | Operating Availability of H.E. Stations during 2021-22                                   | 126             |

## LIST OF ANNEXURES

| <b>Annex No.</b> | <b>Description</b>                                                                                              | <b>Page No.</b> |
|------------------|-----------------------------------------------------------------------------------------------------------------|-----------------|
| 1.1              | Region-wise Installed Capacity of HE Stations (above 25 MW Capacity) as on 31.03.2022                           | 25              |
| 1.2              | Categorization of H.E. Stations (Installed Capacity) as on 31.03.2022                                           | 26              |
| 1.3              | Sector-wise/Utilities-wise Installed Capacity of HE Station (above 25 MW Capacity) as on 31.03.2022             | 27              |
| 1.4              | Station-wise Installed Capacity and Design Energy of HE Stations (above 25 MW Capacity) as on 31.03.2022        | 29              |
| 1.5              | Capacity-wise Grouping of Hydroelectric Stations as on 31.03.2022                                               | 41              |
| 1.6              | Hydro Generating units added during 2021-22                                                                     | 42              |
| 2.1              | Generation Performance of HE Stations during 2021-22                                                            | 54              |
| 3.1              | Salient Data of Important reservoirs and Associated H.E. Stations                                               | 81              |
| 4.1              | Details of long duration Planned Maintenance in Hydro-Electric units with Outage duration of 50 hours and above | 93              |
| 5.1              | Details of long duration Forced Outages in Hydro-Electric units with Outage duration of 24 hours and above      | 114             |
| 6.1              | Operating Availability of Hydro-electric units during 2021-22                                                   | 140             |
| 7.1              | Miscellaneous Outages of Hydro-Electric units during 2021-22                                                    | 195             |
| 8.1              | Hydro-Electric Generating units likely to be added during 2021-22                                               | 246             |
| 8.2              | Sector-wise Performance of Hydro-Electric Stations during 2020-21 & Targets for 2021-22                         | 248             |
| 9.1              | State-wise List of Hydro RM&U Schemes completed up to VIII th Plan to XII th Plan                               | 255             |
| 9.2              | State-wise List of Hydro RMU&LE schemes completed in the IX Plan                                                | 256             |
| 9.3              | State-wise List of Hydro RMU&LE schemes completed in the X Plan                                                 | 258             |
| 9.4              | State-wise List of Hydro RMU&LE schemes completed in the XI Plan                                                | 261             |
| 9.5              | State-wise List of Hydro RMU&LE schemes completed in the XII Plan                                               | 263             |
| 9.6              | State-wise List of Hydro RMU&LE schemes programmed for completion during 2017-22                                | 265             |
| 9.7              | State-wise List of Hydro RMU&LE schemes programmed for completion during 2022-27                                | 267             |

# SUMMARY

## SUMMARY

### 1.0 General

**1.1** This review covers the performance of Hydro-Electric (HE) Stations having installed capacity of more than 25 MW. As on 31<sup>st</sup> March, 2022 there were 727 HE generating units installed in 210 Hydro-Electric Stations with an aggregate installed capacity of 46722.50 MW in operation. Performance of 44 important Reservoir based schemes has also been discussed separately in the report.

**1.2** Region-wise summary of the existing HE Stations in operation with installed capacity above 25 MW as on 31.3.2022 in the country vis-à-vis that on 31.3.2021 is given below in **Table S-1**.

**TABLE S-1**

**REGION-WISE SUMMARY OF HYDRO-ELECTRIC STATIONS  
(2021-22 VIS-A-VIS 2020-21)**

| Region           | No of Stations as on |            | No of Units as on |            | Capacity (MW) as on |                 |
|------------------|----------------------|------------|-------------------|------------|---------------------|-----------------|
|                  | 31.03.22             | 31.03.21   | 31.03.22          | 31.03.21   | 31.03.22            | 31.03.21        |
| Northern         | 75                   | 73         | 256               | 251        | 19576.25            | 19233.27        |
| Western          | 28                   | 28         | 101               | 101        | 7392                | 7392            |
| Southern         | 70                   | 70         | 246               | 247        | 11739.5             | 11694.5         |
| Eastern          | 23                   | 24         | 86                | 85         | 5987.75             | 5862.45         |
| N-Eastern        | 14                   | 14         | 38                | 36         | 2027.0              | 2027            |
| <b>All India</b> | <b>210</b>           | <b>209</b> | <b>727</b>        | <b>720</b> | <b>46722.50</b>     | <b>46209.22</b> |

**1.3** The report contains outage data of 210 H.E. Stations (above 25 MW) covering 727 units and having an aggregate installed capacity of 46722.50 MW which was made available by various utilities for the purpose of this Review.

**1.4** The performance review also analyses year-wise generation, planned maintenance, forced outages and operating availability for the last 10 years (viz 2011-12 to 2021-22).

**1.5** This review covers information in respect of renovation & modernization, uprating and life extension of HE stations in the country for the year 2021-22, achievements during the year 2021-22 and programme for renovation, modernization, life extension and uprating of HE Stations for the year 2021-22.

## 1.6 The report comprises of ten chapters as under:

| Chapter No. | Particulars                                                 |
|-------------|-------------------------------------------------------------|
| 1           | Hydro-Electric Potential and Development                    |
| 2           | Generation Performance                                      |
| 3           | Major Reservoir Based H.E. Schemes                          |
| 4           | Planned Maintenance of H.E. Units                           |
| 5           | Forced Outage of H.E. Units                                 |
| 6           | Operating Availability of H.E. Units                        |
| 7           | Miscellaneous Outages of H.E. Units                         |
| 8           | Generation Programme for the year 2019-20                   |
| 9           | Renovation & Modernisation of Hydro-Electric Power Projects |
| 10          | Definitions and Abbreviations                               |

## 2.0 Generation Performance

The generation from the hydro electric power stations in the country during 2021-22 was 151627.33 MU (excluding import from Bhutan), which was about 0.86 % higher than the generation during 2020-21 and about 1.39% higher than the generation targets for 2021-22.

### 2.1 Utility-wise/ Sector-wise Performance of H.E. Stations

The utility-wise/ sector-wise target of energy generation vis-à-vis actual generation and surplus /shortfall in respect of Hydro Electric stations are given below in **Table S-2**.

**TABLE S-2**  
**UTILITY-WISE PERFORMANCE OF HYDRO ELECTRIC STATIONS**  
**(2021-22 VIS-A-VIS 2020-21)**

| Utilities      | Installed Capacity (MW)<br>(As on 31.03.2022) | Energy Generation |         |             |          |                                 |         |
|----------------|-----------------------------------------------|-------------------|---------|-------------|----------|---------------------------------|---------|
|                |                                               | Target (MU)       |         | Actual (MU) |          | Surplus (+)/ Shortfall (-) in % |         |
|                |                                               | 2021-22           | 2020-21 | 2021-22     | 2020-21  | 2021-22                         | 2020-21 |
| CENTRAL SECTOR |                                               |                   |         |             |          |                                 |         |
| BBMB           | 2938.3                                        | 9650              | 9600    | 9794.82     | 11478    | 1.50                            | 19.56   |
| NHPC LTD       | 5451.2                                        | 26000             | 24542   | 24382.6     | 24084.69 | -6.22                           | -1.86   |
| SJVNLTD        | 1912.02                                       | 9111              | 8678    | 9048.61     | 9094.35  | -0.68                           | 4.80    |
| NTPC LTD       | 800                                           | 3100              | 3482    | 3120.14     | 3221.41  | 0.65                            | -7.48   |
| THDC LTD       | 1400                                          | 4160              | 4160    | 4288.75     | 4261.72  | 3.09                            | 2.45    |
| NHDC LTD       | 1520                                          | 3900              | 2700    | 2645.41     | 4236.17  | -32.17                          | 56.90   |
| DVC            | 143.2                                         | 215               | 206     | 466.89      | 365.47   | 117.16                          | 77.41   |
| NEEPCO LTD     | 1500                                          | 4908              | 4472    | 4674.39     | 3881.89  | -4.76                           | -13.20  |
| SUB TOTAL      | 15664.72                                      | 61044             | 57840   | 58421.61    | 60623.7  | -4.30                           | 4.81    |

| Utilities      | Installed Capacity (MW)<br>(As on 31.03.2022) | Energy Generation |         |             |          |                                    |         |
|----------------|-----------------------------------------------|-------------------|---------|-------------|----------|------------------------------------|---------|
|                |                                               | Target (MU)       |         | Actual (MU) |          | Surplus (+)/<br>Shortfall (-) in % |         |
|                |                                               | 2021-22           | 2020-21 | 2021-22     | 2020-21  | 2021-22                            | 2020-21 |
| PRIVATE SECTOR |                                               |                   |         |             |          |                                    |         |
| MPCL           | 86.00                                         | 344               | 157     | 314.96      | 334.88   | -8.44                              | 113.30  |
| EPPL           | 100.00                                        | 367               | 367     | 345.66      | 370.47   | -5.81                              | 0.95    |
| ADHPL          | 192.00                                        | 676               | 692     | 637.44      | 640.53   | -5.70                              | -7.44   |
| GBHPPL         | 70.00                                         | 270               | 260     | 251.37      | 275.95   | -6.90                              | 6.13    |
| JSW ENERGY     | 1345.00                                       | 5431              | 5407    | 5563.8      | 5672.61  | 2.45                               | 4.91    |
| IAEPL          | 36.00                                         | 158               | 273     | 146.54      | 159.35   | -7.25                              | -41.63  |
| AHPC LTD       | 330.00                                        | 1310              | 1310    | 1421.89     | 1438     | 8.54                               | 9.77    |
| JPVL           | 400.00                                        | 1590              | 1438    | 1801.24     | 1778.42  | 13.29                              | 23.67   |
| DLHP           | 34.00                                         | 36                | 36      | 33.94       | 34.29    | -5.72                              | -4.75   |
| GIPL           | 110.00                                        | 500               | 500     | 514.21      | 488.37   | 2.84                               | -2.33   |
| TPCL           | 447.00                                        | 1470              | 1470    | 1589.99     | 1524.7   | 8.16                               | 3.72    |
| DEPL           | 96.00                                         | 408               | 408     | 424.69      | 399.92   | 4.09                               | -1.98   |
| SEPL           | 97.00                                         | 421               | 421     | 453.07      | 369.75   | 7.62                               | -12.17  |
| SNEHA KINETIC  | 96.00                                         | 460               | 460     | 481.45      | 458.95   | 4.66                               | -0.23   |
| NTPGPL         | 0.00                                          | 0                 | 344     | 0           | 0        | 0                                  | 0       |
| HSPPL          | 100.00                                        | 39                | 0       | 57.18       | 0        | 46.62                              | 0       |
| L&T            | 99.00                                         | 293               | 145     | 80.44       | 0        | -72.55                             | -100.00 |
| GMR            | 180                                           | 273               | 39      | 0           | 0        | -100.00                            | -100.00 |
| MBPC           | 113.00                                        | 256               | 22      | 295.43      | 0        | 15.40                              | -100.00 |
| SUB TOTAL      | 3931.00                                       | 14302             | 13749   | 14413.3     | 13946.19 | 0.78                               | 1.43    |
| STATE SECTOR   |                                               |                   |         |             |          |                                    |         |
| JKSPDCL        | 1110                                          | 4887              | 4915    | 5116.09     | 4940.83  | 4.69                               | 0.53    |
| HPPCL          | 406                                           | 821               | 805     | 649.55      | 437.76   | -20.88                             | -45.62  |
| HPSEBL         | 372                                           | 1603              | 1602    | 1768.66     | 1564.35  | 10.33                              | -2.35   |
| BVPC           | 0                                             | 0                 | 272     | 0           | 0        |                                    | -100.00 |
| RRVUNL         | 411                                           | 370               | 340     | 481.84      | 469.63   | 30.23                              | 38.13   |
| PSPCL          | 1051                                          | 3969              | 3805    | 3007.86     | 3951     | -24.22                             | 3.84    |
| UPJVNL         | 501.6                                         | 1519              | 1115    | 1402.68     | 1572.35  | -7.66                              | 41.02   |
| UJVNL          | 1252.15                                       | 4612              | 4410    | 4987.18     | 4487.97  | 8.13                               | 1.77    |
| SSNNL          | 1450                                          | 2832              | 3200    | 1748.01     | 3245.24  | -38.28                             | 1.41    |
| GSECL          | 540                                           | 889               | 754     | 873.5       | 988.12   | -1.74                              | 31.05   |
| MAHAGENCO      | 2406                                          | 4109              | 3755    | 4078.97     | 3574.57  | -0.73                              | -4.81   |
| MPPGCL         | 875                                           | 2526              | 2092    | 2345.79     | 2656.06  | -7.13                              | 26.96   |
| CSPGCL         | 120                                           | 280               | 250     | 404.13      | 419.19   | 44.33                              | 67.68   |

| Utilities              | Installed Capacity (MW)<br>(As on 31.03.2022) | Energy Generation |               |                  |                 |                                    |              |
|------------------------|-----------------------------------------------|-------------------|---------------|------------------|-----------------|------------------------------------|--------------|
|                        |                                               | Target (MU)       |               | Actual (MU)      |                 | Surplus (+)/<br>Shortfall (-) in % |              |
|                        |                                               | 2021-22           | 2020-21       | 2021-22          | 2020-21         | 2021-22                            | 2020-21      |
| APGENCO                | 1796.75                                       | 3636              | 3174          | 4037.32          | 4129.94         | 11.04                              | 30.12        |
| TSGENCO                | 2405.6                                        | 4018              | 3211          | 5626.63          | 3645.38         | 40.04                              | 13.53        |
| KPCL                   | 3617.2                                        | 12409             | 11468         | 13731.48         | 12403.59        | 10.66                              | 8.16         |
| KSEBL                  | 1856.5                                        | 6505              | 5900          | 9317.44          | 6628.39         | 43.24                              | 12.35        |
| TANGEDCO               | 2178.2                                        | 4483              | 4040          | 5212.07          | 5212.71         | 16.26                              | 29.03        |
| JUUNL                  | 130                                           | 110               | 110           | 302.49           | 50              | 174.99                             | -54.55       |
| OHPC                   | 2039.80                                       | 5959              | 5372          | 4512.12          | 6193.91         | -24.28                             | 15.30        |
| TUL                    | 1200                                          | 5652              | 5300          | 6315.53          | 6043.98         | 11.74                              | 14.04        |
| WBSEDCL                | 986                                           | 1578              | 1578          | 1630.14          | 1759.64         | 3.30                               | 11.51        |
| APGCL                  | 100                                           | 380               | 380           | 401.12           | 203.03          | 5.56                               | -46.57       |
| MePGCL                 | 322                                           | 1051              | 920           | 841.82           | 1151.99         | -19.90                             | 25.22        |
| <b>SUB TOTAL</b>       | <b>27126.80</b>                               | <b>74198</b>      | <b>68768</b>  | <b>78792.42</b>  | <b>75729.63</b> | <b>6.19</b>                        | <b>10.12</b> |
| <b>TOTAL ALL INDIA</b> | <b>46722.52</b>                               | <b>149544</b>     | <b>140357</b> | <b>151627.33</b> | <b>150299.5</b> | <b>1.39</b>                        | <b>7.08</b>  |

During the year 2021-22, overall hydro generation was more than the target in respect of BBMB, SJVNL, DVC, THDC, & NHDC LTD in Central Sector and MPCL, EPPL, GBHPPL, JSW ENERGY, IAEPL, AHPCL, JPVL, TPCL in Private Sector. As regards generation by State Electricity Boards/Corporations / Departments, hydro generation was more than the target in respect of JKSPDCL, RRVUNL, PSPCL, UPJVNL, UJVNL, SSNNL, MPPGCL, GSECL, CSPGCL, APGENCO, TSGENCO, KPCL, TANGEDCO, OHPC, TUL, WBSEDCL and MePGCL.

## 2.2 Sector-wise and Region Wise Performance of H.E. Stations

Sector-wise and Region-wise generation performance of H.E. Stations during 2021-22 is given in **Table S-3 & S-4**. It is seen that there was excess generation as compared to target in State Sector & Private Sector. The overall generation of Central Sector hydro stations remained below the targets.

**TABLE S-3**

**SECTOR-WISE PERFORMANCE OF HYDRO ELECTRIC STATIONS  
(2021-22 VIS-A-VIS 2020-21)**

| Sector       | Installed Capacity (MW)<br>(As on 31.03.2022) | Energy Generation (MU) |                  |                  |                  |                             |             |
|--------------|-----------------------------------------------|------------------------|------------------|------------------|------------------|-----------------------------|-------------|
|              |                                               | Target                 |                  | Actual           |                  | Surplus (+)/ Deficit(-)in % |             |
|              |                                               | 2021-22                | 2020-21          | 2021-22          | 2020-21          | 2021-22                     | 2020-21     |
| Central      | 15664.72                                      | 61044.00               | 57840.00         | 58421.61         | 60623.70         | -4.30                       | 4.81        |
| State        | 27126.80                                      | 74198.00               | 68768.00         | 78792.42         | 75729.63         | 6.19                        | 10.12       |
| Private      | 3931                                          | 14302                  | 13749.00         | 14413.3          | 13946.19         | 0.78                        | 1.43        |
| <b>Total</b> | <b>46722.52</b>                               | <b>149544</b>          | <b>140357.00</b> | <b>151627.33</b> | <b>150299.52</b> | <b>1.39</b>                 | <b>7.08</b> |

**TABLE S-4**

**REGION-WISE PERFORMANCE OF HYDRO ELECTRIC STATIONS  
(2021-22 VIS-A-VIS 2020-21)**

| Sector        | Installed Capacity (MW)<br>(As on 31.03.2022) | Energy Generation (MU) |               |                  |                  |                             |             |
|---------------|-----------------------------------------------|------------------------|---------------|------------------|------------------|-----------------------------|-------------|
|               |                                               | Target                 |               | Actual           |                  | Surplus (+)/ Deficit(-)in % |             |
|               |                                               | 2021-22                | 2020-21       | 2021-22          | 2020-21          | 2021-22                     | 2020-21     |
| Northern      | 19576.25                                      | 75684                  | 73243         | 73866.02         | 75233.86         | -2.40                       | 2.72        |
| Western       | 7392                                          | 16042                  | 14257         | 13719.74         | 16678.34         | -14.48                      | 16.98       |
| Southern      | 11739.5                                       | 30439                  | 27293         | 37206.43         | 31353.95         | 22.23                       | 14.88       |
| Eastern       | 5987.75                                       | 20540                  | 19192         | 20462.33         | 21174.84         | -0.38                       | 10.33       |
| North Eastern | 2027.0                                        | 6839                   | 6372          | 6372.81          | 5858.53          | -6.82                       | -8.06       |
| <b>Total</b>  | <b>46722.50</b>                               | <b>149544.00</b>       | <b>140357</b> | <b>151627.33</b> | <b>150299.52</b> | <b>1.39</b>                 | <b>7.08</b> |

### 3.0 Outage Analysis

For outage data analysis during 2021-22, outage data of 210 H.E. Stations (above 25 MW capacity) covering 727 units and having an aggregate installed capacity of 46722.50 MW made available by various utilities have been considered for the purpose of this Review. Region-wise details of these 210 hydro power stations are given below in **Table S-5**.

TABLE S-5

**REGION-WISE SUMMARY OF HE STATIONS ANALYSED  
(2021-22 VIS-A-VIS 2020-21)**

| Region           | No. of Stations |            | No. of Units |            | Capacity(MW) as on |                 |
|------------------|-----------------|------------|--------------|------------|--------------------|-----------------|
|                  | 2021-22         | 2020-21    | 2021-22      | 2020-21    | 2021-22            | 2020-21         |
| Northern         | 75              | 73         | 256          | 251        | 19576.25           | 19233.27        |
| Western          | 28              | 28         | 101          | 101        | 7392               | 7392            |
| Southern         | 70              | 70         | 246          | 247        | 11739.5            | 11694.5         |
| Eastern          | 23              | 24         | 86           | 85         | 5987.75            | 5862.45         |
| North Eastern    | 14              | 14         | 38           | 36         | 2027.0             | 2027            |
| <b>All India</b> | <b>210</b>      | <b>209</b> | <b>727</b>   | <b>720</b> | <b>46722.50</b>    | <b>46209.22</b> |

### 3.1 Planned Maintenance

The number of H.E. Stations falling under various ranges of non-availability due to planned maintenance during the year 2021-22 vis-à-vis 2020-21 is summarized below in Table S-6.

TABLE S-6

**NON-AVAILABILITY OF HE STATIONS DUE TO PLANNED OUTAGES  
(2021-22 VIS-A-VIS 2020-21)**

| % Non-Availability due to planned maintenance | 2021-22    |            |                 |            | 2020-21    |            |                 |            |
|-----------------------------------------------|------------|------------|-----------------|------------|------------|------------|-----------------|------------|
|                                               | Stations   |            | Capacity        |            | Stations   |            | Capacity        |            |
|                                               | No.        | % of Total | MW              | % of Total | No.        | % of Total | MW              | % of Total |
| ≤ 5                                           | 165        | 78.57      | 37515.57        | 80.29      | 158        | 76.33      | 34696.37        | 75.09      |
| >5 to 10                                      | 23         | 10.95      | 3814.95         | 8.17       | 27         | 12.08      | 6465.20         | 13.99      |
| >10 to 15                                     | 12         | 5.71       | 3594.20         | 7.69       | 9          | 4.35       | 1530.15         | 3.31       |
| >15 to 20                                     | 4          | 1.90       | 1087.80         | 2.33       | 4          | 1.93       | 1550.00         | 3.35       |
| >20 to 25                                     | 1          | 0.48       | 30.00           | 0.06       | 1          | 0.48       | 304.00          | 0.66       |
| >25 to 30                                     | 1          | 0.48       | 50.00           | 0.11       | 5          | 2.42       | 938.50          | 2.03       |
| above 30                                      | 4          | 1.90       | 630.00          | 1.35       | 5          | 2.42       | 725.00          | 1.57       |
| <b>Total</b>                                  | <b>210</b> | <b>100</b> | <b>46722.52</b> | <b>100</b> | <b>209</b> | <b>100</b> | <b>46209.22</b> | <b>100</b> |

It could be seen from above that 165 nos. (78.57% of total) hydro-electric stations had non-availability factor less than or equal to 5% due to planned maintenance during 2021-22 as compared to 158 nos. (76.33% of total) during 2020-21.

Non-availability due to planned maintenance was more than 30% at 4 nos. (1.90% of total) H.E. Stations during 2021-22 and which is similar to 2019-20. The details of these stations for 2021-22 is given below in **Table S-7**.

**TABLE S-7**  
**H.E. STATIONS HAVING HIGH PLANNED MAINTENANCE**  
**FOR THE PERIOD: (2021-22)**

| Sl. No | Name of Station/<br>Utility          | Capacity<br>(MW) | N.A. due to<br>P.M.*(%) | Remarks                |
|--------|--------------------------------------|------------------|-------------------------|------------------------|
| 1      | BANSAGAR<br>TONS-I HPS /<br>MPPGCL   | 315.0            | 33.333                  | CAPITAL/3 YEARLY MTCE. |
| 2      | NARIAMANGLAM<br>HPS / KSEB           | 52.6500          | 33.333                  | ANNUAL MAINTENANCE     |
| 3      | PYKARA<br>ULTIMATE HPS /<br>TANGEDCO | 150.0            | 33.333                  | ANNUAL MAINTENANCE     |
| 4      | SEWA-II HPS /<br>NHPC                | 120.0            | 89.492                  | SURGE SHAFT            |

\* N.A. -Non-Availability, P.M. - Planned Maintenance

43% of stations had operational availability lower than 95% on account of planned maintenance. These utilities, therefore, need to improve their O&M practices to bring down their total outages.

It is observed from above that stations may be having high planned maintenance outages on account of ageing, O&M management issues, etc. Further, those stations which are having continuously high planned maintenance/forced outages over past few years may be requiring major repair & maintenance works or Renovation & Modernisation (R&M) works for improving the availability, reliability & security of the plant besides providing life extension where the assets have outlived their useful life.

The duration of various types of periodic planned maintenance varied considerably from station to station. Details of average time taken for various types of maintenance are given in **Table S-8**.

**TABLE S-8**

**AVERAGE DURATION OF VARIOUS TYPES OF PLANNED  
MAINTENANCE FOR THE PERIOD: (2021-22)**

| <b>Sl. No</b> | <b>Type of Planned maintenance</b> | <b>Average duration at any unit (hrs.)</b> |
|---------------|------------------------------------|--------------------------------------------|
| 1             | ANNUAL MAINTENANCE                 | 649.76                                     |
| 2             | AUXILIARY SYSTEM                   | 4.53                                       |
| 3             | CAPITAL/3 YEARLY MTCE.             | 795.93                                     |
| 4             | GENERATOR                          | 89.13                                      |
| 5             | INSPECTION /MTCE                   | 16.96                                      |
| 6             | MONTHLY MAINTENANCE                | 37.18                                      |
| 7             | OTHER EQUIPMENT                    | 146.46                                     |
| 8             | RENOVATION/MODERNISATION           | 2821.34                                    |
| 9             | ROUTINE MAINTENANCE                | 3.5                                        |
| 10            | TURBINE                            | 15.41                                      |
| 11            | MISCELLANEOUS                      | 732.21                                     |

It has been observed that there were wide variations in the time taken at different hydro units for the same type of periodic maintenance. The reasons for this can be attributed to following factors.

- The nature and the extent of work involved may vary from unit to unit.
- Availability of spare parts could be a constraint at some units.
- The working of the agency entrusted with the maintenance work could be different.
- Administrative and procedural difficulties may be faced at some of the stations.

However, the analysis of outage data indicates there is enough scope of considerable reduction in outage duration of units by adopting best management practices including planning and contract management.

Summary of planned maintenance carried out on various equipments like generators, turbine and other equipments during 2021-22 vis-à-vis 2020-21 is given below in **Table S-9**.

**TABLE S-9**

**DURATION OF PLANNED MAINTENANCE FOR GENERATOR,  
TURBINE & OTHER EQUIPMENTS  
(2021-22 vis-à-vis 2020-21)**

| S.No. | Equipments      | Duration                   |         |               |         |
|-------|-----------------|----------------------------|---------|---------------|---------|
|       |                 | Maximum Hours for any unit |         | Average Hours |         |
|       |                 | 2021-22                    | 2020-21 | 2021-22       | 2020-21 |
| 1     | Generator       | 751.27                     | 5271.93 | 89.13         | 819.55  |
| 2     | Turbine         | 75.82                      | 4313.53 | 15.41         | 426.28  |
| 3     | Other Equipment | 684.42                     | 2167.62 | 146.46        | 552.64  |
| 4     | Civil Structure | 9.70                       | 0       | 9.70          | 0       |

It could be seen that the average hours utilized for carrying out various repairs decreased for generator and turbine during 2021-22 as compared to 2020-21.

### 3.2 Forced Outages

The summary of forced outages caused due to break-down of generator, turbine and other equipment during 2021-22 vis-à-vis 2020-21 is given below in **Table S-10**.

**TABLE S-10**

**FORCED OUTAGES DUE TO GENERATOR, TURBINE & OTHER  
EQUIPMENT FAULTS  
(2021-22 vis-à-vis 2020-21)**

| Sl. No. | Equipment       | Forced Outage (Hours) |                  | % of total Forced Outage |                                      |
|---------|-----------------|-----------------------|------------------|--------------------------|--------------------------------------|
|         |                 | 2021-22               | 2020-21          | 2021-22                  | Increase/ Decrease vis-à-vis 2020-21 |
| 1       | Generator       | 44588.94              | 29383.71         | 28.58                    | -51.75                               |
| 2       | Turbine         | 64968.00              | 77437.71         | 41.64                    | 16.10                                |
| 3       | Civil Structure | 42932.26              | 45016.77         | 27.51                    | 4.63                                 |
| 4       | Other Equipment | 3551.99               | 21805.83         | 2.28                     | 83.71                                |
|         | <b>Total</b>    | <b>156041.19</b>      | <b>173644.02</b> | <b>100.00</b>            | <b>10.14</b>                         |

It is observed that forced outages in 2021-22 vis-à-vis 2020-21 have decreased on account of turbine and other equipment whereas the same have decreased on account of generator and civil structures.

### 3.3 Operating Availability

The number of H.E. Stations falling under various ranges of operating availability during the year 2021-22 is summarized below in **Table S-11**.

**TABLE S-11**  
**OPERATING AVAILABILITY OF H.E. STATIONS**  
**PERIOD: 2021-22**

| <b>OPERATING AVAILABILITY (%)</b> | <b>NO. OF STATIONS</b> | <b>% OF TOTAL STATIONS</b> | <b>INSTALLED CAPACITY (MW)</b> | <b>% OF TOTAL INSTALLED CAPACITY</b> |
|-----------------------------------|------------------------|----------------------------|--------------------------------|--------------------------------------|
| ≥95%                              | 149                    | 70.95                      | 33943.37                       | 72.65                                |
| >90 to 95                         | 23                     | 10.95                      | 5044.20                        | 10.80                                |
| >85 to 90                         | 15                     | 7.14                       | 3595.95                        | 7.70                                 |
| >80 to 85                         | 6                      | 2.86                       | 1305.00                        | 2.79                                 |
| < 80                              | 17                     | 8.10                       | 2834.00                        | 6.07                                 |
| <b>Total</b>                      | <b>210</b>             | <b>100.00</b>              | <b>46722.52</b>                | <b>100.00</b>                        |

Operating availability of 23 nos. HE stations (10.96% of total HE Stations) was below 85% (4139 MW) due to planned maintenance (capital overhauling, R&MU works, annual maintenance etc.) carried out for long duration and forced outages (turbine vibration, repair of runner/underwater parts, fire at cable gallery etc.) in these HE Stations.

Region-wise planned maintenance, forced outages and operating availability of H.E. units for 2021-22 is indicated below in **Table S-12**.

**TABLE S-12**  
**AVAILABILITY OF UNITS - REGION-WISE**  
**PERIOD: 2021-22**

| SL. No. | REGION           | NO.OF UNITS | INSTALLED CAPACITY (MW) | PLANNED MAINTENANCE (%) | FORCED OUTAGE (%) | OPERATING AVAILABILITY |
|---------|------------------|-------------|-------------------------|-------------------------|-------------------|------------------------|
| 1       | Northern         | 256         | 19576.25                | 4.24                    | 1.83              | 93.92                  |
| 2       | Western          | 101         | 7392                    | 2.59                    | 3.93              | 93.47                  |
| 3       | Southern         | 246         | 11739.5                 | 3.04                    | 2.31              | 94.64                  |
| 4       | Eastern          | 86          | 5987.75                 | 4.16                    | 0.40              | 95.43                  |
| 5       | North Eastern    | 38          | 2027.0                  | 1.46                    | 16.27             | 82.28                  |
|         | <b>All India</b> | <b>727</b>  | <b>46722.50</b>         | <b>3.45</b>             | <b>2.88</b>       | <b>93.67</b>           |

On analyzing various types of planned shutdowns, it may be concluded that:

Generating units installed in Northern Region accounted for maximum non-availability due to planned maintenance (4.24%) whereas generating units installed in North Eastern Region accounted for the least non-availability due to planned maintenance (1.46%) as indicated in **Table S-12** above.

### **3.4 General Overview**

General overview indicating generation, planned maintenance (PM), forced outage (FO) and operating availability (OP.AV.) of H.E. Stations during the past 10 years is given below:

## OVERVIEW

| YEAR    | INSTALLED<br>CAPACITY | GENERATION     |                |                       | UNITS ANALYSED |             | PM   | FO   | OP.AV |
|---------|-----------------------|----------------|----------------|-----------------------|----------------|-------------|------|------|-------|
|         | (MW)                  | TARGET<br>(MU) | ACTUAL<br>(MU) | VARIA-<br>TION<br>(%) | Nos.           | CAP<br>(MW) | %    | %    | %     |
| 2021-22 | 46722.50              | 149544         | 151627.33      | 1.39                  | 727            | 46722.50    | 3.45 | 2.88 | 93.67 |
| 2020-21 | 46209.22              | 140357         | 150299.52      | (+)7.08               | 720            | 46209.22    | 4.06 | 3.27 | 92.68 |
| 2019-20 | 45699.20              | 136932         | 155769         | (+)13.75              | 712            | 45699.20    | 4.12 | 1.91 | 93.97 |
| 2018-19 | 45399.22              | 130000         | 134894         | (+)3.76               | 710            | 45399.22    | 5.85 | 2.87 | 91.28 |
| 2017-18 | 45293.42              | 141400         | 126122         | (-)10.20              | 712            | 45293.42    | 5.54 | 3.17 | 91.29 |
| 2016-17 | 44478.42              | 134000         | 122378         | (-)7.67               | 695            | 44478.42    | 6.43 | 3.33 | 90.24 |
| 2015-16 | 42783.42              | 128000         | 121377         | (-)5.17               | 676            | 42783.42    | 7.21 | 4.86 | 87.93 |
| 2014-15 | 41262.42              | 124267         | 129244         | (+)3.98               | 659            | 41262.42    | 7.21 | 4.30 | 88.49 |
| 2013-14 | 40531.41              | 122263         | 134848         | (+)10.29              | 653            | 40531.41    | 5.97 | 5.55 | 88.48 |
| 2012-13 | 39491.40              | 122045         | 113720         | (-)6.82               | 634            | 39491.40    | 7.56 | 3.27 | 89.17 |
| 2011-12 | 38990.40              | 112050         | 130510         | (+)16.47              | 620            | 38990.40    | 7.43 | 4.48 | 88.09 |
| 2010-11 | 37567.40              | 111352         | 114257         | (+)2.61               | 609            | 37567.40    | 7.23 | 3.94 | 88.83 |
| 2009-10 | 36863.40              | 115468         | 103916         | (-)10.00              | 589            | 36203.40    | 6.19 | 2.90 | 90.91 |

# CHAPTER-1

## HYDRO-ELECTRIC POTENTIAL AND DEVELOPMENT

## CHAPTER-1

### HYDRO-ELECTRIC POTENTIAL AND DEVELOPMENT

#### 1.1 Hydro-electric Potential

Reassessment studies of Hydro-electric Potential in various river basins of the country were carried out by Central Electricity Authority during the period 1978-87. As per these studies, total Hydro-electric Power potential in the country was assessed as 84044 MW (at 60% load factor) from a total of 845 number of identified H.E. Schemes which when fully developed would result in an installed capacity of about 148701 MW on the basis of probable average load factor. The total energy potential is assessed as 600 billion units per year. The identified potential of H.E. schemes above 25 MW installed capacity works out to be 145320 MW from a total of 592 H.E. schemes.

As on 31.03.2022, H.E. Schemes having total installed capacity of 41778.9 MW (28.75%) excluding pumped storage stations of capacity of 4745.60 MW have already been developed and the schemes under construction account for capacity of 11083.5 MW (7.63%), (excluding PSS of 1500 MW). As such, about 63.62% identified capacity is yet to be harnessed. Summary of the status of Hydro-electric Potential development in the country is indicated in **Tables 1.1, and 1.2** respectively as well as shown in **Exhibits 1.1 and 1.2**.

**TABLE 1.1**

#### **REGION-WISE/STATE-WISE STATUS OF HYDRO-ELECTRIC CAPACITY (In terms of Installed Capacity-above 25 MW as on 31.03.2022)**

| Region/ State        | Identified Capacity as per reassessment study (MW) |              | Capacity Developed |              | Capacity Under construction |              | Capacity yet to be developed |              |
|----------------------|----------------------------------------------------|--------------|--------------------|--------------|-----------------------------|--------------|------------------------------|--------------|
|                      | Total (MW)                                         | Above 25 MW  | (MW)               | (%)          | (MW)                        | (%)          | (MW)                         | (%)          |
| <b>NORTHERN</b>      |                                                    |              |                    |              |                             |              |                              |              |
| Jammu & Kashmir      | 14146                                              | 13543        | 3360.0             | 29.05        | 2559.5                      | 22.13        | 5647.5                       | 48.82        |
| Ladhak               | 2377                                               | 2046         | 89.0               | 4.35         | 0.0                         | 0.00         | 1957.0                       | 95.65        |
| Himachal Pradesh     | 18820                                              | 18540        | 10065.0            | 54.49        | 2190.0                      | 11.86        | 6215.0                       | 33.65        |
| Punjab               | 971                                                | 971          | 1096.3             | 100          | 206.0                       | 21.22        | 0.0                          | 0.00         |
| Haryana              | 64                                                 | 64           | 0.0                | 0            | 0.0                         | 0.00         | 0.0                          | 0.00         |
| Rajasthan            | 496                                                | 483          | 411.0              | 85.09        | 0.0                         | 0.00         | 0.0                          | 0.00         |
| Uttarakhand          | 18175                                              | 17998        | 3855.4             | 21.42        | 1391.0                      | 7.73         | 12751.7                      | 70.85        |
| Uttar Pradesh        | 723                                                | 664          | 501.6              | 75.54        | 0.0                         | 0.00         | 162.4                        | 24.46        |
| <b>Sub Total(NR)</b> | <b>53395</b>                                       | <b>52263</b> | <b>19378.3</b>     | <b>37.08</b> | <b>6346.5</b>               | <b>12.14</b> | <b>26538.3</b>               | <b>50.78</b> |
| <b>WESTERN</b>       |                                                    |              |                    |              |                             |              |                              |              |
| Madhya Pradesh       | 2243                                               | 1970         | 2235.0             | 100          | 400.00                      | 20.30        | 0.0                          | 0.00         |
| Chhattisgarh         | 2242                                               | 2202         | 120.0              | 5.45         | 0.00                        | 0.00         | 2082.0                       | 94.55        |
| Gujarat              | 619                                                | 590          | 550.0              | 100          | 0.00                        | 0.00         | 0.0                          | 0.00         |
| Maharashtra          | 3769                                               | 3314         | 2647.0             | 79.87        | 0.00                        | 0.00         | 667.0                        | 20.13        |

| Region/ State          | Identified Capacity as per reassessment study (MW) |               | Capacity Developed |              | Capacity Under construction |              | Capacity yet to be developed |              |
|------------------------|----------------------------------------------------|---------------|--------------------|--------------|-----------------------------|--------------|------------------------------|--------------|
|                        | Total (MW)                                         | Above 25 MW   | (MW)               | (%)          | (MW)                        | (%)          | (MW)                         | (%)          |
| Goa                    | 55                                                 | 55            | 0.0                | 0.00         | 0.00                        | 0.00         | 55.0                         | 100.00       |
| <b>Sub Total (WR)</b>  | <b>8928</b>                                        | <b>8131</b>   | <b>5552.0</b>      | <b>68.28</b> | <b>400.00</b>               | <b>4.92</b>  | <b>2179.0</b>                | <b>26.80</b> |
| <b>SOUTHERN</b>        |                                                    |               |                    |              |                             |              |                              |              |
| Andhra Pradesh         | 2366                                               | 2341          | 1610.0             | 49.37        | 960.0                       | 29.44        | 691.0                        | 21.19        |
| Telangana              | 2058                                               | 2019          | 800.0              | 72.79        | 0.0                         | 0.00         | 299.0                        | 27.21        |
| Karnataka              | 6602                                               | 6459          | 3689.2             | 57.12        | 0.0                         | 0.00         | 2769.8                       | 42.88        |
| Kerala                 | 3514                                               | 3378          | 1856.5             | 54.96        | 100.0                       | 2.96         | 1421.5                       | 42.08        |
| Tamil Nadu             | 1918                                               | 1693          | 1778.2             | 100          | 0.0                         | 0.00         | 0.0                          | 0.00         |
| <b>Sub Total (SR)</b>  | <b>16458</b>                                       | <b>15890</b>  | <b>9733.9</b>      | <b>61.26</b> | <b>1060.0</b>               | <b>6.67</b>  | <b>5096.1</b>                | <b>32.07</b> |
| <b>EASTERN</b>         |                                                    |               |                    |              |                             |              |                              |              |
| Jharkhand              | 753                                                | 582           | 210.0              | 36.08        | 0.0                         | 0.00         | 372.0                        | 63.92        |
| Bihar                  | 70                                                 | 40            | 0.0                | 0.00         | 0.0                         | 0.00         | 0.0                          | 0.00         |
| Odisha                 | 2999                                               | 2981          | 2154.6             | 72.28        | 0.0                         | 0.00         | 826.5                        | 27.72        |
| West Bengal            | 2841                                               | 2829          | 441.2              | 15.60        | 120.0                       | 4.24         | 2267.8                       | 80.16        |
| Sikkim                 | 4286                                               | 4248          | 2282.0             | 53.72        | 1037                        | 24.42        | 929.0                        | 21.87        |
| <b>Sub Total (ER)</b>  | <b>10949</b>                                       | <b>10680</b>  | <b>5087.8</b>      | <b>47.64</b> | <b>1157</b>                 | <b>10.83</b> | <b>4435.3</b>                | <b>41.53</b> |
| <b>NORTH EASTERN</b>   |                                                    |               |                    |              |                             |              |                              |              |
| Meghalaya              | 2394                                               | 2298          | 322.0              | 14.01        | 0.0                         | 0.00         | 1976.0                       | 85.99        |
| Tripura                | 15                                                 | 0             | 0.0                | 0.00         | 0.0                         | 0.00         | 0.0                          | 0.00         |
| Manipur                | 1784                                               | 1761          | 105.0              | 5.96         | 0.0                         | 0.00         | 1656.0                       | 94.04        |
| Assam                  | 680                                                | 65            | 350.0              | 53.85        | 120.0                       | 18.46        | 180.0                        | 27.69        |
| Nagaland               | 1574                                               | 1452          | 75.0               | 5.17         | 0.0                         | 0.00         | 1377.0                       | 94.83        |
| Arunachal Pradesh      | 50328                                              | 50064         | 1115.0             | 2.23         | 2000.0                      | 3.99         | 46949.0                      | 93.78        |
| Mizoram                | 2196                                               | 2131          | 60.0               | 2.82         | 0.0                         | 0.00         | 2071.0                       | 97.18        |
| <b>Sub Total (NER)</b> | <b>58971</b>                                       | <b>58356</b>  | <b>2027.0</b>      | <b>3.47</b>  | <b>2120.0</b>               | <b>3.63</b>  | <b>54209.0</b>               | <b>92.89</b> |
| <b>ALL INDIA</b>       | <b>148701</b>                                      | <b>145320</b> | <b>41778.9</b>     | <b>28.75</b> | <b>11083.5</b>              | <b>7.63</b>  | <b>92457.6</b>               | <b>63.62</b> |

**Note:-** In addition to above 8 PSS ( 4745.6 MW) are under operation, 2 PSS (1500 MW) are under active construction, 1 PSS (80 MW) on which construction is held up and 2 PSS (2200 MW) is Concurred by CEA , 17 PSS (16770 MW) are under S&I, 1 PSS of I.C. 660 MW is under Held up and 14 PSS (8855 MW) are under PFR/PIR/DPR list.







# REGION-WISE STATUS OF HYDRO-ELECTRIC CAPACITY AS ON 31.03.2022


EXHIBIT 1.1

YTD= Yet to be Developed

UC=Under Construction

I/O=In Operation





**TABLE 1.2**

**STATUS OF H.E. POTENTIAL DEVELOPMENT - BASIN-WISE**  
(In terms of Installed Capacity-above 25 MW as on 31.03.2022)

| River Basin                 | Identified Capacity as per Reassessment Study (MW) |               | Capacity Developed |              | Capacity Under Construction |             | Capacity Yet to be Developed |              |
|-----------------------------|----------------------------------------------------|---------------|--------------------|--------------|-----------------------------|-------------|------------------------------|--------------|
|                             | Total                                              | Above 25      | (MW)               | (%)          | (MW)                        | (%)         | (MW)                         | (%)          |
| Indus                       | 33832                                              | 33028         | 14439.3            | 43.72        | 4911.5                      | 14.87       | 13677.2                      | 41.41        |
| Ganga                       | 20711                                              | 20252         | 5567.2             | 27.49        | 1435                        | 7.09        | 13249.85                     | 65.42        |
| Central Indian River System | 4152                                               | 3868          | 3159.8             | 81.69        | 400                         | 10.34       | 308.2                        | 7.97         |
| West Flowing Rivers System  | 9430                                               | 8997          | 5676.7             | 63.10        | 100.0                       | 1.11        | 3220.3                       | 35.79        |
| East Flowing Rivers System  | 14511                                              | 13775         | 8249.0             | 59.88        | 960.0                       | 6.97        | 4566.1                       | 33.15        |
| Brahmaputra                 | 66065                                              | 65400         | 4687.0             | 7.17         | 3277                        | 5.01        | 57436.0                      | 87.82        |
| <b>Total</b>                | <b>148701</b>                                      | <b>145320</b> | <b>41778.9</b>     | <b>28.75</b> | <b>11083.5</b>              | <b>7.63</b> | <b>92457.6</b>               | <b>63.62</b> |

**Note:-** In addition to above 8 PSS ( 4745.6 MW) are under operation, 2 PSS (1500 MW) are under active construction, 1 PSS (80 MW) on which construction is held up and 2 PSS (2200 MW) is Concurred by CEA , 17 PSS (16770 MW) are under S&I, 1 PSS of I.C. 660 MW is under Held up and 14 PSS (8855 MW) are under PFR/PIR/DPR list.

## 1.2 Growth of Installed Capacity

A small Hydro-Electric Plant (130 KW) established near Darjeeling in 1897 ushered the beginning of hydro-electric power development in the country. Since then, development of hydro-electric power in the country has made rapid strides. The hydel installed capacity which was only 508 MW in 1947 with 12 H.E. Stations, 51 units and the maximum unit size of 22 MW at Bhira H.E. station under Tata, has risen to 46722.50 MW (as on 31.03.2022) from H.E. stations above 25 MW capacity. The maximum unit size now is 250 MW at Koyna Stage-IV under MAHAGENCO, Nathpa Jhakri under SJVNL, Tehri under THDC and Karcham Wangtoo of JSW Energy.

Contribution of electricity generation from Hydro Electric Power Stations has risen from 2.2 BU during 1947 to about 151.6 BU in 2021-22. Hydro generation during 2021-22 was about 1.3 BU (i.e. 0.86%) more than the generation of 150.3 BU during 2020-21.

## 1.3 Share of Hydro-electric Installed Capacity & Generation


The installed capacity of Hydro-Electric Stations viz-à-viz total capacity, the contribution in generation by hydro-electric plants and trend of hydro capacity & generation over the years are indicated in **Table-1.3** and at **Exhibits 1.3, 1.4 and 1.5**. From **Table 1.3**, it may be observed that the overall share of hydro in terms of installed capacity in the country rose from 37.3% at the end of 1947 to 50.6% during 1962-63. However, thereafter, the share of hydro progressively increased and is presently 11.69% at the end of 2021-22. The generation from hydro stations during the year 2021-22 accounted for 11.54% of the total energy generation in the country.

**TABLE 1.3**  
**HYDRO-ELECTRIC CAPACITY & GENERATION**  
**VIS-À-VIS TOTAL CAPACITY & GENERATION**


| Year     | Installed Capacity |            |                     | Generation |            |                     |
|----------|--------------------|------------|---------------------|------------|------------|---------------------|
|          | Total (MW)         | Hydro (MW) | Hydro as % of Total | Total (MU) | Hydro (MU) | Hydro as % of Total |
| 1950     | 1713               | 560        | 32.63               | 5106       | 2519       | 49.33               |
| 1955-56  | 2886               | 1061       | 36.76               | 9145       | 4295       | 46.97               |
| 1960-61  | 4653               | 1917       | 41.20               | 16937      | 7837       | 46.27               |
| 1962-63  | 5801               | 2936       | 50.61               | 22365      | 11805      | 52.78               |
| 1965-66  | 9027               | 4124       | 45.68               | 32890      | 15225      | 46.29               |
| 1968-69  | 12957              | 5907       | 45.59               | 47434      | 20723      | 43.69               |
| 1973-74  | 16664              | 6966       | 41.80               | 66689      | 28972      | 43.44               |
| 1978-79  | 26680              | 10833      | 40.60               | 102523     | 47159      | 46.00               |
| 1979-80  | 28448              | 11384      | 40.02               | 104627     | 45478      | 43.47               |
| 1984-85  | 42585              | 14460      | 33.96               | 156859     | 53948      | 34.39               |
| 1989-90  | 63636              | 18307      | 28.77               | 245437     | 62116      | 25.31               |
| 1991-92  | 69065              | 19194      | 27.79               | 287028     | 72757      | 25.35               |
| 1996-97  | 85795              | 21658      | 25.24               | 395889     | 68901      | 17.40               |
| 1997-98  | 89203              | 21904      | 24.58               | 421748     | 74582      | 17.68               |
| 1998-99  | 92269              | 22479      | 24.10               | 447464     | 82923      | 18.53               |
| 1999-00  | 97837              | 23857      | 24.37               | 481128     | 80755      | 16.78               |
| 2000-01  | 101450             | 25153      | 24.75               | 499429     | 74362      | 14.89               |
| 2001-02  | 105046             | 26269      | 25.01               | 515066     | 73759      | 14.32               |
| 2002-03  | 107877             | 26767      | 24.81               | 531607     | 63834      | 12.01               |
| 2003-04  | 112684             | 29507      | 26.19               | 558113     | 73775      | 13.22               |
| 2004-05  | 118419             | 30936      | 26.12               | 587416     | 84495      | 14.38               |
| 2005-06  | 124287             | 32326      | 26.01               | 624631     | 101293     | 16.22               |
| 2006-07  | 132321             | 34662      | 26.19               | 659513     | 113359     | 17.19               |
| 2007-08  | 143061             | 37002      | 25.86               | 704469     | 123424     | 17.52               |
| 2008-09* | 147917             | 36846      | 24.91               | 714653     | 109840     | 15.37               |
| 2009-10* | 159398             | 36863      | 23.13               | 763429     | 103916     | 13.61               |
| 2010-11* | 173626             | 37567      | 21.64               | 805532     | 114257     | 14.18               |
| 2011-12* | 199877             | 38990      | 19.51               | 871602     | 130510     | 14.97               |
| 2012-13* | 223344             | 39491      | 17.68               | 907262     | 113720     | 12.53               |
| 2013-14* | 243029             | 40531      | 16.68               | 961552     | 134848     | 14.02               |
| 2014-15* | 267637             | 41267      | 15.42               | 1043665    | 129244     | 12.38               |
| 2015-16* | 302088             | 42783      | 14.16               | 1102578    | 121377     | 11.01               |
| 2016-17* | 326849             | 44478      | 13.61               | 1154524    | 122378     | 10.60               |
| 2017-18* | 344002             | 45293      | 13.17               | 1201528    | 126123     | 10.50               |
| 2018-19* | 356100             | 45399      | 12.75               | 1244930    | 134894     | 10.84               |
| 2019-20* | 370106.46          | 45699.2    | 12.34               | 1244989.43 | 155769.12  | 12.51               |
| 2020-21* | 382151.22          | 46209.20   | 12.09               | 1225842.14 | 150299.52  | 12.26               |
| 2021-22* | 399496.61          | 46722.50   | 11.69               | 1313453.87 | 151627.33  | 11.54               |

\* Capacity above 25 MW only has been considered.


EXHIBIT 1.3



GROWTH OF HYDRO GENERATION (MU) VIZ-À-VIZ OTHER SOURCES SINCE 1947



# SHARE OF HYDRO CAPACITY AND HYDRO GENERATION SINCE 1947



#### 1.4 Monitored Hydro Installed Capacity

For generation performance, the monitored hydro-electric installed capacity in the country as on 31.03.2022 was 46722.50 MW (above 25 MW capacity). Region-wise summary of the hydel installed capacity is given in **Table 1.4**. Region-wise, type-wise and construction-wise categorization of stations is given in **Annex-1.1** while Sector-wise/Utility-wise and Station-wise/State-wise details of installed capacity are given in **Annex 1.2 to 1.4**.

**TABLE 1.4**

**REGION-WISE SUMMARY OF HYDRO-ELECTRIC INSTALLED CAPACITY  
(Above 25 MW capacity as on 31.03.2022)**

| S.No.        | Region        | No. of Units | Installed Capacity (MW) |
|--------------|---------------|--------------|-------------------------|
| 1.           | Northern      | 256          | 19576.25                |
| 2.           | Western       | 101          | 7392                    |
| 3.           | Southern      | 246          | 11739.5                 |
| 4.           | Eastern       | 86           | 5987.75                 |
| 5.           | North-Eastern | 38           | 2027.0                  |
| <b>Total</b> |               | <b>727</b>   | <b>46722.50</b>         |

Capacity-wise grouping of H.E. Stations as on 31.03.2022 is given in **Annex- 1.5**. It is observed that 106 stations with installed capacity above 100 MW constitute more than 50.50% of the overall hydro capacity.

7 H.E. Generating units having installed capacity of 393 MW were added during the year 2021-22. Details of these units are given in **Annex-1.6**.

Share of hydro installed capacity and hydro generation viz-a-viz total installed capacity and total generation in the country as on 31.03.2022 was 11.69% and 11.54% respectively. These details are indicated in **Exhibits 1.6 and 1.7**. Sector-wise distribution of hydro installed capacity (MW) in Central, Private and State Sectors was 33.53%, 8.41% and 58.06% respectively. Sector-wise distribution of hydro generation (MU) in Central, Private and State sectors was 38.53%, 9.51% and 51.96% respectively. These details are illustrated in **Exhibits 1.8 & 1.9**.

#### 1.5 Hydro Generating Units : Indigenous and imported

As on 31.03.2022, there were 727 hydro generating units in operation at 210 stations comprising of indigenous and imported units as per details given in **Table 1.5** below. The domestic supplier, BHEL, has a share of about 42.69% of total capacity for both turbines & generators whereas other domestic suppliers together have a meagre share of about 6.88% of total capacity.

Among the imported turbines and generators, Japan, UK and Canada are the top three suppliers of turbines and generators in term of numbers but capacity-wise, Japan, Canada and USSR are the top three suppliers.

**TABLE 1.5**

**HYDRO GENERATING UNITS INDIGENOUS/IMPORTED  
FROM VARIOUS COUNTRIES AS ON 31-03-2022**

| Name of the Country | Turbines supplied |              |                 |              | Generators supplied |              |                 |              |
|---------------------|-------------------|--------------|-----------------|--------------|---------------------|--------------|-----------------|--------------|
|                     | Units             |              | Capacity        |              | Units               |              | Capacity        |              |
|                     | No.               | % of Total   | MW              | % of Total   | No.                 | % of Total   | MW              | % of Total   |
| <b>A-Indigenous</b> |                   |              |                 |              |                     |              |                 |              |
| BHEL                | 310               | 42.69        | 20030.30        | 42.87        | 310                 | 42.54        | 20030.30        | 42.87        |
| Others              | 54                | 6.88         | 3395.50         | 7.27         | 54                  | 7.02         | 3394            | 7.26         |
| <b>Sub Total</b>    | <b>364</b>        | <b>49.57</b> | <b>23425.80</b> | <b>50.14</b> | <b>364</b>          | <b>50.07</b> | <b>23424.30</b> | <b>50.13</b> |
| <b>B-Imported</b>   |                   |              |                 |              |                     |              |                 |              |
| USA                 | 9                 | 1.24         | 351.00          | 0.75         | 6                   | 0.83         | 543.15          | 1.16         |
| U.K.                | 63                | 8.67         | 1242.10         | 2.66         | 63                  | 8.67         | 1676.90         | 3.59         |
| France              | 31                | 4.26         | 2179.20         | 4.66         | 15                  | 2.06         | 1726            | 3.69         |
| Canada              | 44                | 6.05         | 3132.00         | 6.70         | 44                  | 6.05         | 3132            | 6.70         |
| USSR                | 26                | 3.58         | 2804.00         | 6.00         | 26                  | 3.58         | 2804            | 6.00         |
| Switzerland         | 21                | 2.89         | 790.20          | 1.69         | 21                  | 2.89         | 219             | 0.47         |
| Japan               | 76                | 10.45        | 6398.20         | 13.69        | 76                  | 10.45        | 5822.20         | 12.46        |
| Other               | 93                | 12.79        | 6400            | 13.70        | 112                 | 15.41        | 7374.95         | 15.78        |
| <b>Sub Total</b>    | <b>363</b>        | <b>49.93</b> | <b>23296.70</b> | <b>49.86</b> | <b>363</b>          | <b>49.93</b> | <b>23298.20</b> | <b>49.87</b> |
| <b>Total</b>        | <b>727</b>        | <b>100</b>   | <b>46722.50</b> | <b>100</b>   | <b>727</b>          | <b>100</b>   | <b>46722.50</b> | <b>100</b>   |

EXHIBIT-1.6

CONTRIBUTION OF HYDRO CAPACITY  
(AS ON 31.03.2022)




EXHIBIT-1.8

SECTOR-WISE HYDRO CAPACITY  
(AS ON 31.03.2022)




EXHIBIT-1.7

CONTRIBUTION OF HYDRO GENERATION  
(DURING 2021-22)





EXHIBIT-1.9

SECTOR-WISE HYDRO GENERATION  
(DURING 2021-22)



**REGION-WISE / SECTOR-WISE INSTALLED CAPACITY OF H.E. STATIONS IN THE COUNTRY**  
**(ABOVE 25 MW CAPACITY)**

**(As on 31.03.2022)**

| REGION        | DESIGN ENERGY (MU) | CONVENTIONAL HE STATIONS |              |                         | PUMPED STORAGE SCHEMES (PSS) |              |                         | CONVENTIONAL + PUMPED STORAGE SCHEMES (PSS) |             |                               |
|---------------|--------------------|--------------------------|--------------|-------------------------|------------------------------|--------------|-------------------------|---------------------------------------------|-------------|-------------------------------|
|               |                    | NO. OF STATIONS          | NO. OF UNITS | INSTALLED CAPACITY (MW) | NO. OF STATIONS              | NO. OF UNITS | INSTALLED CAPACITY (MW) | NO. OF STATIONS                             | TOTAL UNITS | TOTAL INSTALLED CAPACITY (MW) |
| NORTHERN      | 76490.50           | 75                       | 256          | 19576                   | 0                            | 0            | 0.00                    | 75                                          | 256         | 19576.25                      |
| WESTERN       | 16607.21           | 24                       | 88           | 5552.00                 | 4                            | 13           | 1840.00                 | 28                                          | 101         | 7392.00                       |
| SOUTHERN      | 33900.85           | 67                       | 229          | 9734.00                 | 3                            | 17           | 2006                    | 70                                          | 246         | 11739.60                      |
| EASTERN       | 20204.86           | 23                       | 82           | 5088                    | 1                            | 4            | 900.00                  | 24                                          | 86          | 5987.75                       |
| NORTH EASTERN | 9412.73            | 14                       | 38           | 2027.00                 | 0                            | 0            | 0.00                    | 14                                          | 38          | 2027.00                       |
| <b>TOTAL</b>  | <b>156616.15</b>   | <b>203</b>               | <b>693</b>   | <b>41977</b>            | <b>8</b>                     | <b>34</b>    | <b>4745.6</b>           | <b>210*</b>                                 | <b>727</b>  | <b>46722.6</b>                |

\* Total number of HE stations are 210 as NJ Sagar HE Station (Sothern Region) is having one conventional unit and remaining seven units are PSS

**NOTE:**

**Note:** Following two Hydro Stations have conventional as well as PSS capacity:

| Sl. No. | Station   | State/Region           | Installed Capacity (MW) |                |
|---------|-----------|------------------------|-------------------------|----------------|
|         |           |                        | Conventional            | PSS            |
| 1       | N J Sagar | Telangana/<br>Southern | 1X110 =110              | 7X100.8=705.60 |

**SECTOR-WISE INSTALLED CAPACITY OF H.E. STATIONS IN THE COUNTRY**  
**(ABOVE 25 MW CAPACITY)**

| SECTOR       | NO. OF UTILITIES | NO. OF STATION | NO. OF UNITS | INSTALLED CAPACITY (MW) |
|--------------|------------------|----------------|--------------|-------------------------|
| CENTRAL      | 8                | 42             | 163          | 15664.70                |
| STATE        | 23               | 146            | 504          | 27126.80                |
| PRIVATE      | 17               | 22             | 60           | 3931.00                 |
| <b>TOTAL</b> | <b>48</b>        | <b>210</b>     | <b>727</b>   | <b>46722.50</b>         |

**Categorisation of HE Stations (Installed Capacity)****1. Operation-wise****(As on 31.03.2022)**

| Sector                           | RoR       |                | RoR (P)   |                 | Storage (S) |                |           |                 |          |                | Total*      |                 |
|----------------------------------|-----------|----------------|-----------|-----------------|-------------|----------------|-----------|-----------------|----------|----------------|-------------|-----------------|
|                                  | No.       | MW             | No.       | MW              | S(P)        |                | S(MPP)    |                 | PSS      |                | No.         | MW              |
|                                  |           |                |           |                 | No.         | MW             | No.       | MW              | No.      | MW             |             |                 |
| <b>Central</b>                   | 8         | 2115.50        | 19        | 7263.00         | 6           | 1725.00        | 9         | 4561.20         | 0        | 0.00           | 42          | 15664.70        |
| <b>State</b>                     | 15        | 892.15         | 50        | 7590.00         | 32          | 6479.65        | 43        | 7569.40         | 7        | 4595.60        | 147         | 27126.80        |
| <b>Private</b>                   | 5         | 892.00         | 13        | 2592.00         | 3           | 297.00         | 0         | 0.00            | 1        | 150.00         | 22          | 3931.00         |
| <b>Total (Nos./MW Capacity)*</b> | <b>28</b> | <b>3899.65</b> | <b>82</b> | <b>17445.00</b> | <b>41</b>   | <b>8501.65</b> | <b>52</b> | <b>12130.60</b> | <b>8</b> | <b>4745.60</b> | <b>210*</b> | <b>46722.50</b> |
| <b>% of Total</b>                | <b>14</b> | <b>8.77</b>    | <b>41</b> | <b>39.22</b>    | <b>20.5</b> | <b>19.11</b>   | <b>26</b> | <b>27.27</b>    | <b>4</b> | <b>10.67</b>   | <b>100</b>  | <b>100</b>      |

**2. Power House Construction-wise**

| Sector                           | Surface      |                 | Underground  |                 | Total       |                 |
|----------------------------------|--------------|-----------------|--------------|-----------------|-------------|-----------------|
|                                  | No.          | MW              | No.          | MW              | No.         | MW              |
| <b>Central</b>                   | 29           | 9566.5          | 13           | 6098.2          | <b>42</b>   | <b>15664.7</b>  |
| <b>State</b>                     | 124          | 17954.8         | 23           | 9172            | <b>147</b>  | <b>27126.8</b>  |
| <b>Private</b>                   | 13           | 1448            | 9            | 2483            | <b>22</b>   | <b>3931</b>     |
| <b>Total (Nos./MW Capacity)*</b> | <b>166</b>   | <b>28969.30</b> | <b>45</b>    | <b>17753.20</b> | <b>210*</b> | <b>46722.50</b> |
| <b>% of Total</b>                | <b>79.05</b> | <b>62.00</b>    | <b>21.43</b> | <b>38.00</b>    | <b>100</b>  | <b>100</b>      |

\* Total number of HE Stations are 210 as NJ Sagar HE Station (Southern Region) is having one Conventional unit.

Abbreviations:

RoR - Run-of-River type

RoR(P) – Run-of-River with Pondage

S(P) – Storage (Conventional) for Power Generation purpose only

S(MPP) – Storage (Conventional) for Multipurpose Project

PSS – Pumped Storage Scheme

**SECTOR-WISE/UTILITY-WISE INSTALLED CAPACITY OF H.E. STATIONS IN THE COUNTRY  
(ABOVE 25 MW CAPACITY)**

(As on 31.03.2022)

| Sl. No.               | NAME OF THE SECTOR/<br>UTILITY | NO. OF STATIONS | NO. OF UNITS | INSTALLED CAPACITY (MW) | DESIGN ENERGY (MU) |
|-----------------------|--------------------------------|-----------------|--------------|-------------------------|--------------------|
| <b>CENTRAL SECTOR</b> |                                |                 |              |                         |                    |
| 1                     | BBMB                           | 6               | 28           | 2938.30                 | 9515.00            |
| 2                     | NHPC                           | 20              | 70           | 5451.20                 | 24680.34           |
| 3                     | SJVNL                          | 2               | 12           | 1912.02                 | 8490.08            |
| 4                     | NTPC                           | 1               | 4            | 800.00                  | 3054.79            |
| 5                     | THDC                           | 2               | 8            | 1400.00                 | 3952.00            |
| 6                     | NHDC                           | 2               | 16           | 1520.00                 | 3146.57            |
| 7                     | DVC                            | 2               | 5            | 143.20                  | 374.00             |
| 8                     | NEEPCO                         | 7               | 20           | 1500.00                 | 7397.04            |
|                       | <b>SUB-TOTAL CENTRAL</b>       | <b>42</b>       | <b>163</b>   | <b>15664.72</b>         | <b>60609.82</b>    |
| <b>PRIVATE SECTOR</b> |                                |                 |              |                         |                    |
| 1                     | MPCL                           | 1               | 2            | 86                      | 370.93             |
| 2                     | EPPL                           | 1               | 2            | 100                     | 403.00             |
| 3                     | GBHPPL                         | 1               | 2            | 70                      | 291.73             |
| 4                     | ADHPL                          | 1               | 2            | 192                     | 678.18             |
| 5                     | HBPCL                          | 2               | 7            | 1345                    | 5344.06            |
| 6                     | JPPVL                          | 1               | 4            | 400                     | 1774.42            |
| 7                     | AHPC                           | 1               | 4            | 330                     | 1396.84            |
| 8                     | IAEPL                          | 1               | 3            | 36                      | 157.82             |
| 9                     | TPCL                           | 4               | 15           | 447                     | 1220.00            |
| 10                    | GIPL                           | 1               | 2            | 110                     | 537.81             |
| 11                    | DEPL                           | 1               | 2            | 96                      | 459.02             |
| 12                    | DLHP                           | 1               | 1            | 34                      | 50.00              |
| 13                    | SKPPPL                         | 1               | 2            | 96                      | 431.00             |
| 14                    | SEPL                           | 1               | 2            | 97                      | 425.05             |
| 15                    | RENEW POWER PVT LTD.           | 1               | 3            | 99                      | 473.00             |
| 16                    | MBPCL                          | 1               | 2            | 113                     | 434.00             |
| 17                    | HSPPL                          | 1               | 2            | 100                     | 524.00             |
| 18                    | GMR                            | 1               | 3            | 180                     | 769.39             |
|                       | <b>SUB-TOTAL PRIVATE</b>       | <b>22</b>       | <b>60</b>    | <b>3931.00</b>          | <b>15740.25</b>    |

| STATE SECTOR |                        |            |            |                 |                  |
|--------------|------------------------|------------|------------|-----------------|------------------|
| 1            | HPSEBL                 | 4          | 12         | 372.00          | 1691.62          |
| 2            | HPPCL                  | 3          | 8          | 406.00          | 955.03           |
| 3            | JKSPDCL                | 4          | 12         | 1110.00         | 4833.30          |
| 4            | PSPCL                  | 8          | 25         | 1051.00         | 4207.00          |
| 5            | RRVUNL                 | 4          | 11         | 411.00          | 1046.00          |
| 6            | UPJVNL                 | 4          | 15         | 501.60          | 1707.00          |
| 7            | UJVNL                  | 10         | 34         | 1252.15         | 4848.10          |
| 8            | GSECL                  | 2          | 8          | 540.00          | 1598.00          |
| 9            | SSNNL                  | 2          | 11         | 1450.00         | 3848.00          |
| 10           | MPPGCL                 | 8          | 23         | 875.00          | 2561.64          |
| 11           | CSPGC                  | 1          | 3          | 120.00          | 245.00           |
| 12           | MAHAGENCO              | 8          | 24         | 2406.00         | 3938.00          |
| 13           | APGENCO                | 8          | 34         | 1796.75         | 5738.00          |
| 14           | TSGENCO                | 7          | 36         | 2405.60         | 5045.85          |
| 15           | KPCL                   | 14         | 66         | 3617.20         | 12981.00         |
| 16           | KSEB                   | 14         | 47         | 1856.50         | 6458.00          |
| 17           | TANGEDCO               | 27         | 69         | 2178.20         | 4348.00          |
| 18           | JUUNL                  | 2          | 2          | 130.00          | 149.00           |
| 19           | OHPC                   | 6          | 31         | 2039.80         | 5676.00          |
| 20           | WBSEDCL                | 3          | 12         | 986.00          | 1610.00          |
| 21           | TUL                    | 1          | 6          | 1200.00         | 5214.00          |
| 22           | APGCL                  | 1          | 2          | 100.00          | 390.00           |
| 23           | MePGCL                 | 5          | 13         | 322.00          | 1177.69          |
|              | <b>SUB-TOTAL STATE</b> | <b>146</b> | <b>504</b> | <b>27126.80</b> | <b>80266.23</b>  |
|              | <b>TOTAL</b>           | <b>210</b> | <b>727</b> | <b>46722.50</b> | <b>156616.30</b> |

**State-wise/Station-wise Installed Capacity of H.E. Stations in the Country**  
(Above 25 MW Capacity)

As on 31.03.2022

| Sl No. | Utilities/Stations               | No. of Stations | No. of Units | Type of Project | No. of Units X Capacity(MW ) | Capacity (MW)  | Design Energy (MU) | Year of Commissioning                                         |
|--------|----------------------------------|-----------------|--------------|-----------------|------------------------------|----------------|--------------------|---------------------------------------------------------------|
|        | <b>Conventional H E Stations</b> |                 |              |                 |                              |                |                    |                                                               |
|        | <b>Northern Region</b>           |                 |              |                 |                              |                |                    |                                                               |
|        | <b>BBMB</b>                      |                 |              |                 |                              |                |                    |                                                               |
|        | <b>HIMACHAL PRADESH</b>          |                 |              |                 |                              |                |                    |                                                               |
| 1      | Bhakra Left                      | 1               | 5            | MP              | (1X108+4X126)                | 612.00         | 3924.00            | 1960 (108 MW)<br>1961 (486 MW)                                |
| 2      | Bhakra Right                     | 1               | 5            | MP              | (5X157)                      | 785.00         |                    | 1966 (314 MW)<br>1967 (314 MW)<br>1968 (157 MW)               |
| 3      | Dehar                            | 1               | 6            | R(P)            | (6X165)                      | 990.00         | 3110.00            | 1977 (165 MW)<br>1978 (165 MW)                                |
| 4      | Pong                             | 1               | 6            | MP              | (6X66)                       | 396.00         | 1123.00            | 1978 (198 MW)<br>1979 (66 MW)<br>1982 (66 MW)<br>1983 (66 MW) |
|        | <b>Sub-Total BBMB (HP)</b>       | <b>4</b>        | <b>22</b>    |                 |                              | <b>2783.00</b> | <b>8157.00</b>     |                                                               |
|        | <b>NHPC</b>                      |                 |              |                 |                              |                |                    |                                                               |
| 5      | Baira Siul                       | 1               | 3            | R(P)            | (3X60)                       | 180.00         | 779.28             | 1980 (132 MW)<br><del>1981 (66 MW)</del>                      |
| 6      | Chamera-I                        | 1               | 3            | S               | (3X180)                      | 540.00         | 1664.56            | 1994 (540 MW)                                                 |
| 7      | Chamera-II                       | 1               | 3            | R(P)            | (3X100)                      | 300.00         | 1499.89            | 2003 (200 MW)<br><del>2004 (100 MW)</del>                     |
| 8      | Chamera-III                      | 1               | 3            | R(P)            | (3X77)                       | 231.00         | 1108.00            | 2012 (231 MW)                                                 |
| 9      | Parbati-III                      | 1               | 4            | R(P)            | (4X130)                      | 520.00         | 1977.23            | 2014 (520 MW)                                                 |
|        | <b>Sub-Total HP</b>              | <b>5</b>        | <b>16</b>    |                 |                              | <b>1771.00</b> | <b>7028.96</b>     |                                                               |
|        | <b>SJVNL</b>                     |                 |              |                 |                              |                |                    |                                                               |
| 10     | Nathpa Jhakri                    | 1               | 6            | R(P)            | (6X250)                      | 1500.00        | 6612.00            | 2003 (500 MW)<br>2004 (1000 MW)                               |
| 11     | Rampur                           | 1               | 6            | R               | (6X68.67)                    | 412.00         | 1878.08            | 2014 (412 MW)                                                 |
|        | <b>Total SJVNL</b>               | <b>2</b>        | <b>12</b>    |                 |                              | <b>1912.00</b> | <b>8490.08</b>     |                                                               |
|        | <b>NTPC LTD.</b>                 |                 |              |                 |                              |                |                    |                                                               |
| 12     | Koldam                           | 1               | 4            | S               | (4X200)                      | 800.00         | 3054.79            | 2015 (800 MW)                                                 |
|        | <b>Total NTPC LTD.</b>           | <b>1</b>        | <b>4</b>     |                 |                              | <b>800.00</b>  | <b>3054.79</b>     |                                                               |
|        | <b>Total Central Sector-HP</b>   | <b>12</b>       | <b>54</b>    |                 |                              | <b>7266.00</b> | <b>26730.83</b>    |                                                               |
|        | <b>HPSEBL</b>                    |                 |              |                 |                              |                |                    |                                                               |
| 13     | Bassi                            | 1               | 4            | R(P)            | (4X16.5)                     | 66.00          | 346.77             | 1970 (33 MW)<br><del>1971 (66 MW)</del>                       |
| 14     | Giri Bata                        | 1               | 2            | R(P)            | (2X30)                       | 60.00          | 240.00             | 1978 (60 MW)                                                  |
| 15     | Larji'                           | 1               | 3            | R(P)            | (3X42)                       | 126.00         | 586.85             | 2006 (126 MW)                                                 |
| 16     | Sanjay                           | 1               | 3            | R(P)            | (3X40)                       | 120.00         | 518.00             | 1989 (120 MW)                                                 |
|        | <b>Total HPSEBL</b>              | <b>4</b>        | <b>12</b>    |                 |                              | <b>372.00</b>  | <b>1691.62</b>     |                                                               |
|        | <b>HPPCL</b>                     |                 |              |                 |                              |                |                    |                                                               |
| 17     | Integrated Kashang               | 1               | 3            | R (P)           | (3X65)                       | 195            | 245.80             | <del>2016 (120 MW)</del>                                      |
| 18     | Sainj                            | 1               | 2            | R(P)            | (2X50)                       | 100            | 323.23             | 2017 (100 MW)                                                 |
| 19     | Sawara Kuddu                     | 1               | 3            | R               | (3X37)                       | 111            | 386.00             | 2020 (111 MW)                                                 |
|        | <b>Total HPPCL</b>               | <b>3</b>        | <b>8</b>     |                 |                              | <b>406.00</b>  | <b>955.03</b>      |                                                               |
|        | <b>PSPCL</b>                     |                 |              |                 |                              |                |                    |                                                               |
| 20     | Shanan                           | 1               | 5            | R(P)            | (1X50)+(4X15)                | 110.00         | 585.00             | 1932 (60 MW)<br>1982 (50 MW)                                  |
|        | <b>Sub Total PSPCL-HP</b>        | <b>1</b>        | <b>5</b>     |                 |                              | <b>110.00</b>  | <b>585.00</b>      |                                                               |
|        | <b>Total State Sector</b>        | <b>8</b>        | <b>25</b>    |                 |                              | <b>888.00</b>  | <b>3231.65</b>     |                                                               |
|        | <b>Private Sector</b>            |                 |              |                 |                              |                |                    |                                                               |
|        | <b>MPCL</b>                      |                 |              |                 |                              |                |                    |                                                               |

| Sl. No. | Units/Stations                   | No. of Stations | Units      | Type of Project | Capacity(MW ) | (MW)            | Energy (MU)     | Year of Commissioning                                            |
|---------|----------------------------------|-----------------|------------|-----------------|---------------|-----------------|-----------------|------------------------------------------------------------------|
|         | <b>Conventional H E Stations</b> |                 |            |                 |               |                 |                 |                                                                  |
| 21      | Malana                           | 1               | 2          | R(P)            | (2X43)        | 86.00           | 370.93          | 2001 (86 MW)                                                     |
|         | <b>Total MPCL</b>                | <b>1</b>        | <b>2</b>   |                 |               | <b>86.00</b>    | <b>370.93</b>   |                                                                  |
|         | <b>GBHPPL</b>                    |                 |            |                 |               |                 |                 |                                                                  |
| 22      | Budhil                           | 1               | 2          | R(P)            | (2X35)        | 70.00           | 291.73          | 2012 (70 MW)                                                     |
|         | <b>Total GBHPPL</b>              | <b>1</b>        | <b>2</b>   |                 |               | <b>70.00</b>    | <b>291.73</b>   |                                                                  |
|         | <b>EPPL</b>                      |                 |            |                 |               |                 |                 |                                                                  |
| 23      | Malana-II                        | 1               | 2          | R(P)            | (2X50)        | 100.00          | 403.00          | 2011 (100 MW)                                                    |
|         | <b>Total EPPL</b>                | <b>1</b>        | <b>2</b>   |                 |               | <b>100.00</b>   | <b>403.00</b>   |                                                                  |
|         | <b>IA Energy</b>                 |                 |            |                 |               |                 |                 |                                                                  |
| 24      | Chanju-I                         | 1               | 3          | R(P)            | (3X12)        | 36.00           | 157.82          | 2017 (12 MW)                                                     |
|         | <b>Total IA Energy</b>           | <b>1</b>        | <b>3</b>   |                 |               | <b>36.00</b>    | <b>157.82</b>   |                                                                  |
| 25      | Allain Duhangan                  | 1               | 2          | R(P)            | (2X96)        | 192.00          | 678.18          | 2010 (192 MW)                                                    |
|         | <b>Total ADHPL</b>               | <b>1</b>        | <b>2</b>   |                 |               | <b>192.00</b>   | <b>678.18</b>   |                                                                  |
|         | <b>HBPCL</b>                     |                 |            |                 |               |                 |                 |                                                                  |
| 26      | Baspa                            | 1               | 3          | R(P)            | (3X100)       | 300.00          | 1213.00         | 2003 (300 MW)                                                    |
| 27      | Karcham Wangtoo                  | 1               | 4          | R(P)            | (4X261.25)    | 1045.00         | 4131.06         | 2011 (1000 MW)                                                   |
|         | <b>Total HBPCL</b>               | <b>2</b>        | <b>7</b>   |                 |               | <b>1345.00</b>  | <b>5344.06</b>  |                                                                  |
|         | <b>HSPPL</b>                     |                 |            |                 |               |                 |                 |                                                                  |
| 28      | Sorang                           | 1               | 2          | R               | (2X50)        | 100.00          | 524.00          | 2021 (100 MW)                                                    |
|         | <b>Total HSPPL</b>               | <b>1</b>        | <b>2</b>   |                 |               | <b>100.00</b>   | <b>524.00</b>   |                                                                  |
|         | <b>GMR</b>                       |                 |            |                 |               |                 |                 |                                                                  |
| 29      | Bajoli Holi                      | 1               | 3          | R               | (3X60)        | 180.00          | 769.39          | Mar 2022 (180)                                                   |
|         | <b>Total GMR</b>                 | <b>1</b>        | <b>3</b>   |                 |               | <b>180.00</b>   | <b>769.39</b>   |                                                                  |
|         | <b>Total PVT</b>                 | <b>9</b>        | <b>23</b>  |                 |               | <b>2109.00</b>  | <b>8539.11</b>  |                                                                  |
|         | <b>Total Himachal Pradesh</b>    | <b>29</b>       | <b>102</b> |                 |               | <b>10263.00</b> | <b>38501.59</b> |                                                                  |
|         | <b>JAMMU &amp; KASHMIR</b>       |                 |            |                 |               |                 |                 |                                                                  |
|         | <b>JKSPDC</b>                    |                 |            |                 |               |                 |                 |                                                                  |
| 30      | Baglihar-I                       | 1               | 3          | R(P)            | (3X150)       | 450.00          | 2643.00         | 2008 (450 MW)                                                    |
| 31      | Baglihar-II                      | 1               | 3          | R(P)            | (3X150)       | 450.00          | 1302.30         | 2015 (450 MW)                                                    |
| 32      | Lower Jhelum                     | 1               | 3          | R(P)            | (3X35)        | 105.00          | 533.00          | 1978 (35 MW)<br>1979 (70 MW)                                     |
| 33      | Upper Sindh-II                   | 1               | 3          | R(P)            | (3X35)        | 105.00          | 355.00          | 2000 (35 MW)<br>2001 (35 MW)<br>2002 (35 MW)                     |
|         | <b>Total JKSPDC</b>              | <b>4</b>        | <b>12</b>  |                 |               | <b>1110.00</b>  | <b>4833.30</b>  |                                                                  |
|         | <b>NHPC</b>                      |                 |            |                 |               |                 |                 |                                                                  |
| 34      | Dulhasti                         | 1               | 3          | R(P)            | (3X130)       | 390.00          | 1907.00         | 2007 (390 MW)                                                    |
| 35      | Salal-I&II                       | 1               | 6          | R               | (3X115)       | 690.00          | 3082.00         | 1987 (345 MW)<br>1993 (115 MW)<br>1994 (115 MW)<br>1995 (115 MW) |
| 36      | Uri-I                            | 1               | 4          | R               | (4X120)       | 480.00          | 2587.38         | 1996 (120 MW)<br>1997 (360 MW)                                   |
| 37      | Uri-II                           | 1               | 4          | R               | (4X60)        | 240.00          | 1124.00         | 2013 (180 MW)                                                    |
| 38      | Sewa-II                          | 1               | 3          | R(P)            | (3X40)        | 120.00          | 533.52          | 2010 (120 MW)                                                    |
| 39      | Keshanganga                      | 1               | 3          | R(P)            | (3X110)       | 330.00          | 1705.62         | 2018 (330 MW)                                                    |
|         | <b>Sub-Total NHPC</b>            | <b>6</b>        | <b>23</b>  |                 |               | <b>2250.00</b>  | <b>10939.52</b> |                                                                  |
|         | <b>Total Jammu &amp; Kashmir</b> | <b>10</b>       | <b>35</b>  |                 |               | <b>3360.00</b>  | <b>15772.82</b> |                                                                  |
|         | <b>LADAKH</b>                    |                 |            |                 |               |                 |                 |                                                                  |
|         | <b>NHPC</b>                      |                 |            |                 |               |                 |                 |                                                                  |
| 40      | Chutak                           | 1               | 4          | R               | (4X11)        | 44.00           | 213.00          | 2012 (33 MW)<br>2013 (11 MW)                                     |
| 41      | Nimoo Bazgo                      | 1               | 3          | R(P)            | (3X15)        | 45.00           | 239.00          | 2013 (45 MW)                                                     |
|         | <b>Sub-Total NHPC</b>            | <b>2</b>        | <b>7</b>   |                 |               | <b>89.00</b>    | <b>452.00</b>   |                                                                  |

| Sl. No. | Names/Stations                   | No. of Stations | Units     | Type of Project | Capacity(MW )       | (MW)           | Energy (MU)    | Year of Commissioning                                 |
|---------|----------------------------------|-----------------|-----------|-----------------|---------------------|----------------|----------------|-------------------------------------------------------|
|         | <b>Conventional H E Stations</b> |                 |           |                 |                     |                |                |                                                       |
|         | <b>Total Ladakh</b>              | <b>2</b>        | <b>7</b>  |                 |                     | <b>89.00</b>   | <b>452.00</b>  |                                                       |
|         | <b>PUNJAB</b>                    |                 |           |                 |                     |                |                |                                                       |
|         | <b>PSPCL</b>                     |                 |           |                 |                     |                |                |                                                       |
| 42      | Anandpur Sahib-I                 | 1               | 2         | R               | (2X33.5)            | 67.00          | 909.00         | 1985 (67 MW)                                          |
| 43      | Anandpur Sahib-I                 | 1               | 2         | R               | (2X33.5)            | 67.00          |                | 1985 (67 MW)                                          |
| 44      | Mukerian-I                       | 1               | 3         | R               | (3X15)              | 45.00          | 1206.00        | 1983 (45 MW)                                          |
| 45      | Mukerian-II                      | 1               | 3         | R               | (3X15)              | 45.00          |                | 1988 (30 MW)<br>1989 (15 MW)                          |
| 46      | Mukerian-III                     | 1               | 3         | R               | (3X19.5)            | 58.50          |                | 1989 (58.50 MW)                                       |
| 47      | Mukerian-IV                      | 1               | 3         | R               | (3X19.5)            | 58.50          |                | 1989 (58.50 MW)                                       |
| 48      | Ranjit Sagar                     | 1               | 4         | S               | (4X150)             | 600.00         | 1507.00        | 2000 (600 MW)                                         |
|         | <b>Total PSPCL</b>               | <b>7</b>        | <b>20</b> |                 |                     | <b>941.00</b>  | <b>3622.00</b> |                                                       |
|         | <b>BBMB</b>                      |                 |           |                 |                     |                |                |                                                       |
| 49      | Ganguwal                         | 1               | 3         | R               | (2X24.2)+(1X 29.25) | 77.65          | 1358           | 1955 (48.4 MW)<br>1962 (29.25 MW)                     |
| 50      | Kotla                            | 1               | 3         | R               | (2X24.2)+(1X 29.25) | 77.65          |                | 1956 (48.4 MW)<br>1961 (29.25 MW)                     |
|         | <b>Sub-Total BBMB (Punjab)</b>   | <b>2</b>        | <b>6</b>  |                 |                     | <b>155.30</b>  | <b>1358.00</b> |                                                       |
|         | <b>Total Punjab</b>              | <b>9</b>        | <b>26</b> |                 |                     | <b>1096.30</b> | <b>4980.00</b> |                                                       |
|         | <b>Rajasthan</b>                 |                 |           |                 |                     |                |                |                                                       |
|         | <b>RRVUNL</b>                    |                 |           |                 |                     |                |                |                                                       |
| 51      | Jawahar Sagar                    | 1               | 3         | R(P)            | (3X33)              | 99.00          | 298.00         | 1973 (99 MW)                                          |
| 52      | Mahi Bajaj-I                     | 1               | 2         | MP              | (2X25)              | 50.00          | 289.00         | 1986 (50 MW)                                          |
| 53      | Mahi Bajaj-II                    | 1               | 2         | R(P)            | (2X45)              | 90.00          |                | 1989 (90 MW)                                          |
| 54      | R P Sagar                        | 1               | 4         | MP              | (4X43)              | 172.00         | 459.00         | 1968 (129 MW)<br>1969 (43 MW)                         |
|         | <b>Total RRVUNL</b>              | <b>4</b>        | <b>11</b> |                 |                     | <b>411.00</b>  | <b>1046.00</b> |                                                       |
|         | <b>Total Rajasthan</b>           | <b>4</b>        | <b>11</b> |                 |                     | <b>411.00</b>  | <b>1046.00</b> |                                                       |
|         | <b>UTTARAKHAND</b>               |                 |           |                 |                     |                |                |                                                       |
|         | <b>NHPC</b>                      |                 |           |                 |                     |                |                |                                                       |
| 55      | Dhaulti Ganga                    | 1               | 4         | R(P)            | (4X70)              | 280.00         | 1134.69        | 2005 (280 MW)                                         |
| 56      | Tanakpur                         | 1               | 3         | R               | (3X31.4)            | 94.20          | 452.19         | 1992 (94.2 MW)                                        |
|         | <b>Sub-Total NHPC</b>            | <b>2</b>        | <b>7</b>  |                 |                     | <b>374.20</b>  | <b>1586.88</b> |                                                       |
|         | <b>THDC</b>                      |                 |           |                 |                     |                |                |                                                       |
| 57      | Tehri St-I                       | 1               | 4         | MP              | (4X250)             | 1000.00        | 2797.00        | 2006 (500 MW)<br>2007 (500 MW)                        |
| 58      | Koteswar                         | 1               | 4         | R(P)            | (4X100)             | 400.00         | 1155.00        | 2011 (200 MW)<br>2012 (200 MW)                        |
|         | <b>Total THDC</b>                | <b>2</b>        | <b>8</b>  |                 |                     | <b>1400.00</b> | <b>3952.00</b> |                                                       |
|         | <b>Sub Total Central</b>         | <b>4</b>        | <b>15</b> |                 |                     | <b>1774.20</b> | <b>5538.88</b> |                                                       |
|         | <b>State Sector</b>              |                 |           |                 |                     |                |                |                                                       |
|         | <b>UJVNL</b>                     |                 |           |                 |                     |                |                |                                                       |
| 59      | Chibro (Yamuna)                  | 1               | 4         | R(P)            | (4X60)              | 240.00         | 750.00         | 1975 (180 MW)<br>1976 (60 MW)                         |
| 60      | Chilla                           | 1               | 4         | R               | (4X36)              | 144.00         | 725.00         | 1980 (108 MW)<br>1981 (36 MW)                         |
| 61      | Dhakrani                         | 1               | 3         | R               | (3X11.25)           | 33.75          | 169.00         | 1965 (11.25 MW)<br>1966 (11.25 MW)<br>1970 (11.25 MW) |
| 62      | Dhalipur                         | 1               | 3         | R               | (3X17)              | 51.00          | 192.00         | 1965 (17 MW)<br>1966 (17 MW)<br>1970 (17 MW)          |
| 63      | Khatima                          | 1               | 3         | R               | (3X13.8)            | 41.40          | 208.00         | 1955 (13.8 MW)<br>1956 (27.6 MW)                      |
| 64      | Khodri                           | 1               | 4         | R(P)            | (4X30)              | 120.00         | 345.00         | 1984 (120 MW)                                         |
| 65      | Kulhal                           | 1               | 3         | R               | (3X10)              | 30.00          | 164.00         | 1975 (30 MW)                                          |

| Sl. No. | Names/Stations                   | No. of Stations | Units      | Type of Project | Capacity(MW) | (MW)            | Energy (MU)     | Year of Commissioning                        |
|---------|----------------------------------|-----------------|------------|-----------------|--------------|-----------------|-----------------|----------------------------------------------|
|         | <b>Conventional H E Stations</b> |                 |            |                 |              |                 |                 |                                              |
| 66      | Maneri Bhali-I                   | 1               | 3          | R(P)            | (3X30)       | 90.00           | 395.00          | 1984 (90 MW)                                 |
| 67      | Maneri Bhali-II                  | 1               | 4          | R(P)            | (4X76)       | 304.00          | 1566.10         | 2008 (304 MW)                                |
| 68      | Ramganga                         | 1               | 3          | MP              | (3X66)       | 198.00          | 334.00          | 1975 (66 MW)<br>1976 (66 MW)<br>1977 (66 MW) |
|         | <b>Total UJVNL</b>               | <b>10</b>       | <b>34</b>  |                 |              | <b>1252.15</b>  | <b>4848.10</b>  |                                              |
|         | <b>Private Sector</b>            |                 |            |                 |              |                 |                 |                                              |
|         | <b>AHPC</b>                      |                 |            |                 |              |                 |                 |                                              |
| 69      | Shrinagar                        | 1               | 4          | R(P)            | (4X82.50)    | 330.00          | 1396.84         | 2015 (330 MW)                                |
|         | <b>JPPVL</b>                     |                 |            |                 |              |                 |                 |                                              |
| 70      | Vishnu Prayag                    | 1               | 4          | R               | (4X100)      | 400.00          | 1774.42         | 2006 (400 MW)                                |
|         | <b>L&amp;T</b>                   |                 |            |                 |              |                 |                 |                                              |
| 71      | Singoli Bhatwari                 | 1               | 3          | R               | (3X33)       | 99.00           | 473.00          | 2020 (33 MW)                                 |
|         | <b>Sub Total Private</b>         | <b>3</b>        | <b>11</b>  |                 |              | <b>829.00</b>   | <b>3644.26</b>  |                                              |
|         | <b>Total Uttarakhand</b>         | <b>17</b>       | <b>60</b>  |                 |              | <b>3855.35</b>  | <b>14031.24</b> |                                              |
|         | <b>UPJVNL</b>                    |                 |            |                 |              |                 |                 |                                              |
|         | <b>UTTAR PRADESH</b>             |                 |            |                 |              |                 |                 |                                              |
| 72      | Khara                            | 1               | 3          | R(P)            | (3X24)       | 72.00           | 385.00          | 1992 (72 MW)                                 |
| 73      | Matatila                         | 1               | 3          | MP              | (3X10.2)     | 30.60           | 123.00          | 1965 (30.6 MW)                               |
| 74      | Obra                             | 1               | 3          | MP              | (3X33)       | 99.00           | 279.00          | 1970 (66 MW)<br>1971 (33 MW)                 |
| 75      | Rihand                           | 1               | 6          | MP              | (6X50)       | 300.00          | 920.00          | 1962 (250 MW)<br>1966 (50 MW)                |
|         | <b>Total UPJVNL</b>              | <b>4</b>        | <b>15</b>  |                 |              | <b>501.60</b>   | <b>1707.00</b>  |                                              |
|         | <b>Total Northern Region</b>     | <b>75</b>       | <b>256</b> |                 |              | <b>19576.25</b> | <b>76490.65</b> |                                              |
|         | <b>Western Region</b>            |                 |            |                 |              |                 |                 |                                              |
|         | <b>MADHYA PRADESH</b>            |                 |            |                 |              |                 |                 |                                              |
|         | <b>NHDC</b>                      |                 |            |                 |              |                 |                 |                                              |
| 76      | Indira Sagar                     | 1               | 8          | MP              | (8X125)      | 1000.00         | 1980.00         | 2004 (875 MW)<br>2005 (125 MW)               |
| 77      | Omkareshwar                      | 1               | 8          | MP              | (8X65)       | 520.00          | 1166.57         | 2007 (520 MW)                                |
|         | <b>Sub-Total NHDC</b>            | <b>2</b>        | <b>16</b>  |                 |              | <b>1520.00</b>  | <b>3146.57</b>  |                                              |
|         | <b>Total Central</b>             | <b>2</b>        | <b>16</b>  |                 |              | <b>1520.00</b>  | <b>3146.57</b>  |                                              |
|         | <b>MPPGCL</b>                    |                 |            |                 |              |                 |                 |                                              |
| 78      | Bansagar Tons-I                  | 1               | 3          | R(P)            | (3X105)      | 315.00          | 900.00          | 1991 (105 MW)<br>1992 (210 MW)               |
| 79      | Bansagar Tons-III                | 1               | 2          | R               | (2X15)       | 30.00           | 113.00          | 2002 (30 MW)                                 |
| 80      | Bansagar Tons-II                 | 1               | 3          | MP              | (3X20)       | 60.00           | 143.00          | 2000 (20 MW)<br>2001 (20 MW)<br>2002 (20 MW) |
| 81      | Bargi                            | 1               | 2          | MP              | (2X45)       | 90.00           | 508.08          | 1988 (90 MW)                                 |
| 82      | Gandhi Sagar                     | 1               | 5          | MP              | (5X23)       | 115.00          | 420.48          | 1960 (69 MW)<br>1963 (23 MW)<br>1966 (23 MW) |
| 83      | Madhikhera                       | 1               | 3          | MP              | (3X20)       | 60.00           | 74.12           | 2006 (40 MW)<br>2007 (20 MW)                 |
| 84      | Rajghat                          | 1               | 3          | MP              | (3X15)       | 45.00           | 87.60           | 1999 (45 MW)                                 |
|         | <b>Sub-Total MPPGCL</b>          | <b>7</b>        | <b>21</b>  |                 |              | <b>715.00</b>   | <b>2246.28</b>  |                                              |
|         | <b>Total Madhya Pradesh</b>      | <b>9</b>        | <b>37</b>  |                 |              | <b>2235.00</b>  | <b>5392.85</b>  |                                              |

| Sl. No. | Names/Stations                                     | No. of Stations | Units     | Type of Project | Capacity(MW )  | (MW)           | Energy (MU)    | Year of Commissioning                                           |
|---------|----------------------------------------------------|-----------------|-----------|-----------------|----------------|----------------|----------------|-----------------------------------------------------------------|
|         | <b>Conventional H E Stations</b>                   |                 |           |                 |                |                |                |                                                                 |
|         | <b>MAHARASHTRA</b>                                 |                 |           |                 |                |                |                |                                                                 |
|         | <b>MAHAGENCO</b>                                   |                 |           |                 |                |                |                |                                                                 |
| 85      | Bhira Tail Race                                    | 1               | 2         | R(P)            | (2X40)         | 80.00          | 75.00          | 1987 (40 MW)<br>1988 (40 MW)                                    |
| 86      | Koyna DPH                                          | 1               | 2         | S               | (2X18)         | 36.00          | 146.00         | 1980 (18 MW)<br>1981 (18 MW)                                    |
| 87      | Koyna-I&II                                         | 1               | 8         | S               | (4X70)+(4X80)  | 600.00         | 3030.00        | 1962 (140 MW)<br>1963 (140 MW)<br>1966 (240 MW)<br>1967 (80 MW) |
| 88      | Koyna-III                                          | 1               | 4         | R(P)            | (4X80)         | 320.00         |                | 1975 (160 MW)<br>1977 (80 MW)<br>1978 (80 MW)                   |
| 89      | Koyna-IV                                           | 1               | 4         | S               | (4X250)        | 1000.00        |                | 1999 (500 MW)<br>2000 (500 MW)                                  |
| 90      | Tillari                                            | 1               | 1         | R(P)            | (1X60)         | 60.00          | 133.00         | 1986 (60 MW)                                                    |
| 91      | Vaitarna                                           | 1               | 1         | S               | (1X60)         | 60.00          | 144.00         | 1976 (60 MW)                                                    |
|         | <b>Sub-Total MAHAGENCO</b>                         | <b>7</b>        | <b>22</b> |                 |                | <b>2156.00</b> | <b>3528.00</b> |                                                                 |
|         | <b>MPPGCL</b>                                      |                 |           |                 |                |                |                |                                                                 |
| 92      | Pench                                              | 1               | 2         | MP              | (2X80)         | 160.00         | 315.36         | 1986 (80 MW)<br>1987 (80 MW)                                    |
|         | <b>Sub-Total MPPGCL</b>                            | <b>1</b>        | <b>2</b>  |                 |                | <b>160.00</b>  | <b>315.36</b>  |                                                                 |
|         | <b>Total State SECTOR</b>                          | <b>8</b>        | <b>24</b> |                 |                | <b>2316.00</b> | <b>3843.36</b> |                                                                 |
|         | <b>Private Sector</b>                              |                 |           |                 |                |                |                |                                                                 |
|         | <b>Dodson-Lindblom Hydro Power Pvt. Ltd.(DLHP)</b> |                 |           |                 |                |                |                |                                                                 |
| 93      | Bhandardhara St-II                                 | 1               | 1         | R(P)            | (1X34)         | 34.00          | 50.00          | 1996 (34 MW)                                                    |
|         | <b>Sub-Total DLHP</b>                              | <b>1</b>        | <b>1</b>  |                 |                | <b>34.00</b>   | <b>50.00</b>   |                                                                 |
|         | <b>Tata Power Company</b>                          |                 |           |                 |                |                |                |                                                                 |
| 94      | Bhira                                              | 1               | 6         | S               | (6X25)         | 150.00         | 775.00         | 1927 (125 MW)<br>1949 (25 MW)                                   |
| 95      | Bhiyapuri                                          | 1               | 5         | S               | 3X24) + (2X1.5 | 75.00          | 220.00         | 1997 (3 MW)<br>1998 (48 MW)<br>1999 (24 MW)                     |
| 96      | Khopoli                                            | 1               | 3         | S               | (3X24)         | 72.00          | 225.00         | 2001 (24 MW)<br>2002 (24 MW)<br>2003 (24 MW)                    |
|         | <b>Sub-Total TPCL</b>                              | <b>3</b>        | <b>14</b> |                 |                | <b>297.00</b>  | <b>1220.00</b> |                                                                 |
|         | <b>Total Pvt. (Maharashtra)</b>                    | <b>4</b>        | <b>15</b> |                 |                | <b>331.00</b>  | <b>1270.00</b> |                                                                 |
|         | <b>Total Maharashtra</b>                           | <b>12</b>       | <b>39</b> |                 |                | <b>2647.00</b> | <b>5113.36</b> |                                                                 |
|         | <b>CHHATISGARG</b>                                 |                 |           |                 |                |                |                |                                                                 |
|         | <b>CSPGCL</b>                                      |                 |           |                 |                |                |                |                                                                 |
|         | <b>State Sector</b>                                |                 |           |                 |                |                |                |                                                                 |
| 97      | Hasdeobango                                        | 1               | 3         | MP              | (3X40)         | 120.00         | 245.00         | 1994 (80 MW)<br>1995 (40 MW)                                    |
|         | <b>Total CSPGCL</b>                                | <b>1</b>        | <b>3</b>  |                 |                | <b>120.00</b>  | <b>245.00</b>  |                                                                 |
|         | <b>Total Chhatisgarh</b>                           | <b>1</b>        | <b>3</b>  |                 |                | <b>120.00</b>  | <b>245.00</b>  |                                                                 |
|         | <b>GUJARAT</b>                                     |                 |           |                 |                |                |                |                                                                 |
|         | <b>State Sector</b>                                |                 |           |                 |                |                |                |                                                                 |
|         | <b>GSECL</b>                                       |                 |           |                 |                |                |                |                                                                 |
| 96      | Ukai                                               | 1               | 4         | MP              | (4X75)         | 300.00         | 1080.00        | 1974 (150 MW)                                                   |

| Sl. No. | Names/Stations                   | No. of Stations | Units     | Type of Project | Capacity(MW) | (MW)           | Energy (MU)     | Year of Commissioning                                            |
|---------|----------------------------------|-----------------|-----------|-----------------|--------------|----------------|-----------------|------------------------------------------------------------------|
|         | <b>Conventional H E Stations</b> |                 |           |                 |              |                |                 |                                                                  |
|         | <b>Sub-Total GSECL</b>           | <b>1</b>        | <b>4</b>  |                 |              | <b>300.00</b>  | <b>1080.00</b>  |                                                                  |
|         | <b>SSNNL</b>                     |                 |           |                 |              |                |                 |                                                                  |
| 98      | Sardar Sarovar CHPH              | 1               | 5         | R(P)            | (5X50)       | 250.00         | 213.00          | 2004 (250 MW)                                                    |
|         | <b>Sub-Total SSNNL</b>           | <b>1</b>        | <b>5</b>  |                 |              | <b>250.00</b>  | <b>213.00</b>   |                                                                  |
|         | <b>Total Gujarat</b>             | <b>2</b>        | <b>9</b>  |                 |              | <b>550.00</b>  | <b>1293.00</b>  |                                                                  |
|         | <b>Total Western Region</b>      | <b>24</b>       | <b>88</b> |                 |              | <b>5552.00</b> | <b>12044.21</b> |                                                                  |
|         | <b>Southern Region</b>           |                 |           |                 |              |                |                 |                                                                  |
|         | <b>ANDHRA PRADESH</b>            |                 |           |                 |              |                |                 |                                                                  |
|         | <b>APGENCO</b>                   |                 |           |                 |              |                |                 |                                                                  |
|         | <b>State Sector</b>              |                 |           |                 |              |                |                 |                                                                  |
| 99      | Lower Sileru                     | 1               | 4         | S               | (4X115)      | 460.00         | 1070.00         | 1976 (230 MW)<br>1977 (115 MW)<br>1978 (115 MW)                  |
| 100     | N J Sagar RBC & EXT.             | 1               | 3         | MP              | (3X30)       | 90.00          | 156.00          | 1990 (30 MW)<br>1992 (60 MW)                                     |
| 101     | Srisaillam                       | 1               | 7         | MP              | (7X110)      | 770.00         | 2900.00         | 1982 (220 MW)<br>1983 (110 MW)<br>1984 (110 MW)<br>1986 (220 MW) |
| 102     | Upper Sileru-I&II                | 1               | 4         | S               | (4X60)       | 240.00         | 529.00          | 1994 (60 MW)<br>1995 (60 MW)                                     |
| 103     | N J Sagar TPD                    | 1               | 2         | R(P)            | (2X25)       | 50.00          | 177.00          | 2017 (50 MW)                                                     |
|         | <b>Total APGENCO</b>             | <b>5</b>        | <b>20</b> |                 |              | <b>1610.00</b> | <b>4832.00</b>  |                                                                  |
|         | <b>Total Andhra Pradesh</b>      | <b>5</b>        | <b>20</b> |                 |              | <b>1610.00</b> | <b>4832.00</b>  |                                                                  |
|         | <b>TELANGANA</b>                 |                 |           |                 |              |                |                 |                                                                  |
|         | <b>TSGENCO</b>                   |                 |           |                 |              |                |                 |                                                                  |
|         | <b>State Sector</b>              |                 |           |                 |              |                |                 |                                                                  |
| 105     | Priyadarshni Jurala              | 1               | 6         | R(P)            | (6X39)       | 234.00         | 404.00          | 2008 (78 MW)<br>2009 (39 MW)<br>2010 (78 MW)<br>2011 (39 MW)     |
| 106     | Pochampad                        | 1               | 4         | MP              | (4X9)        | 36.00          | 147.00          | 1987-1988, 2010                                                  |
| 107     | N J Sagar                        | 1               | 1         | MP              | (1X110)      | 110.00         |                 | 1978 (110 MW)                                                    |
| 108     | N J Sagar LBC                    | 1               | 2         | R               | (2X30)       | 60.00          | 104.00          | 1983 (60 MW)                                                     |
| 109     | Lower Jurala                     | 1               | 6         | R(P)            | (6X40)       | 240.00         | 534.43          | 2015 (80 MW)<br>2016 (160 MW)                                    |
| 110     | Pulinchinthala                   | 1               | 4         | R(P)            | (4X30)       | 120.00         | 219.42          | 2016 (60 MW)<br>2017 (60 MW)                                     |
|         | <b>Total TSGENCO</b>             | <b>6</b>        | <b>23</b> |                 |              | <b>800.00</b>  | <b>1408.85</b>  |                                                                  |
|         | <b>Total Telangana</b>           | <b>6</b>        | <b>23</b> |                 |              | <b>800.00</b>  | <b>1408.85</b>  |                                                                  |
|         | <b>KARNATAKA</b>                 |                 |           |                 |              |                |                 |                                                                  |
|         | <b>KPCL</b>                      |                 |           |                 |              |                |                 |                                                                  |
|         | <b>State Sector</b>              |                 |           |                 |              |                |                 |                                                                  |

| Sl. No. | Names/Stations                   | No. of Stations | Units     | Type of Project | Capacity(MW )   | (MW)           | Energy (MU)     | Year of Commissioning                                                                                                         |
|---------|----------------------------------|-----------------|-----------|-----------------|-----------------|----------------|-----------------|-------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Conventional H E Stations</b> |                 |           |                 |                 |                |                 |                                                                                                                               |
| 111     | Almatti                          | 1               | 6         | MP              | (5X55)+(1X15)   | 290.00         | 483.00          | 2004 (70 MW)<br>2005 (220 MW)                                                                                                 |
| 112     | Gerusoppa(Sharavathy Tail Race)  | 1               | 4         | R(P)            | (4X60)          | 240.00         | 622.00          | 2001 (180 MW)<br>2002 (60 MW)                                                                                                 |
| 113     | Ghat Prabha                      | 1               | 2         | MP              | (2X16)          | 32.00          | 131.00          | 1992 (32 MW)                                                                                                                  |
| 114     | Mahatma Gandhi (Jog)             | 1               | 8         | S               | X21.6)+(4X13.2) | 139.20         | 118.00          | 1949 (26.4 MW)<br>1950 (13.2 MW)<br>1952 (65 MW)<br>2001 (13.2 MW)<br>2002 (21.6 MW)                                          |
| 115     | Kadra                            | 1               | 3         | S               | (3X50)          | 150.00         | 570.00          | 1997 (50 MW)<br>1999 (100 MW)                                                                                                 |
| 116     | Kalinadi (Nagihari)              | 1               | 6         | S               | (6X150)         | 900.00         | 3385.00         | 1979 (135 MW)<br>1980 (135 MW)<br>1981 (135 MW)<br>1982 (135 MW)<br>1983 (135 MW)                                             |
| 117     | Kalinadi (Supa)                  | 1               | 2         | S               | (2X50)          | 100.00         | 542.00          | 1985 (100 MW)                                                                                                                 |
| 118     | Kodasali                         | 1               | 3         | S               | (3X40)          | 120.00         | 512.00          | 1998 (40 MW)<br>1999 (80 MW)                                                                                                  |
| 119     | Lingnamakki                      | 1               | 2         | S               | (2X27.5)        | 55.00          | 254.00          | 1979 (27.5 MW)<br>1980 (27.5 MW)                                                                                              |
| 120     | Munirabad                        | 1               | 3         | MP              | (2X9)+(1X10)    | 28.00          | 66.00           | 1962 (18 MW)<br>1965 (10 MW)                                                                                                  |
| 121     | Sharavathy                       | 1               | 10        | S               | (10X103.5)      | 1035.00        | 4932.00         | 1964 (103.5 MW)<br>1965 (103.5 MW)<br>1967 (207 MW)<br>1968 (311 MW)<br>1971 (103.5 MW)<br>1976 (103.5 MW)<br>1977 (103.5 MW) |
| 122     | Sivasamundrum                    | 1               | 10        | R(P)            | (4X6)+(6X3)     | 42.00          | 183.00          | 1922 (3 MW)<br>1923 (3 MW)<br>1924 (9 MW)<br>1925 (3 MW)                                                                      |
| 123     | Varahi                           | 1               | 4         | R(P)            | (4X115)         | 460.00         | 1060.00         | 1989 (115 MW)<br>1990 (115 MW)<br>2009 (230 MW)                                                                               |
| 124     | Bhadra                           | 1               | 3         | MP              | (2x12)+(1x2)    | 26.00          | 123.00          | 1965 (26 MW)                                                                                                                  |
|         | <b>Total KPCL</b>                | <b>14</b>       | <b>66</b> |                 |                 | <b>3617.20</b> | <b>12981.00</b> |                                                                                                                               |
|         | <b>APGENCO</b>                   |                 |           |                 |                 |                |                 |                                                                                                                               |
| 125     | T B Dam                          | 1               | 4         | MP              | (4X9)           | 36.00          | 236.00          | 1957 (18 MW)<br>1964 (18 MW)                                                                                                  |
| 126     | Hampi                            | 1               | 4         | MP              | (4X9)           | 36.00          |                 | 1958 (18 MW)<br>1964 (18 MW)                                                                                                  |
|         | <b>Sub-Total APGENCO</b>         | <b>2</b>        | <b>8</b>  |                 |                 | <b>72.00</b>   | <b>236.00</b>   |                                                                                                                               |
|         | <b>Total Karnataka</b>           | <b>16</b>       | <b>74</b> |                 |                 | <b>3689.20</b> | <b>13217.00</b> |                                                                                                                               |
|         | <b>KERALA</b>                    |                 |           |                 |                 |                |                 |                                                                                                                               |
|         | <b>KSEB</b>                      |                 |           |                 |                 |                |                 |                                                                                                                               |
|         | <b>State Sector</b>              |                 |           |                 |                 |                |                 |                                                                                                                               |
| 127     | Idamalayar                       | 1               | 2         | MP              | (2X37.5)        | 75.00          | 380.00          | 1987 (75 MW)                                                                                                                  |

| Sl. No. | Names/Stations                   | No. of Stations | Units     | Type of Project | Capacity(MW)  | (MW)           | Energy (MU)    | Year of Commissioning                                           |
|---------|----------------------------------|-----------------|-----------|-----------------|---------------|----------------|----------------|-----------------------------------------------------------------|
|         | <b>Conventional H E Stations</b> |                 |           |                 |               |                |                |                                                                 |
| 128     | Idukki                           | 1               | 6         | MP              | (6X130)       | 780.00         | 2398.00        | 1976 (390 MW)<br>1985 (130 MW)<br>1986 (260 MW)                 |
| 129     | Kakkad                           | 1               | 2         | R(P)            | (2X25)        | 50.00          | 262.00         | 1999 (50 MW)                                                    |
| 130     | Kuttiyadi                        | 1               | 3         | MP              | (3X25)        | 75.00          | 323.00         | 1972 (75 MW)                                                    |
| 131     | Kuttiyadi Extn.                  | 1               | 1         | MP              | (1X50)        | 50.00          |                | 2001 (50 MW)                                                    |
| 132     | Kuttiyadi Additional Extn.       | 1               | 2         | MP              | (2X50)        | 100.00         |                | 2010 (100 MW)                                                   |
| 133     | Lower Periyar                    | 1               | 3         | R(P)            | (3X60)        | 180.00         | 493.00         | 1997 (180 MW)                                                   |
| 134     | Nariamangalam                    | 1               | 3         | S               | (3X15)        | 45.00          | 237.00         | 1961 (30 MW)<br>1963 (15 MW)                                    |
| 135     | Pallivasal                       | 1               | 6         | S               | (3X5)+(3X7.5) | 37.50          | 284.00         | 1948 (7.5 MW)<br>1949 (7.5 MW)<br>1951 (7.5 MW)<br>2001 (15 MW) |
| 136     | Panniar                          | 1               | 2         | S               | (2X15)        | 30.00          | 158.00         | 1963 (15 MW)<br>2001 (15 MW)                                    |
| 137     | Poringalkuttu                    | 1               | 4         | S               | (4X8)         | 32.00          | 170.00         | 1957 (8 MW)<br>1958 (8 MW)<br>1959 (8 MW)<br>1960 (8 MW)        |
| 138     | Sabirigiri                       | 1               | 6         | S               | (6X50)        | 300.00         | 1338.00        | 1960 (150 MW)<br>1967 (150 MW)                                  |
| 139     | Sengulam                         | 1               | 4         | S               | (4X12)        | 48.00          | 182.00         | 1954 (24 MW)<br>2001 (24 MW)                                    |
| 140     | Sholayar                         | 1               | 3         | S               | (3X18)        | 54.00          | 233.00         | 1956 (18 MW)<br>1968 (36 MW)                                    |
|         | <b>Total KSEB</b>                | <b>14</b>       | <b>47</b> |                 |               | <b>1856.50</b> | <b>6458.00</b> |                                                                 |
|         | <b>Total Kerala</b>              | <b>14</b>       | <b>47</b> |                 |               | <b>1856.50</b> | <b>6458.00</b> |                                                                 |
|         | <b>TAMILNADU</b>                 |                 |           |                 |               |                |                |                                                                 |
|         | <b>TANGEDCO</b>                  |                 |           |                 |               |                |                |                                                                 |
| 141     | Aliyar                           | 1               | 1         | MP              | (1X60)        | 60.00          | 175.00         | 1970 (60 MW)                                                    |
| 142     | Bhavani Kattalai Barrage-I       | 1               | 2         | R(P)            | (2X15)        | 30.00          | 90.00          | 2006 (30 MW)                                                    |
| 143     | Bhavani Kattalai Barrage-II      | 1               | 2         | R(P)            | (2X15)        | 30.00          | 100.00         | 2013 (30 MW)                                                    |
| 144     | Bhavani Kattalai Barrage-III     | 1               | 2         | R(P)            | (2X15)        | 30.00          | 80.00          | 2012 (15 MW)<br>2013 (15 MW)                                    |
| 145     | Kodayar-I                        | 1               | 1         | MP              | (1X60)        | 60.00          | 165.00         | 1970 (60 MW)                                                    |
| 146     | Kodayar-I                        | 1               | 1         | MP              | (1X40)        | 40.00          |                | 1971 (40 MW)                                                    |
| 147     | Kundah-I                         | 1               | 3         | S               | (3X20)        | 60.00          | 1387.00        | 1960 (40 MW)<br>1964 (20 MW)                                    |
| 148     | Kundah-II                        | 1               | 5         | S               | (5X35)        | 175.00         |                | 1960 (35 MW)<br>1961 (105 MW)<br>1964 (35 MW)                   |
| 149     | Kundah-III                       | 1               | 3         | S               | (3X60)        | 180.00         |                | 1965 (120 MW)<br>1978 (60 MW)                                   |
| 150     | Kundah-IV                        | 1               | 2         | S               | (2X50)        | 100.00         |                | 1966 (50 MW)<br>1978 (50 MW)                                    |
| 151     | Kundah-V                         | 1               | 2         | S               | (2X20)        | 40.00          |                | 1964 (20 MW)<br>1988 (20 MW)                                    |
| 152     | Lower Mettur-I                   | 1               | 2         | R(P)            | (2X15)        | 30.00          |                | 1988 (30 MW)                                                    |

| Sr.No. | Names/Stations                   | No. of Stations | Units      | Type of Project | Capacity(MW )         | (MW)           | Energy (MU)     | Year of Commissioning                                         |
|--------|----------------------------------|-----------------|------------|-----------------|-----------------------|----------------|-----------------|---------------------------------------------------------------|
|        | <b>Conventional H E Stations</b> |                 |            |                 |                       |                |                 |                                                               |
| 153    | Lower Mettur-II                  | 1               | 2          | R(P)            | (2X15)                | 30.00          | 252.00          | 1988 (30 MW)                                                  |
| 154    | Lower Mettur-III                 | 1               | 2          | R(P)            | (2X15)                | 30.00          |                 | 1987 (15 MW)<br>1988 (15 MW)                                  |
| 155    | Lower Mettur-IV                  | 1               | 2          | R(P)            | (2X15)                | 30.00          |                 | 1989 (15 MW)<br>1988 (15 MW)                                  |
| 156    | Mettur Dam                       | 1               | 4          | MP              | (4X12.5)              | 50.00          | 541.00          | 1937 (25 MW)<br>1938 (12.5 MW)<br>1946 (12.5 MW)              |
| 157    | Mettur Tunnel                    | 1               | 4          | MP              | (4X50)                | 200.00         |                 | 1965 (50 MW)<br>1966 (150 MW)                                 |
| 158    | Moyar                            | 1               | 3          | S               | (3X12)                | 36.00          | 115.00          | 1952 (24 MW)<br>1953 (12 MW)                                  |
| 159    | Papanasam                        | 1               | 4          | MP              | (4X8)                 | 32.00          | 105.00          | 1944 (16 MW)<br>1945 (8 MW)<br>1951 (8 MW)                    |
| 160    | Parson's Valley                  | 1               | 1          | S               | (1X30)                | 30.00          | 53.00           | 2000 (30 MW)                                                  |
| 161    | Periyar                          | 1               | 4          | MP              | (3X42)+(1X35)         | 161.00         | 409.00          | 1958 (35 MW)<br>1959 (70 MW)<br>1965 (35 MW)                  |
| 162    | Pykara                           | 1               | 6          | S               | (3X7)+(2X13.6)+(1X11) | 59.20          | 274.00          | 1932 (14 MW)<br>1933 (7 MW)<br>1939 (11 MW)<br>1954 (27.2 MW) |
| 163    | Pykara Ultimate                  | 1               | 3          | S               | (3X50)                | 150.00         | 30.00           | 2005 (150 MW)                                                 |
| 164    | Sarakarpathy                     | 1               | 1          | R(P)            | (1X30)                | 30.00          | 162.00          | 1966 (30 MW)                                                  |
| 165    | Sholayar-I                       | 1               | 2          | S               | (2X35)                | 70.00          | 254.00          | 1971 (70 MW)                                                  |
| 166    | Suruliyar                        | 1               | 1          | S               | (1X35)                | 35.00          | 79.00           | 1978 (35 MW)                                                  |
|        | <b>Total TANGEDCO</b>            | <b>26</b>       | <b>65</b>  |                 |                       | <b>1778.20</b> | <b>4271.00</b>  |                                                               |
|        | <b>Total Tamilnadu</b>           | <b>26</b>       | <b>65</b>  |                 |                       | <b>1778.20</b> | <b>4271.00</b>  |                                                               |
|        | <b>Total Southern Region</b>     | <b>67</b>       | <b>229</b> |                 |                       | <b>9733.90</b> | <b>30186.85</b> |                                                               |
|        | <b>Eastern Region</b>            |                 |            |                 |                       |                |                 |                                                               |
|        | <b>WEST BENGAL</b>               |                 |            |                 |                       |                |                 |                                                               |
|        | <b>DVC</b>                       |                 |            |                 |                       |                |                 |                                                               |
| 167    | Maithon                          | 1               | 3          | MP              | 1X23.2)+(2X20         | 63.20          | 137.00          | 1957 (20 MW)<br>1958 (43.2 MW)                                |
|        | <b>Sub-Total DVC</b>             | <b>1</b>        | <b>3</b>   |                 |                       | <b>63.20</b>   | <b>137.00</b>   |                                                               |
|        | <b>NHPC</b>                      |                 |            |                 |                       |                |                 |                                                               |
| 168    | Teesta Low Dam-III               | 1               | 4          | R(P)            | (4X33)                | 132.00         | 594.00          | 2013 (132 MW)                                                 |
| 169    | Teesta Low Dam-IV                | 1               | 4          | R(P)            | (4X40)                | 160.00         | 719.67          | 2016 (120 MW)                                                 |
|        | <b>Sub Total NHPC</b>            | <b>2</b>        | <b>8</b>   |                 |                       | <b>292.00</b>  | <b>1313.67</b>  |                                                               |
|        | <b>Sub-Total Central</b>         | <b>3</b>        | <b>11</b>  |                 |                       | <b>355.20</b>  | <b>1450.67</b>  |                                                               |
|        | <b>WBSEDCL</b>                   |                 |            |                 |                       |                |                 |                                                               |
| 170    | Jaldhaka                         | 1               | 4          | R(P)            | (4X9)                 | 36.00          | 165.00          | 1967 (18 MW)<br>1972 (9 MW)                                   |
| 171    | Rammam                           | 1               | 4          | R               | (4X12.5)              | 50.00          | 210.00          | 1995 (25 MW)<br>1996 (25 MW)                                  |
|        | <b>Sub-Total WBSEDCL</b>         | <b>2</b>        | <b>8</b>   |                 |                       | <b>86.00</b>   | <b>375.00</b>   |                                                               |
|        | <b>Total West Bengal</b>         | <b>5</b>        | <b>19</b>  |                 |                       | <b>441.20</b>  | <b>1825.67</b>  |                                                               |
|        | <b>SIKKIM</b>                    |                 |            |                 |                       |                |                 |                                                               |
|        | <b>NHPC</b>                      |                 |            |                 |                       |                |                 |                                                               |
| 172    | Rangit                           | 1               | 3          | R(P)            | (3X20)                | 60.00          | 338.61          | 2000 (60 MW)                                                  |
| 173    | Teesta-V                         | 1               | 3          | R(P)            | (3X170)               | 510.00         | 2572.70         | 2008 (510 MW)                                                 |
|        | <b>Sub-Total NHPC</b>            | <b>2</b>        | <b>6</b>   |                 |                       | <b>570.00</b>  | <b>2911.31</b>  |                                                               |
|        | <b>State Sector</b>              |                 |            |                 |                       |                |                 |                                                               |
|        | <b>Teesta Urja Ltd.</b>          |                 |            |                 |                       |                |                 |                                                               |
| 174    | Teesta-III                       | 1               | 6          | R(P)            | (6X200)               | 1200.00        | 5214.00         | 2017 (1200 MW)                                                |

| Sl.No. | Names/Stations                                        | No. of Stations | Units     | Type of Project | Capacity(MW)                       | (MW)           | Energy (MU)     | Year of Commissioning                                         |
|--------|-------------------------------------------------------|-----------------|-----------|-----------------|------------------------------------|----------------|-----------------|---------------------------------------------------------------|
|        | <b>Conventional H E Stations</b>                      |                 |           |                 |                                    |                |                 |                                                               |
|        | <b>Sub-Total TUL</b>                                  | <b>1</b>        | <b>6</b>  |                 |                                    | <b>1200.00</b> | <b>5214.00</b>  |                                                               |
|        | <b>Private</b>                                        |                 |           |                 |                                    |                |                 |                                                               |
|        | <b>GIPL (Gati Infra Pvt. Ltd.)</b>                    |                 |           |                 |                                    |                |                 |                                                               |
| 175    | Chujachen                                             | 1               | 2         | R(P)            | (2*55)                             | 110.00         | 537.81          | 2013 (110 MW)                                                 |
|        | <b>Sneha Kinetic Power Projects Pvt. Ltd.(SKPPPL)</b> |                 |           |                 |                                    |                |                 |                                                               |
| 176    | Dikchu                                                | 1               | 2         | R(P)            | (2*48)                             | 96.00          | 431.00          | 2017 (96 MW)                                                  |
|        | <b>Shiga Energy Pvt. Ltd.(SEPL)</b>                   |                 |           |                 |                                    |                |                 |                                                               |
| 177    | Tashiding                                             | 1               | 2         | R(P)            | (2*48.50)                          | 97.00          | 425.05          | 2017 (97 MW)                                                  |
|        | <b>DANS Energy Pvt. Ltd. (DEPL)</b>                   |                 |           |                 |                                    |                |                 |                                                               |
| 178    | Jorethang Loop                                        | 1               | 2         | R(P)            | (2*48)                             | 96.00          | 459.02          | 2015 (96 MW)                                                  |
|        | <b>MBPC</b>                                           |                 |           |                 |                                    |                |                 |                                                               |
| 179    | Rongnichu                                             | 1               | 2         | R               | (2X56.5)                           | 113.00         | 434.00          | 2021 (113 MW)                                                 |
|        | <b>Sub-Total Private</b>                              | <b>5</b>        | <b>10</b> |                 |                                    | <b>512.00</b>  | <b>2286.88</b>  |                                                               |
|        | <b>Total Sikkim</b>                                   | <b>8</b>        | <b>22</b> |                 |                                    | <b>2282.00</b> | <b>10412.19</b> |                                                               |
|        | <b>JAHARKHAND</b>                                     |                 |           |                 |                                    |                |                 |                                                               |
| 180    | Panchet                                               | 1               | 2         | MP              | (2X40)                             | 80.00          | 237.00          | 1959 (40 MW)                                                  |
|        | <b>Sub-Total DVC</b>                                  | <b>1</b>        | <b>2</b>  |                 |                                    | <b>80.00</b>   | <b>237.00</b>   |                                                               |
|        | <b>JUUNL</b>                                          |                 |           |                 |                                    |                |                 |                                                               |
| 181    | Subernrekha-I                                         | 1               | 1         | MP              | (1X65)                             | 65.00          | 149.00          | 1977 (65 MW)                                                  |
| 182    | Subernrekha-II                                        | 1               | 1         | R(P)            | (1X65)                             | 65.00          |                 | 1980 (65 MW)                                                  |
|        | <b>Total JUUNL</b>                                    | <b>2</b>        | <b>2</b>  |                 |                                    | <b>130.00</b>  | <b>149.00</b>   |                                                               |
|        | <b>Total Jharkhand</b>                                | <b>3</b>        | <b>4</b>  |                 |                                    | <b>210.00</b>  | <b>386.00</b>   |                                                               |
|        | <b>ODISHA</b>                                         |                 |           |                 |                                    |                |                 |                                                               |
|        | <b>OHPC</b>                                           |                 |           |                 |                                    |                |                 |                                                               |
| 183    | Balimela                                              | 1               | 8         | MP              | (6X60)+(2X75)                      | 510.00         | 1183.00         | 1973 (60 MW)<br>1974 (120 MW)<br>1975 (60 MW)<br>1976 (60 MW) |
| 184    | Hirakud (Burla)                                       | 1               | 7         | MP              | (2X43.65)+(1X37.5)+(2X49.5)+(2X32) | 287.80         | 684.00          | 1956 (32 MW)<br>1957 (81.5 MW)                                |
| 185    | Hirakud (Chiplima)                                    | 1               | 3         | R(P)            | (3X24)                             | 72.00          | 490.00          | 1962 (48 MW)<br>1964 (24 MW)                                  |
| 186    | Rengali                                               | 1               | 5         | MP              | (5X50)                             | 250.00         | 525.00          | 1985 (50 MW)<br>1986 (50 MW)<br>1989 (50 MW)                  |
| 187    | Upper Indravati                                       | 1               | 4         | MP              | (4X150)                            | 600.00         | 1962.00         | 1999 (300 MW)<br>2000 (150 MW)<br>2001 (150 MW)               |
| 188    | Upper Kolab                                           | 1               | 4         | MP              | (4X80)                             | 320.00         | 832.00          | 1988 (160 MW)<br>1990 (80 MW)                                 |
|        | <b>Total OHPC</b>                                     | <b>6</b>        | <b>31</b> |                 |                                    | <b>2039.80</b> | <b>5676.00</b>  |                                                               |
|        | <b>APGENCO</b>                                        |                 |           |                 |                                    |                |                 |                                                               |
| 186    | Machkund                                              | 1               | 6         | S               | (3X17)+(3X21.25)                   | 114.75         | 670.00          | 1955 (34 MW)<br>1956 (17 MW)<br>1959 (63.75 MW)               |
|        | <b>Sub-Total APGENCO</b>                              | <b>1</b>        | <b>6</b>  |                 |                                    | <b>114.75</b>  | <b>670</b>      |                                                               |
|        | <b>Total Odisha</b>                                   | <b>7</b>        | <b>37</b> |                 |                                    | <b>2154.55</b> | <b>6346</b>     |                                                               |
|        | <b>Total Eastern Region</b>                           | <b>23</b>       | <b>82</b> |                 |                                    | <b>5087.75</b> | <b>18969.86</b> |                                                               |
|        | <b>North Eastern Region</b>                           |                 |           |                 |                                    |                |                 |                                                               |
|        | <b>ARUNACHAL PRADESH</b>                              |                 |           |                 |                                    |                |                 |                                                               |
|        | <b>NEEPCO</b>                                         |                 |           |                 |                                    |                |                 |                                                               |
| 187    | Ranganadi                                             | 1               | 3         | R(P)            | (3X135)                            | 405.00         | 1509.66         | 2002 (405 MW)                                                 |
| 188    | Pare                                                  | 1               | 2         | R (P)           | (2X55)                             | 110.00         | 506.42          | 2018 (110 MW)                                                 |
| 189    | Kameng                                                | 1               | 4         | R (P)           | (3X150)                            | 600.00         | 3353.00         | 2020 (300 MW)                                                 |
|        | <b>Sub-Total NEEPCO Ar.P</b>                          | <b>3</b>        | <b>9</b>  |                 |                                    | <b>1115.00</b> | <b>5369.08</b>  |                                                               |
|        | <b>Total Arunachal Pradesh</b>                        | <b>3</b>        | <b>9</b>  |                 |                                    | <b>1115.00</b> | <b>5369.08</b>  |                                                               |
|        | <b>ASSAM</b>                                          |                 |           |                 |                                    |                |                 |                                                               |
|        | <b>NEEPCO</b>                                         |                 |           |                 |                                    |                |                 |                                                               |

| Sl. No. | Names/Stations                   | No. of Stations | Units      | Type of Project | Capacity(MW) | (MW)            | Energy (MU)      | Year of Commissioning                         |
|---------|----------------------------------|-----------------|------------|-----------------|--------------|-----------------|------------------|-----------------------------------------------|
|         | <b>Conventional H E Stations</b> |                 |            |                 |              |                 |                  |                                               |
| 190     | Kopoli                           | 1               | 4          | S               | (4X50)       | 200.00          | 1186.14          | 1988 (100 MW)<br>1996 (50 MW)<br>1997 (50 MW) |
| 191     | Khondong                         | 1               | 2          | S               | (2X25)       | 50.00           | 363.95           | 1984 (50 MW)                                  |
|         | <b>Sub-Total NEEPCO Assam</b>    | <b>2</b>        | <b>6</b>   |                 |              | <b>250.00</b>   | <b>1550.09</b>   |                                               |
|         | <b>APGCL</b>                     |                 |            |                 |              |                 |                  |                                               |
| 192     | Karbi Langpi                     | 1               | 2          | R(P)            | (2X50)       | 100.00          | 390.00           | 2007 (100 MW)                                 |
|         | <b>Sub-Total APGCL</b>           | <b>1</b>        | <b>2</b>   |                 |              | <b>100.00</b>   | <b>390.00</b>    |                                               |
|         | <b>Total Assam</b>               | <b>3</b>        | <b>8</b>   |                 |              | <b>350.00</b>   | <b>1940.09</b>   |                                               |
|         | <b>MIZORAM</b>                   |                 |            |                 |              |                 |                  |                                               |
|         | <b>NEEPCO</b>                    |                 |            |                 |              |                 |                  |                                               |
| 193     | Tuirial                          | 1               | 2          | S               | (2X30)       | 60.00           | 250.63           | 2017 (60 MW)                                  |
|         | <b>Total NEEPCO Mizoram</b>      | <b>1</b>        | <b>2</b>   |                 |              | <b>60.00</b>    | <b>250.63</b>    |                                               |
|         | <b>Total Mizoram</b>             | <b>1</b>        | <b>2</b>   |                 |              | <b>60.00</b>    | <b>250.63</b>    |                                               |
|         | <b>NAGALAND</b>                  |                 |            |                 |              |                 |                  |                                               |
|         | <b>NEEPCO</b>                    |                 |            |                 |              |                 |                  |                                               |
| 194     | Doyang                           | 1               | 3          | S               | (3X25)       | 75.00           | 227.24           | 2000 (75 MW)                                  |
|         | <b>Total-NEEPCO Nagaland</b>     | <b>1</b>        | <b>3</b>   |                 |              | <b>75.00</b>    | <b>227.24</b>    |                                               |
|         | <b>Total Nagaland</b>            | <b>1</b>        | <b>3</b>   |                 |              | <b>75.000</b>   | <b>227.240</b>   |                                               |
|         | <b>MANIPUR</b>                   |                 |            |                 |              |                 |                  |                                               |
|         | <b>NHPC</b>                      |                 |            |                 |              |                 |                  |                                               |
| 195     | Loktak                           | 1               | 3          | MP              | (3X35)       | 105.00          | 448.00           | 1983 (105 MW)                                 |
|         | <b>Sub-Total NHPC</b>            | <b>1</b>        | <b>3</b>   |                 |              | <b>105.00</b>   | <b>448.00</b>    |                                               |
|         | <b>Total Manipur</b>             | <b>1</b>        | <b>3</b>   |                 |              | <b>105.000</b>  | <b>448.000</b>   |                                               |
|         | <b>MEGHALAYA</b>                 |                 |            |                 |              |                 |                  |                                               |
|         | <b>MePGCL</b>                    |                 |            |                 |              |                 |                  |                                               |
| 196     | Kyrdemkulai                      | 1               | 2          | R(P)            | (2X30)       | 60.00           | 118.00           | 1979 (60 MW)                                  |
| 197     | Umiyam St. I                     | 1               | 4          | S               | (4X9)        | 36.00           | 128.00           | 1965 (36 MW)                                  |
| 198     | New Umetru                       | 1               | 2          | R(P)            | (2X20)       | 40.00           | 235.00           | 2017 (20 MW)                                  |
| 199     | Umiyam St. IV                    | 1               | 2          | R(P)            | (2X30)       | 60.00           | 324.00           | 1992 (60 MW)                                  |
| 200     | Myntdu St-I                      | 1               | 3          | R(P)            | (3X42)       | 126.00          | 372.69           | 2011 (84 MW)<br>2013 (42 MW)                  |
|         | <b>Total MePGCL</b>              | <b>5</b>        | <b>13</b>  |                 |              | <b>322.00</b>   | <b>1177.69</b>   |                                               |
|         | <b>Total Meghalaya</b>           | <b>5</b>        | <b>13</b>  |                 |              | <b>322.00</b>   | <b>1177.69</b>   |                                               |
|         | <b>Total NE Region</b>           | <b>14</b>       | <b>38</b>  |                 |              | <b>2027.00</b>  | <b>9412.73</b>   |                                               |
|         | <b>Total</b>                     | <b>203</b>      | <b>693</b> |                 |              | <b>41976.90</b> | <b>147104.30</b> |                                               |
|         | <b>Pumped Storage Schemes</b>    |                 |            |                 |              |                 |                  |                                               |
|         | <b>Western Region</b>            |                 |            |                 |              |                 |                  |                                               |
|         | <b>GUJARAT</b>                   |                 |            |                 |              |                 |                  |                                               |
|         | <b>State Sector</b>              |                 |            |                 |              |                 |                  |                                               |
|         | <b>GSECL</b>                     |                 |            |                 |              |                 |                  |                                               |
| 1       | Kadana                           | 1               | 4          | PSS             | (4X60)       | 240.00          | 518.00           | 1990 (120 MW)<br>1998 (120 MW)                |
|         | <b>SSNNL</b>                     |                 |            |                 |              |                 |                  |                                               |
| 2       | Sardar Sarovar RBPH              | 1               | 6          | PSS             | (6X200)      | 1200.00         | 3635.00          | 2005 (800 MW)<br>2006 (400 MW)                |
|         | <b>Total Gujarat</b>             | <b>2</b>        | <b>10</b>  |                 |              | <b>1440.00</b>  | <b>4153.00</b>   |                                               |
|         | <b>MAHARASHTRA</b>               |                 |            |                 |              |                 |                  |                                               |
|         | <b>State Sector</b>              |                 |            |                 |              |                 |                  |                                               |
|         | <b>MAHAGENCO</b>                 |                 |            |                 |              |                 |                  |                                               |
| 3       | Ghatgarh                         | 1               | 2          | PSS             | (2X125)      | 250.00          | 410.00           | 2008 (250 MW)                                 |
|         | <b>Private Sector</b>            |                 |            |                 |              |                 |                  |                                               |

| Sl. No. | Names/Stations                   | No. of Stations | Units      | Type of Project | Capacity(MW) | (MW)            | Energy (MU)      | Year of Commissioning                                                                                        |
|---------|----------------------------------|-----------------|------------|-----------------|--------------|-----------------|------------------|--------------------------------------------------------------------------------------------------------------|
|         | <b>Conventional H E Stations</b> |                 |            |                 |              |                 |                  |                                                                                                              |
|         | <b>Tata Power Company</b>        |                 |            |                 |              |                 |                  |                                                                                                              |
| 4       | Bhira                            | 1               | 1          | PSS             | (1X150)      | 150.00          |                  | 1927 (125 MW)<br>1949 (25 MW)                                                                                |
|         | <b>Sub-Total Maharashtra</b>     | <b>2</b>        | <b>3</b>   |                 |              | <b>400.00</b>   | <b>410.00</b>    |                                                                                                              |
|         | <b>Total Western Region</b>      | <b>4</b>        | <b>13</b>  |                 |              | <b>1840.00</b>  | <b>4563.00</b>   |                                                                                                              |
|         | <b>Southern Region</b>           |                 |            |                 |              |                 |                  |                                                                                                              |
|         | <b>TELANGANA</b>                 |                 |            |                 |              |                 |                  |                                                                                                              |
|         | <b>State Sector</b>              |                 |            |                 |              |                 |                  |                                                                                                              |
|         | <b>TSGENCO</b>                   |                 |            |                 |              |                 |                  |                                                                                                              |
| 5       | N J Sagar                        | 1               | 7          | PSS             | (7X100.8)    | 705.60          | 2237.00          | 1980 (100.8 MW)<br>1981 (100.8 MW)<br>1982 (100.8 MW)<br>1983 (100.8 MW)<br>1984 (100.8 MW)<br>1985 (202 MW) |
| 6       | Srisailem LBPG                   | 1               | 6          | PSS             | (6X150)      | 900.00          | 1400.00          | 2001 (300 MW)<br>2002 (450 MW)<br>2003 (150 MW)                                                              |
|         | <b>Sub-Total TELANGANA</b>       | <b>2</b>        | <b>13</b>  |                 |              | <b>1605.60</b>  | <b>3637.00</b>   |                                                                                                              |
|         | <b>TAMIL NADU</b>                |                 |            |                 |              |                 |                  |                                                                                                              |
| 7       | Kadamparai                       | 1               | 4          | PSS             | (4X100)      | 400.00          | 77.00            | 1987 (100 MW)<br>1988 (200 MW)<br>1989 (100 MW)                                                              |
|         | <b>Sub-Total TAMIL NADU</b>      | <b>1</b>        | <b>4</b>   |                 |              | <b>400.00</b>   | <b>77.00</b>     |                                                                                                              |
|         | <b>Total Southern Region</b>     | <b>3</b>        | <b>17</b>  |                 |              | <b>2005.60</b>  | <b>3714.00</b>   |                                                                                                              |
|         | <b>Eastern Region</b>            |                 |            |                 |              |                 |                  |                                                                                                              |
|         | <b>JHARKHAND</b>                 |                 |            |                 |              |                 |                  |                                                                                                              |
|         | <b>Central Sector</b>            |                 |            |                 |              |                 |                  |                                                                                                              |
| 8       | Panchet                          | 1               | 1          | PSS             | (1X40)       | 40.00           |                  | 1991 (40 MW)                                                                                                 |
|         | <b>WEST BENGAL</b>               |                 |            |                 |              |                 |                  |                                                                                                              |
|         | <b>State Sector</b>              |                 |            |                 |              |                 |                  |                                                                                                              |
|         | <b>WBSEDCL</b>                   |                 |            |                 |              |                 |                  |                                                                                                              |
| 9       | Purulia                          | 1               | 4          | PSS             | (4X225)      | 900.00          | 1235.00          | 2007                                                                                                         |
|         | <b>Sub-Total</b>                 | <b>1</b>        | <b>4</b>   |                 |              | <b>900.00</b>   | <b>1235.00</b>   |                                                                                                              |
|         | <b>Total- PSS</b>                | <b>8</b>        | <b>34</b>  |                 |              | <b>4745.60</b>  | <b>9512.00</b>   |                                                                                                              |
|         | <b>Total (Conventional+PSS)</b>  | <b>210</b>      | <b>727</b> |                 |              | <b>46722.50</b> | <b>156616.30</b> |                                                                                                              |

NOTE: Following Hydro Stations have conventional as well as PSS capacity:

| Sl. No. | Station   | State/Region           | Installed Capacity (MW) |                |
|---------|-----------|------------------------|-------------------------|----------------|
|         |           |                        | Conventional            | PSS            |
| 1       | N J Sagar | Telangana/<br>Southern | 1X110 =110              | 7X100.8=705.60 |

## CAPACITY-WISE GROUPING OF HYDRO-ELECTRIC STATIONS

As on 31.03.2022

| STATION CAPACITY | NUMBER OF STATIONS |            | NUMBER OF UNITS |            | TOTAL CAPACITY |            |
|------------------|--------------------|------------|-----------------|------------|----------------|------------|
| RANGE (MW)       | No                 | %          | No              | %          | MW             | %          |
| > 25 - 100       | 106                | 50.50      | 279             | 38.40      | 6236.1         | 13.30      |
| >100 - 500       | 77                 | 36.60      | 295             | 40.60      | 18253.7        | 39.10      |
| >500 - 1000      | 23                 | 11.00      | 125             | 17.20      | 17297.60       | 37.00      |
| >1000            | 4                  | 1.90       | 28              | 3.80       | 4935.00        | 10.60      |
| <b>TOTAL</b>     | <b>210</b>         | <b>100</b> | <b>727</b>      | <b>100</b> | <b>46722.4</b> | <b>100</b> |

**HYDRO GENERATING UNITS ADDED DURING 2021-22**

| SL. NO.         | NAME OF THE STATION | UTILITY | STATE            | UNIT NO. | CAPACITY (MW) | DATE OF COMMISSIONING |
|-----------------|---------------------|---------|------------------|----------|---------------|-----------------------|
| PRIVATE SECTOR  |                     |         |                  |          |               |                       |
| 1               | Rongnichu           | MBPC    | Sikkim           | 1.00     | 56.50         | 2021                  |
|                 |                     |         |                  | 1.00     | 56.50         |                       |
| 2               | Sorang              | HSPPL   | Himachal Pradesh | 1.00     | 50.00         | 2021                  |
|                 |                     |         |                  | 1.00     | 50.00         |                       |
| 3               | Bajoli Holi         | GMR     | Himachal Pradesh | 1.00     | 60.00         | March, 2022           |
|                 |                     |         |                  | 1.00     | 60.00         |                       |
|                 |                     |         |                  | 1.00     | 60.00         |                       |
| ALL INDIA TOTAL |                     |         |                  |          | 393           |                       |

# CHAPTER-2

## GENERATION PERFORMANCE

## CHAPTER-2

### GENERATION PERFORMANCE

**2.1** Generation from hydro-electric power stations (above 25 MW capacity) in the country during 2021-22 was 151.62 BU against the target of 149.54 BU which was 1.39% more than the target. The generation during 2021-22 was .88 % higher than the generation in 2020-21 i.e. 150.29 BU.

**2.2** The month-wise and cumulative generation from hydro stations in the country viz-a-viz targets have been shown at **Exhibit-2.1** and are given in **Table 2.1** below.

**TABLE 2.1**

#### MONTH-WISE & CUMULATIVE GENERATION VIS-À-VIS TARGET IN MU PERIOD: 2021-22

| Month     | APR   | MAY   | JUNE  | JULY  | AUG   | SEP   | OCT    | NOV    | DEC    | JAN    | FEB    | MAR    |
|-----------|-------|-------|-------|-------|-------|-------|--------|--------|--------|--------|--------|--------|
| Target    | 10402 | 13266 | 15341 | 17622 | 19342 | 17642 | 12757  | 9505   | 8548   | 8062   | 7796   | 9261   |
| Gen.      | 8266  | 11752 | 16008 | 18745 | 20270 | 17765 | 15535  | 9706   | 8066   | 7497   | 7433   | 10584  |
| Cum. Tar  | 10402 | 23668 | 39009 | 56631 | 75973 | 93615 | 106372 | 115877 | 124425 | 132487 | 140283 | 149544 |
| Cum. Gen. | 8266  | 20018 | 36026 | 54771 | 75041 | 92807 | 108341 | 118047 | 126113 | 133610 | 141043 | 151627 |

### **2.3 Utility-wise/ Sector-wise Performance of H.E. Stations**


The utility-wise/ sector-wise target of energy generation viz-a-viz actual generation and surplus /shortfall in respect of Hydro-electric stations during 2021-22 & 2020-21 are given below in **Table 2.2**.

**TABLE 2.2**


#### UTILITY-WISE PERFORMANCE OF HYDRO ELECTRIC STATIONS (2021-22 VIS-A-VIS 2020-21)

| Utilities      | Installed Capacity (MW)<br>(As on 31.03.2022) | Generation  |         |             |          |                                 |         |
|----------------|-----------------------------------------------|-------------|---------|-------------|----------|---------------------------------|---------|
|                |                                               | Target (MU) |         | Actual (MU) |          | Surplus (+)/ Shortfall (-) in % |         |
|                |                                               | 2021-22     | 2020-21 | 2021-22     | 2020-21  | 2021-22                         | 2020-21 |
| CENTRAL SECTOR |                                               |             |         |             |          |                                 |         |
| BBMB           | 2938.3                                        | 9650        | 9600    | 9794.82     | 11478    | 1.50                            | 19.56   |
| NHPC LTD       | 5451.2                                        | 26000       | 24542   | 24382.6     | 24084.69 | -6.22                           | -1.86   |
| SJVN LTD       | 1912.02                                       | 9111        | 8678    | 9048.61     | 9094.35  | -0.68                           | 4.80    |
| NTPC LTD       | 800                                           | 3100        | 3482    | 3120.14     | 3221.41  | 0.65                            | -7.48   |
| THDC LTD       | 1400                                          | 4160        | 4160    | 4288.75     | 4261.72  | 3.09                            | 2.45    |

MONTHLY ALL INDIA HYDRO GENERATION VS TARGETS  
DURING 2021-22



ALL INDIA CUMMULATIVE GENERATION VS TARGETS  
DURING 2021-22



| Utilities             | Installed Capacity (MW)<br>(As on 31.03.2020) | Generation   |              |                 |                 |                                    |             |
|-----------------------|-----------------------------------------------|--------------|--------------|-----------------|-----------------|------------------------------------|-------------|
|                       |                                               | Target (MU)  |              | Actual (MU)     |                 | Surplus (+)/<br>Shortfall (-) in % |             |
|                       |                                               | 2021-22      | 2020-21      | 2021-22         | 2020-21         | 2021-22                            | 2020-21     |
| NHDC                  | 1520                                          | 3900         | 2700         | 2645.41         | 4236.17         | -32.17                             | 56.90       |
| DVC                   | 143.2                                         | 215          | 206          | 466.89          | 365.47          | 117.16                             | 77.41       |
| NEEPCO LTD            | 1500                                          | 4908         | 4472         | 4674.39         | 3881.89         | -4.76                              | -13.20      |
| <b>TOTAL CENTRAL</b>  | <b>15664.72</b>                               | <b>61044</b> | <b>57840</b> | <b>58421.61</b> | <b>60623.7</b>  | <b>-4.30</b>                       | <b>4.81</b> |
| <b>PRIVATE SECTOR</b> |                                               |              |              |                 |                 |                                    |             |
| MPCL                  | 86.00                                         | 344          | 157          | 314.96          | 334.88          | -8.44                              | 113.30      |
| EPPL                  | 100.00                                        | 367          | 367          | 345.66          | 370.47          | -5.81                              | 0.95        |
| ADHPL                 | 192.00                                        | 676          | 692          | 637.44          | 640.53          | -5.70                              | -7.44       |
| GBHPPL                | 70.00                                         | 270          | 260          | 251.37          | 275.95          | -6.90                              | 6.13        |
| JSW ENERGY            | 1345.00                                       | 5431         | 5407         | 5563.8          | 5672.61         | 2.45                               | 4.91        |
| IAEPL                 | 36.00                                         | 158          | 273          | 146.54          | 159.35          | -7.25                              | -41.63      |
| AHPC LTD              | 330.00                                        | 1310         | 1310         | 1421.89         | 1438            | 8.54                               | 9.77        |
| JPVL                  | 400.00                                        | 1590         | 1438         | 1801.24         | 1778.42         | 13.29                              | 23.67       |
| DLHP                  | 34.00                                         | 36           | 36           | 33.94           | 34.29           | -5.72                              | -4.75       |
| GIPL                  | 110.00                                        | 500          | 500          | 514.21          | 488.37          | 2.84                               | -2.33       |
| TPCL                  | 447.00                                        | 1470         | 1470         | 1589.99         | 1524.7          | 8.16                               | 3.72        |
| DEPL                  | 96.00                                         | 408          | 408          | 424.69          | 399.92          | 4.09                               | -1.98       |
| SEPL                  | 97.00                                         | 421          | 421          | 453.07          | 369.75          | 7.62                               | -12.17      |
| SNEHA KINETIC         | 96.00                                         | 460          | 460          | 481.45          | 458.95          | 4.66                               | -0.23       |
| NTPGPL                | 0.00                                          | 0            | 344          | 0               | 0               | 0                                  | 0           |
| HSPPL                 | 100.00                                        | 39           | 0            | 57.18           | 0               | 46.62                              | 0           |
| L&T                   | 99.00                                         | 293          | 145          | 80.44           | 0               | -72.55                             | -100.00     |
| GMR                   | 180                                           | 273          | 39           | 0               | 0               | -100.00                            | -100.00     |
| MBPC                  | 113.00                                        | 256          | 22           | 295.43          | 0               | 15.40                              | -100.00     |
| <b>TOTAL PRIVATE</b>  | <b>3931.00</b>                                | <b>14302</b> | <b>13749</b> | <b>14413.3</b>  | <b>13946.19</b> | <b>0.78</b>                        | <b>1.43</b> |
| <b>STATE SECTOR</b>   |                                               |              |              |                 |                 |                                    |             |
| JKSPDCL               | 1110                                          | 4887         | 4915         | 5116.09         | 4940.83         | 4.69                               | 0.53        |
| HPPCL                 | 406                                           | 821          | 805          | 649.55          | 437.76          | -20.88                             | -45.62      |
| HPSEBL                | 372                                           | 1603         | 1602         | 1768.66         | 1564.35         | 10.33                              | -2.35       |
| BVPC                  | 0                                             | 0            | 272          | 0               | 0               |                                    | -100.00     |
| RRVUNL                | 411                                           | 370          | 340          | 481.84          | 469.63          | 30.23                              | 38.13       |
| PSPCL                 | 1051                                          | 3969         | 3805         | 3007.86         | 3951            | -24.22                             | 3.84        |
| UPJVNL                | 501.6                                         | 1519         | 1115         | 1402.68         | 1572.35         | -7.66                              | 41.02       |
| UJVNL                 | 1252.15                                       | 4612         | 4410         | 4987.18         | 4487.97         | 8.13                               | 1.77        |

| Utilities              | Installed Capacity (MW)<br>(As on 31.03.2020) | Generation    |               |                  |                 |                                    |              |
|------------------------|-----------------------------------------------|---------------|---------------|------------------|-----------------|------------------------------------|--------------|
|                        |                                               | Target (MU)   |               | Actual (MU)      |                 | Surplus (+)/<br>Shortfall (-) in % |              |
|                        |                                               | 2021-22       | 2020-21       | 2021-22          | 2020-21         | 2021-22                            | 2020-21      |
| SSNNL                  | 1450                                          | 2832          | 3200          | 1748.01          | 3245.24         | -38.28                             | 1.41         |
| GSECL                  | 540                                           | 889           | 754           | 873.5            | 988.12          | -1.74                              | 31.05        |
| MAHAGENCO              | 2406                                          | 4109          | 3755          | 4078.97          | 3574.57         | -0.73                              | -4.81        |
| MPPGCL                 | 875                                           | 2526          | 2092          | 2345.79          | 2656.06         | -7.13                              | 26.96        |
| CSPGCL                 | 120                                           | 280           | 250           | 404.13           | 419.19          | 44.33                              | 67.68        |
| APGENCO                | 1796.75                                       | 3636          | 3174          | 4037.32          | 4129.94         | 11.04                              | 30.12        |
| TSGENCO                | 2405.6                                        | 4018          | 3211          | 5626.63          | 3645.38         | 40.04                              | 13.53        |
| KPCL                   | 3617.2                                        | 12409         | 11468         | 13731.48         | 12403.59        | 10.66                              | 8.16         |
| KSEBL                  | 1856.5                                        | 6505          | 5900          | 9317.44          | 6628.39         | 43.24                              | 12.35        |
| TANGEDCO               | 2178.2                                        | 4483          | 4040          | 5212.07          | 5212.71         | 16.26                              | 29.03        |
| JUUNL                  | 130                                           | 110           | 110           | 302.49           | 50              | 174.99                             | -54.55       |
| OHPC                   | 2039.80                                       | 5959          | 5372          | 4512.12          | 6193.91         | -24.28                             | 15.30        |
| TUL                    | 1200                                          | 5652          | 5300          | 6315.53          | 6043.98         | 11.74                              | 14.04        |
| WBSEDCL                | 986                                           | 1578          | 1578          | 1630.14          | 1759.64         | 3.30                               | 11.51        |
| APGCL                  | 100                                           | 380           | 380           | 401.12           | 203.03          | 5.56                               | -46.57       |
| MePGCL                 | 322                                           | 1051          | 920           | 841.82           | 1151.99         | -19.90                             | 25.22        |
| <b>TOTAL STATE</b>     | <b>27126.80</b>                               | <b>74198</b>  | <b>68768</b>  | <b>78792.42</b>  | <b>75729.63</b> | <b>6.19</b>                        | <b>10.12</b> |
| <b>TOTAL ALL INDIA</b> | <b>46722.52</b>                               | <b>149544</b> | <b>140357</b> | <b>151627.33</b> | <b>150299.5</b> | <b>1.39</b>                        | <b>7.08</b>  |

During the year 2021-22, overall hydro generation was more than the target in respect of BBMB, THDC & DVC in Central Sector and JSW Energy, AHPCL, JPVL, GIPL, TPCL, SEPL, DEPL, HSPPL, MBPC and SNEHA KINETIC in Private Sector. As regards, generation by State Electricity Boards/Corporations / Departments, hydro generation was more than the target in respect of JKSPDCL, HPSEBL, PSPCL, UJVNL, CSPGCL, APGENCO, TSGENCO, KPCL, KBSEBL, TANGEDCO, TUL, and WBSEDCL.

## 2.4 Region-wise Performance of H.E. Stations

Region-wise generation performance of hydroelectric stations during 2021-22 is indicated in **Table 2.3**.

**TABLE 2.3**  
**GENERATION PERFORMANCE – REGION-WISE**  
**(2021-22)**

| S. No. | Region                   | Installed Capacity as on 31.03.2022 (MW) | Generation During 2021-22 |                  |                                            |
|--------|--------------------------|------------------------------------------|---------------------------|------------------|--------------------------------------------|
|        |                          |                                          | Target (MU)               | Actual (MU)      | Shortfall (-)/ Surplus (+) Over Target (%) |
| 1      | Northern                 | 19576.25                                 | 75684.00                  | 73866.02         | -2.40                                      |
| 2      | Western                  | 7392                                     | 16042.00                  | 13719.74         | -14.48                                     |
| 3      | Southern                 | 11739.5                                  | 30439.00                  | 37206.43         | 22.23                                      |
| 4      | Eastern                  | 5987.75                                  | 20540.00                  | 20462.33         | -0.38                                      |
| 5      | North-Eastern            | 2027.0                                   | 6839.00                   | 6372.81          | -6.82                                      |
|        | <b>Total (All India)</b> | <b>46722.50</b>                          | <b>149544.00</b>          | <b>151627.33</b> | <b>1.39</b>                                |

- Hydel generation during 2021-22 has exceeded the target in Southern Region whereas it was lower than the target in Northern, Western, Eastern Region & North-Eastern Region of the country primarily on account of lower inflows/rainfall in project catchment area.
- Hydel generation during 2021-22 was 151627.33 MU against the target of 149544 MU viz higher in generation by 2083.33 MU (9%). However, actual hydel generation during 2021-22 is more than previous year generation of 150299.52 MU by 0.88%.

Region-wise generation targets viz-a-viz achievements are indicated at **Exhibit-2.2**.

**2.5** Sector-wise generation performance during the year 2021-22 viz-a-viz targets is given in **Table 2.4**.

Generation from H.E. Stations under Central Sector, State Sector & Private Sector has been more than the target.

**TABLE 2.4**

**SECTOR-WISE GENERATION PERFORMANCE  
PERIOD: 2021-22**

| Sl. No. | Sector       | Installed Capacity as on 31.03.2022 (MW) | Generation    |                  |                                           |
|---------|--------------|------------------------------------------|---------------|------------------|-------------------------------------------|
|         |              |                                          | Target (MU)   | Actual (MU)      | Shortfall (-) Surplus (+) Over Target (%) |
| 1       | Central      | 15664.72                                 | 61044.00      | 58421.61         | -4.30                                     |
| 2       | State        | 27126.80                                 | 74198.00      | 78792.42         | 6.19                                      |
| 3       | Private      | 3931                                     | 14302         | 14413.3          | 0.78                                      |
|         | <b>Total</b> | <b>46722.52</b>                          | <b>149544</b> | <b>151627.33</b> | <b>1.39</b>                               |


**2.6** Details of actual generation during 2021-22 for all the hydro stations (above 25 MW capacity) in the country are given in **Annex 2.1**. It is observed that 109 Nos. of stations have exceeded the target level of generation while the generation has been less than targets in case of 101 stations. List of stations where generation exceeded the target during 2021-22 is given in **Table 2.5**.

**TABLE 2.5**

**H.E. STATIONS ACHIEVING HIGHER GENERATION VIS-A-VIS TARGET  
PERIOD: 2021-22**

| S. No. | Actual Generation as % of Target | Hydro Electric Stations |                            |                                                                                                                                                                                                 |
|--------|----------------------------------|-------------------------|----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|        |                                  | No. of Stations         | % of total No. of Stations | Name of the Station                                                                                                                                                                             |
| 1      | 150 & above                      | 16                      | 7.6                        | N.J.Sagar RBC, N.J.Sagar TPD, Jog, Munirabad, Idukki, Lower Periyar, Sabarigiri, Kodayar I&II, Periyar, Sholayar I, N.J.Sagar LBC, Pulichinthala, Panchet, Subernarekha I&II, Maithon, Khandong |
| 2      | 140 - 150                        | 7                       | 3.3                        | Sorang, Hasdeo Bango, Poringalkuthu, Bhadra, N.J.Sagar PSS, Pochampad, Srisailem LB                                                                                                             |

## REGION-WISE ACTUAL GENERATION VS TARGET DURING 2021-22



|   |           |    |       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|---|-----------|----|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 3 | 130 - 140 | 9  | 4.2   | Mahi Bajaj I & II, Dhalipur (Y.St.I), Srisailam RB, Supa DPH, Shivasamudram, T.B.Dam & Hampi, Kakkad, Mettur Tunnel, Papanasam                                                                                                                                                                                                                                                                                                                                                         |
| 4 | 120 - 130 | 10 | 4.7   | Sainj, Giri Bata, Sanjay, Ganguwal , Kotla, Koyna St.I&II, Kalinadi, Bhawani K Barrage-III, Mettur Dam, Rammam II                                                                                                                                                                                                                                                                                                                                                                      |
| 5 | 110 - 120 | 24 | 11.4  | Kashang I, Tanakpur, Khodri (Y.St.II), Maneri Bhali-I, Vishnu Prayag, Ukai, Bansagar Tons-I, Madhikheda, Bhira Tail Race, Koyna St.III, Kodasali, Kuttiadi & Kuttiady Addl., Panniar, Sengulam, Sholayar, Bhawani K Barrage-II, Kundah I-V, Lower Mettur I-IV, Sarkarpathy, Rengali, Machkund, Teesta III, Rongnichu, Jaldhaka I                                                                                                                                                       |
| 6 | 100 - 110 | 43 | 20.47 | Dehar, Rampur, Kol Dam, Bassi, Shanan, Baspa-II, Karcham Wangtoo, Uri, Uri –II, Baglihar, Baglihar II, Lower Jhelum, Nimoo Bazgo, Khara, Obra, Dhauliganga, Tehri, Koteswar, Chibro (Y.St.II), Chilla, Khatima, Kulhal (Y.St.IV), Maneri Bhali-II, Srinagar, Bansagar Tons-II, Tillari, Khopoli, Gurusoppa, Ghatprabha, Sharavathy, Varahi, Idamalayar, Pallivasal, Bhawani K Barrage-I, Pykara Ultimate, Hirakud I&II, Jorethang Loop, Tashiding, Chuzachen HEP, Dikchu, Karbi Langpi |

H.E. Stations where generation was lower than the target have been listed in **Table 2.6** below:

**TABLE 2.6**

**H.E. STATIONS HAVING SHORTFALL IN GENERATION VIS-A-VIS TARGETS  
PERIOD: 2021-22**

| S. No. | Actual Generation as % of Target | Hydro Electric Stations |                            |                                                                                                                                                                                                                                                                                                                                                                          |
|--------|----------------------------------|-------------------------|----------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|        |                                  | No. of Stations         | % of total No. of Stations | Name of the Station                                                                                                                                                                                                                                                                                                                                                      |
| 1      | 90 -100                          | 33                      | 15.71                      | Bhakra L&R, Pong, Baira Siul, Chamara-II, Chamara-III, Naptha Jhakri, Larji, Allain Duhangan, Malana-II, Budhil, Chanju I, Malana, Dulhasti, Salal-I, Jawahar Sagar, Dhakrani (Y.St.I), Ram Ganga, Bargi, Koyna DPH, Koyna IV, Bhandardhara – II, Bhivpuri, Kadra, Neriamangalam, Moyar, Lower Jurala, Priyadarshni Jurala, Rangit, Teesta-V, Purulia PSS, Kameng, Pare, |

|   |        |    |      |                                                                                                                                                                                       |
|---|--------|----|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|   |        |    |      | Ranganadi, Loktak (Manipur)                                                                                                                                                           |
| 2 | 80-90  | 15 | 7.14 | Kishenganga, Upper Sindh II, Chutak, Mukerian I – IV, Rihand, Sardar Sarovar CHPH, Rajghat, Vaitarna, Pench, Almatti Dam, Lingnamakki, Parson's Valley, Kyrdekulai, Myntdu, New Umtru |
| 3 | 70 -80 | 10 | 4.76 | Chamera-I , Parbati III, Ranjit Sagar, Matatilla, Upper sileru I & II, Lower Sileru, Kadamparai PSS, Balimela, Umium St.IV, Tuirial                                                   |
| 4 | 60 -70 | 4  | 1.9  | Kadana PSS, Indira Sagar, Omkareshwar, Umium St.I,                                                                                                                                    |
| 5 | 50 -60 | 5  | 2.3  | Sewa-II, A.P.Sahib I & II, Gandhi Sagar, Upper Indravati, Upper Kolab                                                                                                                 |
| 6 | 40 -50 | 4  | 1.9  | Sardar Sarovar RBPH, Bansagar Tons-III, Bhira, Doyang                                                                                                                                 |
| 7 | 30 -40 | 1  | 0.47 | Suruliyar                                                                                                                                                                             |
| 8 | 10 -30 | 3  | 1.4  | Singoli Bhatwari, Ghatghar PSS, Aliyar                                                                                                                                                |
| 9 | 0 -10  | 5  | 2.3  | Parbati II, Swara Kuddu, Bajoli Holi, Naitwar Mori, Pykara                                                                                                                            |

The Utilities showing excess/shortfall in generation over the target are indicated in **Exhibit- 2.3**.

**2.7** Hydro Generation is a function of availability of Water and that of Generating units. Rainfall is the primary source of water, which is highly variable in time and space. However, there could be no direct comparison between the rainfall and the energy generation during these years of data due to different installed capacities. While the rainfall has definite impact on the level of generation, it could also be impacted by the duration of forced and planned outages especially in the case of ROR projects. Region-wise Hydel generation during last five years is given below in **Table 2.7**


TABLE-2.7

**REGION-WISE HYDEL GENERATION AND RAINFALL  
DURING 2016-17 TO 2021-22**

| Region          | Installed Capacity as on 31.03.2022 (MW) | Generation (BU)     |                     |                     |                     |                     |                     |
|-----------------|------------------------------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|
|                 |                                          | 2016-17             | 2017-18             | 2018-19             | 2019-20             | 2020-21             | 2021-22             |
| Northern        | 19576.25                                 | 71.76               | 74.73               | 72.40               | 80.55               | 75.23               | 73.86               |
| Western         | 7392.00                                  | 17.18               | 9.18                | 9.76                | 17.81               | 16.67               | 13.71               |
| Southern        | 11739.5                                  | 17.04               | 19.02               | 28.81               | 31.75               | 31.35               | 37.20               |
| Eastern         | 5987.75                                  | 11.75               | 17.52               | 18.90               | 20.82               | 21.17               | 20.46               |
| North Eastern   | 2027                                     | 4.65                | 5.67                | 5.02                | 48.20               | 58.58               | 63.72               |
| <b>Total</b>    | <b>46722.50</b>                          | <b>122.38</b>       | <b>126.12</b>       | <b>134.90</b>       | <b>155.76</b>       | <b>150.29</b>       | <b>151.62</b>       |
| <b>Rainfall</b> |                                          | <b>2016-17 (mm)</b> | <b>2017-18 (mm)</b> | <b>2018-19 (mm)</b> | <b>2019-20 (mm)</b> | <b>2020-21 (mm)</b> | <b>2021-22 (mm)</b> |
| All-India       |                                          | 1083.1              | 1127.1              | 1020.8              | 968.3               |                     |                     |

It can be observed from the above table that maximum hydro generation of 155.7 BU was achieved during the year 2019-20 as compared previous four years mainly due to better rainfall in the catchment areas of hydro power stations besides increase in installed capacity.

## UTILITY-WISE EXCESS/ SHORTFALL IN GENERATION DURING 2021-22



**REGION/SECTOR/STATION-WISE ACTUAL GENERATION VIS-A-VIS TARGET OF H.E.STATIONS (I. C. ABOVE 25 MW ) IN THE COUNTRY DURING THE YEAR CURRENT YEAR 2021-2022**

| REGION/ UTILITY/ STATION             | INSTALLED<br>CAPACITY<br>AS ON<br>31.03.2022<br>(MW) | DESIGN<br>ENERGY<br>(MU) | 2021-2022 |          |                                  |
|--------------------------------------|------------------------------------------------------|--------------------------|-----------|----------|----------------------------------|
|                                      |                                                      |                          | TARGET    | ACTUAL   | % OF<br>ACTUAL<br>OVER<br>TARGET |
| NORTHERN REGION                      |                                                      |                          |           |          |                                  |
| HIMACHAL PRADESH                     |                                                      |                          |           |          |                                  |
| CENTRAL SECTOR                       |                                                      |                          |           |          |                                  |
| BBMB                                 |                                                      |                          |           |          |                                  |
| Bhakra L&R                           | 1397.00                                              | 3924.00                  | 4550.00   | 4357.67  | 95.77                            |
| Dehar                                | 990.00                                               | 3110.00                  | 2950.00   | 3109.73  | 105.41                           |
| Pong                                 | 396.00                                               | 1123.00                  | 1150.00   | 1103.65  | 95.97                            |
| Total BBMB-HP                        | 2783.00                                              | 8157.00                  | 8650.00   | 8571.05  | 99.09                            |
| NHPC                                 |                                                      |                          |           |          |                                  |
| Baira Siul                           | 180.00                                               | 779.28                   | 650.00    | 587.23   | 90.34                            |
| Chamera-I                            | 540.00                                               | 1664.56                  | 2460.00   | 1899.27  | 77.21                            |
| Chamera-II                           | 300.00                                               | 1499.89                  | 1450.00   | 1358.68  | 93.70                            |
| Chamera-III                          | 231.00                                               | 1108.00                  | 1050.00   | 1004.26  | 95.64                            |
| Parbati III                          | 520.00                                               | 1977.23                  | 810.00    | 613.34   | 75.72                            |
| Parbati II*                          |                                                      |                          | 450.00    | 0.00     | 0.00                             |
| Total NHPC -HP                       | 1771.00                                              | 7028.96                  | 6870.00   | 5462.78  | 79.52                            |
| SJVN                                 |                                                      |                          |           |          |                                  |
| Naptha Jhakri                        | 1500.00                                              | 6612.00                  | 7104.00   | 7067.40  | 99.48                            |
| Rampur                               | 412.02                                               | 1878.08                  | 1977.00   | 1981.21  | 100.21                           |
| Total SJVN                           | 1912.02                                              | 8490.08                  | 9111.00   | 9048.61  | 99.32                            |
| NTPC                                 |                                                      |                          |           |          |                                  |
| Kol Dam                              | 800.00                                               | 3054.79                  | 3100.00   | 3120.14  | 100.65                           |
| Total NTPC                           | 800.00                                               | 3054.79                  | 3100.00   | 3120.14  | 100.65                           |
| Total Central-HP                     | 7266.02                                              | 26730.83                 | 27731.00  | 26202.58 | 94.49                            |
| STATE SECTOR                         |                                                      |                          |           |          |                                  |
| HPPCL                                |                                                      |                          |           |          |                                  |
| Kashang I                            | 65.00                                                | 245.80                   | 185.00    | 209.41   | 113.19                           |
| Kashang II & III                     | 130.00                                               |                          |           |          |                                  |
| Sainj                                | 100.00                                               | 323.23                   | 340.00    | 418.83   | 123.19                           |
| Swara Kuddu                          | 111.00                                               | 386.00                   | 296.00    | 21.31    | 7.20                             |
| Total HPPCL                          | 406.00                                               | 955.03                   | 821.00    | 649.55   | 79.12                            |
| HPSEB LTD                            |                                                      |                          |           |          |                                  |
| Bassi                                | 66.00                                                | 346.77                   | 304.00    | 317.35   | 104.39                           |
| Giri Bata                            | 60.00                                                | 240.00                   | 180.00    | 227.63   | 126.46                           |
| Larji                                | 126.00                                               | 586.85                   | 619.00    | 580.87   | 93.84                            |
| Sanjay                               | 120.00                                               | 518.00                   | 500.00    | 642.81   | 128.56                           |
| Total HPSEB LTD                      | 372.00                                               | 1691.62                  | 1603.00   | 1768.66  | 110.33                           |
| Beas Valley Power. Corp. Ltd. (BVPC) |                                                      |                          |           |          |                                  |
| Uhl-III*                             | 0.00                                                 |                          |           |          |                                  |
| Total BVPC                           |                                                      |                          |           |          |                                  |
| PSPCL                                |                                                      |                          |           |          |                                  |
| Shanan                               | 110.00                                               | 585.00                   | 502.00    | 521.90   | 103.96                           |
| Total PSPCL-HP                       | 110.00                                               | 585.00                   | 502.00    | 521.90   | 103.96                           |
| Total State Sector-HP                | 888.00                                               | 3231.65                  | 2926.00   | 2940.11  | 100.48                           |
| PRIVATE                              |                                                      |                          |           |          |                                  |
| Allain Duhangan Power Power Ltd.     |                                                      |                          |           |          |                                  |
| Allain Duhangan                      | 192.00                                               | 678.18                   | 676.00    | 637.44   | 94.30                            |
| Everest Power Private Ltd.           |                                                      |                          |           |          |                                  |
| Malana-II                            | 100.00                                               | 403.00                   | 367.00    | 345.66   | 94.19                            |
| HBPCL                                |                                                      |                          |           |          |                                  |
| Baspa-II                             | 300.00                                               | 1213.00                  | 1300.00   | 1320.35  | 101.57                           |
| Karcham Wangtoo                      | 1045.00                                              | 4131.06                  | 4131.00   | 4243.45  | 102.72                           |
| Total HBPCL                          | 1345.00                                              | 5344.06                  | 5431.00   | 5563.80  | 102.45                           |
| GBHPPL                               |                                                      |                          |           |          |                                  |
| Budhil                               | 70.00                                                | 291.73                   | 270.00    | 251.37   | 93.10                            |

**REGION/SECTOR/STATION-WISE ACTUAL GENERATION VIS-A-VIS TARGET OF H.E.STATIONS (I. C. ABOVE 25 MW ) IN THE COUNTRY DURING THE YEAR CURRENT YEAR 2021-2022**

| REGION/ UTILITY/ STATION              | INSTALLED<br>CAPACITY<br>AS ON<br>31.03.2022<br>(MW) | DESIGN<br>ENERGY<br>(MU) | 2021-2022 |          |                                  |
|---------------------------------------|------------------------------------------------------|--------------------------|-----------|----------|----------------------------------|
|                                       |                                                      |                          | TARGET    | ACTUAL   | % OF<br>ACTUAL<br>OVER<br>TARGET |
| IA Energy Pvt. Ltd.                   |                                                      |                          |           |          |                                  |
| Chanju I                              | 36.00                                                | 157.82                   | 158.00    | 146.54   | 92.75                            |
| Malana Power Company Ltd.             |                                                      |                          |           |          |                                  |
| Malana                                | 86.00                                                | 370.93                   | 344.00    | 314.96   | 91.56                            |
| NSL Tidond Power Generation Pvt. Ltd. |                                                      |                          |           |          |                                  |
| Tidong*                               |                                                      |                          | 0.00      | 0.00     |                                  |
| Himachal Sorang Power Limited (HSPL)  |                                                      |                          |           |          |                                  |
| Sorang                                | 100                                                  | 524                      | 39.00     | 57.18    | 146.62                           |
| GMR                                   |                                                      |                          |           |          |                                  |
| Bajoli Holi                           | 180                                                  |                          | 273.00    | 0.00     | 0.00                             |
| Total Private-HP                      | 2109                                                 | 7769.72                  | 7558      | 7317     | 96.81                            |
| Total H.P.                            | 10263.02                                             | 37732.20                 | 38215.00  | 36459.64 | 95.41                            |
| JAMMU & KASHMIR                       |                                                      |                          |           |          |                                  |
| CENTRAL SECTOR                        |                                                      |                          |           |          |                                  |
| NHPC                                  |                                                      |                          |           |          |                                  |
| Dulhasti                              | 390.00                                               | 1907.00                  | 2260.00   | 2216.13  | 98.06                            |
| Salal-I                               | 345.00                                               | 3082.00                  | 3600.00   | 3485.52  | 96.82                            |
| Salal-II                              | 345.00                                               |                          |           |          |                                  |
| Sewa-II                               | 120.00                                               | 533.52                   | 125.00    | 62.89    | 50.31                            |
| Uri                                   | 480.00                                               | 2587.38                  | 2950.00   | 3037.45  | 102.96                           |
| Uri -II                               | 240.00                                               | 1124.00                  | 1570.00   | 1649.52  | 105.06                           |
| Kishenganga                           | 330.00                                               | 1705.62                  | 1685.00   | 1506.42  | 89.40                            |
| Total NHPC -J&K                       | 2250.00                                              | 10939.52                 | 12190.00  | 11957.93 | 98.10                            |
| Total Central Sector - J&K            | 2250.00                                              | 10939.52                 | 12190.00  | 11957.93 | 98.10                            |
| STATE SECTOR                          |                                                      |                          |           |          |                                  |
| JKSPDC                                |                                                      |                          |           |          |                                  |
| Baglihar                              | 450.00                                               | 2643.00                  | 2536.00   | 2676.88  | 105.56                           |
| Baglihar II                           | 450.00                                               | 1302.30                  | 1450.00   | 1561.02  | 107.66                           |
| Lower Jhelum                          | 105.00                                               | 533.00                   | 591.00    | 622.96   | 105.41                           |
| Upper Sindh II                        | 105.00                                               | 355.00                   | 310.00    | 255.23   | 82.33                            |
| Total JKSPDC                          | 1110.00                                              | 4833.30                  | 4887.00   | 5116.09  | 104.69                           |
| Total State Sector-J&K                | 1110.00                                              | 4833.30                  | 4887.00   | 5116.09  | 104.69                           |
| Total Jammu & Kashmir                 | 3360.00                                              | 15772.82                 | 17077.00  | 17074.02 | 99.98                            |
| LADHAK                                |                                                      |                          |           |          |                                  |
| CENTRAL SECTOR                        |                                                      |                          |           |          |                                  |
| NHPC                                  |                                                      |                          |           |          |                                  |
| Chutak                                | 44.00                                                | 213.00                   | 209.00    | 170.54   | 81.60                            |
| Nimoo Bazgo                           | 45.00                                                | 239.00                   | 235.00    | 235.44   | 100.19                           |
| Total Central Sector-Ladhak           | 89.00                                                | 452.00                   | 444.00    | 405.98   | 91.44                            |
| Total Ladhak                          | 89.00                                                | 452.00                   | 444.00    | 405.98   | 91.44                            |
| PUNJAB                                |                                                      |                          |           |          |                                  |
| CENTRAL SECTOR                        |                                                      |                          |           |          |                                  |
| BBMB                                  |                                                      |                          |           |          |                                  |
| Ganguwal                              | 77.65                                                | 1358.00                  | 500.00    | 609.88   | 121.98                           |
| Kotla                                 | 77.65                                                |                          | 500.00    | 613.89   | 122.78                           |
| Total BBMB-Punjab                     | 155.30                                               | 1358.00                  | 1000.00   | 1223.77  | 122.38                           |
| STATE SECTOR                          |                                                      |                          |           |          |                                  |
| PSPCL                                 |                                                      |                          |           |          |                                  |
| A.P.Sahib I & II                      | 134.00                                               | 909.00                   | 709.00    | 396.28   | 55.89                            |
| Mukerian I - IV                       | 207.00                                               | 1206.00                  | 1120.00   | 926.69   | 82.74                            |
| Ranjit Sagar                          | 600.00                                               | 1507.00                  | 1638.00   | 1162.99  | 71.00                            |
| Total PSPCL                           | 941                                                  | 3622                     | 3467      | 2486     | 71.70                            |
| Total State Sector-Punjab             | 941.00                                               | 3622.00                  | 3467.00   | 2485.96  | 71.70                            |
| Total Punjab                          | 1096.30                                              | 4980.00                  | 4467.00   | 3709.73  | 83.05                            |
| RAJASTHAN                             |                                                      |                          |           |          |                                  |
| STATE SECTOR                          |                                                      |                          |           |          |                                  |
| RRVUNL                                |                                                      |                          |           |          |                                  |
| Jawahar Sagar                         | 99.00                                                | 298.00                   | 230.00    | 210.67   | 91.60                            |
| Mahi Bajaj I & II                     | 140.00                                               | 289.00                   | 140.00    | 187.84   | 134.17                           |
| R.P. Sagar                            | 172.00                                               | 459.00                   | 0.00      | 83.33    |                                  |
| Total RRVUNL                          | 411.00                                               | 1046.00                  | 370.00    | 481.84   | 130.23                           |
| Total State sector-Rajasthan          | 411.00                                               | 1046.00                  | 370.00    | 481.84   | 130.23                           |

**REGION/SECTOR/STATION-WISE ACTUAL GENERATION VIS-A-VIS TARGET OF H.E.STATIONS (I. C. ABOVE 25 MW ) IN THE COUNTRY DURING THE YEAR CURRENT YEAR 2021-2022**

| REGION/ UTILITY/ STATION              | INSTALLED CAPACITY AS ON 31.03.2022 (MW) | DESIGN ENERGY (MU) | 2021-2022       |                 |                         |
|---------------------------------------|------------------------------------------|--------------------|-----------------|-----------------|-------------------------|
|                                       |                                          |                    | TARGET          | ACTUAL          | % OF ACTUAL OVER TARGET |
| <b>Total Rajasthan</b>                | <b>411.00</b>                            | <b>1046.00</b>     | <b>370.00</b>   | <b>481.84</b>   | <b>130.23</b>           |
| <b>UTTAR PRADESH</b>                  |                                          |                    |                 |                 |                         |
| STATE SECTOR                          |                                          |                    |                 |                 |                         |
| UPJVNL                                |                                          |                    |                 |                 |                         |
| Khara                                 | 72.00                                    | 385.00             | 334.00          | 357.57          | 107.06                  |
| Matatilla                             | 30.60                                    | 123.00             | 120.00          | 87.04           | 72.53                   |
| Obra                                  | 99.00                                    | 279.00             | 300.00          | 311.58          | 103.86                  |
| Rihand                                | 300.00                                   | 920.00             | 765.00          | 646.49          | 84.51                   |
| <b>Total UPJVNL</b>                   | <b>501.60</b>                            | <b>1707.00</b>     | <b>1519.00</b>  | <b>1402.68</b>  | <b>92.34</b>            |
| <b>Total State Sector-UP</b>          | <b>501.60</b>                            | <b>1707.00</b>     | <b>1519.00</b>  | <b>1402.68</b>  | <b>92.34</b>            |
| <b>Total Uttar Pradesh</b>            | <b>501.60</b>                            | <b>1707.00</b>     | <b>1519.00</b>  | <b>1402.68</b>  | <b>92.34</b>            |
| <b>UTTARAKHAND</b>                    |                                          |                    |                 |                 |                         |
| CENTRAL SECTOR                        |                                          |                    |                 |                 |                         |
| NHPC                                  |                                          |                    |                 |                 |                         |
| Dhauliganga                           | 280.00                                   | 1134.69            | 1175.00         | 1212.42         | 103.18                  |
| Tanakpur                              | 94.20                                    | 452.19             | 452.00          | 540.21          | 119.52                  |
| <b>Total NHPC-UK</b>                  | <b>374</b>                               | <b>1586.88</b>     | <b>1627</b>     | <b>1753</b>     | <b>107.72</b>           |
| NTPC                                  |                                          |                    |                 |                 |                         |
| Tapovan Vishnugad                     | 0.00                                     |                    | 0.00            | 0.00            |                         |
| <b>Total NTPC-UK</b>                  | <b>0</b>                                 |                    | <b>0</b>        | <b>0</b>        |                         |
| THDC LTD                              |                                          |                    |                 |                 |                         |
| Tehri                                 | 1000.00                                  | 2797.00            | 3000.00         | 3098.11         | 103.27                  |
| Koteshwar                             | 400.00                                   | 1155.00            | 1160.00         | 1190.64         | 102.64                  |
| <b>Total THDC LTD</b>                 | <b>1400.00</b>                           | <b>3952.00</b>     | <b>4160.00</b>  | <b>4288.75</b>  | <b>103.09</b>           |
| SJVN                                  |                                          |                    |                 |                 |                         |
| Naitwar Mori                          | 0.00                                     |                    | 30.00           |                 | 0.00                    |
| <b>Total SJVN</b>                     |                                          |                    |                 |                 |                         |
| <b>Total Central Sector - UK</b>      | <b>1774.20</b>                           | <b>5538.88</b>     | <b>5787.00</b>  | <b>6041.38</b>  | <b>104.40</b>           |
| STATE SECTOR                          |                                          |                    |                 |                 |                         |
| UJVNL                                 |                                          |                    |                 |                 |                         |
| Chibro (Y.St.II)                      | 240.00                                   | 750.00             | 850.00          | 903.86          | 106.34                  |
| Chilla                                | 144.00                                   | 725.00             | 750.00          | 799.36          | 106.58                  |
| Dhakrani (Y.St.I)                     | 33.75                                    | 169.00             | 160.00          | 155.64          | 97.28                   |
| Dhalipur (Y.St.I)                     | 51.00                                    | 192.00             | 185.00          | 246.78          | 133.39                  |
| Khatima                               | 41.40                                    | 208.00             | 224.00          | 229.75          | 102.57                  |
| Khodri (Y.St.II)                      | 120.00                                   | 345.00             | 363.00          | 430.84          | 118.69                  |
| Kulhal (Y.St.IV)                      | 30.00                                    | 164.00             | 150.00          | 160.08          | 106.72                  |
| Maneri Bhal-I                         | 90.00                                    | 395.00             | 360.00          | 398.98          | 110.83                  |
| Maneri Bhal-II                        | 304.00                                   | 1566.10            | 1320.00         | 1412.53         | 107.01                  |
| Ram Ganga                             | 198.00                                   | 334.00             | 250.00          | 249.36          | 99.74                   |
| Vyasi                                 | 0.00                                     |                    |                 |                 |                         |
| <b>Total UJVNL</b>                    | <b>1252.15</b>                           | <b>4848.10</b>     | <b>4612.00</b>  | <b>4987.18</b>  | <b>108.13</b>           |
| <b>Total State Sector-Uttarakhand</b> | <b>1252.15</b>                           | <b>4848.10</b>     | <b>4612.00</b>  | <b>4987.18</b>  | <b>108.13</b>           |
| PRIVATE SECTOR                        |                                          |                    |                 |                 |                         |
| AHPC LTD                              |                                          |                    |                 |                 |                         |
| Srinagar                              | 330.00                                   | 1396.84            | 1310.00         | 1421.89         | 108.54                  |
| Jaiprakash Power Venture Ltd.         |                                          |                    |                 |                 |                         |
| Vishnu Prayag                         | 400.00                                   | 1774.42            | 1590.00         | 1801.24         | 113.29                  |
| L&T                                   |                                          |                    |                 |                 |                         |
| Singoli Bhatwari                      | 99.00                                    | 473                | 293.00          | 80.44           | 27.45                   |
| <b>Total Private Sector - UK</b>      | <b>829.00</b>                            | <b>3644.26</b>     | <b>3193.00</b>  | <b>3303.57</b>  | <b>103.46</b>           |
| <b>Total Uttarakhand</b>              | <b>3855.35</b>                           | <b>14031.24</b>    | <b>13592.00</b> | <b>14332.13</b> | <b>105.45</b>           |
| <b>Total N. REGION</b>                | <b>19576.27</b>                          | <b>75721.26</b>    | <b>75684.00</b> | <b>73866.02</b> | <b>97.60</b>            |
| <b>WESTERN REGION</b>                 |                                          |                    |                 |                 |                         |
| CHHATISGARH                           |                                          |                    |                 |                 |                         |
| STATE SECTOR                          |                                          |                    |                 |                 |                         |
| CSPGC                                 |                                          |                    |                 |                 |                         |
| Hasdeo Bango                          | 120.00                                   | 274.00             | 280.00          | 404.13          | 144.33                  |
| <b>Total CSPGC</b>                    | <b>120.00</b>                            | <b>274.00</b>      | <b>280.00</b>   | <b>404.13</b>   | <b>144.33</b>           |
| <b>Total State Sector-Chhatisgarh</b> | <b>120.00</b>                            | <b>274.00</b>      | <b>280.00</b>   | <b>404.13</b>   | <b>144.33</b>           |
| <b>Total Chhatisgarh</b>              | <b>120.00</b>                            | <b>274.00</b>      | <b>280.00</b>   | <b>404.13</b>   | <b>144.33</b>           |
| <b>GUJARAT</b>                        |                                          |                    |                 |                 |                         |
| STATE SECTOR                          |                                          |                    |                 |                 |                         |
| GSECL                                 |                                          |                    |                 |                 |                         |

**REGION/SECTOR/STATION-WISE ACTUAL GENERATION VIS-A-VIS TARGET OF H.E.STATIONS (I. C. ABOVE 25 MW ) IN THE COUNTRY DURING THE YEAR CURRENT YEAR 2021-2022**

| REGION/ UTILITY/ STATION                              | INSTALLED CAPACITY AS ON 31.03.2022 (MW) | DESIGN ENERGY (MU) | 2021-2022      |                |                         |
|-------------------------------------------------------|------------------------------------------|--------------------|----------------|----------------|-------------------------|
|                                                       |                                          |                    | TARGET         | ACTUAL         | % OF ACTUAL OVER TARGET |
| Kadana PSS                                            | 240.00                                   | 518.00             | 329.00         | 218.26         | 66.34                   |
| Ukai                                                  | 300.00                                   | 1080.00            | 560.00         | 655.24         | 117.01                  |
| <b>Total GSECL</b>                                    | <b>540.00</b>                            | <b>1598.00</b>     | <b>889.00</b>  | <b>873.50</b>  | <b>98.26</b>            |
| <b>SSNNL</b>                                          |                                          |                    |                |                |                         |
| Sardar Sarovar CHPH                                   | 250.00                                   | 213.00             | 970.00         | 824.27         | 84.98                   |
| Sardar Sarovar RBPH                                   | 1200.00                                  | 3635.00            | 1862.00        | 923.74         | 49.61                   |
| <b>Total SSNNL</b>                                    | <b>1450.00</b>                           | <b>3848.00</b>     | <b>2832.00</b> | <b>1748.01</b> | <b>61.72</b>            |
| <b>Total State Sector -Gujarat</b>                    | <b>1990.00</b>                           | <b>5446.00</b>     | <b>3721.00</b> | <b>2621.51</b> | <b>70.45</b>            |
| <b>Total Gujarat</b>                                  | <b>1990.00</b>                           | <b>5446.00</b>     | <b>3721.00</b> | <b>2621.51</b> | <b>70.45</b>            |
| <b>MADHYA PRADESH</b>                                 |                                          |                    |                |                |                         |
| <b>CENTRAL</b>                                        |                                          |                    |                |                |                         |
| <b>NHDC</b>                                           |                                          |                    |                |                |                         |
| Indira Sagar                                          | 1000.00                                  | 1980.00            | 2565.00        | 1717.17        | 66.95                   |
| Omkareshwar                                           | 520.00                                   | 1166.57            | 1335.00        | 928.24         | 69.53                   |
| <b>Total NHDC</b>                                     | <b>1520.00</b>                           | <b>3146.57</b>     | <b>3900.00</b> | <b>2645.41</b> | <b>67.83</b>            |
| <b>Total Central Sector-MP</b>                        |                                          |                    | <b>3900</b>    | <b>2645</b>    | <b>67.83</b>            |
| <b>STATE SECTOR</b>                                   |                                          |                    |                |                |                         |
| <b>MPPGCL</b>                                         |                                          |                    |                |                |                         |
| Bansagar Tons-I                                       | 315.00                                   | 900.00             | 980.00         | 1121.45        | 114.43                  |
| Bansagar Tons-II                                      | 30.00                                    | 113.00             | 81.00          | 85.43          | 105.47                  |
| Bansagar Tons-III                                     | 60.00                                    | 143.00             | 110.00         | 49.86          | 45.33                   |
| Bargi                                                 | 90.00                                    | 508.08             | 420.00         | 382.35         | 91.04                   |
| Gandhi Sagar                                          | 115.00                                   | 420.48             | 380.00         | 211.68         | 55.71                   |
| Madhikheda                                            | 60.00                                    | 74.12              | 105.00         | 116.50         | 110.95                  |
| Rajghat                                               | 45.00                                    | 87.60              | 88.00          | 74.04          | 84.14                   |
| <b>Total MPPGCL</b>                                   | <b>715.00</b>                            | <b>2246.28</b>     | <b>2164.00</b> | <b>2041.31</b> | <b>94.33</b>            |
| <b>Total State-MP</b>                                 | <b>715.00</b>                            | <b>2246.28</b>     | <b>2164.00</b> | <b>2041.31</b> | <b>94.33</b>            |
| <b>SMHPCL(PVT.)</b>                                   |                                          |                    |                |                |                         |
| Maheshwar*                                            |                                          |                    | 0.00           | 0.00           |                         |
| <b>Total M.P.</b>                                     | <b>2235.00</b>                           | <b>5392.85</b>     | <b>6064</b>    | <b>4687</b>    | <b>77.29</b>            |
| <b>MAHARASHTRA</b>                                    |                                          |                    |                |                |                         |
| <b>STATE SECTOR</b>                                   |                                          |                    |                |                |                         |
| <b>MAHAGENCO</b>                                      |                                          |                    |                |                |                         |
| Bhira Tail Race                                       | 80.00                                    | 75.00              | 85.00          | 100.97         | 118.79                  |
| Ghatghar PSS                                          | 250.00                                   | 146.00             | 386.00         | 93.52          | 24.23                   |
| Koyna DPH                                             | 36.00                                    | 410.00             | 136.00         | 132.46         | 97.40                   |
| Koyna St.I&II                                         | 600.00                                   | 3030.00            | 1025.00        | 1259.39        | 122.87                  |
| Koyna St.III                                          | 320.00                                   |                    | 568.00         | 673.90         | 118.64                  |
| Koyna IV                                              | 1000.00                                  |                    | 1655.00        | 1573.37        | 95.07                   |
| Tillari                                               | 60.00                                    | 133.00             | 110.00         | 116.72         | 106.11                  |
| Vaitarna                                              | 60.00                                    | 144.00             | 144.00         | 128.64         | 89.33                   |
| <b>Total MAHAGENCO</b>                                | <b>2406.00</b>                           | <b>3938.00</b>     | <b>4109</b>    | <b>4079</b>    | <b>99.27</b>            |
| <b>MPPGPCL</b>                                        |                                          |                    |                |                |                         |
| Pench                                                 | 160.00                                   | 315.36             | 362.00         | 304.48         | 84.11                   |
| <b>Total MPPGPCL-Maha.</b>                            | <b>160.00</b>                            | <b>315.36</b>      | <b>362.00</b>  | <b>304.48</b>  | <b>84.11</b>            |
| <b>Total State Sector-Maha.</b>                       | <b>2566.00</b>                           | <b>4253.36</b>     | <b>4471.00</b> | <b>4383.45</b> | <b>98.04</b>            |
| <b>PRIVATE SECTOR</b>                                 |                                          |                    |                |                |                         |
| <b>Dodson-Lindblom Hydro Power Pvt. Ltd. (DLHPPL)</b> |                                          |                    |                |                |                         |
| Bhandardhara - II                                     | 34.00                                    | 50.00              | 36.00          | 33.94          | 94.28                   |
| <b>Total DLHP</b>                                     | <b>34.00</b>                             | <b>50.00</b>       | <b>36.00</b>   | <b>33.94</b>   | <b>94.28</b>            |
| <b>Tata Power Company Ltd.</b>                        |                                          |                    |                |                |                         |
| Bhira                                                 | 150.00                                   | 775.00             | 900.00         | 397.19         | 44.13                   |
| Bhira PSS                                             | 150.00                                   |                    | 0.00           | 627.39         |                         |
| Bhivpuri                                              | 75.00                                    | 220.00             | 285.00         | 272.27         | 95.53                   |
| Khopoli                                               | 72.00                                    | 225.00             | 285.00         | 293.14         | 102.86                  |
| <b>Total TPCL</b>                                     | <b>447.00</b>                            | <b>1220.00</b>     | <b>1470.00</b> | <b>1589.99</b> | <b>108.16</b>           |
| <b>Total Private Sector-Maharashtra</b>               | <b>481.00</b>                            | <b>1270.00</b>     | <b>1506.00</b> | <b>1623.93</b> | <b>107.83</b>           |
| <b>Total Maharashtra</b>                              | <b>3047.00</b>                           | <b>5523.36</b>     | <b>5977.00</b> | <b>6007.38</b> | <b>100.51</b>           |
| <b>Total Western</b>                                  | <b>7392.00</b>                           | <b>16636.21</b>    | <b>16042</b>   | <b>13720</b>   | <b>85.52</b>            |
| <b>SOUTHERN REGION</b>                                |                                          |                    |                |                |                         |
| <b>ANDHRA PRADESH</b>                                 |                                          |                    |                |                |                         |
| <b>STATE SECTOR</b>                                   |                                          |                    |                |                |                         |
| <b>APGENCO</b>                                        |                                          |                    |                |                |                         |
| N.J.Sagar TPD                                         | 50.00                                    | 177.00             | 90.00          | 137.59         | 152.88                  |
| N.J.Sagar RBC                                         | 90.00                                    | 156.00             | 128.00         | 279.08         | 218.03                  |

**REGION/SECTOR/STATION-WISE ACTUAL GENERATION VIS-A-VIS TARGET OF H.E.STATIONS (I. C. ABOVE 25 MW ) IN THE COUNTRY DURING THE YEAR CURRENT YEAR 2021-2022**

| REGION/ UTILITY/ STATION            | INSTALLED CAPACITY AS ON 31.03.2022 (MW) | DESIGN ENERGY (MU) | 2021-2022       |                 |                         |
|-------------------------------------|------------------------------------------|--------------------|-----------------|-----------------|-------------------------|
|                                     |                                          |                    | TARGET          | ACTUAL          | % OF ACTUAL OVER TARGET |
| Srisaillam RB                       | 770.00                                   | 2900.00            | 1047.00         | 1438.92         | 137.43                  |
| Upper sileru I & II                 | 240.00                                   | 529.00             | 472.00          | 362.01          | 76.70                   |
| Lower Sileru                        | 460.00                                   | 1070.00            | 1131.00         | 896.23          | 79.24                   |
| <b>Total APGENCO</b>                | <b>1610.00</b>                           | <b>4832.00</b>     | <b>2868.00</b>  | <b>3113.83</b>  | <b>108.57</b>           |
| <b>Total State Sector-AP</b>        | <b>1610.00</b>                           | <b>4832.00</b>     | <b>2868.00</b>  | <b>3113.83</b>  | <b>108.57</b>           |
| <b>Total Andhra Pradesh</b>         | <b>1610.00</b>                           | <b>4832.00</b>     | <b>2868.00</b>  | <b>3113.83</b>  | <b>108.57</b>           |
| <b>KARNATAKA</b>                    |                                          |                    |                 |                 |                         |
| <b>STATE SECTOR</b>                 |                                          |                    |                 |                 |                         |
| <b>KPCL</b>                         |                                          |                    |                 |                 |                         |
| Almatti Dam                         | 290.00                                   | 483.00             | 590.00          | 499.58          | 84.67                   |
| Bhadra                              | 26.00                                    | 123.00             | 50.00           | 72.30           | 144.60                  |
| Gerusoppa                           | 240.00                                   | 622.00             | 531.00          | 543.26          | 102.31                  |
| Ghatprabha                          | 32.00                                    | 131.00             | 92.00           | 94.97           | 103.23                  |
| Jog                                 | 139.20                                   | 118.00             | 258.00          | 554.33          | 214.86                  |
| Kadra                               | 150.00                                   | 570.00             | 412.00          | 402.14          | 97.61                   |
| Kalinadi                            | 900.00                                   | 3385.00            | 2984.00         | 3686.96         | 123.56                  |
| Supa DPH                            | 100.00                                   | 542.00             | 462.00          | 609.78          | 131.99                  |
| Kodasali                            | 120.00                                   | 512.00             | 380.00          | 425.56          | 111.99                  |
| Lingnamakki                         | 55.00                                    | 254.00             | 333.00          | 277.88          | 83.45                   |
| Munirabad                           | 28.00                                    | 66.00              | 82.00           | 132.06          | 161.05                  |
| Sharavathy                          | 1035.00                                  | 4932.00            | 4967.00         | 4994.34         | 100.55                  |
| Shivasamudram                       | 42.00                                    | 183.00             | 225.00          | 301.01          | 133.78                  |
| Varahi                              | 460.00                                   | 1060.00            | 1043.00         | 1137.31         | 109.04                  |
| <b>Total KPCL</b>                   | <b>3617.20</b>                           | <b>12981.00</b>    | <b>12409.00</b> | <b>13731.48</b> | <b>110.66</b>           |
| <b>APGENCO</b>                      |                                          |                    |                 |                 |                         |
| T.B.Dam & Hampi                     | 72.00                                    | 236.00             | 156.00          | 204.98          | 131.40                  |
| <b>Total APGENCO-Karnataka</b>      | <b>72.00</b>                             | <b>236.00</b>      | <b>156.00</b>   | <b>204.98</b>   | <b>131.40</b>           |
| <b>Total State Sector-Karnataka</b> | <b>3689.20</b>                           | <b>13217.00</b>    | <b>12565.00</b> | <b>13936.46</b> | <b>110.91</b>           |
| <b>Total Karnataka</b>              | <b>3689.20</b>                           | <b>13217.00</b>    | <b>12565.00</b> | <b>13936.46</b> | <b>110.91</b>           |
| <b>KERALA</b>                       |                                          |                    |                 |                 |                         |
| <b>STATE SECTOR</b>                 |                                          |                    |                 |                 |                         |
| <b>KSEB Ltd.</b>                    |                                          |                    |                 |                 |                         |
| Idamalayar                          | 75.00                                    | 380.00             | 362.00          | 377.02          | 104.15                  |
| Idukki                              | 780.00                                   | 2398.00            | 2242.00         | 3709.85         | 165.47                  |
| Kakkad                              | 50.00                                    | 262.00             | 206.00          | 272.56          | 132.31                  |
| Kuttiadi & Kuttiady Addl.           | 225.00                                   | 323.00             | 671.00          | 746.70          | 111.28                  |
| Lower Periyar                       | 180.00                                   | 493.00             | 530.00          | 811.91          | 153.19                  |
| Neriamangalam                       | 45.00                                    | 237.00             | 341.00          | 312.39          | 91.61                   |
| Pallivasal                          | 37.50                                    | 284.00             | 160.00          | 162.33          | 101.46                  |
| Pallivasal New                      |                                          |                    |                 |                 |                         |
| Panniar                             | 30.00                                    | 158.00             | 176.00          | 210.66          | 119.69                  |
| Poringalkuthu                       | 32.00                                    | 170.00             | 156.00          | 220.41          | 141.29                  |
| Sabarigiri                          | 300.00                                   | 1338.00            | 1269.00         | 2047.45         | 161.34                  |
| Sengulam                            | 48.00                                    | 182.00             | 157.00          | 183.64          | 116.97                  |
| Sholayar                            | 54.00                                    | 233.00             | 235.00          | 262.52          | 111.71                  |
| Thottiyar                           |                                          |                    |                 |                 |                         |
| <b>Total KSEB LTD.</b>              | <b>1856.50</b>                           | <b>6458.00</b>     | <b>6505.00</b>  | <b>9317.44</b>  | <b>143.24</b>           |
| <b>Total State Sector-Kerala</b>    | <b>1856.50</b>                           | <b>6458.00</b>     | <b>6505.00</b>  | <b>9317.44</b>  | <b>143.24</b>           |
| <b>Total Kerala</b>                 | <b>1856.50</b>                           | <b>6458.00</b>     | <b>6505.00</b>  | <b>9317.44</b>  | <b>143.24</b>           |
| <b>TAMIL NADU</b>                   |                                          |                    |                 |                 |                         |
| <b>STATE SECTOR</b>                 |                                          |                    |                 |                 |                         |
| <b>TANGEDCO</b>                     |                                          |                    |                 |                 |                         |
| Aliyar                              | 60.00                                    | 175.00             | 133.00          | 22.64           | 17.02                   |
| Bhawani K Barrage-III               | 30.00                                    | 90.00              | 51.00           | 63.50           | 124.51                  |
| Bhawani K Barrage-II                | 30.00                                    | 100.00             | 70.00           | 78.73           | 112.47                  |
| Bhawani K Barrage-I                 | 30.00                                    | 80.00              | 71.00           | 76.07           | 107.14                  |
| Kadamparai PSS                      | 400.00                                   | 77.00              | 378.00          | 265.63          | 70.27                   |
| Kodayar I&II                        | 100.00                                   | 165.00             | 120.00          | 246.35          | 205.29                  |
| Kundah I-V                          | 555.00                                   | 1387.00            | 1405.00         | 1652.80         | 117.64                  |
| Lower Mettur I-IV                   | 120.00                                   | 252.00             | 245.00          | 291.10          | 118.82                  |
| Mettur Dam                          | 50.00                                    | 541.00             | 110.00          | 135.34          | 123.04                  |
| Mettur Tunnel                       | 200.00                                   |                    | 300.00          | 392.49          | 130.83                  |
| Moyar                               | 36.00                                    | 115.00             | 110.00          | 104.47          | 94.97                   |

**REGION/SECTOR/STATION-WISE ACTUAL GENERATION VIS-A-VIS TARGET OF H.E.STATIONS (I. C. ABOVE 25 MW ) IN THE COUNTRY DURING THE YEAR CURRENT YEAR 2021-2022**

| REGION/ UTILITY/ STATION              | INSTALLED CAPACITY AS ON 31.03.2022 (MW) | DESIGN ENERGY (MU) | 2021-2022       |                 |                         |
|---------------------------------------|------------------------------------------|--------------------|-----------------|-----------------|-------------------------|
|                                       |                                          |                    | TARGET          | ACTUAL          | % OF ACTUAL OVER TARGET |
| Papanasam                             | 32.00                                    | 105.00             | 118.00          | 163.37          | 138.45                  |
| Parson's Valley                       | 30.00                                    | 53.00              | 50.00           | 41.13           | 82.26                   |
| Periyar                               | 161.00                                   | 409.00             | 490.00          | 779.16          | 159.01                  |
| Pykara                                | 59.20                                    | 274.00             | 38.00           | 0.12            | 0.32                    |
| Pykara Ultimate                       | 150.00                                   | 30.00              | 319.00          | 322.37          | 101.06                  |
| Sarkarpathy                           | 30.00                                    | 162.00             | 121.00          | 143.41          | 118.52                  |
| Sholayar I                            | 70.00                                    | 254.00             | 254.00          | 400.15          | 157.54                  |
| Suruliyar                             | 35.00                                    | 79.00              | 100.00          | 33.24           | 33.24                   |
| <b>Total TANGEDCO</b>                 | <b>2178.20</b>                           | <b>4348.00</b>     | <b>4483.00</b>  | <b>5212.07</b>  | <b>116.26</b>           |
| <b>Total State Sector-TN</b>          | <b>2178.20</b>                           | <b>4348.00</b>     | <b>4483.00</b>  | <b>5212.07</b>  | <b>116.26</b>           |
| <b>Total Tamilnadu</b>                | <b>2178.20</b>                           | <b>4348.00</b>     | <b>4483.00</b>  | <b>5212.07</b>  | <b>116.26</b>           |
| <b>TELANGANA</b>                      |                                          |                    |                 |                 |                         |
| <b>STATE SECTOR</b>                   |                                          |                    |                 |                 |                         |
| <b>TSGENCO</b>                        |                                          |                    |                 |                 |                         |
| Lower Jurala                          | 240.00                                   | 534.43             | 370.00          | 369.90          | 99.97                   |
| N.J.Sagar PSS                         | 815.60                                   | 2237.00            | 1535.00         | 2262.45         | 147.39                  |
| N.J.Sagar LBC                         | 60.00                                    | 104.00             | 97.00           | 148.30          | 152.89                  |
| Pochampad                             | 36.00                                    | 147.00             | 75.00           | 110.79          | 147.72                  |
| Priyadarshni Jurala                   | 234.00                                   | 404.00             | 354.00          | 343.95          | 97.16                   |
| Pulichinthala                         | 120.00                                   | 219.42             | 170.00          | 315.16          | 185.39                  |
| Srisaillam LB                         | 900.00                                   | 1400.00            | 1417.00         | 2076.08         | 146.51                  |
| <b>Total TSGENCO</b>                  | <b>2405.60</b>                           | <b>5045.85</b>     | <b>4018.00</b>  | <b>5626.63</b>  | <b>140.04</b>           |
| <b>Total State Sector-Telangana</b>   | <b>2405.60</b>                           | <b>5045.85</b>     | <b>4018.00</b>  | <b>5626.63</b>  | <b>140.04</b>           |
| <b>Total Telangana</b>                | <b>2405.60</b>                           | <b>5045.85</b>     | <b>4018.00</b>  | <b>5626.63</b>  | <b>140.04</b>           |
| <b>Total Southern</b>                 | <b>11739.50</b>                          | <b>33900.85</b>    | <b>30439.00</b> | <b>37206.43</b> | <b>122.23</b>           |
| <b>EASTERN REGION</b>                 |                                          |                    |                 |                 |                         |
| <b>JHARKHAND</b>                      |                                          |                    |                 |                 |                         |
| <b>CENTRAL SECTOR</b>                 |                                          |                    |                 |                 |                         |
| <b>DVC</b>                            |                                          |                    |                 |                 |                         |
| Panchet                               | 80.00                                    | 237.00             | 108.00          | 245.47          | 227.29                  |
| <b>Total DVC</b>                      | <b>80.00</b>                             | <b>237.00</b>      | <b>108.00</b>   | <b>245.47</b>   | <b>227.29</b>           |
| <b>Total Central Sector-Jharkhand</b> | <b>80.00</b>                             | <b>237.00</b>      | <b>108.00</b>   | <b>245.47</b>   | <b>227.29</b>           |
| <b>STATE SECTOR</b>                   |                                          |                    |                 |                 |                         |
| <b>JUUNL</b>                          |                                          |                    |                 |                 |                         |
| Subernarekha I&II                     | 130.00                                   | 149.00             | 110.00          | 302.49          | 274.99                  |
| <b>Total Jharkhand</b>                | <b>130.00</b>                            | <b>149.00</b>      | <b>110</b>      | <b>302</b>      | <b>274.99</b>           |
| <b>Total State Sector-Jharkhand</b>   | <b>130.00</b>                            | <b>149.00</b>      | <b>110</b>      | <b>302</b>      | <b>274.99</b>           |
| <b>Total Jharkhand</b>                | <b>210.00</b>                            | <b>386.00</b>      | <b>218</b>      | <b>548</b>      | <b>251.36</b>           |
| <b>ODISHA</b>                         |                                          |                    |                 |                 |                         |
| <b>STATE SECTOR</b>                   |                                          |                    |                 |                 |                         |
| <b>OHPC</b>                           |                                          |                    |                 |                 |                         |
| Balimela                              | 510.00                                   | 1183.00            | 1400.00         | 1062.04         | 75.86                   |
| Hirakud I&II                          | 359.80                                   | 1174.00            | 945.00          | 975.84          | 103.26                  |
| Rengali                               | 250.00                                   | 525.00             | 782.00          | 866.39          | 110.79                  |
| Upper Indravati                       | 600.00                                   | 1962.00            | 2066.00         | 1156.65         | 55.98                   |
| Upper Kolab                           | 320.00                                   | 832.00             | 766.00          | 451.20          | 58.90                   |
| <b>Total OHPC</b>                     | <b>2039.80</b>                           | <b>5676.00</b>     | <b>5959.00</b>  | <b>4512.12</b>  | <b>75.72</b>            |
| <b>APGENCO</b>                        |                                          |                    |                 |                 |                         |
| Machkund                              | 114.75                                   | 670.00             | 612.00          | 718.51          | 117.40                  |
| <b>Total APGENCO-Odisha</b>           | <b>114.75</b>                            | <b>670.00</b>      | <b>612.00</b>   | <b>718.51</b>   | <b>117.40</b>           |
| <b>Total State Sector-Odisha</b>      | <b>2154.55</b>                           | <b>6346.00</b>     | <b>6571.00</b>  | <b>5230.63</b>  | <b>79.60</b>            |
| <b>Total Odisha</b>                   | <b>2154.55</b>                           | <b>6346.00</b>     | <b>6571.00</b>  | <b>5230.63</b>  | <b>79.60</b>            |
| <b>SIKKIM</b>                         |                                          |                    |                 |                 |                         |
| <b>CENTRAL SECTOR</b>                 |                                          |                    |                 |                 |                         |
| <b>NHPC</b>                           |                                          |                    |                 |                 |                         |
| Rangit                                | 60.00                                    | 338.61             | 345.00          | 337.70          | 97.88                   |
| Teesta-V                              | 510.00                                   | 2572.70            | 2754.00         | 2671.82         | 97.02                   |
| <b>Total NHPC</b>                     | <b>570.00</b>                            | <b>2911.31</b>     | <b>3099.00</b>  | <b>3009.52</b>  | <b>97.11</b>            |
| <b>Total Central Sector-Sikkim</b>    | <b>570.00</b>                            | <b>2911.31</b>     | <b>3099.00</b>  | <b>3009.52</b>  | <b>97.11</b>            |
| <b>STATE SECTOR</b>                   |                                          |                    |                 |                 |                         |
| <b>Teesta Urja Ltd. (TUL)</b>         |                                          |                    |                 |                 |                         |

**REGION/SECTOR/STATION-WISE ACTUAL GENERATION VIS-A-VIS TARGET OF H.E.STATIONS (I. C. ABOVE 25 MW ) IN THE COUNTRY DURING THE YEAR CURRENT YEAR 2021-2022**

| REGION/ UTILITY/ STATION                      | INSTALLED CAPACITY AS ON 31.03.2022 (MW) | DESIGN ENERGY (MU) | 2021-2022       |                 |                         |
|-----------------------------------------------|------------------------------------------|--------------------|-----------------|-----------------|-------------------------|
|                                               |                                          |                    | TARGET          | ACTUAL          | % OF ACTUAL OVER TARGET |
| Teesta III                                    | 1200.00                                  | 5214.00            | 5652.00         | 6315.53         | 111.74                  |
| <b>Total TUL</b>                              | <b>1200.00</b>                           | <b>5214.00</b>     | <b>5652.00</b>  | <b>6315.53</b>  | <b>111.74</b>           |
| <b>Total State Sector-Sikkim</b>              | <b>1200.00</b>                           | <b>5214.00</b>     | <b>5652.00</b>  | <b>6315.53</b>  | <b>111.74</b>           |
| <b>PRIVATE SECTOR</b>                         |                                          |                    |                 |                 |                         |
| <b>DANS Energy Pvt. Ltd. (DEPL)</b>           |                                          |                    |                 |                 |                         |
| Jorethang Loop                                | 96.00                                    | 459.00             | 408.00          | 424.69          | 104.09                  |
| <b>Shiga Energy Pvt. Ltd.(SEPL)</b>           |                                          |                    |                 |                 |                         |
| Tashiding                                     | 97.00                                    | 425.05             | 421.00          | 453.07          | 107.62                  |
| <b>Gati Infrastructure Pvt. Ltd. (GIPL)</b>   |                                          |                    |                 |                 |                         |
| Chuzachen HEP                                 | 110.00                                   | 537.81             | 500.00          | 514.21          | 102.84                  |
| <b>Sneha Kinetic</b>                          |                                          |                    |                 |                 |                         |
| Dikchu                                        | 96.00                                    | 431.00             | 460.00          | 481.45          | 104.66                  |
| <b>MBPC</b>                                   |                                          |                    |                 |                 |                         |
| Rongnichu                                     | 113.00                                   | 434.00             | 256.00          | 295.43          | 115.40                  |
| <b>Total Private-Sikkim</b>                   | <b>512.00</b>                            | <b>2286.86</b>     | <b>2045</b>     | <b>2169</b>     | <b>106.06</b>           |
| <b>Total Sikkim</b>                           | <b>2282.00</b>                           | <b>10412.17</b>    | <b>10796.00</b> | <b>11493.90</b> | <b>106.46</b>           |
| <b>WEST BENGAL</b>                            |                                          |                    |                 |                 |                         |
| <b>CENTRAL SECTOR</b>                         |                                          |                    |                 |                 |                         |
| <b>NHPC</b>                                   |                                          |                    |                 |                 |                         |
| Teesta Low Dam-III                            | 132.00                                   | 594.00             | 550.00          | 601.51          | 109.37                  |
| Teesta Low Dam-IV                             | 160.00                                   | 719.67             | 720.00          | 736.77          | 102.33                  |
| <b>Total NHPC</b>                             | <b>292.00</b>                            | <b>1313.67</b>     | <b>1270.00</b>  | <b>1338.28</b>  | <b>105.38</b>           |
| <b>DVC</b>                                    |                                          |                    |                 |                 |                         |
| Maithon                                       | 63.20                                    | 137.00             | 107.00          | 221.42          | 206.93                  |
| <b>Total DVC-WB</b>                           | <b>63.20</b>                             | <b>137.00</b>      | <b>107.00</b>   | <b>221.42</b>   | <b>206.93</b>           |
| <b>Total Central Sector-WB</b>                | <b>355.20</b>                            | <b>1450.67</b>     | <b>1377.00</b>  | <b>1559.70</b>  | <b>113.27</b>           |
| <b>STATE SECTOR</b>                           |                                          |                    |                 |                 |                         |
| <b>WBSEDCL</b>                                |                                          |                    |                 |                 |                         |
| Jaldhaka I                                    | 36.00                                    | 165.00             | 158.00          | 178.11          | 112.73                  |
| Purulia PSS                                   | 900.00                                   | 1235.00            | 1200.00         | 1183.71         | 98.64                   |
| Rammam II                                     | 50.00                                    | 210.00             | 220.00          | 268.32          | 121.96                  |
| <b>Total WBSEDCL</b>                          | <b>986.00</b>                            | <b>1610.00</b>     | <b>1578.00</b>  | <b>1630.14</b>  | <b>103.30</b>           |
| <b>Total State Sector -WB</b>                 | <b>986.00</b>                            | <b>1610.00</b>     | <b>1578.00</b>  | <b>1630.14</b>  | <b>103.30</b>           |
| <b>Total West Bengal</b>                      | <b>1341.20</b>                           | <b>3060.67</b>     | <b>2955.00</b>  | <b>3189.84</b>  | <b>107.95</b>           |
| <b>Total Eastern</b>                          | <b>5987.75</b>                           | <b>20204.84</b>    | <b>20540.00</b> | <b>20462.33</b> | <b>99.62</b>            |
| <b>NORTH EASTERN REGION</b>                   |                                          |                    |                 |                 |                         |
| <b>ARUNACHAL PRADESH</b>                      |                                          |                    |                 |                 |                         |
| <b>CENTRAL SECTOR</b>                         |                                          |                    |                 |                 |                         |
| <b>NHPC</b>                                   |                                          |                    |                 |                 |                         |
| Lower Subansiri                               |                                          |                    |                 |                 |                         |
| <b>Total NHPC-Ar. Pradesh</b>                 |                                          |                    |                 |                 |                         |
| <b>NEEPCO</b>                                 |                                          |                    |                 |                 |                         |
| Kameng                                        | 600.00                                   | 3353.00            | 2600.00         | 2576.38         | 99.09                   |
| Pare                                          | 110.00                                   | 506.42             | 460.00          | 430.57          | 93.60                   |
| Ranganadi                                     | 405.00                                   | 1509.66            | 1270.00         | 1154.33         | 90.89                   |
| <b>Total NEEPCO-Arunachal Pradesh</b>         | <b>1115.00</b>                           | <b>5369.08</b>     | <b>4330.00</b>  | <b>4161</b>     | <b>96.10</b>            |
| <b>Total Central Sector-Arunachal Pradesh</b> |                                          |                    | <b>4330.00</b>  | <b>4161.28</b>  | <b>96.10</b>            |
| <b>Total Arunachal Pradesh</b>                | <b>1115.00</b>                           | <b>5369.08</b>     | <b>4330.00</b>  | <b>4161.28</b>  | <b>96.10</b>            |
| <b>ASSAM</b>                                  |                                          |                    |                 |                 |                         |
| <b>CENTRAL SECTOR</b>                         |                                          |                    |                 |                 |                         |
| <b>NEEPCO</b>                                 |                                          |                    |                 |                 |                         |
| Kopili                                        | 200.00                                   | 1186.14            | 0.00            | 0.00            |                         |
| Khandong                                      | 50.00                                    | 363.95             | 176.00          | 275.12          | 156.32                  |
| <b>Total NEEPCO-Assm</b>                      | <b>250.00</b>                            | <b>1550.09</b>     | <b>176.00</b>   | <b>275.12</b>   | <b>156.32</b>           |
| <b>Total Central Sector-Assam</b>             | <b>250.00</b>                            | <b>1550.09</b>     | <b>176.00</b>   | <b>275.12</b>   | <b>156.32</b>           |
| <b>STATE SECTOR</b>                           |                                          |                    |                 |                 |                         |
| <b>APGCL</b>                                  |                                          |                    |                 |                 |                         |
| Karbi Langpi                                  | 100.00                                   | 390.00             | 380.00          | 401.12          | 105.56                  |
| <b>Total APGCL</b>                            | <b>100.00</b>                            | <b>390.00</b>      | <b>380.00</b>   | <b>401.12</b>   | <b>105.56</b>           |

**REGION/SECTOR/STATION-WISE ACTUAL GENERATION VIS-A-VIS TARGET OF H.E.STATIONS (I. C. ABOVE 25 MW ) IN THE COUNTRY DURING THE YEAR CURRENT YEAR 2021-2022**

| REGION/ UTILITY/ STATION      | INSTALLED CAPACITY AS ON 31.03.2022 (MW) | DESIGN ENERGY (MU) | 2021-2022 |           |                         |
|-------------------------------|------------------------------------------|--------------------|-----------|-----------|-------------------------|
|                               |                                          |                    | TARGET    | ACTUAL    | % OF ACTUAL OVER TARGET |
| Total State Sector-Assam      | 100.00                                   | 390.00             | 380.00    | 401.12    | 105.56                  |
| Total Assam                   | 350.00                                   | 1940.09            | 556.00    | 676.24    | 121.63                  |
| <b>NAGALAND</b>               |                                          |                    |           |           |                         |
| CENTRAL SECTOR                |                                          |                    |           |           |                         |
| NEEPCO                        |                                          |                    |           |           |                         |
| Doyang                        | 75.00                                    | 227.24             | 221.00    | 100.55    | 45.50                   |
| Total NEEPCO-Nagaland         | 75.00                                    | 227.24             | 221.00    | 100.55    | 45.50                   |
| Total Central Sector-Nagaland | 75.00                                    | 227.24             | 221.00    | 100.55    | 45.50                   |
| Total Nagaland                | 75.00                                    | 227.24             | 221.00    | 100.55    | 45.50                   |
| <b>MANIPUR</b>                |                                          |                    |           |           |                         |
| CENTRAL SECTOR                |                                          |                    |           |           |                         |
| NHPC                          |                                          |                    |           |           |                         |
| Loktak (Manipur)              | 105.00                                   | 448.00             | 500.00    | 455.48    | 91.10                   |
| Total NHPC-Manipur            | 105.00                                   | 448.00             | 500.00    | 455.48    | 91.10                   |
| Total Central Sector-Manipur  | 105.00                                   | 448.00             | 500.00    | 455.48    | 91.10                   |
| Total Manipur                 | 105.00                                   | 448.00             | 500.00    | 455.48    | 91.10                   |
| <b>MEGHALAYA</b>              |                                          |                    |           |           |                         |
| STATE SECTOR                  |                                          |                    |           |           |                         |
| MePGCL                        |                                          |                    |           |           |                         |
| Kyrdemkulai                   | 60.00                                    | 118.00             | 126.00    | 110.21    | 87.47                   |
| Myntdu                        | 126.00                                   | 128.00             | 461.00    | 380.37    | 82.51                   |
| New Umtru                     | 40.00                                    | 235.00             | 184.00    | 160.81    | 87.40                   |
| Umium St.I                    | 36.00                                    | 324.00             | 106.00    | 64.91     | 61.24                   |
| Umium St.IV                   | 60.00                                    | 372.69             | 174.00    | 125.52    | 72.14                   |
| Total MePGCL                  | 322.00                                   | 1177.69            | 1051.00   | 841.82    | 80.10                   |
| Total State Sector-Meghalaya  | 322.00                                   | 1177.69            | 1051.00   | 841.82    | 80.10                   |
| Total Meghalaya               | 322.00                                   | 1177.69            | 1051.00   | 841.82    | 80.10                   |
| <b>MIZORAM</b>                |                                          |                    |           |           |                         |
| CENTRAL SECTOR                |                                          |                    |           |           |                         |
| Tuirial                       | 60.00                                    | 250.63             | 181.00    | 137.44    | 75.93                   |
| Total NEEPCO-Mizoram          | 60.00                                    | 250.63             | 181.00    | 137.44    | 75.93                   |
| Total Central Sector-Mizoram  | 60.00                                    | 250.63             | 181.00    | 137.44    | 75.93                   |
| Total Mizoram                 | 60.00                                    | 250.63             | 181.00    | 137.44    | 75.93                   |
| Total N.Eastern               | 2027.00                                  | 9412.73            | 6839.00   | 6372.81   | 93.18                   |
| Total All India               | 46722.52                                 | 155875.89          | 149544    | 151627.33 | 101.39                  |
| IMPORT FROM BHUTAN            |                                          |                    | 8765.50   | 8765.50   | 100.00                  |

# CHAPTER-3

## MAJOR RESERVOIR BASED HE STATIONS

## CHAPTER – 3

### MAJOR RESERVOIR/ STORAGE BASED H.E. STATIONS

#### 3.1 Introduction

Some of the hydro-electric schemes are provided with storage reservoirs. The excess water during monsoon period after generation is stored in these reservoirs which are utilized to augment flows during non-monsoon period. The regulated discharges from reservoirs are utilized for power generation, irrigation and other purposes. Reservoir based schemes are of two types i.e. single purpose and multipurpose. Single purpose schemes are operated in the interest of power generation while the multipurpose storage schemes are operated for more than one purpose with irrigation, water supply, flood control, pisciculture, navigation, etc. as primary objectives and power generation as incidental. Reservoir based schemes afford greater utilization of the available inflows approaching to long term average inflows resulting in greater firm power benefits. These schemes are the source of flexible generation and can be operated as base load or peaking station depending upon the requirement of the Grid System.

#### 3.2 Major Reservoir Based Stations

CEA is presently monitoring 44 H.E. Stations of aggregate installed capacity of 18277.65 MW in the country on 37 major reservoirs as listed below:

| S. No.         | H.E. Stations   | Installed Capacity (MW) | Utility | State            | Reservoirs   |                                               |
|----------------|-----------------|-------------------------|---------|------------------|--------------|-----------------------------------------------|
|                |                 |                         |         |                  | Name         | Multipurpose (MP)/ Storage (S) for Power Only |
|                | Northern Region |                         |         |                  |              |                                               |
| 1              | Bhakra (L)      | 612                     | BBMB    | Himachal Pradesh | Bhakra       | MP                                            |
| 2              | Bhakra (R)      | 785                     | BBMB    |                  | Pong         | MP                                            |
| 3              | Pong            | 396                     | BBMB    |                  |              |                                               |
| 4              | Chamera-I       | 540                     | NHPC    | Himachal Pradesh | Chamera      | S                                             |
| 5              | Ranjit Sagar    | 600                     | PSPCL   | Punjab           | Ranjit Sagar | MP                                            |
| 6              | Tehri           | 1000                    | THDC    | Uttarakhand      | Tehri        | MP                                            |
| 7              | Ram Ganga       | 198                     | UJVNL   | Uttarakhand      | Ram Ganga    | MP                                            |
| 8              | Rihand          | 300                     | UPJVNL  | Uttar Pradesh    | Rihand       | MP                                            |
| 9              | RP Sagar        | 172                     | RRVUNL  | Rajasthan        | RP Sagar     | MP                                            |
| Sub-Total (NR) |                 | 4603                    |         |                  |              |                                               |

| S. No.         | H.E. Stations           | Installed Capacity (MW) | Utility   | State          | Reservoirs      |                                           |
|----------------|-------------------------|-------------------------|-----------|----------------|-----------------|-------------------------------------------|
|                |                         |                         |           |                | Name            | Multipurpose (MP)/ Storage for Power Only |
|                | Western Region          |                         |           |                |                 |                                           |
| 10             | Ukai                    | 300                     | GSECL     | Gujarat        | Ukai            | MP                                        |
| 11             | Sardar Sarovar (RBPH)   | 1200                    | SSNNL     | Gujarat        | Sardar Sarovar  | MP                                        |
| 12             | Gandhi Sagar            | 115                     | MPPGCL    | Madhya Pradesh | Gandhi Sagar    | MP                                        |
| 13             | Bansagar-III            | 30                      | MPPGCL    | Madhya Pradesh | Bansagar        | MP                                        |
| 14             | Indira Sagar            | 1000                    | NHDC      | Madhya Pradesh | Indira Sagar    | MP                                        |
| 15             | Koyna-I&II              | 600                     | MAHAGENCO | Maharashtra    | Koyna           | MP                                        |
| 16             | Koyna-IV                | 1000                    | MAHAGENCO | Maharashtra    |                 |                                           |
| 17             | Koyna DPH               | 36                      | MAHAGENCO | Maharashtra    |                 |                                           |
| 18             | Pench                   | 160                     | MPPGCL    | Maharashtra    | Pench           | MP                                        |
| 19             | Bhira                   | 150                     | TPCL      | Maharashtra    | Bhira           | MP                                        |
| 20             | Bhira PSS               | 150                     |           |                |                 |                                           |
| Sub-Total (WR) |                         | 4741                    |           |                |                 |                                           |
|                | Southern Region         |                         |           |                |                 |                                           |
| 21             | Upper Sileru            | 240                     | APGENCO   | Andhra Pradesh | Sileru          | S                                         |
| 22             | Lower Sileru            | 460                     | APGENCO   | Andhra Pradesh |                 |                                           |
| 23             | Srisaillam RB           | 770                     | APGENCO   | Andhra Pradesh | Srisaillam      | MP                                        |
| 24             | NJ Sagar + NJ Sagar PSS | 815.6                   | TSGENCO   | Telangana      | Nagarjuna Sagar | MP                                        |
| 25             | Sharavathy              | 1035                    | KPCL      | Karnataka      | Sharavathy      | S                                         |
| 26             | Kalinadi (Nagjhari)     | 900                     | KPCL      | Karnataka      | Supa            | S                                         |
| 27             | Supa DPH                | 100                     | KPCL      | Karnataka      |                 |                                           |
| 28             | Almatti                 | 290                     | KPCL      | Karnataka      | Almatti         | MP                                        |
| 29             | Varahi                  | 460                     | KPCL      | Karnataka      | Varahi          | S                                         |
| 30             | Idukki                  | 780                     | KSEB      | Kerala         | Idukki          | MP                                        |
| 31             | Sabarigiri              | 300                     | KSEB      | Kerala         | Sabarigiri      | MP                                        |
| 32             | Pallivasal              | 37.5                    | KSEB      | Kerala         | Madupetty       | S                                         |
| 33             | Idamalayar              | 75                      | KSEB      | Kerala         | Idamalayar      | MP                                        |
| 34             | Mettur Dam              | 50                      | TANGEDCO  | Tamil Nadu     | Mettur          | MP                                        |


| S. No.                                  | H.E. Stations         | Installed Capacity (MW) | Utility  | State      | Reservoirs  |                                           |
|-----------------------------------------|-----------------------|-------------------------|----------|------------|-------------|-------------------------------------------|
|                                         |                       |                         |          |            | Name        | Multipurpose (MP)/ Storage for Power Only |
| 35                                      | Mettur Tunnel         | 200                     | TANGEDCO | Tamil Nadu | Mettur      | MP                                        |
| 36                                      | Periyar               | 161                     | TANGEDCO | Tamil Nadu | Periyar     | MP                                        |
| <b>Sub-Total (SR)</b>                   |                       | <b>6674.10</b>          |          |            |             |                                           |
| <b>Eastern and North Eastern Region</b> |                       |                         |          |            |             |                                           |
| 37                                      | Machkund              | 114.75                  | APGENCO  | Odisha     | Machkund    | MP                                        |
| 38                                      | Hirakud I (Burla)     | 287.8                   | OHPC     | Odisha     | Hirakud     | MP                                        |
| 39                                      | Hirakud II (Chiplima) | 72                      |          |            |             |                                           |
| 40                                      | Balimela              | 510                     | OHPC     | Odisha     | Balimela    | MP                                        |
| 41                                      | Indravati             | 600                     | OHPC     | Odisha     | Indravati   | MP                                        |
| 42                                      | Upper Kolab           | 320                     | OHPC     | Odisha     | Upper Kolab | MP                                        |
| 43                                      | Rengali               | 250                     | OHPC     | Odisha     | Rengali     | MP                                        |
| 44                                      | Loktak                | 105                     | NHPC     | Manipur    | Loktak      | MP                                        |
| <b>Sub-Total (ER/NER)</b>               |                       | <b>2259.55</b>          |          |            |             |                                           |
| <b>Total (All India)</b>                |                       | <b>18277.65</b>         |          |            |             |                                           |

Salient details of 37 Nos. Major reservoirs are indicated in **Annex-3.1**. These stations constitute about 39.11% (31.04% Multipurpose & 8.07% Storage for power only) of the total hydel installed capacity and generated about 30.09% (23.49% Multipurpose & 6.6% Storage for power only) of the total Hydel generation during 2021-22 as briefly indicated in **Table-3.1**.





**TABLE - 3.1**

**CONTRIBUTION BY IMPORTANT RESERVOIR (STORAGE) BASED H.E. STATIONS**





| S. No. | Description             | Major Reservoir Based Stations |                        | Other Stations | Total     |
|--------|-------------------------|--------------------------------|------------------------|----------------|-----------|
|        |                         | Multipurpose (MP)              | Storage for Power only |                |           |
| 1.     | Installed Capacity (MW) | 14505                          | 3772.5                 | 28444.85       | 46722.50  |
|        | Percentage of Total (%) | 31.04                          | 8.07                   | 60.88          | 100       |
| 2.     | Energy Generation (MU)  | 35619.98                       | 10061                  | 105946.35      | 151627.33 |
|        | Percentage of Total (%) | 23.49                          | 6.6                    | 69.87          | 100       |







MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS







MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS







MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS







MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS







MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS







MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS







MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS




MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS



MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS



MONTH-WISE MAXIMUM LEVEL OF IMPORTANT RESERVOIRS



### 3.3 Inflows

Inflows to the reservoirs are primarily dependent on rainfall during monsoon in the catchment area of the reservoirs. However, in case of the hydro projects in Himalayan Region including Bhakra, Pong, Ranjit Sagar and Tehri projects etc., snow melt in the catchment area during summer also contributes to their inflows. The inflows into the reservoirs during 2021-22 vis-à-vis 2020-21 are given at **Exhibit 3.1**. Inflows into the reservoirs and generation during the year 2021-22 vis-à-vis 2020-21 and 10 years average is given below at **Table-3.2**.

**TABLE 3.2**  
**HYDRO RESERVOIRS (STORAGE TYPE) - INFLOW & ENERGY GENERATION**

| S. No                  | STATION        | Inflows                |               |               |                                       | Generation            |              |              |                                               |
|------------------------|----------------|------------------------|---------------|---------------|---------------------------------------|-----------------------|--------------|--------------|-----------------------------------------------|
|                        |                | 10 years Average (MCM) | 2020-21 (MCM) | 2021-22 (MCM) | 2021-22 Inflow as % of 2020-21 inflow | 10 years Average (MU) | 2020-21 (MU) | 2021-22 (MU) | 2021-22 generation as compared to 2020-21 (%) |
| 1                      | 2              | 3                      | 4             | 5             | 6=<br>(5/4*100)                       | 7                     | 8            | 9            | 10=<br>(9/8*100)                              |
| <b>Northern Region</b> |                |                        |               |               |                                       |                       |              |              |                                               |
| 1                      | Bhakra         | 17369                  | 16600         | 15347         | 108                                   | 5467                  | 5436         | 4358         | 80                                            |
| 2                      | Pong           | 8843                   | 6946          | 7396          | 94                                    | 1579                  | 1776         | 1104         | 62                                            |
| 3                      | RanjitSagar    | 6298                   | 5536          | 5036          | 110                                   | 1715                  | 1499         | 1163         | 78                                            |
| 4                      | Chamera-I*     | 6156                   | 5494          | 5197          | 106                                   | 2474                  | 2265         | 1899         | 84                                            |
| 5                      | Tehri          | 7378                   | 6564          | 7241          | 91                                    | 3283                  | 3040         | 3098         | 102                                           |
| 6                      | Ram Ganga      | 3359                   | 1240          | 26320         | 5                                     | 277                   | 261          | 249          | 96                                            |
| 7                      | RP Sagar       | 4127                   | 1266          | 0             | 0                                     | 353                   | 10           | 83           | 827                                           |
| 8                      | Rihand         | 5119                   | 6615          | 5184          | 128                                   | 547                   | 791          | 646          | 82                                            |
| <b>Sub Total (NR)</b>  |                | <b>58649</b>           | <b>58649</b>  | <b>50260</b>  | <b>45400</b>                          | <b>111</b>            | <b>15695</b> | <b>15078</b> | <b>84</b>                                     |
| <b>Western Region</b>  |                |                        |               |               |                                       |                       |              |              |                                               |
| 9                      | Ukai           | 7229                   | 9862          | 9911          | 100                                   | 522                   | 651          | 655          | 101                                           |
| 10                     | Sardar Sarovar | 28585                  | 32209         | 13837         | 233                                   | 2497                  | 3245         | 1748         | 54                                            |
| 11                     | Gandhi Sagar   | 4220                   | 4041          | 4182          | 97                                    | 270                   | 148          | 212          | 143                                           |
| 12                     | Bansagar*      | 4677                   | 6493          | 4453          | 146                                   | 83                    | 136          | 135          | 100                                           |
| 13                     | Pench*         | 987                    | 2768          | 848           | 327                                   | 316                   | 415          | 304          | 73                                            |
| 14                     | Indira Sagar   | 22922                  | 30816         | 3047          | 1011                                  | 2536                  | 2794         | 1717         | 61                                            |
| 15                     | Koyna          | 3535                   | 134           | 160           | 84                                    | 1146                  | 3173         | 3639         | 115                                           |
| 16                     | Bhira          | 907                    | 984           | 893           | 110                                   | 626                   | 945          | 1025         | 108                                           |
| <b>Sub Total (WR)</b>  |                | <b>73062</b>           | <b>87307</b>  | <b>37331</b>  | <b>234</b>                            | <b>7996</b>           | <b>11506</b> | <b>9436</b>  | <b>82</b>                                     |

| <b>Southern Region</b>      |               |                        |               |               |                                       |                       |              |              |                                               |
|-----------------------------|---------------|------------------------|---------------|---------------|---------------------------------------|-----------------------|--------------|--------------|-----------------------------------------------|
| S. No.                      | STATION       | Inflows                |               |               |                                       | Generation            |              |              |                                               |
|                             |               | 10 years Average (MCM) | 2020-21 (MCM) | 2021-22 (MCM) | 2021-22 Inflow as % of 2020-21 inflow | 10 years Average (MU) | 2020-21 (MU) | 2021-22 (MU) | 2021-22 generation as compared to 2020-21 (%) |
|                             |               |                        |               |               | 6=<br>(5/4*100)                       |                       |              |              | 10=<br>(9/8*100)                              |
| 1                           | 2             | 3                      | 4             | 5             |                                       | 7                     | 8            | 9            |                                               |
| 17                          | Srisailem     | 18783                  | 46722         | 31499         | 148                                   | 935                   | 1157         | 1439         | 116                                           |
| 18                          | Upper Sileru* | 2199                   | 7813          | 1533          | 510                                   | 462                   | 620          | 362          | 103                                           |
| 19                          | Lower Sileru* | 3255                   | 4732          | 1997          | 237                                   | 1089                  | 1293         | 896          | 66                                            |
| 20                          | N.J. Sagar    | 81411                  | 39861         | 25738         | 155                                   | 79                    | 210          | 417          | 86                                            |
| 21                          | Sharavathy    | 4520                   | 5103          | 4914          | 104                                   | 4384                  | 4583         | 4994         | 112                                           |
| 22                          | Supa          | 2668                   | 3138          | 3113          | 101                                   | 438                   | 444          | 610          | 132                                           |
| 23                          | Almatti       | 12367                  | 20209         | 694           | 2911                                  | 450                   | 644          | 500          | 98                                            |
| 24                          | Varahi*       | 491                    | 655           | 646           | 101                                   | 1028                  | 1093         | 1137         | 108                                           |
| 25                          | Idukki        | 1581                   | 1491          | 2723          | 55                                    | 2223                  | 2530         | 3710         | 72                                            |
| 26                          | Sabarigiri    | 874                    | 857           | 1367          | 63                                    | 1210                  | 1228         | 2047         | 91                                            |
| 27                          | Madupetty     | 216                    | 201           | 117           | 172                                   | 197                   | 134          | 162          | 106                                           |
| 28                          | Idamalayar    | 1124                   | 999           | 1433          | 70                                    | 304                   | 290          | 377          | 90                                            |
| 29                          | Mettur        | 5156                   | 5435          | 6903          | 79                                    | 288                   | 471          | 528          | 110                                           |
| 30                          | Periyar       | 576                    | 742           | 1024          | 73                                    | 395                   | 548          | 779          | 92                                            |
| <b>Sub Total (SR)</b>       |               | <b>135221</b>          | <b>137959</b> | <b>83701</b>  | <b>165</b>                            | <b>13482</b>          | <b>15244</b> | <b>17958</b> | <b>118</b>                                    |
| <b>Eastern Region</b>       |               |                        |               |               |                                       |                       |              |              |                                               |
| 31                          | Machkund      | 1255                   | 1139          | 1081          | 105                                   | 564                   | 666          | 719          | 108                                           |
| 32                          | Hirakud       | 25715                  | 39601         | 20631         | 192                                   | 845                   | 953          | 976          | 102                                           |
| 33                          | Balimela      | 3530                   | 4677          | 3016          | 155                                   | 1223                  | 1656         | 1062         | 64                                            |
| 34                          | Indravati     | 3209                   | 2208          | 1402          | 158                                   | 1936                  | 1757         | 1157         | 66                                            |
| 35                          | Upper Kolab   | 1981                   | 1179          | 910           | 130                                   | 717                   | 813          | 451          | 56                                            |
| 36                          | Rengali       | 9628                   | 12718         | 14087         | 90                                    | 693                   | 1015         | 866          | 85                                            |
| <b>Sub Total (ER)</b>       |               | <b>45318</b>           | <b>61522</b>  | <b>41127</b>  | <b>150</b>                            | <b>5978</b>           | <b>6860</b>  | <b>5231</b>  | <b>76</b>                                     |
| <b>North Eastern Region</b> |               |                        |               |               |                                       |                       |              |              |                                               |
| 37                          | Loktak        | 2522                   | 2425          | 1159          | 209                                   | 580                   | 622          | 455          | 73                                            |
| <b>Sub Total (NER)</b>      |               | <b>2242</b>            | <b>2425</b>   | <b>1159</b>   | <b>209</b>                            | <b>580</b>            | <b>580</b>   | <b>622</b>   | <b>455</b>                                    |
| <b>Total (All India)</b>    |               | <b>314492</b>          | <b>339473</b> | <b>235039</b> | <b>144</b>                            | <b>43731</b>          | <b>49310</b> | <b>45681</b> | <b>93</b>                                     |

\* Only 4 years average inflows available.

### 3.4 Reservoir Levels

The maximum reservoir level attained during the year depends on the depleted reservoir level in the preceding year, besides the inflows during the current year. Water level touched FRL at Chamara, Bansagar, Koyna, Bhira, Lower Sileru, Almatti, Sabirigiri, Madupetty, Idamalayar, Mettur, Periyar, Rengali and Loktak reservoirs during 2017-18. Month-wise maximum levels of major reservoirs during 2021-22 vis-à-vis 2020-21 are indicated at **Exhibits 3.2** to **Exhibits 3.11**.

### 3.5 Generation

Generation from reservoir (storage) based H.E. Stations during the year, apart from priorities of releases for other purposes like irrigation, drinking water etc., depends on various factors such as water level of the reservoir at the end of the preceding year, inflows during the year, draw down level by the end of the year, availability of generating units etc. In 19 Nos. out of 44 Nos. reservoir based hydel stations, annual generation during the year 2021-22 was more than the annual generation targets. Generation from 44 H.E. Stations on 37 major reservoirs during the year 2020-21 has been 45681 MU, showing decrease by 9.3 % over the 2020-21 generation of 49310 MU. Station-wise generation of reservoir stations during the year 2021-22 as compared to that of last year 2020-21 is shown in **Table 3.2** above. The reservoir based stations have been grouped in terms of percentage achievement of generation over targets in **Table 3.3** below:


**TABLE 3.3**

#### **GENERATION PERFORMANCE OF MAJOR RESERVOIR BASED STATIONS**

| S. No. | % of Actual Generation over Target | Reservoir based Stations |                                     |                                                                                                                    |
|--------|------------------------------------|--------------------------|-------------------------------------|--------------------------------------------------------------------------------------------------------------------|
|        |                                    | No.                      | % of total Reservoir based Stations | Name                                                                                                               |
| 1      | 120 & Above                        | 10                       | 22.72                               | Ranjit Sagar, Gandhi Sagar, Srisaïlam RB, NJ Sagar, Kalinadi, Idukki, Sabarigiri, Pallivasal, Idamalayar, Periyar. |
| 2      | 110 - 120                          | 2                        | 4.54                                | Koyna-I&II, Mettur Dam                                                                                             |
| 3      | 100 - 110                          | 7                        | 15.90                               | Tehri, Ukai, Bhira, Sharavathy, Varahi, Machkund, Hirakud I                                                        |

|   |           |    |       |                                                                                                                                                                                                            |
|---|-----------|----|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 4 | Below 100 | 18 | 40.90 | Bhakra, Pong, Chamera-I, Ranjit Sagar, Ram Ganga, Rihand, Sardar Sarovar (RBPH), Bansagar-III, Indira Sagar, Pench, Upper Sileru, Lower Sileru, Almatti, Balimela, Indravati, Upper Kolab, Rengali, Loktak |
|---|-----------|----|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Generation of major reservoir based H.E. stations during 2021-22 as compared to the generation during last year i.e. 2020-21 is also depicted at **Exhibit-3.12**.



## SALIENT DETAILS OF IMPORTANT RESERVOIRS AND ASSOCIATED H.E. STATIONS

| S. No           | NAME OF RESERVOIR AND ASSOCIATED HE STATIONS | INSTALLED CAPACITY AS ON 31.03.2021 | ANNUAL DESIGN ENERGY | FULL RESER-VOIR LEVEL | MINIMUM DRAW DOWN LEVEL | RESERVOIR CAPACITY AT FRL |          | ENERGY CONTENT AT FRL | LEVELS ATTAINED DURING 2020-21 |                           |           |            |
|-----------------|----------------------------------------------|-------------------------------------|----------------------|-----------------------|-------------------------|---------------------------|----------|-----------------------|--------------------------------|---------------------------|-----------|------------|
|                 |                                              |                                     |                      |                       |                         | GROSS : LIVE              |          |                       | Max.                           | DATE                      | Min       | DATE       |
|                 |                                              | (MW)                                | (MU)                 | (M)                   | (M)                     | (MCM)                     | ( MCM)   | (MU)                  | (M)                            |                           | (M)       |            |
| NORTHERN REGION |                                              |                                     |                      |                       |                         |                           |          |                       |                                |                           |           |            |
| 1               | Bhakra                                       | 1379.00                             | 3924                 | 513.59                | 445.62                  | 8321                      | 6516     | 1729.00               | 506.80                         | 09.09.2020                | 468.45    | 31.03.2021 |
| a               | Bhakra Left                                  | 594.00                              | 3924                 |                       |                         |                           |          |                       |                                |                           |           |            |
| b               | Bhakra Right                                 | 785.00                              |                      |                       |                         |                           |          |                       |                                |                           |           |            |
| 2               | Pong                                         | 396.00                              | 1123                 | 426.72                | 384.05                  | 8053                      | 6946     | 1084.00               | 424.45                         | 01.10.18                  | 389.82    | 28.06.18   |
| 3               | Chamera                                      | 540.00                              | 1664.56              | 760.00                | 749.20                  |                           | 87       |                       | 759.96                         | 20.07.2020                | 751.21    | 20.02.2021 |
| 4               | Ranjit Sagar                                 | 600.00                              | 1507                 | 527.91                | 487.91                  | 3292                      | 2191     | 390.00                | 516.16                         | 16 & 17.09.20             | 493.12    | 28.01.21   |
| 5               | Tehri                                        | 1000.00                             | 2797                 | 829.79                | 740.04                  | 3540                      | 2615     | 1291.49               | 827.84                         | 16.10.2020                | 744.44    | 24.06.2020 |
| 6               | Ramganga                                     | 198.00                              | 334                  | 366                   | 323                     | 2503.96                   | 2109.25  | 480.80                | 359.16                         | 13.11.2020                | 342.14    | 31.03.2021 |
| 7               | Rana Pratap Sagar                            | 172.00                              | 459                  | 352.81                | 343.83                  | 2901                      | 1569     | 175.66                | 281.59                         | 01.10.2020                | 270.09    | 01.07.2020 |
| 8               | Rihand                                       | 300.00                              | 920                  | 268.22                | 252.98                  | 10605                     | 5723     | 1177.00               | 264.57                         | 12.10.2020                | 256.00    | 17.06.2020 |
|                 | Sub-Total NR                                 | 4585.00                             | 12728.56             |                       |                         |                           | 27756.25 |                       |                                |                           |           |            |
| WESTERN REGION  |                                              |                                     |                      |                       |                         |                           |          |                       |                                |                           |           |            |
| 9               | Ukai                                         | 300.00                              | 1080                 | 105.16                | 82.30                   | 8515                      | 6615     | 813.00                | 105.16                         | 01.10.2020                | 97.07     | 30.06.2020 |
| 10              | Sardar Sarovar                               | 1200.00                             | 3635                 | 138.68                | 110.18                  | 9460                      | 5760     | 1817.553              | 138.68                         | 17.09.2020                | 119.29    | 08.04.2020 |
| 11              | Gandhi Sagar                                 | 115.00                              | 420                  | 399.90                | 381.00                  | 7743                      | 6911     | 725.00                | 399.53                         | 04.10.20                  | 394.00    | 31.01.21   |
| 12              | Bansagar                                     | 60.00                               | 143                  | 341.64                | 323.10                  |                           | 4934     |                       | 341.52                         | 01.10.2020                | 335.17    | 31.03.2021 |
| 13              | Pench                                        | 160.00                              | 315                  | 490.00                | 464.00                  |                           | 1045     |                       | 489.99                         | 12.10.2020                | 486.16    | 12.06.2020 |
| 14              | Indira Sagar                                 | 1000.00                             | 1980                 | 262.13                | 243.23                  | 12237                     | 9706     | 1316.12               | 262.13                         | 08.10.2020                | 248.56    | 05.07.2020 |
| 15              | Koyna                                        | 1636.00                             | 3030                 | 657.91                | 609.60                  | 2797                      | 2677     | 3126.00               | 659.43                         | 30.09.2020                | 634.06    | 01.07.2020 |
| a               | Koyna-I & II                                 | 600.00                              | 3030                 |                       |                         |                           |          |                       |                                |                           |           |            |
| c               | Koyna-I & II                                 | 1000                                |                      |                       |                         |                           |          |                       |                                |                           |           |            |
| d               | Koyna DPH                                    | 36                                  |                      |                       |                         |                           |          |                       |                                |                           |           |            |
| 16              | Bhira                                        | 300                                 | 775                  | 606.05                | 590.09                  | 523                       | 522      | 619                   | 606.12                         | 01.09.2020                | 591.71    | 03.07.2020 |
|                 | Sub-Total WR                                 | 4771.00                             | 11378.84             |                       |                         |                           | 38170.33 |                       |                                |                           |           |            |
| SOUTHERN REGION |                                              |                                     |                      |                       |                         |                           |          |                       |                                |                           |           |            |
| 17              | Upper Sileru                                 | 240.00                              | 529                  | 414.53                | 406.51                  |                           | 88       |                       | 413.73                         | 16.08.2020                | 407.97    | 17.04.2020 |
| 18              | Lower Sileru                                 | 460.00                              | 1070                 | 316.08                | 291.01                  |                           | 365      |                       | 316.07                         | 10.10.2020                | 304.89    | 04.04.2020 |
| 19              | Srisaillam                                   | 770.00                              | 2900                 | 269.74                | 243.84                  | 8723                      | 7166     | 1548.00               | 269.74                         | 01.11.2020                | 247.16    | 26.06.2020 |
| 20              | Nagarjuna Sagar                              | 815.60                              | 2237                 | 179.83                | 150.89                  | 11560                     | 6538     | 1398.00               | 179.88                         | 27.9.20, 27.10.20,        | 161.52    | 20.07.2020 |
| 21              | Sharavathy                                   | 1035.00                             | 4932                 | 554.43                | 522.73                  | 5310                      | 4297     | 4394.00               | 553.56                         | 2020 & 18.10.             | 534.80    | 01.07.2020 |
| 22              | SUPA                                         | 955.00                              | 3927                 | 564.00                | 513.50                  | 4178                      | 3758     | 3927.00               | 558.93                         | 29.09.2020, 30.09.2020    | 527.56003 | 03.07.2020 |
| 23              | Almatti                                      | 290.00                              | 483                  | 519.60                | 511.10                  | 2631.50                   | 2628.00  | 175.30                | 519.60                         | 31.08.2020,01.09.2020,01. | 509.40    | 04.06.2020 |

## SALIENT DETAILS OF IMPORTANT RESERVOIRS AND ASSOCIATED H.E. STATIONS

| S. No                | NAME OF RESERVOIR AND ASSOCIATED HE STATIONS | INSTALLED CAPACITY AS ON 31.03.2021 | ANNUAL DESIGN ENERGY | FULL RESER-VOIR LEVEL | MINIMUM DRAW DOWN LEVEL | RESERVOIR CAPACITY AT FRL |           | ENERGY CONTENT AT FRL | LEVELS ATTAINED DURING 2020-21 |              |         |            |
|----------------------|----------------------------------------------|-------------------------------------|----------------------|-----------------------|-------------------------|---------------------------|-----------|-----------------------|--------------------------------|--------------|---------|------------|
|                      |                                              |                                     |                      |                       |                         | GROSS : LIVE              |           |                       | Max.                           | DATE         | Min     | DATE       |
|                      |                                              | (MW)                                | (MU)                 | (M)                   | (M)                     | (MCM)                     | ( MCM)    | (MU)                  | (M)                            |              | (M)     |            |
| 24                   | Varahi                                       | 460.00                              | 1060                 | 594.36                | 565.10                  |                           | 881.50    |                       | 589.20                         | 17th to 20th | 571.74  | 13.06.2020 |
| 25                   | Idukki                                       | 780.00                              | 2398                 | 732.40                | 694.94                  | 1996                      | 1459      | 2146.00               | 731.20                         | 26.10.2020   | 709.71  | 02.07.2020 |
| 26                   | Sabirigiri                                   | 300.00                              | 1338                 | 981.46                | 908.30                  | 454                       | 447       | 764.00                | 979.03                         | 23.10.2020   | 938.07  | 11.06.2020 |
| 27                   | Madupetty                                    | 37.50                               | 284                  | 1599.50               | 1554.48                 |                           | 55.32     | 77.40                 | 1598.30                        | 11.12.2020   | 1567.60 | 30.06.2020 |
| 28                   | Idamalayar                                   | 75.00                               | 380                  | 169.00                | 115.00                  |                           | 1017.80   | 254.45                | 164.74                         | 20.10.2020   | 128.41  | 29.06.2020 |
| 29                   | Mettur                                       | 250.00                              | 541                  | 240.79                | 211.23                  | 2708.80                   | 2645.20   | 204.00                | 106.78                         | 25.12.2020   | 64.00   | 01.08.2020 |
| 30                   | Periyar                                      | 161.00                              | 409                  | 46.33                 | 33.53                   | 443                       | 299       | 216                   | 41.75                          | 13.08.2020   | 34.19   | 01.07.2020 |
|                      | Sub-Total SR                                 | 6629.10                             | 22488.00             |                       |                         |                           | 31645     |                       |                                |              |         |            |
| EASTERN REGION       |                                              |                                     |                      |                       |                         |                           |           |                       |                                |              |         |            |
| 31                   | Machkund                                     | 114.75                              | 670                  | 838.20                | 818.39                  | 970                       | 893       | 552.00                | 838.06                         | 01.10.2020   | 828.79  | 13.06.2020 |
| 32                   | Hirakud                                      | 347.50                              | 1174                 | 192.02                | 179.83                  | 4823                      | 4709      | 372.00                | 192.01                         | 01.10.2020   | 182.76  | 10.07.2020 |
| 33                   | Balimela                                     | 510.00                              | 1183                 | 462.07                | 438.91                  | 3929                      | 2676      | 898.00                | 458.39                         | 24.10.2020   | 444.77  | 03.08.2020 |
| 34                   | Upper Indravati                              | 600.00                              | 1962                 | 642.00                | 625.00                  | 2300                      | 1485.50   | 1213.14               | 638.38                         | 20.10.2020   | 630.58  | 03.08.2020 |
| 35                   | Upper Kolab                                  | 320.00                              | 832                  | 858.00                | 844.00                  | 1215                      | 935.00    | 540                   | 851.37                         | 27.09.2020   | 847.57  | 04.08.2020 |
| 36                   | Rengali                                      | 250.00                              | 525                  | 123.50                | 109.72                  | 3548                      | 3167.81   | 275                   | 123.9                          | 02.09.2020   | 111.2   | 19.06.2020 |
|                      | Sub-Total ER                                 | 2142.25                             | 6346.00              |                       |                         |                           | 13866     |                       |                                |              |         |            |
| NORTH EASTERN REGION |                                              |                                     |                      |                       |                         |                           |           |                       |                                |              |         |            |
| 37                   | Loktak                                       | 105                                 | 448                  | 768.50                | 766.20                  | 435.91                    | 396.44    | 250                   | 769.29                         | 30.09.2020   | 766.01  | 14.04.2020 |
|                      | Sub-Total NER                                | 105                                 | 448                  |                       |                         |                           | 396.44    |                       |                                |              |         |            |
| Total All India      |                                              | 18232.35                            | 53389.40             |                       |                         |                           | 111834.35 |                       |                                |              |         |            |

# CHAPTER-4

## PLANNED MAINTENANCE OF THE UNITS

## CHAPTER-4

### PLANNED MAINTENANCE OF HE UNITS

**4.1** For the purpose of studies and analysis of performance in respect of availability of H.E. Stations, outage data of 727 generating units installed in 210 Hydro Electric Stations was made available by various organizations. The studies indicate that a total of 218275 hours were utilized for carrying out various types of planned maintenance works to facilitate healthy running of generating units. Details of long duration planned outages (50 hours and above) are given in **Annex-4.1**.

**4.2** It is observed that capital maintenance was carried out for 37 generating units whereas annual maintenance was carried out for 128 generating units. Analysis of various types of planned maintenance indicates that while most of the planned outages were for periodic maintenance, many of these outages were for carrying out certain repairs/modification works also. Details of duration of periodic planned maintenance of generator, turbine, auxiliary equipments and civil structures etc. are indicated below in **Table 4.1**.

**TABLE 4.1**  
**DURATION OF PERIODIC PLANNED MAINTENANCE**  
**PERIOD: 2021-22**

| S.NO | Type of Maintenance      | No.<br>of Units | Duration (Hours)     |         |
|------|--------------------------|-----------------|----------------------|---------|
|      |                          |                 | Max. for any<br>unit | Average |
| 1    | ANNUAL MAINTENANCE       | 128             | 8760                 | 649.76  |
| 2    | AUXILIARY SYSTEM         | 2               | 4.94                 | 4.53    |
| 3    | CAPITAL/3 YEARLY MTCE.   | 37              | 8760                 | 795.93  |
| 4    | GENERATOR                | 21              | 751.27               | 89.13   |
| 5    | INSPECTION /MTCE         | 2               | 28.73                | 16.96   |
| 6    | MONTHLY MAINTENANCE      | 20              | 29.65                | 37.18   |
| 7    | OTHER EQUIPMENT          | 6               | 684.42               | 146.46  |
| 8    | RENOVATION/MODERNISATION | 9               | 8760                 | 2821.34 |
| 9    | ROUTINE MAINTENANCE      | 9               | 8.83                 | 3.5     |
| 10   | TURBINE                  | 21              | 75.82                | 15.41   |
| 11   | MISCELLANEOUS            | 51              | 8760                 | 732.21  |

**4.3** There were a total of 666 outages due to Planned Maintenance during the Year 2021-22, out of which about 26.73% were of duration up to 24 hours, while 28.23 % of the planned outages were of duration more than 10 days. Details giving duration pattern of planned maintenance is indicated in **Table 4.2** and illustrated in **Exhibit 4.1**.

**TABLE 4.2**  
**DURATION PATTERN OF PLANNED OUTAGE**  
**PERIOD: 2021-22**

| Sl. No. | Duration                    | Number of Outage | Maintenance % to total number of Outages |
|---------|-----------------------------|------------------|------------------------------------------|
| 1       | more than 10 days           | 188              | 28.23                                    |
| 2       | Less than 6 hour            | 165              | 24.77                                    |
| 3       | 6 to 24 hours               | 178              | 26.73                                    |
| 4       | 1 to 10 days                | 135              | 20.27                                    |
|         | <b>Total No. of Outages</b> | <b>666</b>       | <b>100</b>                               |

#### **4.4 Planned Maintenance age-wise**

Planned maintenance carried out for different age groups of hydro generating units during the year 2021-22 is indicated in **Table 4.3**.

**TABLE 4.3**  
**PLANNED MAINTENANCE AGE-WISE**  
**PERIOD: 2021-22**

| Sl. No. | Year of Commissioning | No. of Units | Installed Capacity (MW) | Planned Outages (Hours) | Non-Availability Per Unit (Hours) |
|---------|-----------------------|--------------|-------------------------|-------------------------|-----------------------------------|
| 1       | 2021-22               | 7            | 393                     | 127                     | 18                                |
| 2       | 2020-21               | 8            | 510.00                  | 0                       | 0                                 |
| 3       | 2019-20               | 2            | 300.00                  | 0                       | 0                                 |
| 4       | 2018-19               | 3            | 140.00                  | 0                       | 0                                 |
| 5       | 2017-18               | 16           | 795.00                  | 7824                    | 489                               |
| 6       | 2016-17               | 18           | 1659.00                 | 3312                    | 184                               |
| 7       | 2015-16               | 17           | 1516.00                 | 4272                    | 251                               |

|    |                      |            |                 |               |            |
|----|----------------------|------------|-----------------|---------------|------------|
| 8  | 2010-11 to 2014-15   | 63         | 4437.02         | 37896         | 602        |
| 9  | 2005-06 to 2009-10   | 66         | 7077.00         | 30480         | 462        |
| 10 | 2000-01 to 2004-05   | 74         | 6741.80         | 38448         | 520        |
| 11 | 1989-90 to 1999-2000 | 86         | 5769.70         | 34464         | 401        |
| 12 | 1978-79 to 1988-89   | 124        | 7259.10         | 71448         | 576        |
| 13 | 1967-68 to 1977-78   | 81         | 5279.75         | 76872         | 949        |
| 14 | Up to 1966-67        | 162        | 4724.85         | 119520        | 738        |
|    | <b>Total</b>         | <b>727</b> | <b>46722.52</b> | <b>218275</b> | <b>300</b> |

It is seen that the average non-availability of units due to planned maintenance is relatively higher in case of older units commissioned from 1967-68 to 1977-78 (949 hrs. /unit).

#### 4.5 Analysis based on Planned Maintenance of different types of Turbines

The details regarding non-availability of generating units due to planned maintenance for different types of turbines are indicated in **Table 4.4** given below.

**TABLE 4.4**  
**PLANNED MAINTENANCE-TURBINE TYPE-WISE**  
**PERIOD: 2021-22**

| Sl. No. | Type of Turbine | No. of Units | Installed Capacity (MW) | Planned Outages (Hours) | Non-Availability Per Unit (Hours) |
|---------|-----------------|--------------|-------------------------|-------------------------|-----------------------------------|
| 1       | BULB            | 26           | 684.00                  | 4689                    | 180                               |
| 2       | FRANCIS         | 419          | 32820.57                | 112263                  | 268                               |
| 3       | KAPLAN          | 133          | 4399.05                 | 41631                   | 313                               |
| 4       | PELTON          | 149          | 8818.90                 | 59691                   | 401                               |
|         | <b>Total</b>    | <b>727</b>   | <b>46722.52</b>         | <b>218275</b>           | <b>300</b>                        |

The average non-availability due to planned maintenance was maximum for Pelton turbine at 401 hrs. /unit followed by Kaplan units at 313 hrs. /unit, while it was minimum for Bulb units at 180 hrs. /unit.

#### 4.6 Analysis based on Make of Generating Units

About 49.57% of the installed capacity of Hydro has been sourced from indigenous suppliers with BHEL alone accounting for about 42.69% of the capacity. The remaining

49.93 % has been imported from various countries like Japan, Canada, UK and France etc. The non-availability due to planned maintenance has been analyzed for generating units both indigenous and imported based on their make/supplier. The details are given below in **Table 4.5**:

**TABLE 4.5**  
**PLANNED MAINTENANCE-SUPPLIER-WISE**  
**PERIOD: 2021-22**

| S. No         | Name of Supplier/<br>Country of Make | No. of Units |            | Installed Capacity (MW) | Non-Availability due to |             |             |
|---------------|--------------------------------------|--------------|------------|-------------------------|-------------------------|-------------|-------------|
|               |                                      | No.          | % of total | MW                      | % of total              | Total Hours | Hours/ Unit |
| A- Indigenous |                                      |              |            |                         |                         |             |             |
| 1             | BHEL                                 | 310          | 42.69      | 20030.30                | 42.87                   | 122444      | 395         |
| 2             | Others                               | 54           | 6.88       | 3395.50                 | 7.27                    | 15316       | 178         |
|               | SUB TOTAL                            | 364          | 49.57      | 23425.80                | 50.14                   | 137760      | 348         |
| B- Imported   |                                      |              |            |                         |                         |             |             |
| 3             | USA                                  | 9            | 1.24       | 351.00                  | 0.75                    | 4648        | 245         |
| 4             | U.K.                                 | 63           | 8.67       | 1242.10                 | 2.66                    | 8916        | 144         |
| 5             | France                               | 31           | 4.26       | 2179.20                 | 4.66                    | 781         | 71          |
| 6             | Canada                               | 44           | 6.05       | 3132.00                 | 6.70                    | 11813       | 311         |
| 7             | USSR                                 | 26           | 3.58       | 2804.00                 | 6.00                    | 10023       | 386         |
| 8             | Switzerland                          | 21           | 2.89       | 790.20                  | 1.69                    | 8879        | 277         |
| 9             | Japan                                | 76           | 10.45      | 6398.20                 | 13.69                   | 24451       | 330         |
| 10            | Other                                | 93           | 12.79      | 6400                    | 13.70                   | 11003       | 159         |
|               | Sub Total                            | 363          | 49.93      | 23296.70                | 49.86                   | 80514       | 243         |
|               | Total                                | 727          | 100        | 46722.50                | 100                     | 218275      | 300         |

It is observed that during the year 2021-22, average non-availability due to planned maintenance of the units supplied by BHEL was 395 hrs. /unit.

Among the imported generating units, the average non-availability due to planned maintenance was the least for units supplied by france (71 hrs. /unit) and was maximum for units supplied by USSR (386 hrs. /unit).

#### **4.7 Planned Maintenance – Region-wise**

Region-wise non-availability of units due to planned maintenance in respect of various hydro power stations is indicated below in **Table 4.6**

**TABLE 4.6**  
**REGION-WISE PLANNED MAINTENANCE**  
**PERIOD: 2021-22**

| <b>S.No</b> | <b>Region</b>    | <b>No. of Units</b> | <b>Installed Capacity (MW)</b> | <b>% Non-availability due to Planned Maintenance</b> |
|-------------|------------------|---------------------|--------------------------------|------------------------------------------------------|
| <b>1</b>    | Northern         | 256                 | 19576.25                       | 4.24                                                 |
| <b>2</b>    | Western          | 101                 | 7392                           | 2.59                                                 |
| <b>3</b>    | Southern         | 246                 | 11739.5                        | 3.04                                                 |
| <b>4</b>    | Eastern          | 86                  | 5987.75                        | 4.16                                                 |
| <b>5</b>    | North Eastern    | 38                  | 2027.0                         | 1.46                                                 |
|             | <b>All India</b> | <b>727</b>          | <b>46722.50</b>                | <b>3.45</b>                                          |

The non-availability of generating unit due to planned maintenance was least in North Eastern Region (1.46%) followed by Western Region at 2.59 %, whereas it was maximum in North Region (4.24 %) followed by Eastern Region (4.16%).

The average non-availability of hydro electric units due to planned maintenance during the year 2021-22 was 3.45% as compared to 4.06% during the year 2020-21.

#### **4.8 Planned Maintenance – Station-wise**

The number of H.E. Stations falling under various ranges of non-availability due to planned maintenance during the year 2021-22 vis-à-vis 2020-21 is summarized below in **Table 4.7**.

**TABLE 4.7**  
**NON-AVAILABILITY OF HE STATIONS DUE TO PLANNED OUTAGES**  
**(2021-22 VIS-A-VIS 2020-21)**

| % Non-Availability due to planned maintenance | 2021-22    |            |                 |            | 2020-21    |            |                 |            |
|-----------------------------------------------|------------|------------|-----------------|------------|------------|------------|-----------------|------------|
|                                               | Stations   |            | Capacity        |            | Stations   |            | Capacity        |            |
|                                               | No.        | % of Total | MW              | % of Total | No.        | % of Total | MW              | % of Total |
| ≤ 5                                           | 165        | 78.57      | 37515.57        | 80.29      | 158        | 76.33      | 34696.37        | 75.09      |
| >5 to 10                                      | 23         | 10.95      | 3814.95         | 8.17       | 27         | 12.08      | 6465.20         | 13.99      |
| >10 to 15                                     | 12         | 5.71       | 3594.20         | 7.69       | 9          | 4.35       | 1530.15         | 3.31       |
| >15 to 20                                     | 4          | 1.90       | 1087.80         | 2.33       | 4          | 1.93       | 1550.00         | 3.35       |
| >20 to 25                                     | 1          | 0.48       | 30.00           | 0.06       | 1          | 0.48       | 304.00          | 0.66       |
| >25 to 30                                     | 1          | 0.48       | 50.00           | 0.11       | 5          | 2.42       | 938.50          | 2.03       |
| above 30                                      | 4          | 1.90       | 630.00          | 1.35       | 5          | 2.42       | 725.00          | 1.57       |
| <b>Total</b>                                  | <b>210</b> | <b>100</b> | <b>46722.52</b> | <b>100</b> | <b>209</b> | <b>100</b> | <b>46209.22</b> | <b>100</b> |

It could be seen from above that 165 nos. (78.57% of total) hydro-electric stations had non-availability factor less than or equal to 5% due to planned maintenance during 2021-22 as compared to 158 nos. (76.33% of total) during 2020-21.

Non-availability due to planned maintenance was more than 30% at 4 nos. (1.90% of total) H.E. Stations during 2021-22 and which was 5 nos. (2.42% of total) in 2020-21 The details of these stations for 2021-22 is given below in **Table 4.8**.

**TABLE 4.8**  
**H.E. STATIONS HAVING HIGH PLANNED MAINTENANCE**  
**FOR THE PERIOD: (2021-22)**

| Sl. No | Name of Station/Utility       | Capacity (MW)      | N.A. due to P.M.* (%) | Reasons                |
|--------|-------------------------------|--------------------|-----------------------|------------------------|
| 1      | BANSAGAR TONS-I HPS / MPPGCL  | 315.0              | 33.333                | CAPITAL/3 YEARLY MTCE. |
| 2      | NARIAMANGLAM HPS / KSEB       | 52.650000000000006 | 33.333                | ANNUAL MAINTENANCE     |
| 3      | PYKARA ULTMATE HPS / TANGEDCO | 150.0              | 33.333                | ANNUAL MAINTENANCE     |
| 4      | SEWA-II HPS / NHPC            | 120.0              | 89.492                | SURGE SHAFT            |

\* N.A. -Non availability, P.M.- Planned Maintenance

33% of stations had operational availability lower than 95% on account of planned maintenance alone against the normative design/plan annual availability of 95% total during the entire station life. These utilities need to improve their O&M practices to bring down their total outages i.e. planned & forced to less than 5% as per best practices.

It is observed from above that stations may be having high planned maintenance outages on account of ageing, O&M management issues, etc. Further, those stations which are having continuously high planned maintenance outages over past few years may be requiring major repair & maintenance works or Renovation & Modernisation (R&M) works for improving the availability, reliability & security of the plant besides providing life extension where the assets have outlived their useful life.

#### 4.9 Planned Maintenance – Utility-wise/Sector-wise

Performance of hydro-electric units under various utilities in Central Sector, State Sector, and Private Sector with respect to non-availability due to planned maintenance is indicated in **Table 4.9**.

In case of Central Sector, non-availability due to planned maintenance was maximum under NHPC (929 hrs. /unit).

In case of State Sector, non-availability due to planned maintenance was maximum under OHPC (669 hrs. /unit).

In case of Private Sector, non-availability due to planned maintenance was maximum under ADHPL (650 hrs. /unit).

It is also observed that the average duration of planned maintenance in respect of H.E. Stations in Central Sector, State Sector and Private Sector is 545 hrs. /Unit, 248 hrs. /Unit and 76 hrs. /Unit respectively.

**TABLE 4.9**  
**SECTOR-WISE/ UTILITY-WISE PERFORMANCE PLANNED MAINTENANCE**  
**PERIOD: 2021-22**


| Sl. No.    | Organization          | No. of Units | Installed Capacity (MW) | Planned Maintenance (Hours) | Planned Maintenance per Unit (Hours) |
|------------|-----------------------|--------------|-------------------------|-----------------------------|--------------------------------------|
| <b>(A)</b> | <b>Central Sector</b> |              |                         |                             |                                      |
| 1          | BBMB                  | 28           | 2938.30                 | 9213                        | 329                                  |
| 2          | DVC                   | 5            | 143.20                  | 781                         | 156                                  |
| 3          | NEEPCO.               | 20           | 1500.00                 | 3974                        | 199                                  |
| 4          | NHDC                  | 16           | 1520.00                 | 5765                        | 360                                  |
| 5          | NHPC                  | 70           | 5451.20                 | 65039                       | 929                                  |
| 6          | NTPC Ltd.             | 4            | 800.00                  | 457                         | 114                                  |

|                         |                       |            |                 |              |            |
|-------------------------|-----------------------|------------|-----------------|--------------|------------|
| 7                       | SJVNL                 | 12         | 1912.02         | 2739         | 228        |
| 8                       | THDC                  | 8          | 1400.00         | 802          | 100        |
| <b>Sub Total (CS)</b>   |                       | <b>163</b> | <b>15664.72</b> | <b>88771</b> | <b>545</b> |
| <b>(B)</b>              | <b>Private Sector</b> |            |                 |              |            |
| 1                       | ADHPL                 | 2          | 192.00          | 1301         | 650        |
| 2                       | AHPC (GVK)            | 4          | 330.00          | 0            | 0          |
| 3                       | DEPL                  | 2          | 96.00           | 1215         | 608        |
| 4                       | DLHP                  | 1          | 34.00           | 0            | 0          |
| 5                       | E.P.P.L.              | 2          | 100.00          | 8            | 4          |
| 6                       | GBHPPL                | 2          | 70.00           | 0            | 0          |
| 7                       | GIPL                  | 2          | 110.00          | 455          | 228        |
| 8                       | GMR BHHPL             | 3          | 180.00          | 0            | 0          |
| 9                       | HBPCL                 | 7          | 1300.00         | 2026         | 289        |
| 10                      | HSPCL                 | 2          | 100.00          | 0            | 0          |
| 11                      | IAEPL                 | 3          | 36.00           | 0            | 0          |
| 12                      | JPPVL                 | 4          | 400.00          | 151          | 38         |
| 13                      | L&T                   | 3          | 99.00           | 0            | 0          |
| 14                      | MBPC                  | 2          | 113.00          | 127          | 63         |
| 15                      | MPCL                  | 2          | 86.00           | 354          | 177        |
| 16                      | SEPL                  | 2          | 97.00           | 222          | 111        |
| 17                      | SKPPPL                | 2          | 96.00           | 0            | 0          |
| 18                      | TATA MAH.             | 15         | 447.00          | 6            | 0          |
| <b>Sub Total (Pvt.)</b> |                       | <b>60</b>  | <b>3931.00</b>  | <b>4555</b>  | <b>76</b>  |
| <b>(C)</b>              | <b>State Sector</b>   |            |                 |              |            |
| 1                       | APGCL                 | 2          | 100.00          | 0            | 0          |
| 2                       | APGENCO               | 34         | 1796.75         | 0            | 0          |
| 3                       | CSPGCL                | 3          | 120.00          | 0            | 0          |
| 4                       | GSECL                 | 8          | 540.00          | 0            | 0          |
| 5                       | HPPCL                 | 8          | 406.00          | 540          | 68         |
| 6                       | HPSEB                 | 12         | 372.00          | 4908         | 409        |
| 7                       | JKSPDC                | 12         | 1110.00         | 2202         | 183        |
| 8                       | JUUNL                 | 2          | 130.00          | 0            | 0          |
| 9                       | KPCL                  | 66         | 3617.20         | 16582        | 251        |
| 10                      | KSEB                  | 47         | 1856.50         | 25278        | 538        |
| 11                      | MAHAGENCO             | 24         | 2406.00         | 893          | 37         |
| 12                      | MeECL                 | 13         | 322.00          | 0            | 0          |
| 13                      | MPPGCL                | 23         | 875.00          | 12607        | 548        |
| 14                      | OHPC                  | 31         | 2039.80         | 20731        | 669        |
| 15                      | PSPCL                 | 25         | 1051.00         | 2671         | 107        |
| 16                      | RRVUNL                | 11         | 411.00          | 0            | 0          |
| 17                      | SSNNL                 | 11         | 1450.00         | 3682         | 335        |

|                          |          |            |                 |               |            |
|--------------------------|----------|------------|-----------------|---------------|------------|
| 18                       | TANGEDCO | 69         | 2178.20         | 23692         | 343        |
| 19                       | TSGENCO  | 36         | 2405.60         | 0             | 0          |
| 20                       | TUL      | 6          | 1200.00         | 1701          | 284        |
| 21                       | UJVNL    | 34         | 1252.15         | 9461          | 278        |
| 22                       | UPJVNL   | 15         | 501.60          | 0             | 0          |
| 23                       | WBSEDCL  | 12         | 986.00          | 0             | 0          |
| <b>Sub Total (State)</b> |          | <b>504</b> | <b>27126.80</b> | <b>124949</b> | <b>248</b> |
| <b>All India</b>         |          | <b>727</b> | <b>46722.52</b> | <b>218275</b> | <b>300</b> |

## DURATION PATTERN OF PLANNED MAINTENANCE DURING

2021-22



**CENTRAL ELECTRICITY AUTHORITY**  
**Hydro WING**  
**Hydro Project Planning & Investigation Division**

**Annex-4.1**

**DETAILS OF LONG DURATION PLANNED OUTAGES IN HYDRO - ELECTRIC UNITS DURING 2021-22**

**(OUTAGE DURATION 50 HOURS AND ABOVE)**

| S.No           | STATION            | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS                  |
|----------------|--------------------|------|------------------|-------------------|-------------------|-----------------|--------------------------|
| <b>Eastern</b> |                    |      |                  |                   |                   |                 |                          |
| <b>OHPC</b>    |                    |      |                  |                   |                   |                 |                          |
| 1              | BALIMELA HPS       | 1    | 60.0             | 04/01/2021        | 03/31/2022        | 8,760.00        | RENOVATION/MODERNISATION |
| <b>GIPL</b>    |                    |      |                  |                   |                   |                 |                          |
| 2              | CHUZACHEN HPS      | 1    | 55.0             | 02/01/2022        | 02/12/2022        | 265.87          | ANNUAL MAINTENANCE       |
|                |                    | 2    | 55.0             | 02/05/2022        | 02/13/2022        | 186.47          | ANNUAL MAINTENANCE       |
| <b>OHPC</b>    |                    |      |                  |                   |                   |                 |                          |
| 3              | HIRAKUD HPS        | 5    | 43.65            | 04/01/2021        | 01/09/2022        | 6,793.48        | RENOVATION/MODERNISATION |
|                |                    | 6    | 43.65            | 04/01/2021        | 11/02/2021        | 5,178.00        | RENOVATION/MODERNISATION |
| <b>DEPL</b>    |                    |      |                  |                   |                   |                 |                          |
| 4              | JORETHANG LOOP     | 1    | 48.0             | 04/01/2021        | 05/21/2021        | 1,215.15        | ANNUAL MAINTENANCE       |
| <b>DVC</b>     |                    |      |                  |                   |                   |                 |                          |
| 5              | MAITHON HPS        | 3    | 20.0             | 04/01/2021        | 05/03/2021        | 781.33          | ANNUAL MAINTENANCE       |
| <b>NHPC</b>    |                    |      |                  |                   |                   |                 |                          |
| 6              | RANGIT HPS         | 1    | 20.0             | 02/11/2022        | 03/05/2022        | 540.20          | ANNUAL MAINTENANCE       |
|                |                    | 2    | 20.0             | 02/11/2022        | 02/13/2022        | 66.50           | MISCELLANEOUS PLANNED    |
|                |                    | 2    | 20.0             | 01/17/2022        | 02/08/2022        | 547.50          | ANNUAL MAINTENANCE       |
|                |                    | 3    | 20.0             | 12/21/2021        | 01/14/2022        | 568.10          | ANNUAL MAINTENANCE       |
|                |                    | 3    | 20.0             | 02/11/2022        | 02/13/2022        | 56.87           | MISCELLANEOUS PLANNED    |
| <b>SEPL</b>    |                    |      |                  |                   |                   |                 |                          |
| 7              | TASHIDING HPS      | 1    | 48.5             | 03/21/2022        | 03/25/2022        | 111.17          | ANNUAL MAINTENANCE       |
|                |                    | 2    | 48.5             | 03/21/2022        | 03/25/2022        | 111.17          | MONTHLY MAINTENANCE      |
| <b>TUL</b>     |                    |      |                  |                   |                   |                 |                          |
| 8              | TEESTA-III HPS     | 1    | 200.0            | 12/23/2021        | 12/31/2021        | 198.62          | ANNUAL MAINTENANCE       |
|                |                    | 2    | 200.0            | 11/20/2021        | 11/30/2021        | 242.88          | ANNUAL MAINTENANCE       |
|                |                    | 3    | 200.0            | 01/04/2022        | 01/13/2022        | 233.67          | ANNUAL MAINTENANCE       |
|                |                    | 4    | 200.0            | 02/16/2022        | 03/05/2022        | 400.42          | GENERATOR TRANSFORMER    |
|                |                    | 4    | 200.0            | 12/02/2021        | 12/06/2021        | 95.10           | ANNUAL MAINTENANCE       |
|                |                    | 5    | 200.0            | 12/07/2021        | 12/20/2021        | 322.32          | ANNUAL MAINTENANCE       |
|                |                    | 5    | 200.0            | 03/08/2022        | 03/12/2022        | 92.93           | MISCELLANEOUS PLANNED    |
| <b>NHPC</b>    |                    |      |                  |                   |                   |                 |                          |
| 9              | TEESTA LOW DAM-III | 1    | 33.0             | 03/02/2022        | 03/17/2022        | 364.97          | ANNUAL MAINTENANCE       |
|                |                    | 2    | 33.0             | 01/05/2022        | 01/21/2022        | 383.82          | ANNUAL MAINTENANCE       |

| S.No                 | STATION           | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS                 |
|----------------------|-------------------|------|------------------|-------------------|-------------------|-----------------|-------------------------|
|                      |                   | 3    | 33.0             | 02/12/2022        | 02/28/2022        | 407.15          | ANNUAL MAINTENANCE      |
|                      |                   | 4    | 33.0             | 01/24/2022        | 02/09/2022        | 385.98          | ANNUAL MAINTENANCE      |
| 10                   | TEESTA LOW DAM-IV | 1    | 40.0             | 07/01/2021        | 07/04/2021        | 96.00           | TESTING/CHECKING        |
|                      |                   | 1    | 40.0             | 10/16/2021        | 10/22/2021        | 145.45          | SWITCHING EQUIPMENT     |
|                      |                   | 2    | 40.0             | 02/17/2022        | 03/06/2022        | 417.52          | ANNUAL MAINTENANCE      |
|                      |                   | 3    | 40.0             | 01/27/2022        | 02/14/2022        | 450.70          | ANNUAL MAINTENANCE      |
|                      |                   | 4    | 40.0             | 01/05/2022        | 01/23/2022        | 449.35          | ANNUAL MAINTENANCE      |
| 11                   | TEESTA V HPS      | 1    | 170.0            | 02/22/2022        | 03/06/2022        | 284.46          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 170.0            | 02/02/2022        | 02/19/2022        | 402.44          | ANNUAL MAINTENANCE      |
|                      |                   | 3    | 170.0            | 01/19/2022        | 01/28/2022        | 238.36          | ANNUAL MAINTENANCE      |
| <b>North Eastern</b> |                   |      |                  |                   |                   |                 |                         |
| <b>NEEPCO.</b>       |                   |      |                  |                   |                   |                 |                         |
| 12                   | DOYANG HPS        | 1    | 25.0             | 04/05/2021        | 05/03/2021        | 690.08          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 25.0             | 02/08/2022        | 02/25/2022        | 409.48          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 25.0             | 05/05/2021        | 05/19/2021        | 347.60          | ANNUAL MAINTENANCE      |
|                      |                   | 3    | 25.0             | 01/06/2022        | 02/04/2022        | 707.00          | ANNUAL MAINTENANCE      |
| 13                   | KAMENG HPS        | 1    | 150.0            | 12/17/2021        | 12/19/2021        | 63.87           | INSPECTION /MTCE        |
|                      |                   | 2    | 150.0            | 12/17/2021        | 12/19/2021        | 61.77           | INSPECTION /MTCE        |
|                      |                   | 3    | 150.0            | 12/17/2021        | 12/19/2021        | 63.47           | INSPECTION /MTCE        |
| <b>NHPC</b>          |                   |      |                  |                   |                   |                 |                         |
| 14                   | LOKTAK HPS        | 1    | 35.0             | 03/02/2022        | 03/12/2022        | 258.60          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 35.0             | 02/01/2022        | 02/11/2022        | 261.62          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 35.0             | 08/31/2021        | 09/04/2021        | 76.63           | PENSTOCK PRESSURE SHAFT |
|                      |                   | 3    | 35.0             | 02/15/2022        | 02/24/2022        | 235.72          | ANNUAL MAINTENANCE      |
| <b>NEEPCO.</b>       |                   |      |                  |                   |                   |                 |                         |
| 15                   | PARE              | 1    | 55.0             | 01/19/2022        | 02/04/2022        | 384.00          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 55.0             | 02/14/2022        | 02/19/2022        | 141.02          | ANNUAL MAINTENANCE      |
| 16                   | RANGANADI HPS     | 1    | 135.0            | 12/03/2021        | 12/12/2021        | 221.92          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 135.0            | 01/03/2022        | 01/11/2022        | 197.00          | ANNUAL MAINTENANCE      |
| 17                   | TUIRIAL HPS       | 1    | 30.0             | 04/16/2021        | 04/29/2021        | 336.00          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 30.0             | 05/04/2021        | 05/18/2021        | 350.87          | ANNUAL MAINTENANCE      |
| <b>Northern</b>      |                   |      |                  |                   |                   |                 |                         |
| <b>ADHPL</b>         |                   |      |                  |                   |                   |                 |                         |
| 18                   | ALLAIN DUHANGAN   | 1    | 96.0             | 12/01/2021        | 12/24/2021        | 548.75          | ANNUAL MAINTENANCE      |
|                      |                   | 2    | 96.0             | 04/08/2021        | 04/15/2021        | 165.12          | MISC. SHORT DURATION    |
|                      |                   | 2    | 96.0             | 01/03/2022        | 01/21/2022        | 440.05          | ANNUAL MAINTENANCE      |
| <b>JKSPDC</b>        |                   |      |                  |                   |                   |                 |                         |
| 19                   | BAGLIHAR HPS      | 2    | 150.0            | 11/22/2021        | 02/22/2022        | 2,201.83        | ANNUAL MAINTENANCE      |
| <b>NHPC</b>          |                   |      |                  |                   |                   |                 |                         |

| S.No         | STATION          | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS                  |
|--------------|------------------|------|------------------|-------------------|-------------------|-----------------|--------------------------|
| 20           | BAIRA SIUL HPS   | 1    | 60.0             | 06/06/2021        | 06/20/2021        | 357.17          | TURBINE INSPECTION MISC  |
|              |                  | 1    | 60.0             | 05/29/2021        | 06/05/2021        | 192.00          | TURBINE INSPECTION MISC  |
|              |                  | 1    | 60.0             | 01/03/2022        | 01/07/2022        | 113.77          | DRAFT TUBE               |
|              |                  | 2    | 60.0             | 01/03/2022        | 01/07/2022        | 120.00          | DRAFT TUBE               |
|              |                  | 2    | 60.0             | 01/08/2022        | 02/07/2022        | 740.40          | ANNUAL MAINTENANCE       |
|              |                  | 3    | 60.0             | 04/01/2021        | 08/27/2021        | 3,562.00        | RENOVATION/MODERNISATION |
|              |                  | 3    | 60.0             | 01/03/2022        | 01/07/2022        | 113.52          | DRAFT TUBE               |
| <b>HBPCL</b> |                  |      |                  |                   |                   |                 |                          |
| 21           | BASPA HPS        | 1    | 100.0            | 01/06/2022        | 01/14/2022        | 193.50          | ANNUAL MAINTENANCE       |
|              |                  | 1    | 100.0            | 02/09/2022        | 02/12/2022        | 72.00           | GOVERNOR SYSTEM          |
|              |                  | 2    | 100.0            | 03/07/2022        | 03/16/2022        | 218.00          | ANNUAL MAINTENANCE       |
|              |                  | 3    | 100.0            | 01/19/2022        | 01/28/2022        | 217.50          | ANNUAL MAINTENANCE       |
| <b>BBMB</b>  |                  |      |                  |                   |                   |                 |                          |
| 22           | BHAKRA LEFT HPS  | 3    | 126.0            | 04/01/2021        | 11/09/2021        | 5,352.00        | UPRATING                 |
|              |                  | 5    | 126.0            | 04/10/2021        | 05/01/2021        | 493.00          | ANNUAL MAINTENANCE       |
| 23           | BHAKRA RIGHT HPS | 9    | 157.0            | 05/08/2021        | 05/27/2021        | 461.15          | ANNUAL MAINTENANCE       |
| <b>NHPC</b>  |                  |      |                  |                   |                   |                 |                          |
| 24           | CHAMERA-I HPS    | 1    | 180.0            | 12/01/2021        | 01/15/2022        | 1,086.77        | R AND M / REFURBISHMENT  |
|              |                  | 2    | 180.0            | 12/01/2021        | 01/14/2022        | 1,075.30        | ANNUAL MAINTENANCE       |
|              |                  | 3    | 180.0            | 12/01/2021        | 01/20/2022        | 1,205.00        | R AND M / REFURBISHMENT  |
| 25           | CHAMERA-II HPS   | 1    | 100.0            | 02/06/2022        | 03/10/2022        | 776.20          | CAPITAL MAINTENANCE      |
|              |                  | 2    | 100.0            | 01/17/2022        | 02/01/2022        | 352.37          | ANNUAL MAINTENANCE       |
|              |                  | 3    | 100.0            | 11/22/2021        | 12/07/2021        | 367.68          | ANNUAL MAINTENANCE       |
| 26           | CHAMERA-III HPS  | 2    | 77.0             | 08/25/2021        | 09/04/2021        | 251.75          | GENERATOR TRANSFORMER    |
|              |                  | 2    | 77.0             | 01/21/2022        | 02/09/2022        | 464.37          | CAPITAL MAINTENANCE      |
|              |                  | 3    | 77.0             | 02/11/2022        | 02/22/2022        | 268.85          | ANNUAL MAINTENANCE       |
| 27           | CHUTAK HPS       | 1    | 11.0             | 11/17/2021        | 01/10/2022        | 1,296.72        | ANNUAL MAINTENANCE       |
|              |                  | 2    | 11.0             | 11/15/2021        | 12/23/2021        | 909.38          | ANNUAL MAINTENANCE       |
|              |                  | 3    | 11.0             | 01/02/2022        | 01/29/2022        | 647.38          | ANNUAL MAINTENANCE       |
|              |                  | 4    | 11.0             | 01/23/2022        | 02/15/2022        | 563.30          | ANNUAL MAINTENANCE       |
| <b>BBMB</b>  |                  |      |                  |                   |                   |                 |                          |
| 28           | DEHAR HPS        | 1    | 165.0            | 05/03/2021        | 05/20/2021        | 425.48          | ANNUAL MAINTENANCE       |
| <b>UJVNL</b> |                  |      |                  |                   |                   |                 |                          |
| 29           | DHAKRANI HPS     | 1    | 11.25            | 01/11/2022        | 03/31/2022        | 1,896.92        | ANNUAL MAINTENANCE       |
|              |                  | 3    | 11.25            | 01/25/2022        | 02/22/2022        | 662.67          | ANNUAL MAINTENANCE       |
| 30           | DHALIPUR HPS     | 3    | 17.0             | 11/15/2021        | 12/03/2021        | 443.92          | ANNUAL MAINTENANCE       |
| <b>NHPC</b>  |                  |      |                  |                   |                   |                 |                          |
| 31           | DHAULI GANGA HPS | 2    | 70.0             | 02/15/2022        | 03/11/2022        | 575.30          | ANNUAL MAINTENANCE       |
|              |                  | 4    | 70.0             | 01/14/2022        | 02/04/2022        | 525.47          | ANNUAL MAINTENANCE       |

| S.No             | STATION             | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS                 |
|------------------|---------------------|------|------------------|-------------------|-------------------|-----------------|-------------------------|
| 32               | DULHASTI HPS        | 1    | 130.0            | 02/02/2022        | 02/16/2022        | 345.13          | ANNUAL MAINTENANCE      |
|                  |                     | 2    | 130.0            | 03/06/2022        | 03/13/2022        | 171.65          | ANNUAL MAINTENANCE      |
|                  |                     | 3    | 130.0            | 02/18/2022        | 03/03/2022        | 313.43          | ANNUAL MAINTENANCE      |
|                  |                     | 3    | 130.0            | 07/31/2021        | 08/04/2021        | 88.30           | TURBINE INSPECTION MISC |
| <b>BBMB</b>      |                     |      |                  |                   |                   |                 |                         |
| 33               | GANGUWAL HPS        | 2    | 24.2             | 11/16/2021        | 11/20/2021        | 98.08           | QUATERLY MAINTENANCE    |
|                  |                     | 3    | 24.2             | 11/08/2021        | 11/12/2021        | 93.92           | QUATERLY MAINTENANCE    |
| <b>HPSEB</b>     |                     |      |                  |                   |                   |                 |                         |
| 34               | GIRI BATA HPS       | 1    | 30.0             | 11/22/2021        | 11/30/2021        | 206.92          | ANNUAL MAINTENANCE      |
|                  |                     | 1    | 30.0             | 12/01/2021        | 01/09/2022        | 955.00          | ANNUAL MAINTENANCE      |
|                  |                     | 2    | 30.0             | 06/08/2021        | 06/11/2021        | 81.00           | INSPECTION /MTCE        |
|                  |                     | 2    | 30.0             | 04/01/2021        | 04/25/2021        | 597.00          | ANNUAL MAINTENANCE      |
| <b>NHPC</b>      |                     |      |                  |                   |                   |                 |                         |
| 35               | KISHANGANGA HPS     | 1    | 110.0            | 02/09/2022        | 02/18/2022        | 226.62          | ANNUAL MAINTENANCE      |
|                  |                     | 1    | 110.0            | 04/01/2021        | 06/07/2021        | 1,609.18        | ANNUAL MAINTENANCE      |
|                  |                     | 2    | 110.0            | 06/02/2021        | 07/08/2021        | 886.24          | STATOR WINDING          |
|                  |                     | 2    | 110.0            | 01/28/2022        | 02/07/2022        | 219.58          | EXTENDED ANNUAL         |
|                  |                     | 2    | 110.0            | 08/21/2021        | 08/23/2021        | 50.03           | MISCELLANEOUS PLANNED   |
|                  |                     | 2    | 110.0            | 01/04/2022        | 01/28/2022        | 587.06          | ANNUAL MAINTENANCE      |
|                  |                     | 3    | 110.0            | 12/15/2021        | 12/29/2021        | 343.81          | ANNUAL MAINTENANCE      |
| <b>NTPC Ltd.</b> |                     |      |                  |                   |                   |                 |                         |
| 36               | KOLDAM              | 1    | 200.0            | 02/17/2022        | 02/21/2022        | 93.00           | ANNUAL MAINTENANCE      |
|                  |                     | 2    | 200.0            | 02/26/2022        | 03/02/2022        | 93.25           | ANNUAL MAINTENANCE      |
|                  |                     | 3    | 200.0            | 01/31/2022        | 02/06/2022        | 142.57          | BOILER OVERHAUL/ ANNUAL |
|                  |                     | 4    | 200.0            | 02/08/2022        | 02/13/2022        | 128.17          | ANNUAL MAINTENANCE      |
| <b>BBMB</b>      |                     |      |                  |                   |                   |                 |                         |
| 37               | KOTLA HPS           | 3    | 24.2             | 11/08/2021        | 11/12/2021        | 93.67           | QUATERLY MAINTENANCE    |
| <b>UJVNL</b>     |                     |      |                  |                   |                   |                 |                         |
| 38               | KULHAL HPS          | 1    | 10.0             | 12/26/2021        | 12/31/2021        | 143.92          | MISCELLANEOUS PLANNED   |
|                  |                     | 3    | 10.0             | 12/01/2021        | 12/22/2021        | 527.92          | MISCELLANEOUS PLANNED   |
| <b>MPCL</b>      |                     |      |                  |                   |                   |                 |                         |
| 39               | MALANA HPS          | 2    | 43.0             | 02/24/2022        | 03/10/2022        | 353.50          | ANNUAL MAINTENANCE      |
| <b>UJVNL</b>     |                     |      |                  |                   |                   |                 |                         |
| 40               | MANERI BHALI-II HPS | 1    | 76.0             | 03/01/2022        | 03/31/2022        | 743.92          | ANNUAL MAINTENANCE      |
|                  |                     | 3    | 76.0             | 01/13/2022        | 02/19/2022        | 900.00          | ANNUAL MAINTENANCE      |
|                  |                     | 4    | 76.0             | 11/12/2021        | 01/06/2022        | 1,333.67        | ANNUAL MAINTENANCE      |
| <b>SJVNL</b>     |                     |      |                  |                   |                   |                 |                         |
| 41               | NATHPA JHAKRI HPS   | 1    | 250.0            | 02/18/2022        | 02/25/2022        | 174.08          | ANNUAL MAINTENANCE      |
|                  |                     | 2    | 250.0            | 01/28/2022        | 02/03/2022        | 167.53          | ANNUAL MAINTENANCE      |
|                  |                     | 3    | 250.0            | 01/15/2022        | 01/24/2022        | 240.00          | ANNUAL MAINTENANCE      |

| S.No         | STATION          | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS               |
|--------------|------------------|------|------------------|-------------------|-------------------|-----------------|-----------------------|
|              |                  | 3    | 250.0            | 01/08/2022        | 01/11/2022        | 72.22           | ANNUAL MAINTENANCE    |
|              |                  | 4    | 250.0            | 01/19/2022        | 01/22/2022        | 90.20           | ANNUAL MAINTENANCE    |
|              |                  | 4    | 250.0            | 01/04/2022        | 01/12/2022        | 206.28          | ANNUAL MAINTENANCE    |
|              |                  | 5    | 250.0            | 02/11/2022        | 02/13/2022        | 60.15           | ANNUAL MAINTENANCE    |
|              |                  | 5    | 250.0            | 02/26/2022        | 03/05/2022        | 183.57          | ANNUAL MAINTENANCE    |
|              |                  | 6    | 250.0            | 02/08/2022        | 02/15/2022        | 184.03          | ANNUAL MAINTENANCE    |
| <b>NHPC</b>  |                  |      |                  |                   |                   |                 |                       |
| 42           | NIMMO BAZGO HPS  | 1    | 15.0             | 11/18/2021        | 12/10/2021        | 538.88          | ANNUAL MAINTENANCE    |
|              |                  | 2    | 15.0             | 12/14/2021        | 01/07/2022        | 567.25          | ANNUAL MAINTENANCE    |
|              |                  | 3    | 15.0             | 01/10/2022        | 01/25/2022        | 372.75          | ANNUAL MAINTENANCE    |
| 43           | PARBATI-III HPS  | 1    | 130.0            | 12/01/2021        | 01/06/2022        | 871.08          | ANNUAL MAINTENANCE    |
|              |                  | 2    | 130.0            | 12/27/2021        | 01/15/2022        | 464.73          | ANNUAL MAINTENANCE    |
|              |                  | 3    | 130.0            | 01/24/2022        | 03/04/2022        | 943.47          | ANNUAL MAINTENANCE    |
|              |                  | 3    | 130.0            | 09/29/2021        | 10/05/2021        | 147.22          | MISCELLANEOUS PLANNED |
|              |                  | 4    | 130.0            | 01/31/2022        | 03/17/2022        | 1,081.35        | ANNUAL MAINTENANCE    |
| <b>BBMB</b>  |                  |      |                  |                   |                   |                 |                       |
| 44           | PONG HPS         | 5    | 66.0             | 04/01/2021        | 07/01/2021        | 2,196.08        | ANNUAL MAINTENANCE    |
| <b>UJVNL</b> |                  |      |                  |                   |                   |                 |                       |
| 45           | RAMGANGA HPS     | 2    | 66.0             | 06/17/2021        | 10/12/2021        | 2,808.25        | ANNUAL MAINTENANCE    |
| <b>SJVNL</b> |                  |      |                  |                   |                   |                 |                       |
| 46           | RAMPUR HPS       | 1    | 68.67            | 01/09/2022        | 01/11/2022        | 65.98           | ANNUAL MAINTENANCE    |
|              |                  | 1    | 68.67            | 02/26/2022        | 03/08/2022        | 252.22          | ANNUAL MAINTENANCE    |
|              |                  | 2    | 68.67            | 01/04/2022        | 01/12/2022        | 196.23          | ANNUAL MAINTENANCE    |
|              |                  | 3    | 68.67            | 02/08/2022        | 02/16/2022        | 187.00          | ANNUAL MAINTENANCE    |
|              |                  | 4    | 68.67            | 01/28/2022        | 02/03/2022        | 160.77          | ANNUAL MAINTENANCE    |
|              |                  | 4    | 68.67            | 02/11/2022        | 02/13/2022        | 59.00           | ANNUAL MAINTENANCE    |
|              |                  | 5    | 68.67            | 01/15/2022        | 01/22/2022        | 173.75          | ANNUAL MAINTENANCE    |
|              |                  | 6    | 68.67            | 02/18/2022        | 02/24/2022        | 155.78          | ANNUAL MAINTENANCE    |
| <b>PSPCL</b> |                  |      |                  |                   |                   |                 |                       |
| 47           | RANJIT SAGAR HPS | 1    | 150.0            | 10/25/2021        | 12/29/2021        | 1,568.17        | ANNUAL MAINTENANCE    |
|              |                  | 1    | 150.0            | 04/16/2021        | 04/29/2021        | 329.08          | MISC. SHORT DURATION  |
|              |                  | 2    | 150.0            | 05/19/2021        | 05/29/2021        | 247.58          | MISC. SHORT DURATION  |
|              |                  | 2    | 150.0            | 02/21/2022        | 03/10/2022        | 418.85          | GENERATOR TRANSFORMER |
|              |                  | 4    | 150.0            | 02/17/2022        | 02/21/2022        | 91.75           | ANNUAL MAINTENANCE    |
| <b>HPPCL</b> |                  |      |                  |                   |                   |                 |                       |
| 48           | SAINJ HPS        | 1    | 50.0             | 02/18/2022        | 02/26/2022        | 196.65          | ANNUAL MAINTENANCE    |
|              |                  | 2    | 50.0             | 02/28/2022        | 03/14/2022        | 343.52          | ANNUAL MAINTENANCE    |
| <b>NHPC</b>  |                  |      |                  |                   |                   |                 |                       |
| 49           | SALAL HPS        | 1    | 115.0            | 11/16/2021        | 11/29/2021        | 315.70          | ANNUAL MAINTENANCE    |

| S.No            | STATION           | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS                  |
|-----------------|-------------------|------|------------------|-------------------|-------------------|-----------------|--------------------------|
|                 |                   | 3    | 115.0            | 01/12/2022        | 03/05/2022        | 1,255.77        | CAPITAL MAINTENANCE      |
|                 |                   | 5    | 115.0            | 03/07/2022        | 03/21/2022        | 341.23          | ANNUAL MAINTENANCE       |
|                 |                   | 6    | 115.0            | 11/24/2021        | 12/11/2021        | 414.80          | ANNUAL MAINTENANCE       |
| <b>HPSEB</b>    |                   |      |                  |                   |                   |                 |                          |
| 50              | SANJAY HPS        | 1    | 40.0             | 04/01/2021        | 04/28/2021        | 665.00          | RENOVATION/MODERNISATION |
|                 |                   | 1    | 40.0             | 12/17/2021        | 02/02/2022        | 1,138.43        | ANNUAL MAINTENANCE       |
|                 |                   | 2    | 40.0             | 10/28/2021        | 12/17/2021        | 1,212.36        | ANNUAL MAINTENANCE       |
| <b>NHPC</b>     |                   |      |                  |                   |                   |                 |                          |
| 51              | SEWA-II HPS       | 1    | 40.0             | 02/22/2022        | 03/22/2022        | 673.70          | STATOR WINDING           |
|                 |                   | 1    | 40.0             | 04/01/2021        | 02/21/2022        | 7,837.78        | SURGE SHAFT HRT MTc.     |
|                 |                   | 2    | 40.0             | 04/01/2021        | 02/21/2022        | 7,841.37        | SURGE SHAFT HRT MTc.     |
|                 |                   | 2    | 40.0             | 02/22/2022        | 02/27/2022        | 129.75          | GENERATOR                |
|                 |                   | 3    | 40.0             | 04/01/2021        | 02/21/2022        | 7,839.33        | SURGE SHAFT HRT MTc.     |
|                 |                   | 3    | 40.0             | 02/21/2022        | 03/01/2022        | 187.33          | GENERATOR                |
| 52              | TANAKPUR HPS      | 1    | 31.4             | 04/01/2021        | 04/23/2021        | 542.12          | ANNUAL MAINTENANCE       |
|                 |                   | 1    | 31.4             | 02/25/2022        | 03/25/2022        | 680.75          | ANNUAL MAINTENANCE       |
|                 |                   | 2    | 31.4             | 01/20/2022        | 02/21/2022        | 775.58          | ANNUAL MAINTENANCE       |
|                 |                   | 2    | 31.4             | 04/01/2021        | 04/08/2021        | 168.85          | ANNUAL MAINTENANCE       |
|                 |                   | 3    | 31.4             | 12/21/2021        | 01/16/2022        | 626.73          | ANNUAL MAINTENANCE       |
|                 |                   | 3    | 31.4             | 04/01/2021        | 04/03/2021        | 57.02           | CAPITAL MAINTENANCE      |
| <b>THDC</b>     |                   |      |                  |                   |                   |                 |                          |
| 53              | TEHRI ST-1 HPS    | 1    | 250.0            | 04/01/2021        | 04/12/2021        | 286.00          | ANNUAL MAINTENANCE       |
|                 |                   | 4    | 250.0            | 04/13/2021        | 05/04/2021        | 514.00          | ANNUAL MAINTENANCE       |
| <b>NHPC</b>     |                   |      |                  |                   |                   |                 |                          |
| 54              | URI-I HPS         | 1    | 120.0            | 01/08/2022        | 01/20/2022        | 300.02          | CAPITAL MAINTENANCE      |
|                 |                   | 2    | 120.0            | 12/20/2021        | 01/06/2022        | 412.95          | CAPITAL MAINTENANCE      |
|                 |                   | 3    | 120.0            | 11/22/2021        | 12/08/2021        | 393.15          | ANNUAL MAINTENANCE       |
|                 |                   | 4    | 120.0            | 12/10/2021        | 12/18/2021        | 198.97          | ANNUAL MAINTENANCE       |
|                 |                   | 4    | 120.0            | 11/29/2021        | 12/08/2021        | 210.88          | MISCELLANEOUS PLANNED    |
| 55              | URI-II HPS        | 1    | 60.0             | 11/22/2021        | 12/04/2021        | 286.62          | ANNUAL MAINTENANCE       |
|                 |                   | 1    | 60.0             | 12/28/2021        | 01/03/2022        | 154.35          | MISCELLANEOUS PLANNED    |
|                 |                   | 2    | 60.0             | 01/07/2022        | 01/19/2022        | 291.12          | ANNUAL MAINTENANCE       |
|                 |                   | 3    | 60.0             | 12/05/2021        | 12/20/2021        | 360.65          | CAPITAL MAINTENANCE      |
|                 |                   | 4    | 60.0             | 12/21/2021        | 12/31/2021        | 241.10          | ANNUAL MAINTENANCE       |
| <b>JPPVL</b>    |                   |      |                  |                   |                   |                 |                          |
| 56              | VISHNU PRAYAG HPS | 1    | 100.0            | 03/01/2022        | 03/03/2022        | 54.68           | ANNUAL MAINTENANCE       |
| <b>Southern</b> |                   |      |                  |                   |                   |                 |                          |
| <b>KPCL</b>     |                   |      |                  |                   |                   |                 |                          |
| 57              | ALMATTI DPH HPS   | 2    | 55.0             | 04/12/2021        | 06/20/2021        | 1,656.08        | ANNUAL MAINTENANCE       |

| S.No            | STATION             | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS                   |
|-----------------|---------------------|------|------------------|-------------------|-------------------|-----------------|---------------------------|
|                 |                     | 2    | 55.0             | 03/03/2022        | 03/31/2022        | 684.42          | GENERATOR TRANSFORMER     |
|                 |                     | 3    | 55.0             | 03/14/2022        | 03/17/2022        | 78.00           | GENERATOR                 |
|                 |                     | 3    | 55.0             | 04/07/2021        | 06/20/2021        | 1,774.08        | ANNUAL MAINTENANCE        |
|                 |                     | 3    | 55.0             | 03/21/2022        | 03/31/2022        | 251.00          | GENERATOR                 |
|                 |                     | 4    | 55.0             | 04/05/2021        | 06/20/2021        | 1,819.00        | ANNUAL MAINTENANCE        |
|                 |                     | 4    | 55.0             | 03/07/2022        | 03/12/2022        | 115.82          | CAPITAL MAINTENANCE       |
|                 |                     | 4    | 55.0             | 03/29/2022        | 03/31/2022        | 58.17           | GENERATOR                 |
|                 |                     | 5    | 55.0             | 03/01/2022        | 03/03/2022        | 50.42           | ANNUAL MAINTENANCE        |
|                 |                     | 5    | 55.0             | 06/01/2021        | 06/20/2021        | 466.33          | ANNUAL MAINTENANCE        |
|                 |                     | 6    | 55.0             | 04/07/2021        | 06/10/2021        | 1,532.58        | ANNUAL MAINTENANCE        |
| <b>TANGEDCO</b> |                     |      |                  |                   |                   |                 |                           |
| 58              | BHAWANI BARRAGE-II  | 1    | 15.0             | 01/28/2022        | 03/16/2022        | 1,116.50        | OVERHAULING WORKS         |
|                 |                     | 2    | 15.0             | 12/08/2021        | 01/11/2022        | 816.92          | MISCELLANEOUS PLANNED     |
| 59              | BHAWANI BARRAGE-III | 1    | 15.0             | 11/01/2021        | 11/05/2021        | 97.08           | MISCELLANEOUS PLANNED     |
| <b>KPCL</b>     |                     |      |                  |                   |                   |                 |                           |
| 60              | GERUSUPPA HPS       | 1    | 60.0             | 11/10/2021        | 11/25/2021        | 369.17          | ANNUAL MAINTENANCE        |
|                 |                     | 2    | 60.0             | 12/20/2021        | 12/27/2021        | 171.22          | RENOVATION/MODERNISATION  |
|                 |                     | 3    | 60.0             | 12/27/2021        | 01/03/2022        | 168.84          | RENOVATION/MODERNISATION  |
|                 |                     | 4    | 60.0             | 11/29/2021        | 12/13/2021        | 345.18          | ANNUAL MAINTENANCE        |
| <b>KSEB</b>     |                     |      |                  |                   |                   |                 |                           |
| 61              | IDAMALAYAR HPS      | 1    | 37.5             | 07/13/2021        | 07/16/2021        | 75.82           | RUNNER INSPECTION         |
|                 |                     | 1    | 37.5             | 11/23/2021        | 12/22/2021        | 685.92          | ANNUAL MAINTENANCE        |
|                 |                     | 2    | 37.5             | 06/29/2021        | 07/27/2021        | 677.53          | ANNUAL MAINTENANCE        |
| 62              | IDUKKI HPS          | 1    | 130.0            | 07/16/2021        | 07/20/2021        | 104.55          | ANNUAL MAINTENANCE        |
|                 |                     | 1    | 130.0            | 08/24/2021        | 09/24/2021        | 756.53          | ANNUAL MAINTENANCE        |
|                 |                     | 1    | 130.0            | 11/24/2021        | 11/28/2021        | 87.67           | RUNNER INSPECTION /REPAIR |
|                 |                     | 2    | 130.0            | 01/19/2022        | 02/11/2022        | 560.22          | ANNUAL MAINTENANCE        |
|                 |                     | 3    | 130.0            | 10/24/2021        | 10/28/2021        | 109.75          | BEARING OIL TOPPING       |
|                 |                     | 3    | 130.0            | 06/10/2021        | 07/14/2021        | 826.12          | ANNUAL MAINTENANCE        |
|                 |                     | 3    | 130.0            | 10/06/2021        | 10/23/2021        | 428.43          | BEARING OIL TOPPING       |
|                 |                     | 4    | 130.0            | 12/27/2021        | 01/17/2022        | 511.47          | ANNUAL MAINTENANCE        |
|                 |                     | 5    | 130.0            | 02/15/2022        | 03/04/2022        | 424.62          | ANNUAL MAINTENANCE        |
|                 |                     | 6    | 130.0            | 04/01/2021        | 04/28/2021        | 663.78          | TESTING/CHECKING          |
|                 |                     | 6    | 130.0            | 05/06/2021        | 05/13/2021        | 175.80          | MISCELLANEOUS PLANNED     |
|                 |                     | 6    | 130.0            | 12/01/2021        | 12/22/2021        | 511.37          | ANNUAL MAINTENANCE        |
| <b>KPCL</b>     |                     |      |                  |                   |                   |                 |                           |
| 63              | JOG HPS             | 1    | 13.2             | 01/04/2022        | 01/13/2022        | 217.75          | SURGE SHAFT HRT MTc.      |
|                 |                     | 1    | 13.2             | 08/23/2021        | 08/25/2021        | 58.33           | INSPECTION OF GENERATING  |

| S.No            | STATION             | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS                  |
|-----------------|---------------------|------|------------------|-------------------|-------------------|-----------------|--------------------------|
|                 |                     | 3    | 13.2             | 01/04/2022        | 01/18/2022        | 337.35          | SURGE SHAFT HRT MTc.     |
|                 |                     | 4    | 13.2             | 01/04/2022        | 01/18/2022        | 337.26          | SURGE SHAFT HRT MTc.     |
|                 |                     | 5    | 21.6             | 04/01/2021        | 07/16/2021        | 2,560.63        | R AND M / REFURBISHMENT  |
|                 |                     | 7    | 21.6             | 07/31/2021        | 08/18/2021        | 438.00          | ANNUAL MAINTENANCE       |
|                 |                     | 8    | 21.6             | 08/15/2021        | 08/17/2021        | 67.50           | ANNUAL MAINTENANCE       |
| <b>TANGEDCO</b> |                     |      |                  |                   |                   |                 |                          |
| 64              | KADAMPARI HPS       | 2    | 100.0            | 04/16/2021        | 07/13/2021        | 2,123.75        | ANNUAL MAINTENANCE       |
| <b>KPCL</b>     |                     |      |                  |                   |                   |                 |                          |
| 65              | KADRA HPS           | 2    | 50.0             | 05/04/2021        | 05/15/2021        | 276.83          | ANNUAL MAINTENANCE       |
| 66              | KODASALI HPS        | 1    | 40.0             | 09/06/2021        | 09/09/2021        | 67.42           | RENOVATION/MODERNISATION |
|                 |                     | 1    | 40.0             | 06/02/2021        | 06/15/2021        | 317.00          | ANNUAL MAINTENANCE       |
|                 |                     | 2    | 40.0             | 01/19/2022        | 01/24/2022        | 127.33          | PENSTOCK PRESSURE SHAFT  |
|                 |                     | 3    | 40.0             | 02/14/2022        | 03/12/2022        | 623.37          | ANNUAL MAINTENANCE       |
|                 |                     | 3    | 40.0             | 05/24/2021        | 05/31/2021        | 172.92          | TURBINE INSPECTION MISC  |
| <b>TANGEDCO</b> |                     |      |                  |                   |                   |                 |                          |
| 67              | KUNDAH-I HPS        | 1    | 20.0             | 04/17/2021        | 05/21/2021        | 820.25          | OVERHAULING WORKS        |
|                 |                     | 2    | 20.0             | 04/20/2021        | 05/11/2021        | 513.50          | MONTHLY MAINTENANCE      |
| 68              | KUNDAH-II HPS       | 4    | 35.0             | 09/27/2021        | 09/29/2021        | 56.33           | MONTHLY MAINTENANCE      |
| <b>KSEB</b>     |                     |      |                  |                   |                   |                 |                          |
| 69              | KUTTIYADI ADDL EXTN | 1    | 50.0             | 03/05/2022        | 03/09/2022        | 109.60          | PENSTOCK PRESSURE SHAFT  |
|                 |                     | 1    | 50.0             | 12/01/2021        | 01/01/2022        | 752.33          | ANNUAL MAINTENANCE       |
|                 |                     | 2    | 50.0             | 03/05/2022        | 03/09/2022        | 109.10          | PENSTOCK PRESSURE SHAFT  |
|                 |                     | 2    | 50.0             | 04/03/2021        | 05/01/2021        | 683.60          | ANNUAL MAINTENANCE       |
| 70              | KUTTIYADI EXTN HPS  | 4    | 50.0             | 05/05/2021        | 06/04/2021        | 731.05          | ANNUAL MAINTENANCE       |
|                 |                     | 4    | 50.0             | 01/24/2022        | 03/23/2022        | 1,401.88        | ANNUAL MAINTENANCE       |
| 71              | KUTTIYADI HPS       | 1    | 25.0             | 01/26/2022        | 01/30/2022        | 113.08          | SCHEDULED CAPITAL        |
|                 |                     | 1    | 25.0             | 03/11/2022        | 03/16/2022        | 136.67          | OVERHAULING WORKS        |
|                 |                     | 1    | 25.0             | 11/01/2021        | 11/26/2021        | 605.40          | ANNUAL MAINTENANCE       |
|                 |                     | 2    | 25.0             | 01/02/2022        | 01/22/2022        | 489.33          | ANNUAL MAINTENANCE       |
|                 |                     | 2    | 25.0             | 03/11/2022        | 03/16/2022        | 136.80          | OVERHAULING WORKS        |
|                 |                     | 2    | 25.0             | 01/26/2022        | 01/30/2022        | 113.37          | SCHEDULED CAPITAL        |
|                 |                     | 3    | 25.0             | 01/26/2022        | 01/30/2022        | 113.25          | SCHEDULED CAPITAL        |
|                 |                     | 3    | 25.0             | 03/11/2022        | 03/16/2022        | 136.70          | OVERHAULING WORKS        |
| <b>TANGEDCO</b> |                     |      |                  |                   |                   |                 |                          |
| 72              | LOWER METTUR-III    | 5    | 15.0             | 04/16/2021        | 05/05/2021        | 452.67          | ANNUAL MAINTENANCE       |
|                 |                     | 5    | 15.0             | 03/02/2022        | 03/21/2022        | 469.00          | ANNUAL MAINTENANCE       |
|                 |                     | 6    | 15.0             | 04/16/2021        | 05/05/2021        | 453.17          | ANNUAL MAINTENANCE       |
| 73              | LOWER METTUR-IV     | 7    | 15.0             | 02/14/2022        | 03/06/2022        | 490.00          | ANNUAL MAINTENANCE       |
|                 |                     | 7    | 15.0             | 04/01/2021        | 04/14/2021        | 329.00          | ANNUAL MAINTENANCE       |

| S.No            | STATION            | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS               |
|-----------------|--------------------|------|------------------|-------------------|-------------------|-----------------|-----------------------|
|                 |                    | 8    | 15.0             | 03/07/2022        | 03/26/2022        | 461.00          | ANNUAL MAINTENANCE    |
| 74              | METTUR DAM HPS     | 2    | 12.5             | 07/03/2021        | 08/03/2021        | 751.27          | INSPECTION /MTCE      |
| 75              | MOYAR HPS          | 1    | 12.0             | 03/24/2022        | 03/28/2022        | 96.50           | MONTHLY MAINTENANCE   |
|                 |                    | 2    | 12.0             | 03/24/2022        | 03/28/2022        | 96.58           | MONTHLY MAINTENANCE   |
|                 |                    | 3    | 12.0             | 03/24/2022        | 03/28/2022        | 96.25           | MONTHLY MAINTENANCE   |
|                 |                    | 3    | 12.0             | 09/26/2021        | 10/22/2021        | 628.33          | OVERHAULING WORKS     |
| <b>KSEB</b>     |                    |      |                  |                   |                   |                 |                       |
| 76              | NARIAMANGLAM HPS   | 1    | 17.55            | 04/01/2021        | 03/31/2022        | 8,760.00        | ANNUAL MAINTENANCE    |
| <b>TANGEDCO</b> |                    |      |                  |                   |                   |                 |                       |
| 77              | PAPANASAM HPS      | 3    | 8.0              | 04/01/2021        | 04/29/2021        | 675.83          | ANNUAL MAINTENANCE    |
|                 |                    | 4    | 8.0              | 04/22/2021        | 05/27/2021        | 837.58          | ANNUAL MAINTENANCE    |
| 78              | PERIYAR HPS        | 2    | 42.0             | 05/01/2021        | 05/13/2021        | 305.33          | MISCELLANEOUS PLANNED |
|                 |                    | 3    | 42.0             | 05/04/2021        | 05/25/2021        | 510.67          | MISCELLANEOUS PLANNED |
|                 |                    | 4    | 35.0             | 04/10/2021        | 05/22/2021        | 1,016.00        | ANNUAL MAINTENANCE    |
| 79              | PYKARA ULTMATE HPS | 2    | 50.0             | 04/01/2021        | 03/31/2022        | 8,760.00        | ANNUAL MAINTENANCE    |
| <b>KSEB</b>     |                    |      |                  |                   |                   |                 |                       |
| 80              | SABARIGIRI HPS     | 1    | 50.0             | 02/07/2022        | 02/23/2022        | 394.78          | ANNUAL MAINTENANCE    |
|                 |                    | 2    | 50.0             | 09/01/2021        | 10/23/2021        | 1,255.62        | ANNUAL MAINTENANCE    |
|                 |                    | 2    | 50.0             | 02/04/2022        | 02/10/2022        | 158.38          | MAIN GENERTATOR       |
|                 |                    | 3    | 50.0             | 12/14/2021        | 01/03/2022        | 499.67          | ANNUAL MAINTENANCE    |
|                 |                    | 5    | 50.0             | 01/10/2022        | 02/02/2022        | 564.67          | ANNUAL MAINTENANCE    |
| <b>TANGEDCO</b> |                    |      |                  |                   |                   |                 |                       |
| 81              | SARKARPATHY HPS    | 1    | 30.0             | 06/02/2021        | 07/09/2021        | 900.17          | MONTHLY MAINTENANCE   |
| 82              | SURULIYAR HPS      | 1    | 35.0             | 07/01/2021        | 07/30/2021        | 719.92          | MISCELLANEOUS PLANNED |
| <b>KPCL</b>     |                    |      |                  |                   |                   |                 |                       |
| 83              | VARAHI HPS         | 1    | 115.0            | 11/09/2021        | 12/11/2021        | 775.43          | ANNUAL MAINTENANCE    |
|                 |                    | 3    | 115.0            | 01/05/2022        | 01/17/2022        | 298.15          | ANNUAL MAINTENANCE    |
| <b>Western</b>  |                    |      |                  |                   |                   |                 |                       |
| <b>MPPGCL</b>   |                    |      |                  |                   |                   |                 |                       |
| 84              | BANSAGAR-II HPS    | 1    | 15.0             | 12/20/2021        | 12/24/2021        | 108.32          | ANNUAL MAINTENANCE    |
|                 |                    | 2    | 15.0             | 04/01/2021        | 09/03/2021        | 3,735.68        | ANNUAL MAINTENANCE    |
| 85              | BANSAGAR TONS-I    | 3    | 105.0            | 04/01/2021        | 03/31/2022        | 8,760.00        | CAPITAL MAINTENANCE   |
| <b>NHDC</b>     |                    |      |                  |                   |                   |                 |                       |
| 86              | INDIRA SAGAR HPS   | 3    | 125.0            | 04/01/2021        | 04/16/2021        | 354.67          | ANNUAL MAINTENANCE    |
|                 |                    | 4    | 125.0            | 04/16/2021        | 05/25/2021        | 949.53          | ANNUAL MAINTENANCE    |
|                 |                    | 5    | 125.0            | 03/01/2022        | 03/11/2022        | 257.90          | ANNUAL MAINTENANCE    |
|                 |                    | 5    | 125.0            | 05/01/2021        | 05/13/2021        | 300.87          | ANNUAL MAINTENANCE    |
|                 |                    | 6    | 125.0            | 05/17/2021        | 05/29/2021        | 287.67          | ANNUAL MAINTENANCE    |
|                 |                    | 7    | 125.0            | 05/31/2021        | 06/11/2021        | 260.28          | ANNUAL MAINTENANCE    |

| S.No             | STATION            | UNIT | CAPACIT<br>Y(MW) | DATE OF<br>OUTAGE | DATE OF<br>RETURN | OUTAGE<br>HOURS | REASONS              |
|------------------|--------------------|------|------------------|-------------------|-------------------|-----------------|----------------------|
|                  |                    | 7    | 125.0            | 03/13/2022        | 03/24/2022        | 275.57          | ANNUAL MAINTENANCE   |
|                  |                    | 8    | 125.0            | 01/21/2022        | 01/24/2022        | 81.37           | MISC. SHORT DURATION |
|                  |                    | 8    | 125.0            | 06/12/2021        | 06/30/2021        | 439.97          | ANNUAL MAINTENANCE   |
| <b>MAHAGENCO</b> |                    |      |                  |                   |                   |                 |                      |
| 87               | KOYNA-I&II HPS     | 5    | 80.0             | 03/02/2022        | 03/06/2022        | 113.33          | CAPITAL MAINTENANCE  |
| <b>NHDC</b>      |                    |      |                  |                   |                   |                 |                      |
| 88               | OMKARESHWAR HPS    | 1    | 65.0             | 04/02/2021        | 04/16/2021        | 337.13          | ANNUAL MAINTENANCE   |
|                  |                    | 2    | 65.0             | 05/01/2021        | 05/08/2021        | 176.10          | ANNUAL MAINTENANCE   |
|                  |                    | 2    | 65.0             | 06/23/2021        | 06/29/2021        | 152.13          | ANNUAL MAINTENANCE   |
|                  |                    | 3    | 65.0             | 05/27/2021        | 06/09/2021        | 320.38          | ANNUAL MAINTENANCE   |
|                  |                    | 4    | 65.0             | 04/16/2021        | 04/29/2021        | 312.45          | ANNUAL MAINTENANCE   |
|                  |                    | 5    | 65.0             | 05/18/2021        | 05/26/2021        | 200.15          | ANNUAL MAINTENANCE   |
|                  |                    | 5    | 65.0             | 06/10/2021        | 06/15/2021        | 128.37          | ANNUAL MAINTENANCE   |
|                  |                    | 6    | 65.0             | 06/16/2021        | 06/22/2021        | 152.82          | ANNUAL MAINTENANCE   |
|                  |                    | 6    | 65.0             | 05/10/2021        | 05/17/2021        | 176.52          | ANNUAL MAINTENANCE   |
|                  |                    | 7    | 65.0             | 03/15/2022        | 03/26/2022        | 273.75          | ANNUAL MAINTENANCE   |
|                  |                    | 8    | 65.0             | 03/02/2022        | 03/14/2022        | 290.75          | ANNUAL MAINTENANCE   |
| <b>SSNNL</b>     |                    |      |                  |                   |                   |                 |                      |
| 89               | S SAROVAR CHPH HPS | 1    | 50.0             | 04/01/2021        | 08/16/2021        | 3,306.07        | CAPITAL MAINTENANCE  |
| 90               | S SAROVAR RBPH HPS | 6    | 200.0            | 04/01/2021        | 04/16/2021        | 366.50          | ANNUAL MAINTENANCE   |
| <b>MAHAGENCO</b> |                    |      |                  |                   |                   |                 |                      |
| 91               | VAITARNA HPS       | 1    | 60.0             | 11/07/2021        | 12/04/2021        | 670.17          | ANNUAL MAINTENANCE   |
|                  |                    | 1    | 60.0             | 12/05/2021        | 12/09/2021        | 109.88          | ANNUAL MAINTENANCE   |

# CHAPTER-5

## FORCED OUTAGES OF HE UNITS

## CHAPTER-5

### FORCED OUTAGES OF HE UNITS

**5.1** Forced outages of generating units are due to various problems in generating equipments, auxiliary systems, civil structures. Based on the analysis carried out for 727 hydro generating units installed in 210 Hydro Electric Power Stations, non-availability of hydro-electric units in the country due to forced outages during the year 2021-22 (excluding miscellaneous outages) was 2.88% as compared to 3.27% during 2020-21.

Unit-wise details of forced outages of duration 24 hours and above are given in **Annex- 5.1**.

During 2021-22, the generator and turbine faults accounted for 28.58% and 41.64% of the forced outages respectively whereas other equipment & civil structure faults accounted for 2.28% & 27.51% respectively of the forced outages. The summary of forced outages caused due to breakdown of generator, turbine and other equipment during 2021-22 vis-à-vis 2020-21 is given in **Table 5.1** below.

**TABLE 5.1**

#### **EQUIPMENT/SYSTEM-WISE FORCED OUTAGES (2021-22 VIS-A-VIS 2020-21)**

| Sl. No. | Equipment    | Forced Outage (Hours) |                  | % of total Forced Outage |               | Increase/ Decrease viz-z-viz 2020-21 |
|---------|--------------|-----------------------|------------------|--------------------------|---------------|--------------------------------------|
|         |              | 2021-22               | 2020-21          | 2021-22                  | 2020-21       |                                      |
| 1       | Generator    | 44588.94              | 29383.71         | 28.58                    | 16.92         | -51.75                               |
| 2       | Turbine      | 64968.00              | 77437.71         | 41.64                    | 44.60         | 16.10                                |
| 3       | Civil        | 42932.26              | 45016.77         | 27.51                    | 25.92         | 4.63                                 |
| 4       | Other        | 3551.99               | 21805.83         | 2.28                     | 12.56         | 83.71                                |
|         | <b>Total</b> | <b>156041.19</b>      | <b>173644.02</b> | <b>100.00</b>            | <b>100.00</b> | <b>10.14</b>                         |

It is observed that forced outages in 2021-22 vis-a-vis 2020-21 have decreased on account of turbine and other equipment whereas the same have decreased on account of generator and civil structures.

## 5.2 FORCED OUTAGE DUE TO GENERATOR COMPONENTS

**5.2.1** The major source of forced outage during 2021-22 includes Stator (51.62 %), followed by Rotor Fault (18.46 %), Excitation System (10.2 %) and Protection system (7.32 %) which together accounted for more than the 88% of the forced outages due to generator components.

The details of forced outages due to various generator faults and associated systems under different categories based on their size are given in **Table 5.2** below:

**TABLE 5.2**  
**FORCED OUTAGE HOURS DUE TO BREAKDOWN OF**  
**GENERATOR COMPONENTS (PERIOD: 2021-22)**

| Sl. No. | Components of Generator     | Unit size up to 50 MW |            | Unit size above 50 MW & up to 100 MW |            | Unit size above 100 MW |            | Total           |            |
|---------|-----------------------------|-----------------------|------------|--------------------------------------|------------|------------------------|------------|-----------------|------------|
| 1       | AUTOMATIC VOLTAGE REGULATOR | 0                     | 0          | 608.35                               | 6.08       | 0                      | 0          | 608.35          | 1.36       |
| 2       | BRAKE AND JACKS             | 3.23                  | 0.01       | 1                                    | 0.01       | 74.63                  | 0.91       | 78.87           | 0.18       |
| 3       | EXCITATION SYSTEM           | 120.6                 | 0.46       | 16.77                                | 0.17       | 4409.57                | 53.96      | 4546.94         | 10.2       |
| 4       | GENERATOR COOLING SYSTEM    | 14.13                 | 0.05       | 0.85                                 | 0.01       | 30.6                   | 0.37       | 45.59           | 0.1        |
| 5       | LOWER GUIDE BEARING         | 30.42                 | 0.12       | 2.88                                 | 0.03       | 732.57                 | 8.96       | 765.87          | 1.72       |
| 6       | MISCELLANEOUS GENERATOR     | 580.95                | 2.2        | 1397.01                              | 13.96      | 109.86                 | 1.34       | 2087.81         | 4.68       |
| 7       | PROTECTION SYSTEM           | 703.69                | 2.66       | 41.87                                | 0.42       | 2519.77                | 30.84      | 3265.32         | 7.32       |
| 8       | ROTOR                       | 142.25                | 0.54       | 7929.75                              | 79.26      | 159.67                 | 1.95       | 8231.67         | 18.46      |
| 9       | STATOR                      | 23000.62              | 87.08      | 0.77                                 | 0.01       | 16.85                  | 0.21       | 23018.23        | 51.62      |
| 10      | THRUST BEARING              | 1761.7                | 6.67       | 1.28                                 | 0.01       | 5.93                   | 0.07       | 1768.91         | 3.97       |
| 11      | UPPER GUIDE BEARING         | 55.63                 | 0.21       | 1.38                                 | 0.01       | 111.96                 | 1.37       | 168.98          | 0.38       |
| 12      | VIBRATION/SOUND/ ALIGNMENT  | 0                     | 0          | 2.4                                  | 0.02       | 0                      | 0          | 2.4             | 0.01       |
|         | <b>Total</b>                | <b>26413.22</b>       | <b>100</b> | <b>10004.31</b>                      | <b>100</b> | <b>8171.42</b>         | <b>100</b> | <b>44588.94</b> | <b>100</b> |

From the Table 5.2, it is observed that Stator fault (87.08) constitute the major reason for forced outage in respect unit size up to 50 MW the major contributors of forced outage in respect unit size above 50 MW.

### 5.3 FORCED OUTAGE DUE TO TURBINE COMPONENTS

**5.3.1** Faults in Miscellaneous Turbine Components parts (44.90%), Other Faults (37.056%) and Runner/underwater parts (13.59%) are the major reasons of forced outages on account of turbine components.

The details of forced outages due to various turbine faults and associated systems under different categories based on their size are given in **Table 5.3** below:

**TABLE 5.3**  
**FORCED OUTAGE HOURS DUE TO BREAKDOWN OF**  
**TURBINE COMPONENTS**  
**PERIOD: 2021-22**

| Sl. No. | Components of Turbine            | Unit size up to 50 MW |              | Unit size above 50 MW & up to 100 MW |            | Unit size above 100 MW |            | Total           |              |
|---------|----------------------------------|-----------------------|--------------|--------------------------------------|------------|------------------------|------------|-----------------|--------------|
| 1       | GOVERNOR SYSTEM                  | 99.05                 | 0.16         | 4.70                                 | 1.67       | 18.38                  | 0.72       | <b>122.13</b>   | <b>0.19</b>  |
| 2       | MISCELLANEOUS TURBINE COMPONENTS | <b>28503.03</b>       | <b>45.87</b> | 113.60                               | 40.41      | 556.65                 | 21.84      | <b>29173.29</b> | <b>44.90</b> |
| 3       | OTHERS                           | 24064.35              | 38.73        | 0.00                                 | 0.00       | 11.30                  | 0.44       | <b>24075.65</b> | <b>37.06</b> |
| 4       | BEARING                          | 84.32                 | 0.14         | 14.35                                | 5.10       | 139.85                 | 5.49       | <b>238.52</b>   | <b>0.37</b>  |
| 5       | GUIDE VANES                      | 2.25                  | 0.00         | 0.00                                 | 0.00       | 813.10                 | 31.90      | <b>815.35</b>   | <b>1.26</b>  |
| 6       | RUNNER/UNDERWATER PARTS          | 8760.00               | 14.10        | 70.71                                | 25.16      | 0.90                   | 0.04       | <b>8831.61</b>  | <b>13.59</b> |
| 7       | SHAFT VIBRATION/ALIGNMENT/S      | 573.51                | 0.92         | 69.18                                | 24.61      | 1003.38                | 39.37      | <b>1646.08</b>  | <b>2.53</b>  |
| 8       | MAIN INLET VALVE                 | 51.62                 | 0.08         | 8.55                                 | 3.04       | 5.20                   | 0.20       | <b>65.37</b>    | <b>0.10</b>  |
|         | <b>Total</b>                     | <b>62138.13</b>       | <b>100</b>   | <b>281.10</b>                        | <b>100</b> | <b>2548.77</b>         | <b>100</b> | <b>64968.00</b> | <b>100</b>   |

From the Table 5.3, it is observed that Miscellaneous turbine components (45.87%) constitute the major reason for forced outage in respect unit size up to 50 MW while Shaft vibrations/alignment constitute the major contributor of forced outage in respect of unit size above 50 MW.

#### 5.4 ANALYSIS BASED ON TYPE OF TURBINE

The analysis of forced outages due to turbine components as per type of turbines is given in **Table 5.4** below:

**TABLE 5.4**  
**FORCED OUTAGES-TURBINE TYPE-WISE**  
**PERIOD: 2021-22**

| S. No. | Type of Turbine | Number of Units | Installed Capacity MW | Forced Outage Hours | Avg. Forced Outage Hours per Unit |
|--------|-----------------|-----------------|-----------------------|---------------------|-----------------------------------|
| 1      | Bulb            | 26              | 684.00                | 0                   | 0                                 |
| 2      | Francis         | 419             | 32820.57              | 54981.33            | 131.22                            |
| 3      | Kaplan          | 133             | 4399.05               | 163.80              | 1.23                              |
| 4      | Pelton          | 149             | 8818.90               | 9822.86             | 69.55                             |
|        | <b>TOTAL</b>    | <b>727</b>      | <b>46722.52</b>       | <b>64968.00</b>     | <b>89.36</b>                      |

Forced outage rate was observed to be the highest in case of Francis turbines (131.22 hrs./unit) followed by Pelton turbines (69.55 hrs./unit) and Kaplan turbines (1.23 hrs./unit).

#### 5.5 ANALYSIS BASED ON MAKE OF UNITS

The comparative performance of generating units of different makes is indicated in **Table 5.5**. The outage figures in the table relate to faults in turbine and generator only.

TABLE 5.5

**FORCED OUTAGES DUE TO FAULT IN TURBINE & GENERATOR  
(SUPPLIER-WISE) PERIOD: 2021-22**

| S. No.              | Name of Supplier/<br>Country of Make | No. of<br>Units | Installed<br>Capacity<br>(MW) | Total No. of<br>Forced<br>Outages<br>Hours) | Average Forced<br>Outages due to<br>Generating Units<br>(Hours/Unit) | Performance<br>Ranking in Term<br>of Lowest<br>Average Outage<br>Hours/Unit |
|---------------------|--------------------------------------|-----------------|-------------------------------|---------------------------------------------|----------------------------------------------------------------------|-----------------------------------------------------------------------------|
| <b>A-Indigenous</b> |                                      |                 |                               |                                             |                                                                      |                                                                             |
| 1                   | BHEL                                 | 310             | 20030.30                      | 72012.95                                    | 232.30                                                               | 5                                                                           |
| 2                   | Others*                              | 54              | 3395.50                       | 35388.64                                    | 411.50                                                               | 9                                                                           |
|                     | <b>SUB TOTAL</b>                     | <b>364</b>      | <b>23425.80</b>               | <b>107401.59</b>                            | <b>271.22</b>                                                        |                                                                             |
| <b>B-Imported</b>   |                                      |                 |                               |                                             |                                                                      |                                                                             |
| 3                   | USA                                  | 9               | 351.00                        | 5537.61                                     | 291.45                                                               | 6                                                                           |
| 4                   | U.K.                                 | 63              | 1242.10                       | 18776.09                                    | 302.84                                                               | 7                                                                           |
| 5                   | France                               | 31              | 2179.20                       | 567.86                                      | 51.62                                                                | 3                                                                           |
| 6                   | Canada                               | 44              | 3132.00                       | 401.68                                      | 10.57                                                                | 1                                                                           |
| 7                   | USSR                                 | 26              | 2804.00                       | 506.92                                      | 19.50                                                                | 2                                                                           |
| 8                   | Switzerland                          | 21              | 790.20                        | 10045.31                                    | 313.92                                                               | 8                                                                           |
| 9                   | Japan                                | 76              | 6398.20                       | 8251.73                                     | 111.51                                                               | 4                                                                           |
| 10                  | Other                                | 93              | 6400                          | 30792.44                                    | 446.27                                                               | 10                                                                          |
|                     | <b>SUB-TOTAL</b>                     | <b>363</b>      | <b>23296.70</b>               | <b>74879.64</b>                             | <b>226.22</b>                                                        |                                                                             |
|                     | <b>TOTAL</b>                         | <b>727</b>      | <b>46722.50</b>               | <b>182281.23</b>                            | <b>250.73</b>                                                        |                                                                             |

\* Indigenous supplier like Andritz India, B Foursess Bangalore, Atstom India, VA Tech India, etc.

It is observed that Performance Ranking in Term of Lowest Average Outage Hours/Unit is best with Imported by country such as USSR, France & Canada.

## 5.6 ANALYSIS AGE-WISE

Details of forced outages of generating units commissioned during different years are indicated in **Table 5.6**. Forced outages caused by equipment failure i.e. the fault relating to generator, turbine, and auxiliary system equipments have been taken into account for the purpose of computation.

**TABLE - 5.6**

**FORCED OUTAGES DUE TO EQUIPMENT BREAKDOWN  
(AGE-WISE) PERIOD: 2021-22**

| <b>S. No.</b> | <b>Year of Commissioning</b> | <b>No. of Units</b> | <b>Installed Capacity (MW)</b> | <b>Forced Outage (Hours)</b> | <b>Average Annual Non-availability per Unit (Hours)</b> |
|---------------|------------------------------|---------------------|--------------------------------|------------------------------|---------------------------------------------------------|
| 1             | 2021-22                      | 7                   | 393                            | 50.23                        | 7.18                                                    |
| 2             | 2020-21                      | 8                   | 510                            | 6.30                         | 0.79                                                    |
| 3             | 2019-20                      | 2                   | 300.00                         | 0.00                         | 0.0                                                     |
| 4             | 2018-19                      | 3                   | 140.00                         | 4.28                         | 1.43                                                    |
| 5             | 2017-18                      | 16                  | 795.00                         | 2801.67                      | 175.10                                                  |
| 6             | 2016-17                      | 18                  | 1,659.00                       | 457.63                       | 25.42                                                   |
| 7             | 2015-16                      | 17                  | 1,516.00                       | 532.38                       | 31.32                                                   |
| 8             | 2010-11 to 2014-15           | 63                  | 4,437.00                       | 1217.83                      | 19.33                                                   |
| 9             | 2005-06 to 2009-10           | 66                  | 7,077.00                       | 9875.94                      | 149.64                                                  |
| 10            | 2000-01 to 2004-05           | 74                  | 6,741.80                       | 9828.11                      | 132.81                                                  |
| 11            | 1989-90 to 1999-2000         | 86                  | 5,769.70                       | 28775.03                     | 334.59                                                  |
| 12            | 1978-79 to 1988-89           | 124                 | 7,259.10                       | 24620.16                     | 198.55                                                  |
| 13            | 1967-68 to 1977-78           | 81                  | 5,279.75                       | 23706.8                      | 292.68                                                  |
| 14            | Up to 1966-67                | 162                 | 4,724.85                       | 62182.2                      | 383.84                                                  |
|               | <b>Total</b>                 | <b>727</b>          | <b>46722.50</b>                | <b>182281.23</b>             | <b>250.73</b>                                           |

It is observed that the per unit forced outage rate was relatively higher in older units and was maximum in the case of units commissioned in Up to 1966-67 (383.84 hrs./unit).

### **5.7 REGION-WISE PERFORMANCE**

The region-wise summary of performance of the hydel generating units is indicated in **Table 5.7**. For the purpose of computation, all types of forced outages/tripping due to faults in generator, turbine, auxiliary system & other equipments and civil structure faults (excluding misc.) have been included.

**TABLE 5.7**  
**FORCED OUTAGES – REGION-WISE**  
**PERIOD: 2021-22**

| S.No | Region           | No. of Units | Installed Capacity (MW) | % Non-availability due to Forced Outages |
|------|------------------|--------------|-------------------------|------------------------------------------|
| 1    | Northern         | 256          | 19576.25                | 1.83                                     |
| 2    | Western          | 101          | 7392                    | 3.93                                     |
| 3    | Southern         | 246          | 11739.5                 | 2.31                                     |
| 4    | Eastern          | 86           | 5987.75                 | 0.40                                     |
| 5    | North Eastern    | 38           | 2027.0                  | 16.27                                    |
|      | <b>All India</b> | <b>727</b>   | <b>46722.50</b>         | <b>2.88</b>                              |

Performance of hydro generating equipment installed in Eastern Region was the best as the non-availability due to forced outages was least (0.40%). The average non-availability of the units in the North Eastern Region (16.27) and in the Western Region (3.93%) was observed to be on the higher side.

#### **5.8 FORCED OUTAGE – UTILITY-WISE**

The forced outages of hydro electric units under various Central Sector Utilities, Private Sector and State Power Generation Corporations are indicated in **Table 5.8**.

All types of forced outages/tripping due to problems in generating units, auxiliary equipments and civil structure have been taken into account for the analysis.

**Table 5.8**  
**FORCED OUTAGES- BOARD /CORPORATION WISE**  
**PERIOD: 2021-22**

| S. No.                | Organization     | No. of Units | Installed Capacity (MW) | Forced Outage (Hours) | Average Annual Forced Outage/Unit (Hours) |
|-----------------------|------------------|--------------|-------------------------|-----------------------|-------------------------------------------|
| <b>Central Sector</b> |                  |              |                         |                       |                                           |
| 1                     | BBMB             | 28           | 2938.30                 | 365.67                | 13.06                                     |
| 2                     | DVC              | 5            | 143.20                  | 567.86                | 113.57                                    |
| 3                     | NEEPCO.          | 20           | 1500.00                 | 45263.01              | 2263.15                                   |
| 4                     | NHDC             | 16           | 1520.00                 | 0.00                  | 0.00                                      |
| 5                     | NHPC             | 70           | 5451.20                 | 2077.40               | 29.68                                     |
| 6                     | NTPC LTD.        | 4            | 800.00                  | 56.75                 | 14.19                                     |
| 7                     | SJVNL            | 12           | 1912.02                 | 194.83                | 16.24                                     |
| 8                     | THDC             | 8            | 1400.00                 | 0.00                  | 0.00                                      |
|                       | <b>Sub Total</b> | <b>163</b>   | <b>15664.72</b>         | <b>48525.53</b>       | <b>297.70</b>                             |

| <b>State Sector</b>   |                  |            |                 |                  |               |
|-----------------------|------------------|------------|-----------------|------------------|---------------|
| 1                     | APGCL            | 2          | 100.00          | 0.00             | 0.00          |
| 2                     | APGENCO          | 34         | 1796.75         | 60.03            | 1.77          |
| 3                     | CSPGCL           | 3          | 120.00          | 0.00             | 0.00          |
| 4                     | GSECL            | 8          | 540.00          | 0.00             | 0.00          |
| 5                     | HPPCL            | 8          | 406.00          | 159.86           | 19.98         |
| 7                     | HPSEB            | 12         | 372.00          | 139.87           | 11.66         |
| 8                     | JKSPDC           | 12         | 1110.00         | 0.00             | 0.00          |
| 9                     | JUUNL            | 2          | 130.00          | 0.00             | 0.00          |
| 10                    | KPCL             | 66         | 3617.20         | 10491.61         | 158.96        |
| 11                    | KSEB             | 47         | 1856.50         | 955.44           | 20.33         |
| 12                    | MAHAGENCO        | 24         | 2406.00         | 6744.77          | 281.03        |
| 13                    | MePGCL           | 13         | 322.00          | 8760.00          | 673.85        |
| 14                    | MPPGCL           | 23         | 875.00          | 19037.15         | 827.70        |
| 15                    | OHPC             | 31         | 2039.80         | 0.00             | 0.00          |
| 16                    | PSPCL            | 25         | 1051.00         | 0.00             | 0.00          |
| 17                    | RRVUNL           | 11         | 411.00          | 32824.35         | 2984.03       |
| 18                    | SSNNL            | 11         | 1450.00         | 4.25             | 0.39          |
| 19                    | TANGEDCO         | 69         | 2178.20         | 30604.25         | 443.54        |
| 20                    | TSGENCO          | 36         | 2405.60         | 7807.30          | 216.87        |
| 21                    | TUL              | 6          | 1200.00         | 1359.17          | 226.53        |
| 22                    | UJVNL            | 34         | 1252.15         | 2453.25          | 72.15         |
| 23                    | UPJVNL           | 15         | 501.60          | 0.00             | 0.00          |
| 24                    | WBSEDCL          | 12         | 986.00          | 0.00             | 0.00          |
|                       | <b>Sub Total</b> | <b>504</b> | <b>27126.80</b> | <b>121401.31</b> | <b>240.88</b> |
| <b>Private Sector</b> |                  |            |                 |                  |               |
| 1                     | ADHPL            | 2          | 192.00          | 129.90           | 64.95         |
| 2                     | AHPC (GVK)       | 4          | 330.00          | 203.50           | 50.88         |
| 3                     | DEPL             | 2          | 96.00           | 15.25            | 7.62          |
| 4                     | DLHP             | 1          | 34.00           | 0.00             | 0.00          |
| 5                     | E.P.P.L.         | 2          | 100.00          | 49.32            | 24.66         |
| 6                     | GBHPPL           | 2          | 70.00           | 2231.71          | 1115.86       |
| 7                     | GIPL             | 2          | 110.00          | 7.67             | 3.83          |
| 8                     | GMR BHHPL        | 3          | 180.00          | 0.00             | 0.00          |

|    |                        |            |                 |                  |               |
|----|------------------------|------------|-----------------|------------------|---------------|
| 9  | HBPCL                  | 7          | 1345.00         | 36.00            | 5.14          |
| 10 | HSPCL                  | 2          | 100.00          | 1.38             | 0.69          |
| 11 | IAEPL                  | 3          | 36.00           | 0.00             | 0.00          |
| 12 | JPPVL                  | 4          | 400.00          | 376.20           | 94.05         |
| 13 | L&T                    | 3          | 99.00           | 0.00             | 0.00          |
| 14 | MBPC                   | 2          | 113.00          | 48.85            | 24.42         |
| 12 | MPCL                   | 2          | 86.00           | 0.00             | 0.00          |
| 13 | SEPL                   | 2          | 97.00           | 263.25           | 131.62        |
| 14 | SKPPPL                 | 2          | 96.00           | 0.00             | 0.00          |
| 15 | TATA MAH.              | 15         | 447.00          | 8991.38          | 599.43        |
|    | <b>Sub Total</b>       | <b>60</b>  | <b>3931.00</b>  | <b>12354.40</b>  | <b>205.91</b> |
|    | <b>All India Total</b> | <b>727</b> | <b>46722.52</b> | <b>182281.23</b> | <b>250.73</b> |

It is observed that utility-wise, per unit forced outages for generating units was maximum in respect of hydro-electric stations under RRVUNL (2984 hrs./unit). On the other hand, the hydro generating units of THDC, NHDC, APGCL, GSECL, CSPGCL, JKSPDC, JUUNL, PSPCL, OHPC, UPJVNL, WBSEDCL, DLHP, GMR BHHPL, IAEPL, L&T, MPCL, SKPPL. have reported nil forced outage operation.

## 5.9 DURATION OF FORCED OUTAGES

There were total 996 forced outages/tripping during the year 2021-22. Duration of individual outage varied widely from a few minutes to the maximum of full year.

The duration pattern of forced outages is indicated in **Table 5.9** and **Exhibit 5.1**. It could be seen that about 71.08% of the total forced shutdown were of duration less than 6 hours while 14.36% of outages were of duration varying from 6 to 24 hours and only 5.22% of shutdowns persisted for more than 10 days.

**TABLE 5.9**  
**DURATION PATTERN OF FORCED OUTAGES**  
**PERIOD: 2021-22**

| S. No. | Duration of Hours           | Number of Outages | % of Total of Outages |
|--------|-----------------------------|-------------------|-----------------------|
| 1      | More than 10 days           | 52                | 5.22                  |
| 2      | Less than 6 hour            | 708               | 71.08                 |
| 3      | 6 to 24 hours               | 143               | 14.36                 |
| 4      | 1 to 10 days                | 93                | 9.34                  |
|        | <b>Total No. of Outages</b> | <b>996</b>        | <b>100</b>            |

## 5.10 FORCED OUTAGES - STATION-WISE

The number of H.E. Stations falling under various ranges of non-availability due to forced outages during the year 2021-22 vis-à-Vis 2020-21 is summarized below in **Table 5.10**.

**TABLE 5.10**  
**NON-AVAILABILITY OF HE STATIONS DUE TO FORCED OUTAGES**  
**(2021-22 VIS-A-VIS 2020-21)**


| % Non-Availability due to Forced Outages | 2021-22    |            |                 |            | 2020-21    |            |                 |            |
|------------------------------------------|------------|------------|-----------------|------------|------------|------------|-----------------|------------|
|                                          | Stations   |            | Capacity        |            | Stations   |            | Stations        |            |
|                                          | No.        | % of Total | MW              | % of Total | No.        | % of Total | MW              | % of Total |
| 0                                        | 128        | 60.95      | 22,682.25       | 48.55      | 124        | 59.90      | 21588.70        | 46.72      |
| >0 to 1                                  | 17         | 8.10       | 6,944.95        | 14.86      | 14         | 5.80       | 4101.30         | 8.88       |
| >1 to 2                                  | 3          | 1.43       | 606.00          | 1.30       | 3          | 1.45       | 975             | 2.11       |
| >2 to 3                                  | 0          | 0.00       | 0.00            | 0.00       | 1          | 0.48       | 75              | 0.16       |
| >3 to 4                                  | 2          | 0.95       | 150.00          | 0.32       | 4          | 1.93       | 1212.20         | 2.62       |
| >4 to 5                                  | 2          | 0.95       | 155.30          | 0.33       | 4          | 1.93       | 1004            | 2.17       |
| >5                                       | 58         | 27.62      | 16,184.02       | 34.64      | 59         | 28.50      | 17253.02        | 37.34      |
| <b>Total</b>                             | <b>210</b> | <b>100</b> | <b>46722.52</b> | <b>100</b> | <b>209</b> | <b>100</b> | <b>46209.22</b> | <b>100</b> |

It could be seen from above that there was no forced outage at 128 nos. (60.95% of total) hydro-electric stations during 2021-22 as compared to 124 nos. (59.90% of total) hydro-electric stations during 2020-21.

27.62% of stations had operational availability lower than 95% on account of forced outages alone against the normative design/planned annual availability of 95% during the entire station life. These utilities need to improve their O&M practices to bring down their total outages i.e. planned & forced to less than 5% as per best practices.

It is observed from above that stations may be having high forced outages on account of ageing, O&M management issues, etc. Further, those stations which are having continuously high planned maintenance/forced outages over past few years may be requiring major repair and maintenance works or Renovation & Modernization (R&M) works for improving the availability, reliability & security of the plant besides providing life extension where the assets have outlived their useful life.

## DURATION PATTERN OF FORCED OUTAGES DURING 2021-22



**CENTRAL ELECTRICITY AUTHORITY**  
**Hydro WING**  
**Hydro Project Planning & Investigation Division**

**Annexure 5.1**

**DETAILS OF LONG DURATION FORCED OUTAGE IN HYDRO-ELECTRIC UNITS DURING: 2021-22**

**(OUTAGE DURATION 24 HOURS AND ABOVE)**

| S.NO      | STATION             | UNIT | CAPACITY(MW) | DATE OD OUTAGE    | DATE OF RETURN    | OUTAGE HOURS | REASONS                                |
|-----------|---------------------|------|--------------|-------------------|-------------------|--------------|----------------------------------------|
| Northern  |                     |      |              |                   |                   |              |                                        |
| ADHPL     |                     |      |              |                   |                   |              |                                        |
| 1         | ALLAIN DUHANGAN HPS | 1    | 96.0         | 11/18/21, 9:45 AM | 11/19/21, 5:59 PM | 32.23        | NEEDLE PROBLEM                         |
| NHPC      |                     |      |              |                   |                   |              |                                        |
| 2         | BAIRA SIUL HPS      | 3    | 60.0         | 9/3/21, 12:32 PM  | 9/4/21, 9:43 PM   | 33.18        | GENERATOR<br>DIFFERENTIALPROTECTION    |
|           |                     | 3    | 60.0         | 9/10/21, 5:30 PM  | 9/19/21, 3:06 PM  | 213.60       | TURBINE MISC. PROBLEM                  |
| GBHPPL    |                     |      |              |                   |                   |              |                                        |
| 3         | BUDHIL HPS          | 1    | 35.0         | 12/29/21, 7:25 PM | 3/16/22, 4:00 PM  | 1844.59      | ABNORMAL SOUND                         |
|           |                     | 2    | 35.0         | 12/29/21, 7:25 PM | 1/14/22, 10:32 PM | 387.12       | A.V.R. FAILURE                         |
| NHPC      |                     |      |              |                   |                   |              |                                        |
| 4         | CHUTAK HPS          | 4    | 11.0         | 7/28/21, 7:23 PM  | 7/30/21, 10:20 AM | 38.95        | TURBINE SHAFT SEAL<br>WORK/REPLACMEENT |
| UJVNL     |                     |      |              |                   |                   |              |                                        |
| 5         | DHAKRANI HPS        | 2    | 11.25        | 5/6/21, 12:00 AM  | 6/25/21, 9:30 PM  | 1221.50      | MISCELLANEOUS                          |
| NHPC      |                     |      |              |                   |                   |              |                                        |
| 6         | DHAULI GANGA HPS    | 1    | 70.0         | 11/29/21, 5:08 PM | 11/30/21, 7:31 PM | 26.38        | MISCELLANEOUS ELECTRICAL WORKS         |
| HPSEB     |                     |      |              |                   |                   |              |                                        |
| 7         | GIRI BATA HPS       | 1    | 30.0         | 6/5/21, 9:00 AM   | 6/6/21, 5:00 PM   | 32.00        | LEAKAGE OIL VENT PIPE                  |
|           |                     | 2    | 30.0         | 5/8/21, 9:00 AM   | 5/11/21, 5:00 PM  | 80.00        | L.T.SUPPLY FAILURE.                    |
| NHPC      |                     |      |              |                   |                   |              |                                        |
| 8         | KISHANGANGA HPS     | 1    | 110.0        | 8/8/21, 9:00 PM   | 8/9/21, 9:07 PM   | 24.11        | NEEDLE PROBLEM                         |
|           |                     | 2    | 110.0        | 5/30/21, 7:10 AM  | 6/1/21, 11:59 PM  | 64.82        | GENERATOR<br>DIFFERENTIALPROTECTION    |
|           |                     | 2    | 110.0        | 11/4/21, 5:45 PM  | 11/5/21, 7:09 PM  | 25.40        | ROTOR EARTH FAULT                      |
| NTPC Ltd. |                     |      |              |                   |                   |              |                                        |
| 9         | KOLDAM              | 4    | 200.0        | 6/27/21, 5:40 AM  | 6/29/21, 2:25 PM  | 56.75        | GENEARTOR MISC.                        |
| E.P.P.L.  |                     |      |              |                   |                   |              |                                        |
| 10        | MALANA-II HPS       | 1    | 50.0         | 2/6/22, 4:29 PM   | 2/8/22, 4:15 PM   | 47.77        | BREAKER/ISOLATOR PROBLEM               |
| UJVNL     |                     |      |              |                   |                   |              |                                        |
| 11        | MANERI BHALI-II HPS | 4    | 76.0         | 8/28/21, 10:30 AM | 8/29/21, 2:00 PM  | 27.50        | MISCELLANEOUS                          |

| S.NO       | STATION           | UNIT | CAPACITY(MW) | DATE OD OUTAGE     | DATE OF RETURN    | OUTAGE HOURS | REASONS                                         |
|------------|-------------------|------|--------------|--------------------|-------------------|--------------|-------------------------------------------------|
|            |                   | 4    | 76.0         | 11/8/21, 9:00 AM   | 11/9/21, 10:30 AM | 25.50        | VIBRATIONS                                      |
| SJVNL      |                   |      |              |                    |                   |              |                                                 |
| 12         | NATHPA JHAKRI HPS | 3    | 250.0        | 2/4/22, 6:51 AM    | 2/6/22, 4:23 PM   | 57.53        | GENERATOR<br>DIFFERENTIALPROTECTION             |
|            |                   | 4    | 250.0        | 2/5/22, 5:00 AM    | 2/6/22, 5:48 PM   | 36.80        | MIV LEAKAGE                                     |
| BBMB       |                   |      |              |                    |                   |              |                                                 |
| 13         | PONG HPS          | 2    | 66.0         | 7/29/21, 3:00 PM   | 7/30/21, 8:20 PM  | 29.33        | COMPRESSED AIR SYSTEM PROBLEM                   |
|            |                   | 3    | 66.0         | 7/29/21, 3:00 PM   | 8/3/21, 4:40 PM   | 121.67       | COMPRESSED AIR SYSTEM PROBLEM                   |
|            |                   | 5    | 66.0         | 7/29/21, 3:00 PM   | 8/1/21, 11:59 PM  | 81.00        | COMPRESSED AIR SYSTEM PROBLEM                   |
|            |                   | 6    | 66.0         | 7/29/21, 3:00 PM   | 8/1/21, 11:59 PM  | 81.00        | COMPRESSED AIR SYSTEM PROBLEM                   |
| UJVNL      |                   |      |              |                    |                   |              |                                                 |
| 14         | RAMGANGA HPS      | 2    | 66.0         | 10/19/21, 12:05 PM | 10/28/21, 8:45 PM | 224.67       | MISCELLANEOUS                                   |
|            |                   | 2    | 66.0         | 11/6/21, 12:00 PM  | 12/15/21, 3:40 PM | 939.67       | MISCELLANEOUS                                   |
| SJVNL      |                   |      |              |                    |                   |              |                                                 |
| 15         | RAMPUR HPS        | 3    | 68.67        | 10/7/21, 4:58 PM   | 10/10/21, 6:01 PM | 73.05        | GEN./TR.BREAKER /AIR LEAK<br>ABCB/MOCB OIL LEAK |
| RRVUNL     |                   |      |              |                    |                   |              |                                                 |
| 16         | R P SAGAR HPS     | 1    | 43.0         | 4/1/21, 12:00 AM   | 12/29/21, 4:21 PM | 6544.35      | FLOODING OF POWER HOUSE                         |
|            |                   | 2    | 43.0         | 4/1/21, 12:00 AM   | 3/31/22, 11:59 PM | 8760.00      | GENERATOR STATOR DAMAGED                        |
|            |                   | 3    | 43.0         | 4/1/21, 12:00 AM   | 3/31/22, 11:59 PM | 8760.00      | FLOODING OF POWER HOUSE                         |
|            |                   | 4    | 43.0         | 4/1/21, 12:00 AM   | 3/31/22, 11:59 PM | 8760.00      | FLOODING OF POWER HOUSE                         |
| HPPCL      |                   |      |              |                    |                   |              |                                                 |
| 17         | SAWRA KUDDU HPS   | 2    | 37.0         | 3/10/22, 12:00 AM  | 3/16/22, 3:51 PM  | 159.86       | TURBINE SHAFT SEAL LEAK/BOLTS<br>BROKEN         |
| AHPC (GVK) |                   |      |              |                    |                   |              |                                                 |
| 18         | SHRINAGAR HPS     | 1    | 82.5         | 6/15/21, 7:45 AM   | 6/22/21, 10:00 PM | 182.25       | DESILTING CHAMBER PROBLEM                       |
| NHPC       |                   |      |              |                    |                   |              |                                                 |
| 19         | TANAKPUR HPS      | 2    | 31.4         | 7/21/21, 12:38 AM  | 7/22/21, 11:42 PM | 47.07        | TURBINE SHAFT SEAL LEAK/BOLTS<br>BROKEN         |
| JPPVL      |                   |      |              |                    |                   |              |                                                 |
| 20         | VISHNU PRAYAG HPS | 2    | 100.0        | 3/13/22, 10:14 PM  | 3/16/22, 6:32 PM  | 68.30        | PENSTOCK LEAKAGE                                |
|            |                   | 3    | 100.0        | 10/30/21, 12:00 AM | 11/11/21, 5:21 PM | 305.35       | BREAKER/ISOLATOR PROBLEM                        |
| Western    |                   |      |              |                    |                   |              |                                                 |
| TATA MAH.  |                   |      |              |                    |                   |              |                                                 |
| 21         | BHIRA PSS HPS     | 1    | 150.0        | 6/20/21, 5:25 AM   | 6/29/21, 6:25 PM  | 229.01       | PENSTOCK EXP. JOINT PROBLEM                     |
| MPPGCL     |                   |      |              |                    |                   |              |                                                 |
| 22         | GANDHI SAGAR HPS  | 1    | 23.0         | 3/2/22, 12:00 AM   | 3/7/22, 11:20 PM  | 143.34       | GEN. TRNASFORMER WINDING<br>TEMP.HIGH           |

| S.NO      | STATION                | UNIT | CAPACITY(MW) | DATE OD OUTAGE     | DATE OF RETURN     | OUTAGE HOURS | REASONS                                      |
|-----------|------------------------|------|--------------|--------------------|--------------------|--------------|----------------------------------------------|
|           |                        | 2    | 23.0         | 4/1/21, 12:00 AM   | 3/31/22, 11:59 PM  | 8760.00      | POWER HOUSE FLOODED                          |
|           |                        | 3    | 23.0         | 4/1/21, 12:00 AM   | 3/31/22, 11:59 PM  | 8760.00      | POWER HOUSE FLOODED                          |
| MAHAGENCO |                        |      |              |                    |                    |              |                                              |
| 23        | GHATGHAR PSS HPS       | 1    | 125.0        | 9/1/21, 8:50 PM    | 9/3/21, 2:10 AM    | 29.33        | MISCELLANEOUS                                |
|           |                        | 1    | 125.0        | 10/2/21, 4:30 PM   | 10/4/21, 1:40 AM   | 33.17        | OIL LEAKAGE PROBLEM<br>OPU/SUM/SYSTEM        |
|           |                        | 1    | 125.0        | 10/7/21, 1:34 AM   | 10/10/21, 12:15 PM | 82.68        | TURBINE BEARING OIL LEAKAGE                  |
|           |                        | 1    | 125.0        | 11/10/21, 11:56 PM | 2/12/22, 8:00 PM   | 2252.07      | STATIC EXCITATION EQUIPMENT<br>PROBLEM       |
|           |                        | 2    | 125.0        | 8/1/21, 5:20 AM    | 8/4/21, 12:30 PM   | 79.17        | MISCELLANEOUS                                |
|           |                        | 2    | 125.0        | 11/10/21, 11:56 PM | 1/15/22, 8:15 PM   | 1580.32      | STATIC EXCITATION EQUIPMENT<br>PROBLEM       |
|           |                        | 2    | 125.0        | 1/19/22, 12:05 PM  | 1/21/22, 4:25 PM   | 52.33        | A.V.R. FAILURE                               |
|           |                        | 2    | 125.0        | 2/17/22, 9:55 PM   | 3/10/22, 8:35 PM   | 502.67       | STATIC EXCITATION EQUIPMENT<br>PROBLEM       |
| TATA MAH. |                        |      |              |                    |                    |              |                                              |
| 24        | KHOPOLI HPS            | 2    | 24.0         | 4/1/21, 12:00 AM   | 3/31/22, 11:59 PM  | 8760.00      | NEEDLE PROBLEM                               |
| MAHAGENCO |                        |      |              |                    |                    |              |                                              |
| 25        | KOYNA-III HPS          | 3    | 80.0         | 4/1/21, 12:00 AM   | 5/29/21, 3:20 PM   | 1407.33      | GENERATOR EARTH FAULT                        |
| MPPGCL    |                        |      |              |                    |                    |              |                                              |
| 26        | PENCH HPS              | 1    | 80.0         | 9/12/21, 12:00 AM  | 9/20/21, 8:14 PM   | 212.23       | GENERATOR ON FIRE                            |
|           |                        | 1    | 80.0         | 10/9/21, 12:00 AM  | 11/25/21, 10:50 AM | 1138.84      | GENEARTOR MISC.                              |
| MAHAGENCO |                        |      |              |                    |                    |              |                                              |
| 27        | VAITARNA HPS           | 1    | 60.0         | 2/22/22, 12:00 AM  | 3/19/22, 7:55 AM   | 607.92       | AVR PROBLEM/TRIPPED                          |
| Southern  |                        |      |              |                    |                    |              |                                              |
| TANGEDCO  |                        |      |              |                    |                    |              |                                              |
| 28        | BHAWANI BARRAGE-II HPS | 2    | 15.0         | 8/22/21, 8:06 PM   | 8/27/21, 8:15 PM   | 120.15       | LUB.OIL SYSTEM PROBLEM                       |
| KPCL      |                        |      |              |                    |                    |              |                                              |
| 29        | GERUSUPPA HPS          | 3    | 60.0         | 5/1/21, 5:50 AM    | 6/11/21, 12:00 AM  | 978.17       | GENEATOR TRANSFORMER /BUSHING<br>OIL LEAKAGE |
| KSEB      |                        |      |              |                    |                    |              |                                              |
| 30        | IDUKKI HPS             | 6    | 130.0        | 6/7/21, 8:55 AM    | 6/10/21, 11:33 AM  | 74.63        | BRAKING SYSTEM PROBLEM                       |
|           |                        | 6    | 130.0        | 6/13/21, 7:48 AM   | 6/14/21, 5:41 PM   | 33.88        | GOVERNING SYSTEM PROBLEM                     |
| KPCL      |                        |      |              |                    |                    |              |                                              |
| 31        | JOG HPS                | 2    | 13.2         | 4/1/21, 12:00 AM   | 3/31/22, 11:59 PM  | 8760.00      | STATOR COIL BURNT                            |
|           |                        | 3    | 13.2         | 4/5/21, 5:10 PM    | 4/7/21, 12:40 PM   | 43.50        | A.V.R. FAILURE                               |
|           |                        | 4    | 13.2         | 4/16/21, 9:05 AM   | 4/19/21, 9:25 AM   | 72.33        | NEEDLE PROBLEM                               |
|           |                        | 6    | 21.6         | 8/16/21, 5:40 PM   | 8/17/21, 8:50 PM   | 27.17        | NEEDLE PROBLEM                               |

| S.NO     | STATION             | UNIT | CAPACITY(MW) | DATE OD OUTAGE    | DATE OF RETURN     | OUTAGE HOURS | REASONS                                         |
|----------|---------------------|------|--------------|-------------------|--------------------|--------------|-------------------------------------------------|
|          |                     | 8    | 21.6         | 4/1/21, 12:00 AM  | 4/12/21, 4:18 PM   | 280.30       | STATOR COIL BURNT                               |
|          |                     | 8    | 21.6         | 7/22/21, 10:50 AM | 7/23/21, 7:05 PM   | 32.25        | NEEDLE PROBLEM                                  |
| TANGEDCO |                     |      |              |                   |                    |              |                                                 |
| 32       | KADAMPARI HPS       | 1    | 100.0        | 4/2/21, 12:00 AM  | 10/18/21, 1:05 AM  | 4777.08      | ROTOR EARTH FAULT                               |
|          |                     | 1    | 100.0        | 12/17/21, 4:15 PM | 3/31/22, 11:55 PM  | 2503.67      | ROTOR MISC. FAULTS                              |
|          |                     | 2    | 100.0        | 9/21/21, 12:05 AM | 10/18/21, 1:05 AM  | 649.00       | ROTOR MISC. FAULTS                              |
|          |                     | 3    | 100.0        | 4/1/21, 12:00 AM  | 3/31/22, 11:59 PM  | 8760.00      | RSD/LOW SCHEDULE                                |
| KPCL     |                     |      |              |                   |                    |              |                                                 |
| 33       | KADRA HPS           | 1    | 50.0         | 5/24/21, 8:30 AM  | 5/27/21, 7:05 PM   | 82.58        | GEN./TR.BREAKER                                 |
|          |                     | 3    | 50.0         | 6/28/21, 10:30 AM | 7/1/21, 7:40 PM    | 81.17        | EHT/ISOLATOR PROBLEMS/MAINT.CHECK               |
| TANGEDCO |                     |      |              |                   |                    |              |                                                 |
| 34       | KODAYAR-I HPS       | 1    | 60.0         | 4/28/21, 11:09 AM | 6/8/21, 12:00 AM   | 972.85       | ROTOR/ Rotor EARTH FAULT                        |
|          |                     | 1    | 60.0         | 3/14/22, 9:50 AM  | 3/17/22, 8:32 AM   | 70.71        | RUNNER                                          |
| 35       | KODAYAR-II HPS      | 2    | 40.0         | 8/29/21, 10:45 PM | 3/22/22, 4:55 PM   | 4914.17      | STATOR                                          |
| 36       | KUNDAH-I HPS        | 1    | 20.0         | 11/28/21, 8:35 AM | 11/29/21, 8:35 PM  | 36.00        | MISCELLANEOUS                                   |
|          |                     | 3    | 20.0         | 6/8/21, 7:40 PM   | 6/10/21, 4:45 PM   | 45.08        | COOLING TOWER PROBLEM                           |
| KSEB     |                     |      |              |                   |                    |              |                                                 |
| 37       | KUTTIYADI ADDL EXTN | 1    | 50.0         | 11/10/21, 8:00 AM | 11/12/21, 5:47 PM  | 57.78        | ROTOR MISC. FAULTS                              |
| 38       | KUTTIYADI EXTN HPS  | 4    | 50.0         | 7/7/21, 12:00 AM  | 7/8/21, 3:21 PM    | 39.35        | ELECTRICAL SYSTEM/PANELS/CONTRACTOR/JUMP STATOR |
| 39       | KUTTIYADI HPS       | 2    | 25.0         | 9/20/21, 8:06 AM  | 9/21/21, 8:02 PM   | 35.93        |                                                 |
| TANGEDCO |                     |      |              |                   |                    |              |                                                 |
| 40       | METTUR TUNNEL HPS   | 4    | 50.0         | 8/13/21, 6:02 AM  | 8/24/21, 7:45 PM   | 277.70       | GEN.PROTECTION RELAY OPERATION                  |
|          |                     | 4    | 50.0         | 11/19/21, 8:50 AM | 11/28/21, 10:03 PM | 229.22       | STATOR EARTH FAULT                              |
| 41       | MOYAR HPS           | 1    | 12.0         | 5/7/21, 4:55 PM   | 5/11/21, 9:05 AM   | 88.17        | LEAKAGE OIL VENT PIPE                           |
|          |                     | 1    | 12.0         | 6/1/21, 4:55 PM   | 6/3/21, 1:00 PM    | 44.08        | SPARKING ACROSS SLIP RING/BRUSHES               |
|          |                     | 1    | 12.0         | 2/1/22, 12:00 AM  | 2/12/22, 8:00 PM   | 284.00       | THRUST BEARING TEMP. HIGH                       |
|          |                     | 2    | 12.0         | 2/13/22, 1:25 AM  | 2/15/22, 6:50 PM   | 65.42        | ROTOR MISC. FAULTS                              |
|          |                     | 3    | 12.0         | 6/10/21, 12:00 PM | 6/12/21, 1:50 PM   | 49.83        | MISCELLANEOUS                                   |
|          |                     | 3    | 12.0         | 10/25/21, 1:10 AM | 11/3/21, 3:20 PM   | 230.17       | VIBRATIONS                                      |
|          |                     | 3    | 12.0         | 12/1/21, 12:00 AM | 1/30/22, 11:55 PM  | 1463.92      | THRUST BEARING TEMP. HIGH                       |
| TSGENCO  |                     |      |              |                   |                    |              |                                                 |
| 42       | NAGARJUN SGR HPS    | 2    | 100.8        | 9/1/21, 12:00 AM  | 9/3/21, 9:07 PM    | 69.12        | TURBINE SHAFT SEAL WORK/REPLACMEENT             |

| S.NO     | STATION                 | UNIT | CAPACITY(MW) | DATE OD OUTAGE     | DATE OF RETURN     | OUTAGE HOURS | REASONS                                            |
|----------|-------------------------|------|--------------|--------------------|--------------------|--------------|----------------------------------------------------|
|          |                         | 3    | 100.8        | 10/2/21, 10:28 PM  | 10/11/21, 5:06 PM  | 210.63       | GEN. TRANSORMER PROTECTION RELAY OPERATION PROBLEM |
|          |                         | 4    | 100.8        | 1/20/22, 8:30 AM   | 2/9/22, 7:38 PM    | 491.13       | GENEATOR TRANSFORMER OIL PROBLEMS/TOPPING          |
|          |                         | 8    | 100.8        | 10/11/21, 4:01 AM  | 10/18/21, 9:13 PM  | 185.20       | GENERATOR TRANSFORMER BUCHOLTZ                     |
| 43       | PRIYADARSHNI JURALA HPS | 5    | 39.0         | 4/1/21, 12:00 AM   | 9/30/21, 12:59 PM  | 4380.98      | REVERSE POWER RELAY OPERATION                      |
| KSEB     |                         |      |              |                    |                    |              |                                                    |
| 44       | SABARIGIRI HPS          | 2    | 50.0         | 10/24/21, 4:09 AM  | 11/7/21, 10:36 AM  | 342.45       | GENERATOR DIFFERENTIALPROTECTION                   |
|          |                         | 6    | 50.0         | 4/1/21, 12:00 AM   | 4/3/21, 5:35 PM    | 65.58        | GENERATOR DIFFERENTIALPROTECTION                   |
| TSGENCO  |                         |      |              |                    |                    |              |                                                    |
| 45       | SRISAILAM LB HPS        | 3    | 150.0        | 4/1/21, 12:00 AM   | 5/17/21, 7:48 PM   | 1123.80      | GENERATOR NEGATIVE PHASE SEQUENCE                  |
|          |                         | 6    | 150.0        | 12/26/21, 12:00 AM | 2/16/22, 6:23 PM   | 1266.38      | GEN.PROTECTION RELAY OPERATION                     |
| TANGEDCO |                         |      |              |                    |                    |              |                                                    |
| 46       | SURULIYAR HPS           | 1    | 35.0         | 9/4/21, 5:55 PM    | 3/31/22, 11:55 PM  | 4998.00      | PENSTOCK REPAIR WORKS                              |
| Eastern  |                         |      |              |                    |                    |              |                                                    |
| DVC      |                         |      |              |                    |                    |              |                                                    |
| 47       | MAITHON HPS             | 1    | 20.0         | 7/1/21, 3:40 AM    | 7/2/21, 11:04 AM   | 31.40        | GOVERNING SYSTEM PROBLEM                           |
|          |                         | 2    | 23.2         | 6/26/21, 1:00 PM   | 6/29/21, 9:55 AM   | 68.92        | EXCT. FAIL/LOSS OF EXCITATION /MISC. PROB.         |
|          |                         | 2    | 23.2         | 10/30/21, 6:00 PM  | 11/3/21, 6:17 PM   | 96.28        | GEN./TR.BREAKER                                    |
|          |                         | 2    | 23.2         | 1/20/22, 9:40 AM   | 1/25/22, 12:55 PM  | 123.25       | GEN./TR.BREAKER                                    |
|          |                         | 3    | 20.0         | 11/8/21, 11:15 AM  | 11/14/21, 5:05 PM  | 149.83       | GOVERNING SYSTEM PROBLEM                           |
| NHPC     |                         |      |              |                    |                    |              |                                                    |
| 48       | RANGIT HPS              | 1    | 20.0         | 4/20/21, 6:30 PM   | 4/22/21, 6:54 PM   | 48.40        | MAL-FUNCTION OF RELAY                              |
|          |                         | 1    | 20.0         | 4/30/21, 6:30 PM   | 5/1/21, 11:59 PM   | 29.50        | EXCITATION PROBLEM                                 |
|          |                         | 2    | 20.0         | 4/14/21, 6:31 PM   | 4/15/21, 11:59 PM  | 29.48        | MAIN INLET VALVE PROBLEM                           |
|          |                         | 2    | 20.0         | 8/27/21, 9:41 AM   | 8/29/21, 4:58 PM   | 55.28        | UGB COOLING SYSTEM PROBLEM                         |
|          |                         | 3    | 20.0         | 11/9/21, 5:55 PM   | 11/10/21, 10:12 PM | 28.28        | TURBINE BEARING PADS DAMAGED                       |
| SEPL     |                         |      |              |                    |                    |              |                                                    |
| 49       | TASHIDING HPS           | 1    | 48.5         | 5/27/21, 12:55 AM  | 5/28/21, 10:00 AM  | 33.08        | DAM RESIDUAL WORKS                                 |
|          |                         | 1    | 48.5         | 6/17/21, 7:30 PM   | 6/19/21, 11:45 AM  | 40.25        | DAM RESIDUAL WORKS                                 |
|          |                         | 1    | 48.5         | 6/25/21, 4:55 AM   | 6/26/21, 6:10 PM   | 37.25        | LINE BREAKER FAULT                                 |
|          |                         | 2    | 48.5         | 5/27/21, 12:55 AM  | 5/28/21, 10:00 AM  | 33.08        | DAM RESIDUAL WORKS                                 |
|          |                         | 2    | 48.5         | 6/17/21, 7:20 PM   | 6/19/21, 12:20 PM  | 41.00        | DAM RESIDUAL WORKS                                 |
|          |                         | 2    | 48.5         | 6/25/21, 4:55 AM   | 6/26/21, 6:00 PM   | 37.08        | BREAKER/ISOLATOR PROBLEM                           |

| S.NO          | STATION                | UNIT | CAPACITY(MW) | DATE OD OUTAGE    | DATE OF RETURN    | OUTAGE HOURS | REASONS                                       |
|---------------|------------------------|------|--------------|-------------------|-------------------|--------------|-----------------------------------------------|
| TUL           |                        |      |              |                   |                   |              |                                               |
| 50            | TEESTA-III HPS         | 3    | 200.0        | 4/21/21, 3:00 PM  | 4/24/21, 6:30 PM  | 75.50        | UPPER GUIDE BEARING MISC.                     |
|               |                        | 4    | 200.0        | 10/11/21, 9:31 PM | 11/7/21, 3:29 PM  | 641.98       | GENERATOR TRANSFORMER                         |
|               |                        | 6    | 200.0        | 4/1/21, 12:00 AM  | 4/16/21, 4:55 PM  | 376.92       | MAIN DISC SEAL<br>PROBLEM/REPLACEMENT         |
|               |                        | 6    | 200.0        | 1/15/22, 9:29 AM  | 1/24/22, 8:02 PM  | 226.55       | BREAKER/ISOLATOR PROBLEM                      |
| NHPC          |                        |      |              |                   |                   |              |                                               |
| 51            | TEESTA LOW DAM-III HPS | 2    | 33.0         | 8/18/21, 12:02 AM | 8/19/21, 10:57 AM | 34.92        | TURBINE SHAFT SEAL<br>WORK/REPLACMEENT        |
| 52            | TEESTA LOW DAM-IV HPS  | 1    | 40.0         | 6/29/21, 7:14 AM  | 6/30/21, 11:59 PM | 40.77        | MAL-FUNCTION OF RELAY                         |
| 53            | TEESTA V HPS           | 3    | 170.0        | 5/17/21, 6:08 PM  | 5/20/21, 12:27 AM | 54.32        | GEN.TR.BREAKER MECH.PROBLEM                   |
| North Eastern |                        |      |              |                   |                   |              |                                               |
| NEEPCO.       |                        |      |              |                   |                   |              |                                               |
| 54            | DOYANG HPS             | 3    | 25.0         | 2/5/22, 6:08 PM   | 2/7/22, 5:23 PM   | 47.25        | COOLING WATER SYSTEM<br>PROBLEM/PIPES REPLACE |
| 55            | KAMENG HPS             | 1    | 150.0        | 4/1/21, 12:00 AM  | 4/18/21, 1:10 PM  | 421.17       | LGB TEMPRATURE HIGH                           |
|               |                        | 1    | 150.0        | 7/29/21, 8:05 AM  | 8/31/21, 2:48 AM  | 786.72       | GUIDE VANES                                   |
|               |                        | 1    | 150.0        | 9/24/21, 2:51 PM  | 9/25/21, 3:54 PM  | 25.05        | MISCELLANEOUS                                 |
|               |                        | 2    | 150.0        | 4/1/21, 12:00 AM  | 4/8/21, 10:22 PM  | 190.37       | LOWER GUIDE BEARING MISC.                     |
|               |                        | 2    | 150.0        | 5/12/21, 10:35 PM | 6/20/21, 5:15 PM  | 930.67       | TURBINE VIBRATION                             |
|               |                        | 2    | 150.0        | 6/20/21, 5:59 PM  | 6/23/21, 8:57 PM  | 74.97        | LGB TEMPRATURE HIGH                           |
|               |                        | 2    | 150.0        | 6/28/21, 7:58 PM  | 6/30/21, 4:26 PM  | 44.47        | LGB TEMPRATURE HIGH                           |
|               |                        | 3    | 150.0        | 4/1/21, 12:00 AM  | 5/14/21, 2:03 PM  | 1046.05      | PENSTOCK REPAIR WORKS                         |
|               |                        | 3    | 150.0        | 6/18/21, 8:32 AM  | 6/19/21, 6:22 PM  | 33.83        | GENERATOR TRANSFORMER                         |
|               |                        | 3    | 150.0        | 8/19/21, 12:00 AM | 9/29/21, 6:44 PM  | 1002.73      | MISCELLANEOUS                                 |
|               |                        | 3    | 150.0        | 10/18/21, 8:06 AM | 11/14/21, 7:19 PM | 659.22       | MISCELLANEOUS                                 |
|               |                        | 3    | 150.0        | 3/7/22, 12:00 AM  | 3/21/22, 7:30 PM  | 355.50       | MISCELLANEOUS                                 |
|               |                        | 4    | 150.0        | 4/1/21, 12:00 AM  | 5/12/21, 7:08 PM  | 1003.13      | PENSTOCK REPAIR WORKS                         |
|               |                        | 4    | 150.0        | 5/17/21, 3:46 PM  | 5/18/21, 6:37 PM  | 26.85        | STATOR EARTH FAULT                            |
|               |                        | 4    | 150.0        | 6/27/21, 12:00 AM | 7/1/21, 6:11 PM   | 114.18       | ROTOR EARTH FAULT                             |
|               |                        | 4    | 150.0        | 9/20/21, 12:00 AM | 1/15/22, 3:32 PM  | 2823.53      | MISCELLANEOUS                                 |
| 56            | KHONDONG HPS           | 2    | 25.0         | 11/22/21, 5:00 PM | 11/23/21, 6:27 PM | 25.45        | ABNORMAL SOUND                                |
| 57            | KOPILI HPS             | 1    | 50.0         | 4/1/21, 12:00 AM  | 3/31/22, 11:59 PM | 8760.00      | PENSTOCK LEAKAGE                              |
|               |                        | 2    | 50.0         | 4/1/21, 12:00 AM  | 3/31/22, 11:59 PM | 8760.00      | PENSTOCK LEAKAGE                              |
|               |                        | 3    | 50.0         | 4/1/21, 12:00 AM  | 3/31/22, 11:59 PM | 8760.00      | PENSTOCK LEAKAGE                              |

| S.NO    | STATION         | UNIT | CAPACITY(MW) | DATE OD OUTAGE    | DATE OF RETURN    | OUTAGE HOURS | REASONS                                  |
|---------|-----------------|------|--------------|-------------------|-------------------|--------------|------------------------------------------|
|         |                 | 4    | 50.0         | 4/1/21, 12:00 AM  | 3/31/22, 11:59 PM | 8760.00      | PENSTOCK LEAKAGE                         |
| MeECL   |                 |      |              |                   |                   |              |                                          |
| 58      | KYRDEMKULAI HPS | 2    | 30.0         | 4/1/21, 12:00 AM  | 3/31/22, 11:59 PM | 8760.00      | RUNNER LABYRING DAMAGED                  |
| NHPC    |                 |      |              |                   |                   |              |                                          |
| 59      | LOKTAK HPS      | 3    | 35.0         | 10/14/21, 1:20 PM | 10/15/21, 5:21 PM | 28.02        | TURBINE SHAFT SEAL LEAK/BOLTS BROKEN     |
|         |                 | 3    | 35.0         | 3/6/22, 4:00 PM   | 3/9/22, 9:35 PM   | 77.58        | GOVERN.SYSTEM TROUB/EQPT. FAIL/EHG FAULT |
| NEEPCO. |                 |      |              |                   |                   |              |                                          |
| 60      | RANGANADI HPS   | 1    | 135.0        | 3/22/22, 12:00 AM | 3/29/22, 2:15 PM  | 182.25       | MISCELLANEOUS                            |
|         |                 | 3    | 135.0        | 4/5/21, 10:30 AM  | 4/6/21, 1:00 PM   | 26.50        | GEN. COOLING SYSTEM MISC. / INSPECTION   |

# CHAPTER-6

## OPERATING AVAILABILITY OF HE UNITS

## CHAPTER-6

### OPERATING AVAILABILITY OF HE UNITS

**6.1** Based on the analysis of data received from the utilities regarding planned maintenance undertaken and forced outages at 727 Hydro Generating units of 210 HE Stations comprising of 46722.52 MW, operating availability of various units and stations has been computed. During the year 2021-22, the average operating availability of hydro generating units on all India basis was 93.67% as compared to 92.68% during 2020-21.

The station-wise/unit-wise non-availability due to Planned Maintenance (P.M) and Forced Outages (F.O) and overall operating availability of various H.E. Stations in the country is indicated in **Annex-6.1**. The station-wise details are also graphically depicted in **Exhibits from 6.1 to 6.14**.

**6.2** The number of H.E. Stations falling under various ranges of operating availability during the year 2021-22 is summarized below in **Table 6.1**.

**TABLE 6.1**

#### OPERATING AVAILABILITY OF H.E. STATIONS (PERIOD: 2021-22)

| Operating Availability (%) | No. of Stations | % of total Stations | Installed Capacity (MW) | % of total Installed Capacity |
|----------------------------|-----------------|---------------------|-------------------------|-------------------------------|
| >=95%                      | 149             | 70.95               | 33943.37                | 72.65                         |
| >=90 to 95                 | 23              | 10.95               | 5044.20                 | 10.80                         |
| >=85 to 90                 | 15              | 7.14                | 3595.95                 | 7.70                          |
| >=80 to 85                 | 6               | 2.86                | 1305.00                 | 2.79                          |
| <80                        | 17              | 8.10                | 2834.00                 | 6.07                          |
| <b>Total</b>               | <b>210</b>      | <b>100.00</b>       | <b>46722.52</b>         | <b>100.00</b>                 |

### 6.3 OPERATING AVAILABILITY – REGION-WISE

Region-wise operating availability of hydro-electric units during 2021-22 is indicated in **Table 6.2**.

**TABLE 6.2**  
**AVAILABILITY OF UNITS - REGION-WISE**  
**PERIOD: 2021-22**

| Sl. No. | Region           | No. of Units | Installed Capacity (MW) | Planned Maintenance | Forced Outage % | Operating Availability (%) |
|---------|------------------|--------------|-------------------------|---------------------|-----------------|----------------------------|
| 1       | Northern         | 256          | 19576.25                | 4.24                | 1.83            | 93.92                      |
| 2       | Western          | 101          | 7392                    | 2.59                | 3.93            | 93.47                      |
| 3       | Southern         | 246          | 11739.5                 | 3.04                | 2.31            | 94.64                      |
| 4       | Eastern          | 86           | 5987.75                 | 4.16                | 0.40            | 95.43                      |
| 5       | N- Eastern       | 38           | 2027.0                  | 1.46                | 16.27           | 82.28                      |
|         | <b>All India</b> | <b>727</b>   | <b>46722.50</b>         | <b>3.45</b>         | <b>2.88</b>     | <b>93.67</b>               |

It is seen that the operating availability of hydel generating units during 2021-22 was the highest (95.43%) in Eastern Region due to relatively lower forced outages. The operating availability was the lowest in case of units in North-Eastern Region (82.28%) due to high planned maintenance and forced outages.

#### **6.4 OPERATING AVAILABILITY: AGE-WISE**

The average operating availability during 2021-22 of hydro units commissioned in various years has been indicated in **Table 6.3**. It is observed that units commissioned during 2020-21 have achieved the operating availability of more than 92%. Operating availability was more than 90% for all the other years.

**TABLE - 6.3**  
**OPERATING AVAILABILITY – AGE-WISE**  
**PERIOD: 2021-22**

| Sl. No. | Year of Commissioning | No. of Units | Installed Capacity (MW) | Operating Availability (%) |
|---------|-----------------------|--------------|-------------------------|----------------------------|
| 1       | 2021-22               | 7            | 393                     | 99.23                      |
| 2       | 2020-21               | 8            | 510                     | 99.97                      |
| 3       | 2019-20               | 2            | 300.00                  | 100.00                     |
| 4       | 2018-19               | 3            | 140.00                  | 100.00                     |
| 5       | 2017-18               | 16           | 795.00                  | 85.86                      |
| 6       | 2016-17               | 18           | 1659.00                 | 96.14                      |
| 7       | 2015-16               | 17           | 1516.00                 | 98.25                      |
| 8       | 2010-11 to 2014-15    | 63           | 4437.00                 | 92.07                      |
| 9       | 2005-06 to 2009-10    | 66           | 7077.00                 | 93.56                      |
| 10      | 2000-01 to 2004-05    | 74           | 6741.80                 | 94.48                      |
| 11      | 1989-90 to 1999-2000  | 86           | 5769.70                 | 90.47                      |
| 12      | 1978-79 to 1988-89    | 124          | 7259.10                 | 90.05                      |
| 13      | 1967-68 to 1977-78    | 81           | 5279.75                 | 86.37                      |
|         | <b>Total</b>          | <b>727</b>   | <b>46722.52</b>         | <b>93.67</b>               |

## 6.5 OPERATING AVAILABILITY – UTILITY-WISE

Sector-wise/State & Private Power Generating Corporation-wise operating availability of HE units is indicated in **Table 6.4**.

It was observed that the operating availability of generating units of Private Sector was the highest (96.53%) followed by State Sector (94.42%) and Central Sector (90.38%).

**TABLE 6.4**

### SECTOR-WISE OPERATING AVAILABILITY OF UTILITIES FOR PERIOD: 2021-22

| S. No.         | Organization | No. of Units | Installed Capacity | Planned Maintenance | Forced Outage | Operating Availability per Unit |
|----------------|--------------|--------------|--------------------|---------------------|---------------|---------------------------------|
|                |              |              | (MW)               | (%)                 | (%)           | (%)                             |
| Central        |              |              |                    |                     |               |                                 |
| 1              | BBMB         | 28           | 2938.30            | 3.76                | 0.15          | 96.09                           |
| 2              | DVC          | 5            | 143.20             | 1.78                | 1.30          | 96.92                           |
| 3              | NEEPCO.      | 20           | 1500.00            | 2.27                | 25.84         | 71.90                           |
| 4              | NHDC         | 16           | 1520.00            | 4.11                | 0.00          | 95.89                           |
| 5              | NHPC         | 70           | 5451.20            | 10.61               | 0.34          | 89.05                           |
| 6              | NTPC Ltd.    | 4            | 800.00             | 1.30                | 0.16          | 98.53                           |
| 7              | SJVNL        | 12           | 1912.02            | 2.61                | 0.19          | 97.21                           |
| 8              | THDC         | 8            | 1400.00            | 1.14                | 0.00          | 98.86                           |
| Sub Total (CS) |              | 163          | 15664.72           | 6.22                | 3.40          | 90.38                           |
| State          |              |              |                    |                     |               |                                 |
| 1              | APGCL        | 2            | 100.00             | 0.00                | 0.00          | 100.00                          |
| 2              | APGENCO      | 34           | 1796.75            | 0.00                | 0.02          | 99.98                           |
| 3              | CSPGCL       | 3            | 120.00             | 0.00                | 0.00          | 100.00                          |
| 4              | GSECL        | 8            | 540.00             | 0.00                | 0.00          | 100.00                          |
| 5              | HPPCL        | 8            | 406.00             | 0.77                | 0.23          | 99.00                           |
| 6              | HPSEB        | 12           | 372.00             | 4.67                | 0.13          | 95.20                           |
| 7              | JKSPDC       | 12           | 1110.00            | 2.09                | 0.00          | 97.91                           |
| 8              | JUUNL        | 2            | 130.00             | 0.00                | 0.00          | 100.00                          |
| 9              | KPCL         | 66           | 3617.20            | 2.87                | 1.81          | 95.32                           |
| 10             | KSEB         | 47           | 1856.50            | 6.14                | 0.23          | 93.63                           |
| 11             | MAHAGENCO    | 24           | 2406.00            | 0.42                | 3.21          | 96.37                           |
| 12             | MeECL        | 13           | 322.00             | 0.00                | 7.69          | 92.31                           |
| 13             | MPPGCL       | 23           | 875.00             | 6.26                | 9.45          | 84.29                           |
| 14             | OHPC         | 31           | 2039.80            | 7.63                | 0.00          | 92.37                           |

| S. No.                   | Organization | No. of Units | Installed Capacity | Planned Maintenance | Forced Outage | Operating Availability per Unit |
|--------------------------|--------------|--------------|--------------------|---------------------|---------------|---------------------------------|
|                          |              |              | (MW)               | (%)                 | (%)           | (%)                             |
| 15                       | PSPCL        | 25           | 1051.00            | 1.22                | 0.00          | 98.78                           |
| 16                       | RRVUNL       | 11           | 411.00             | 0.00                | 34.06         | 65.94                           |
| 17                       | SSNNL        | 11           | 1450.00            | 3.82                | 0.00          | 96.17                           |
| 18                       | TANGEDCO     | 69           | 2178.20            | 3.92                | 5.06          | 91.02                           |
| 19                       | TSGENCO      | 36           | 2405.60            | 0.00                | 2.48          | 97.52                           |
| 20                       | TUL          | 6            | 1200.00            | 3.24                | 2.59          | 94.18                           |
| 21                       | UJVNL        | 34           | 1252.15            | 3.18                | 0.82          | 96.00                           |
| 22                       | UPJVNL       | 15           | 501.60             | 0.00                | 0.00          | 100.00                          |
| 23                       | WBSEDCL      | 12           | 986.00             | 0.00                | 0.00          | 100.00                          |
| <b>Sub Total (State)</b> |              | <b>504</b>   | <b>27126.80</b>    | <b>2.83</b>         | <b>2.75</b>   | <b>94.42</b>                    |
| <b>Private</b>           |              |              |                    |                     |               |                                 |
| 1                        | ADHPL        | 2            | 192.00             | 7.42                | 0.74          | 91.83                           |
| 2                        | AHPC (GVK)   | 4            | 330.00             | 0.00                | 0.58          | 99.42                           |
| 3                        | DEPL         | 2            | 96.00              | 6.94                | 0.09          | 92.98                           |
| 4                        | DLHP         | 1            | 34.00              | 0.00                | 0.00          | 100.00                          |
| 5                        | E.P.P.L.     | 2            | 100.00             | 0.05                | 0.28          | 99.67                           |
| 6                        | GBHPPL       | 2            | 70.00              | 0.00                | 12.74         | 87.26                           |
| 7                        | GIPL         | 2            | 110.00             | 2.60                | 0.04          | 97.36                           |
| 8                        | GMR BHHPL    | 3            | 180.00             | 0.00                | 0.00          | 100.00                          |
| 9                        | HBPCL        | 7            | 1345.00            | 1.17                | 0.06          | 98.78                           |
| 10                       | HSPCL        | 2            | 100.00             | 0.00                | 0.02          | 99.98                           |
| 11                       | IAEPL        | 3            | 36.00              | 0.00                | 0.00          | 100.00                          |
| 12                       | JPPVL        | 4            | 400.00             | 0.43                | 1.07          | 98.49                           |
| 13                       | L&T          | 3            | 99.00              | 0.00                | 0.00          | 100.00                          |
| 14                       | MBPC         | 2            | 113.00             | 0.95                | 0.37          | 98.68                           |
| 15                       | MPCL         | 2            | 86.00              | 2.02                | 0.00          | 97.98                           |
| 16                       | SEPL         | 2            | 97.00              | 1.27                | 1.50          | 97.23                           |
| 17                       | SKPPPL       | 2            | 96.00              | 0.00                | 0.00          | 100.00                          |
| 18                       | TATA MAH.    | 15           | 447.00             | 0.00                | 6.84          | 93.15                           |
| <b>Sub Total (Pvt.)</b>  |              | <b>60</b>    | <b>3931.00</b>     | <b>0.93</b>         | <b>2.54</b>   | <b>96.53</b>                    |
| <b>Grand Total</b>       |              | <b>727</b>   | <b>46722.52</b>    | <b>3.45</b>         | <b>2.88</b>   | <b>93.67</b>                    |

## 6.6 OPERATING AVAILABILITY BELOW 90%- STATION-WISE


It is observed that 11 nos. of stations had operating availability below 90% continuously for last 3 years. The details of these stations is given below in **Table 6.5**. As normative availability factor for entire useful life of station considered during planning stage is 95%, the stations/utilities having lower operating availability factor need to improve their O&M practices to bring down the outages as per best practices.

**TABLE-6.5**

### **OPERATING AVAILABILITY OF H. E. STATIONS CONTINUOUSLY LESS THAN 90% DURING LAST THREE YEARS (2019-20 To 2021-22)**

| Sl. No. | Name of the Stations | Name of the Utility | Installed Capacity (MW) | Operating Availability (%) |         |         |
|---------|----------------------|---------------------|-------------------------|----------------------------|---------|---------|
|         |                      |                     |                         | 2019-20                    | 2020-21 | 2021-22 |
| 1       | BAIRA SIUL HPS       | NHPC                | 180.00                  | 54.21                      | 65.44   | 78.45   |
| 2       | BALIMELA HPS         | OHPC                | 510.00                  | 86.92                      | 87.50   | 87.50   |
| 3       | GHATGHAR PSS HPS     | MAHAGENCO           | 250.00                  | 76.84                      | 52.11   | 73.23   |
| 4       | GIRI BATA HPS        | HPSEB               | 60.00                   | 83.65                      | 73.05   | 88.83   |
| 5       | HIRAKUD HPS          | OHPC                | 275.50                  | 67.56                      | 71.43   | 80.48   |
| 6       | IDUKKI HPS           | KSEB                | 780.00                  | 81.78                      | 80.23   | 88.94   |
| 7       | KADAMPARI HPS        | TANGEDCO            | 400.00                  | 75.00                      | 32.93   | 46.31   |
| 8       | KISHANGANGA HPS      | NHPC                | 330.00                  | 68.90                      | 70.70   | 83.94   |
| 9       | KODAYAR-I HPS        | TANGEDCO            | 60.00                   | 83.76                      | 83.71   | 88.09   |
| 10      | KYRDEMKULAI HPS      | MeECL               | 60.00                   | 50.00                      | 50.00   | 50.00   |
| 11      | PARBATI-III HPS      | NHPC                | 520.00                  | 82.33                      | 85.35   | 89.89   |


OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22



OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22




OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22



OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22




OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22




OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22




OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22




OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22




OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22






OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22




OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22



OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22



OPERATING AVAILABILITY OF H E STATIONS DURING 2021-22



CENTRAL ELECTRICITY AUTHORITY  
Hydro WING  
Hydro Project Planning & Investigation Division  
Annex 6.1

| OPERAING AVAILABILITY OF HYDRO ELECTRIC UNITS DURING 2021-22 |                       |          |                          |                               |                         |                                    |
|--------------------------------------------------------------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| S.No.                                                        | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|                                                              | Northern              |          |                          |                               |                         |                                    |
|                                                              | ADHPL                 |          |                          |                               |                         |                                    |
| 1                                                            | ALLAIN DUHANGAN HPS   | 1        | 96.00                    | 7.30                          | 1.23                    | 91.47                              |
|                                                              |                       | 2        | 96.00                    | 7.55                          | 0.25                    | 92.20                              |
|                                                              | TOTAL                 |          | 192.00                   | 7.42                          | 0.74                    | 91.83                              |
|                                                              | AHPC (GVK)            |          |                          |                               |                         |                                    |
| 2                                                            | SHRINAGAR HPS         | 1        | 82.50                    | 0.00                          | 2.08                    | 97.92                              |
|                                                              |                       | 2        | 82.50                    | 0.00                          | 0.00                    | 100.00                             |
|                                                              |                       | 3        | 82.50                    | 0.00                          | 0.24                    | 99.76                              |
|                                                              |                       | 4        | 82.50                    | 0.00                          | 0.00                    | 100.00                             |
|                                                              | TOTAL                 |          | 330.00                   | 0.00                          | 0.58                    | 99.42                              |
|                                                              | BBMB                  |          |                          |                               |                         |                                    |
| 3                                                            | BHAKRA LEFT HPS       | 1        | 108.00                   | 0.00                          | 0.03                    | 99.97                              |
|                                                              |                       | 2        | 126.00                   | 0.00                          | 0.02                    | 99.98                              |
|                                                              |                       | 3        | 126.00                   | 61.10                         | 0.00                    | 38.90                              |
|                                                              |                       | 4        | 126.00                   | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 5        | 126.00                   | 5.63                          | 0.03                    | 94.35                              |
|       | TOTAL                 |          | 612.00                   | 13.34                         | 0.01                    | 86.64                              |
| 4     | BHAKRA RIGHT HPS      | 6        | 157.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 7        | 157.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 8        | 157.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 9        | 157.00                   | 5.26                          | 0.00                    | 94.74                              |
|       |                       | 10       | 157.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 785.00                   | 1.05                          | 0.00                    | 98.95                              |
| 5     | DEHAR HPS             | 1        | 165.00                   | 4.86                          | 0.00                    | 95.14                              |
|       |                       | 2        | 165.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 165.00                   | 0.00                          | 0.01                    | 99.99                              |
|       |                       | 4        | 165.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 165.00                   | 0.00                          | 0.28                    | 99.72                              |
|       |                       | 6        | 165.00                   | 0.00                          | 0.02                    | 99.98                              |
|       | TOTAL                 |          | 990.00                   | 0.81                          | 0.05                    | 99.14                              |
| 6     | GANGUWAL HPS          | 1        | 29.25                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 24.20                    | 1.12                          | 0.02                    | 98.86                              |
|       |                       | 3        | 24.20                    | 1.07                          | 0.03                    | 98.90                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 77.65                    | 0.73                          | 0.02                    | 99.25                              |
| 7     | KOTLA HPS             | 1        | 29.25                    | 0.00                          | 0.02                    | 99.98                              |
|       |                       | 2        | 24.20                    | 0.00                          | 0.01                    | 99.99                              |
|       |                       | 3        | 24.20                    | 1.07                          | 0.11                    | 98.82                              |
|       | TOTAL                 |          | 77.65                    | 0.36                          | 0.04                    | 99.60                              |
| 8     | PONG HPS              | 1        | 66.00                    | 0.00                          | 0.02                    | 99.98                              |
|       |                       | 2        | 66.00                    | 0.00                          | 0.33                    | 99.67                              |
|       |                       | 3        | 66.00                    | 0.00                          | 1.39                    | 98.61                              |
|       |                       | 4        | 66.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 66.00                    | 25.07                         | 0.92                    | 74.01                              |
|       |                       | 6        | 66.00                    | 0.00                          | 0.94                    | 99.06                              |
|       | TOTAL                 |          | 396.00                   | 4.18                          | 0.60                    | 95.22                              |
|       | E.P.P.L.              |          |                          |                               |                         |                                    |
| 9     | MALANA-II HPS         | 1        | 50.00                    | 0.02                          | 0.55                    | 99.43                              |
|       |                       | 2        | 50.00                    | 0.07                          | 0.02                    | 99.91                              |
|       | TOTAL                 |          | 100.00                   | 0.05                          | 0.28                    | 99.67                              |
|       | GBHPPL                |          |                          |                               |                         |                                    |
| 10    | BUDHIL HPS            | 1        | 35.00                    | 0.00                          | 21.06                   | 78.94                              |
|       |                       | 2        | 35.00                    | 0.00                          | 4.42                    | 95.58                              |

| S.No. | STATION / CORPORATION  | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|------------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                  |          | 70.00                    | 0.00                          | 12.74                   | 87.26                              |
|       | GMR BHHPL              |          |                          |                               |                         |                                    |
| 11    | BAJOLI HOLI HPS        | 1        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 2        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 3        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                  |          | 180.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | HBPCL                  |          |                          |                               |                         |                                    |
| 12    | BASPA HPS              | 1        | 100.00                   | 3.03                          | 0.13                    | 96.84                              |
|       |                        | 2        | 100.00                   | 2.65                          | 0.16                    | 97.19                              |
|       |                        | 3        | 100.00                   | 2.48                          | 0.13                    | 97.39                              |
|       | TOTAL                  |          | 300.00                   | 2.72                          | 0.14                    | 97.14                              |
| 13    | KARCHAM WANGTOO HPS    | 1        | 261.25                   | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 2        | 261.25                   | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 3        | 261.25                   | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 4        | 261.25                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                  |          | 1045.00                  | 0.00                          | 0.00                    | 100.00                             |
|       | HPPCL                  |          |                          |                               |                         |                                    |
| 14    | KASHANG INTEGRATED HEP | 1        | 65.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 2        | 65.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 65.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 195.00                   | 0.00                          | 0.00                    | 100.00                             |
| 15    | SAINJ HPS             | 1        | 50.00                    | 2.24                          | 0.00                    | 97.76                              |
|       |                       | 2        | 50.00                    | 3.92                          | 0.00                    | 96.08                              |
|       | TOTAL                 |          | 100.00                   | 3.08                          | 0.00                    | 96.92                              |
| 16    | SAWRA KUDDU HPS       | 1        | 37.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 37.00                    | 0.00                          | 1.82                    | 98.18                              |
|       |                       | 3        | 37.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 111.00                   | 0.00                          | 0.61                    | 99.39                              |
|       | HPSEB                 |          |                          |                               |                         |                                    |
| 17    | BASSI HPS             | 1        | 16.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 16.50                    | 0.00                          | 0.11                    | 99.89                              |
|       |                       | 3        | 16.50                    | 0.00                          | 0.18                    | 99.82                              |
|       |                       | 4        | 16.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 66.00                    | 0.00                          | 0.07                    | 99.93                              |
| 18    | GIRI BATA HPS         | 1        | 30.00                    | 13.32                         | 0.37                    | 86.31                              |
|       |                       | 2        | 30.00                    | 7.74                          | 0.91                    | 91.35                              |
|       | TOTAL                 |          | 60.00                    | 10.53                         | 0.64                    | 88.83                              |
| 19    | LARJI HPS             | 1        | 42.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 2        | 42.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 42.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 126.00                   | 0.00                          | 0.00                    | 100.00                             |
| 20    | SANJAY HPS            | 1        | 40.00                    | 21.13                         | 0.00                    | 78.87                              |
|       |                       | 2        | 40.00                    | 13.84                         | 0.01                    | 86.15                              |
|       |                       | 3        | 40.00                    | 0.00                          | 0.02                    | 99.98                              |
|       | TOTAL                 |          | 120.00                   | 11.66                         | 0.01                    | 88.34                              |
|       | HSPCL                 |          |                          |                               |                         |                                    |
| 21    | SORANG HPS            | 1        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 50.00                    | 0.00                          | 0.03                    | 99.97                              |
|       | TOTAL                 |          | 100.00                   | 0.00                          | 0.02                    | 99.98                              |
|       | IAEPL                 |          |                          |                               |                         |                                    |
| 22    | CHANJU-I HPS          | 1        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | JKSPDC                |          |                          |                               |                         |                                    |
| 23    | BAGLIHAR HPS          | 1        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 150.00                   | 25.14                         | 0.00                    | 74.86                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 450.00                   | 8.38                          | 0.00                    | 91.62                              |
| 24    | BAGLIHAR II HPS       | 1        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 450.00                   | 0.00                          | 0.00                    | 100.00                             |
| 25    | LOWER JHELUM HPS      | 1        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 105.00                   | 0.00                          | 0.00                    | 100.00                             |
| 26    | UPPER SINDH-II HPS    | 3        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 105.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | JPPVL                 |          |                          |                               |                         |                                    |
| 27    | VISHNU PRAYAG HPS     | 1        | 100.00                   | 0.76                          | 0.00                    | 99.24                              |
|       |                       | 2        | 100.00                   | 0.38                          | 0.79                    | 98.83                              |
|       |                       | 3        | 100.00                   | 0.15                          | 3.50                    | 96.35                              |
|       |                       | 4        | 100.00                   | 0.44                          | 0.00                    | 99.56                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 400.00                   | 0.43                          | 1.07                    | 98.49                              |
|       | L&T                   |          |                          |                               |                         |                                    |
| 28    | SINGOLI BHATWARI HPS  | 1        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 99.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | MPCL                  |          |                          |                               |                         |                                    |
| 29    | MALANA HPS            | 1        | 43.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 43.00                    | 4.04                          | 0.00                    | 95.96                              |
|       | TOTAL                 |          | 86.00                    | 2.02                          | 0.00                    | 97.98                              |
|       | NHPC                  |          |                          |                               |                         |                                    |
| 30    | BAIRA SIUL HPS        | 1        | 60.00                    | 7.84                          | 0.74                    | 91.42                              |
|       |                       | 2        | 60.00                    | 9.82                          | 0.68                    | 89.50                              |
|       |                       | 3        | 60.00                    | 41.96                         | 3.61                    | 54.43                              |
|       | TOTAL                 |          | 180.00                   | 19.87                         | 1.68                    | 78.45                              |
| 31    | CHAMERA-I HPS         | 1        | 180.00                   | 12.41                         | 0.34                    | 87.25                              |
|       |                       | 2        | 180.00                   | 12.28                         | 0.13                    | 87.59                              |
|       |                       | 3        | 180.00                   | 13.76                         | 0.03                    | 86.21                              |
|       | TOTAL                 |          | 540.00                   | 12.81                         | 0.17                    | 87.02                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 32    | CHAMERA-II HPS        | 1        | 100.00                   | 8.86                          | 0.06                    | 91.08                              |
|       |                       | 2        | 100.00                   | 4.04                          | 0.08                    | 95.88                              |
|       |                       | 3        | 100.00                   | 4.22                          | 0.10                    | 95.68                              |
|       | TOTAL                 |          | 300.00                   | 5.71                          | 0.08                    | 94.21                              |
| 33    | CHAMERA-III HPS       | 1        | 77.00                    | 0.00                          | 0.05                    | 99.95                              |
|       |                       | 2        | 77.00                    | 8.19                          | 0.04                    | 91.77                              |
|       |                       | 3        | 77.00                    | 3.07                          | 0.02                    | 96.91                              |
|       | TOTAL                 |          | 231.00                   | 3.75                          | 0.04                    | 96.21                              |
| 34    | CHUTAK HPS            | 1        | 11.00                    | 14.89                         | 0.00                    | 85.11                              |
|       |                       | 2        | 11.00                    | 10.47                         | 0.00                    | 89.53                              |
|       |                       | 3        | 11.00                    | 7.48                          | 0.00                    | 92.52                              |
|       |                       | 4        | 11.00                    | 6.52                          | 0.50                    | 92.98                              |
|       | TOTAL                 |          | 44.00                    | 9.84                          | 0.13                    | 90.04                              |
| 35    | DHAULI GANGA HPS      | 1        | 70.00                    | 0.01                          | 0.42                    | 99.57                              |
|       |                       | 2        | 70.00                    | 6.71                          | 0.30                    | 92.99                              |
|       |                       | 3        | 70.00                    | 0.25                          | 0.44                    | 99.32                              |
|       |                       | 4        | 70.00                    | 6.00                          | 0.37                    | 93.63                              |
|       | TOTAL                 |          | 280.00                   | 3.24                          | 0.38                    | 96.38                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 36    | DULHASTI HPS          | 1        | 130.00                   | 4.05                          | 0.04                    | 95.90                              |
|       |                       | 2        | 130.00                   | 1.96                          | 0.09                    | 97.95                              |
|       |                       | 3        | 130.00                   | 4.86                          | 0.35                    | 94.79                              |
|       | TOTAL                 |          | 390.00                   | 3.63                          | 0.16                    | 96.22                              |
| 37    | KISHANGANGA HPS       | 1        | 110.00                   | 21.01                         | 1.03                    | 77.96                              |
|       |                       | 2        | 110.00                   | 20.05                         | 1.66                    | 78.29                              |
|       |                       | 3        | 110.00                   | 4.28                          | 0.16                    | 95.56                              |
|       | TOTAL                 |          | 330.00                   | 15.11                         | 0.95                    | 83.94                              |
| 38    | NIMMO BAZGO HPS       | 1        | 15.00                    | 6.18                          | 0.06                    | 93.76                              |
|       |                       | 2        | 15.00                    | 6.55                          | 0.02                    | 93.43                              |
|       |                       | 3        | 15.00                    | 4.36                          | 0.04                    | 95.59                              |
|       | TOTAL                 |          | 45.00                    | 5.70                          | 0.04                    | 94.26                              |
| 39    | PARBATI-III HPS       | 1        | 130.00                   | 9.94                          | 0.06                    | 89.99                              |
|       |                       | 2        | 130.00                   | 5.31                          | 0.06                    | 94.63                              |
|       |                       | 3        | 130.00                   | 12.67                         | 0.01                    | 87.32                              |
|       |                       | 4        | 130.00                   | 12.34                         | 0.02                    | 87.63                              |
|       | TOTAL                 |          | 520.00                   | 10.07                         | 0.04                    | 89.89                              |
| 40    | SALAL HPS             | 1        | 115.00                   | 3.60                          | 0.00                    | 96.40                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 2        | 115.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 115.00                   | 14.34                         | 0.01                    | 85.66                              |
|       |                       | 4        | 115.00                   | 0.00                          | 0.13                    | 99.87                              |
|       |                       | 5        | 115.00                   | 3.90                          | 0.00                    | 96.10                              |
|       |                       | 6        | 115.00                   | 4.74                          | 0.00                    | 95.26                              |
|       | TOTAL                 |          | 690.00                   | 4.43                          | 0.02                    | 95.55                              |
| 41    | SEWA-II HPS           | 1        | 40.00                    | 97.16                         | 0.00                    | 2.84                               |
|       |                       | 2        | 40.00                    | 90.99                         | 0.53                    | 8.47                               |
|       |                       | 3        | 40.00                    | 91.63                         | 0.04                    | 8.34                               |
|       | TOTAL                 |          | 120.00                   | 93.26                         | 0.19                    | 6.55                               |
| 42    | TANAKPUR HPS          | 1        | 31.40                    | 13.98                         | 0.45                    | 85.56                              |
|       |                       | 2        | 31.40                    | 11.18                         | 0.89                    | 87.93                              |
|       |                       | 3        | 31.40                    | 7.81                          | 0.14                    | 92.05                              |
|       | TOTAL                 |          | 94.20                    | 10.99                         | 0.50                    | 88.51                              |
| 43    | URI-I HPS             | 1        | 120.00                   | 3.42                          | 0.00                    | 96.57                              |
|       |                       | 2        | 120.00                   | 4.81                          | 0.01                    | 95.18                              |
|       |                       | 3        | 120.00                   | 4.49                          | 0.01                    | 95.50                              |
|       |                       | 4        | 120.00                   | 4.68                          | 0.04                    | 95.28                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 480.00                   | 4.35                          | 0.02                    | 95.63                              |
| 44    | URI-II HPS            | 1        | 60.00                    | 5.06                          | 0.02                    | 94.92                              |
|       |                       | 2        | 60.00                    | 3.35                          | 0.13                    | 96.52                              |
|       |                       | 3        | 60.00                    | 4.27                          | 0.02                    | 95.71                              |
|       |                       | 4        | 60.00                    | 2.88                          | 0.11                    | 97.01                              |
|       | TOTAL                 |          | 240.00                   | 3.89                          | 0.07                    | 96.04                              |
|       | NTPC Ltd.             |          |                          |                               |                         |                                    |
| 45    | KOLDAM                | 1        | 200.00                   | 1.06                          | 0.00                    | 98.94                              |
|       |                       | 2        | 200.00                   | 1.06                          | 0.00                    | 98.94                              |
|       |                       | 3        | 200.00                   | 1.63                          | 0.00                    | 98.37                              |
|       |                       | 4        | 200.00                   | 1.46                          | 0.65                    | 97.89                              |
|       | TOTAL                 |          | 800.00                   | 1.30                          | 0.16                    | 98.53                              |
|       | PSPCL                 |          |                          |                               |                         |                                    |
| 46    | ANANDPUR SAHIB-I HPS  | 1        | 33.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 33.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 67.00                    | 0.00                          | 0.00                    | 100.00                             |
| 47    | ANANDPUR SAHIB-II HPS | 3        | 33.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 33.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 67.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 48    | MUKERIAN-I HPS        | 1        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 45.00                    | 0.00                          | 0.00                    | 100.00                             |
| 49    | MUKERIAN-II HPS       | 4        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 45.00                    | 0.00                          | 0.00                    | 100.00                             |
| 50    | MUKERIAN-III HPS      | 7        | 19.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 8        | 19.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 9        | 19.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 58.50                    | 0.00                          | 0.00                    | 100.00                             |
| 51    | MUKERIAN-IV HPS       | 10       | 19.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 11       | 19.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 12       | 19.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 58.50                    | 0.00                          | 0.00                    | 100.00                             |
| 52    | RANJIT SAGAR HPS      | 1        | 150.00                   | 21.66                         | 0.00                    | 78.34                              |
|       |                       | 2        | 150.00                   | 7.78                          | 0.00                    | 92.22                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 150.00                   | 1.05                          | 0.00                    | 98.95                              |
|       | TOTAL                 |          | 600.00                   | 7.62                          | 0.00                    | 92.38                              |
| 53    | SHANAN HPS            | 1        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 110.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | RRVUNL                |          |                          |                               |                         |                                    |
| 54    | JAWAHAR SAGAR HPS     | 1        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 99.00                    | 0.00                          | 0.00                    | 100.00                             |
| 55    | MAHI BAJAJ-I HPS      | 1        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
| 56    | MAHI BAJAJ-II HPS     | 3        | 45.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 45.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 90.00                    | 0.00                          | 0.00                    | 100.00                             |
| 57    | R P SAGAR HPS         | 1        | 43.00                    | 0.00                          | 74.71                   | 25.29                              |
|       |                       | 2        | 43.00                    | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 3        | 43.00                    | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 4        | 43.00                    | 0.00                          | 100.00                  | 0.00                               |
|       | TOTAL                 |          | 172.00                   | 0.00                          | 93.68                   | 6.32                               |
|       | SJVNL                 |          |                          |                               |                         |                                    |
| 58    | NATHPA JHAKRI HPS     | 1        | 250.00                   | 1.99                          | 0.01                    | 98.00                              |
|       |                       | 2        | 250.00                   | 2.43                          | 0.04                    | 97.53                              |
|       |                       | 3        | 250.00                   | 3.82                          | 0.71                    | 95.47                              |
|       |                       | 4        | 250.00                   | 3.38                          | 0.49                    | 96.13                              |
|       |                       | 5        | 250.00                   | 2.78                          | 0.00                    | 97.22                              |
|       |                       | 6        | 250.00                   | 2.10                          | 0.00                    | 97.90                              |
|       | TOTAL                 |          | 1500.00                  | 2.75                          | 0.21                    | 97.04                              |
| 59    | RAMPUR HPS            | 1        | 68.67                    | 3.63                          | 0.02                    | 96.35                              |
|       |                       | 2        | 68.67                    | 2.24                          | 0.01                    | 97.75                              |
|       |                       | 3        | 68.67                    | 2.13                          | 0.86                    | 97.00                              |
|       |                       | 4        | 68.67                    | 2.51                          | 0.03                    | 97.46                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 5        | 68.67                    | 1.98                          | 0.06                    | 97.96                              |
|       |                       | 6        | 68.67                    | 2.26                          | 0.00                    | 97.74                              |
|       | TOTAL                 |          | 412.02                   | 2.46                          | 0.16                    | 97.38                              |
|       | THDC                  |          |                          |                               |                         |                                    |
| 60    | KOTESHWAR HPS         | 1        | 100.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 100.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 100.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 100.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 400.00                   | 0.00                          | 0.00                    | 100.00                             |
| 61    | TEHRI ST-1 HPS        | 1        | 250.00                   | 3.29                          | 0.00                    | 96.71                              |
|       |                       | 2        | 250.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 250.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 250.00                   | 5.87                          | 0.00                    | 94.13                              |
|       | TOTAL                 |          | 1000.00                  | 2.29                          | 0.00                    | 97.71                              |
|       | UJVNL                 |          |                          |                               |                         |                                    |
| 62    | CHIBRO (YAMUNA) HPS   | 1        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 240.00                   | 0.00                          | 0.00                    | 100.00                             |
| 63    | CHILLA HPS            | 1        | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 144.00                   | 0.00                          | 0.00                    | 100.00                             |
| 64    | DHAKRANI HPS          | 1        | 11.25                    | 21.65                         | 0.00                    | 78.35                              |
|       |                       | 2        | 11.25                    | 0.00                          | 13.94                   | 86.06                              |
|       |                       | 3        | 11.25                    | 7.56                          | 0.00                    | 92.44                              |
|       | TOTAL                 |          | 33.75                    | 9.74                          | 4.65                    | 85.61                              |
| 65    | DHALIPUR HPS          | 1        | 17.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 17.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 17.00                    | 5.07                          | 0.00                    | 94.93                              |
|       | TOTAL                 |          | 51.00                    | 1.69                          | 0.00                    | 98.31                              |
| 66    | KHATIMA HPS           | 1        | 13.80                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 13.80                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 13.80                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 41.40                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 67    | KHODRI HPS            | 1        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 120.00                   | 0.00                          | 0.00                    | 100.00                             |
| 68    | KULHAL HPS            | 1        | 10.00                    | 1.64                          | 0.00                    | 98.36                              |
|       |                       | 2        | 10.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 10.00                    | 6.03                          | 0.00                    | 93.97                              |
|       | TOTAL                 |          | 30.00                    | 2.56                          | 0.00                    | 97.44                              |
| 69    | MANERI BHALI-I HPS    | 1        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 90.00                    | 0.00                          | 0.00                    | 100.00                             |
| 70    | MANERI BHALI-II HPS   | 1        | 76.00                    | 8.49                          | 0.16                    | 91.34                              |
|       |                       | 2        | 76.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 76.00                    | 10.27                         | 0.00                    | 89.73                              |
|       |                       | 4        | 76.00                    | 15.22                         | 0.61                    | 84.17                              |
|       | TOTAL                 |          | 304.00                   | 8.50                          | 0.19                    | 91.31                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 71    | RAMGANGA HPS          | 1        | 66.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 66.00                    | 32.06                         | 13.29                   | 54.65                              |
|       |                       | 3        | 66.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 198.00                   | 10.69                         | 4.43                    | 84.88                              |
|       | UPJVNL                |          |                          |                               |                         |                                    |
| 72    | KHARA HPS             | 1        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 72.00                    | 0.00                          | 0.00                    | 100.00                             |
| 73    | MATATILA HPS          | 1        | 10.20                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 10.20                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 10.20                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 30.60                    | 0.00                          | 0.00                    | 100.00                             |
| 74    | OBRA HPS              | 1        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 33.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 99.00                    | 0.00                          | 0.00                    | 100.00                             |
| 75    | RIHAND HPS            | 1        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION  | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|------------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                        | 3        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 4        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 5        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 6        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                  |          | 300.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | Western                |          |                          |                               |                         |                                    |
|       | CSPGCL                 |          |                          |                               |                         |                                    |
| 76    | HASDEOBANGO HPS        | 1        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 2        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 3        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                  |          | 120.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | DLHP                   |          |                          |                               |                         |                                    |
| 77    | BHANDARDHARA HPS ST-II | 2        | 34.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                  |          | 34.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | GSECL                  |          |                          |                               |                         |                                    |
| 78    | KADANA HPS             | 1        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 2        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 3        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                        | 4        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 240.00                   | 0.00                          | 0.00                    | 100.00                             |
| 79    | UKAI HPS              | 1        | 75.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 75.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 75.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 75.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 300.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | MAHAGENCO             |          |                          |                               |                         |                                    |
| 80    | BHIRA TAIL RACE HPS   | 1        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
| 81    | GHATGHAR PSS HPS      | 1        | 125.00                   | 0.00                          | 27.58                   | 72.42                              |
|       |                       | 2        | 125.00                   | 0.00                          | 25.96                   | 74.04                              |
|       | TOTAL                 |          | 250.00                   | 0.00                          | 26.77                   | 73.23                              |
| 82    | KOYNA DPH HPS         | 1        | 18.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 18.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
| 83    | KOYNA-I&II HPS        | 1        | 70.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 70.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 70.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 4        | 70.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 80.00                    | 1.29                          | 0.00                    | 98.71                              |
|       |                       | 6        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 7        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 8        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 600.00                   | 0.16                          | 0.00                    | 99.84                              |
| 84    | KOYNA-III HPS         | 1        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 80.00                    | 0.00                          | 16.07                   | 83.93                              |
|       |                       | 4        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 320.00                   | 0.00                          | 4.02                    | 95.98                              |
| 85    | KOYNA-IV HPS          | 1        | 250.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 250.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 250.00                   | 0.00                          | 0.35                    | 99.65                              |
|       |                       | 4        | 250.00                   | 0.00                          | 0.10                    | 99.90                              |
|       | TOTAL                 |          | 1000.00                  | 0.00                          | 0.11                    | 99.89                              |
| 86    | TILLARI HPS           | 1        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 60.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 87    | VAITARNA HPS          | 1        | 60.00                    | 8.90                          | 6.94                    | 84.16                              |
|       | TOTAL                 |          | 60.00                    | 8.90                          | 6.94                    | 84.16                              |
|       | MPPGCL                |          |                          |                               |                         |                                    |
| 88    | BANSAGAR-II HPS       | 1        | 15.00                    | 1.24                          | 0.00                    | 98.76                              |
|       |                       | 2        | 15.00                    | 42.64                         | 0.00                    | 57.36                              |
|       | TOTAL                 |          | 30.00                    | 21.94                         | 0.00                    | 78.06                              |
| 89    | BANSAGAR-III HPS      | 1        | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
| 90    | BANSAGAR TONS-I HPS   | 1        | 105.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 105.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 105.00                   | 100.00                        | 0.00                    | 0.00                               |
|       | TOTAL                 |          | 315.00                   | 33.33                         | 0.00                    | 66.67                              |
| 91    | BARGI HPS             | 1        | 45.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 45.00                    | 0.04                          | 0.00                    | 99.96                              |
|       | TOTAL                 |          | 90.00                    | 0.02                          | 0.00                    | 99.98                              |
| 92    | GANDHI SAGAR HPS      | 1        | 23.00                    | 0.00                          | 1.64                    | 98.36                              |
|       |                       | 2        | 23.00                    | 0.00                          | 100.00                  | 0.00                               |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 23.00                    | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 4        | 23.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 23.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 115.00                   | 0.00                          | 40.33                   | 59.67                              |
| 93    | MADHIKHERA HPS        | 1        | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
| 94    | PENCH HPS             | 1        | 80.00                    | 0.00                          | 15.42                   | 84.58                              |
|       |                       | 2        | 80.00                    | 0.00                          | 0.03                    | 99.97                              |
|       | TOTAL                 |          | 160.00                   | 0.00                          | 7.73                    | 92.27                              |
| 95    | RAJGHAT HPS           | 1        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 15.00                    | 0.00                          | 0.23                    | 99.77                              |
|       |                       | 3        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 45.00                    | 0.00                          | 0.08                    | 99.92                              |
|       | NHDC                  |          |                          |                               |                         |                                    |
| 96    | INDIRA SAGAR HPS      | 1        | 125.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 125.00                   | 0.14                          | 0.00                    | 99.86                              |
|       |                       | 3        | 125.00                   | 4.18                          | 0.00                    | 95.82                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 4        | 125.00                   | 10.84                         | 0.00                    | 89.16                              |
|       |                       | 5        | 125.00                   | 6.52                          | 0.00                    | 93.48                              |
|       |                       | 6        | 125.00                   | 3.28                          | 0.00                    | 96.72                              |
|       |                       | 7        | 125.00                   | 6.12                          | 0.00                    | 93.88                              |
|       |                       | 8        | 125.00                   | 5.95                          | 0.00                    | 94.05                              |
|       | TOTAL                 |          | 1000.00                  | 4.63                          | 0.00                    | 95.37                              |
| 97    | OMKARESHWAR HPS       | 1        | 65.00                    | 3.85                          | 0.00                    | 96.15                              |
|       |                       | 2        | 65.00                    | 3.75                          | 0.00                    | 96.25                              |
|       |                       | 3        | 65.00                    | 3.66                          | 0.00                    | 96.34                              |
|       |                       | 4        | 65.00                    | 3.57                          | 0.00                    | 96.43                              |
|       |                       | 5        | 65.00                    | 3.75                          | 0.00                    | 96.25                              |
|       |                       | 6        | 65.00                    | 3.76                          | 0.00                    | 96.24                              |
|       |                       | 7        | 65.00                    | 3.12                          | 0.00                    | 96.88                              |
|       |                       | 8        | 65.00                    | 3.32                          | 0.00                    | 96.68                              |
|       | TOTAL                 |          | 520.00                   | 3.60                          | 0.00                    | 96.40                              |
|       | SSNNL                 |          |                          |                               |                         |                                    |
| 98    | S SAROVAR CHPH HPS    | 1        | 50.00                    | 37.74                         | 0.00                    | 62.26                              |
|       |                       | 2        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 250.00                   | 7.55                          | 0.00                    | 92.45                              |
| 99    | S SAROVAR RBPH HPS    | 1        | 200.00                   | 0.11                          | 0.05                    | 99.84                              |
|       |                       | 2        | 200.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 200.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 200.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 200.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 200.00                   | 4.18                          | 0.00                    | 95.82                              |
|       | TOTAL                 |          | 1200.00                  | 0.72                          | 0.01                    | 99.28                              |
|       | TATA MAH.             |          |                          |                               |                         |                                    |
| 100   | BHIRA HPS             | 1        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
| 101   | BHIRA PSS HPS         | 1        | 150.00                   | 0.07                          | 2.61                    | 97.32                              |
|       | TOTAL                 |          | 150.00                   | 0.07                          | 2.61                    | 97.32                              |
| 102   | BHIVPURI HPS          | 1        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 24.00                    | 0.00                          | 0.02                    | 99.98                              |
|       |                       | 3        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 1.50                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 1.50                     | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 75.00                    | 0.00                          | 0.00                    | 100.00                             |
| 103   | KHOPOLI HPS           | 1        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 24.00                    | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 3        | 24.00                    | 0.00                          | 0.01                    | 99.99                              |
|       | TOTAL                 |          | 72.00                    | 0.00                          | 33.34                   | 66.66                              |
|       | Southern              |          |                          |                               |                         |                                    |
|       | APGENCO               |          |                          |                               |                         |                                    |
| 104   | HAMPI HPS             | 1        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 9.00                     | 0.00                          | 0.14                    | 99.86                              |
|       |                       | 4        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 36.00                    | 0.00                          | 0.03                    | 99.97                              |
| 105   | LOWER SILERU HPS      | 1        | 115.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 115.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 115.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 115.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 460.00                   | 0.00                          | 0.00                    | 100.00                             |
| 106   | NAGARJUN SGR RBC HPS  | 1        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 90.00                    | 0.00                          | 0.00                    | 100.00                             |
| 107   | NAGARJUN SGR TPD      | 1        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
| 108   | SRISAILAM HPS         | 1        | 110.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 110.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 110.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 110.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 110.00                   | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 6        | 110.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 7        | 110.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 770.00                   | 0.00                          | 0.00                    | 100.00                             |
| 109   | T B DAM HPS           | 1        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
| 110   | UPPER SILERU HPS      | 1        | 60.00                    | 0.00                          | 0.14                    | 99.86                              |
|       |                       | 2        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 240.00                   | 0.00                          | 0.03                    | 99.97                              |
|       | KPCL                  |          |                          |                               |                         |                                    |
| 111   | ALMATTI DPH HPS       | 1        | 15.00                    | 0.75                          | 0.09                    | 99.16                              |
|       |                       | 2        | 55.00                    | 27.01                         | 0.05                    | 72.94                              |
|       |                       | 3        | 55.00                    | 25.20                         | 0.06                    | 74.74                              |
|       |                       | 4        | 55.00                    | 22.83                         | 0.00                    | 77.17                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 5        | 55.00                    | 5.90                          | 0.00                    | 94.10                              |
|       |                       | 6        | 55.00                    | 17.54                         | 0.00                    | 82.46                              |
|       | TOTAL                 |          | 290.00                   | 16.54                         | 0.03                    | 83.43                              |
| 112   | BHADRA HPS            | 1        | 2.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 26.00                    | 0.00                          | 0.00                    | 100.00                             |
| 113   | GERUSUPPA HPS         | 1        | 60.00                    | 4.24                          | 0.00                    | 95.76                              |
|       |                       | 2        | 60.00                    | 1.98                          | 0.13                    | 97.89                              |
|       |                       | 3        | 60.00                    | 1.95                          | 11.39                   | 86.66                              |
|       |                       | 4        | 60.00                    | 3.96                          | 0.31                    | 95.72                              |
|       | TOTAL                 |          | 240.00                   | 3.03                          | 2.96                    | 94.01                              |
| 114   | GHAT PRABHA HPS       | 1        | 16.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 16.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 32.00                    | 0.00                          | 0.00                    | 100.00                             |
| 115   | JOG HPS               | 1        | 13.20                    | 3.76                          | 0.00                    | 96.24                              |
|       |                       | 2        | 13.20                    | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 3        | 13.20                    | 4.03                          | 0.70                    | 95.27                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 4        | 13.20                    | 4.10                          | 0.83                    | 95.07                              |
|       |                       | 5        | 21.60                    | 29.25                         | 0.00                    | 70.75                              |
|       |                       | 6        | 21.60                    | 0.02                          | 0.32                    | 99.66                              |
|       |                       | 7        | 21.60                    | 5.32                          | 0.24                    | 94.44                              |
|       |                       | 8        | 21.60                    | 1.00                          | 3.57                    | 95.44                              |
|       | TOTAL                 |          | 139.20                   | 5.93                          | 13.21                   | 80.86                              |
| 116   | KADRA HPS             | 1        | 50.00                    | 0.00                          | 0.94                    | 99.06                              |
|       |                       | 2        | 50.00                    | 3.16                          | 0.00                    | 96.84                              |
|       |                       | 3        | 50.00                    | 0.00                          | 0.93                    | 99.07                              |
|       | TOTAL                 |          | 150.00                   | 1.05                          | 0.62                    | 98.32                              |
| 117   | KALINADI HPS          | 1        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 900.00                   | 0.00                          | 0.00                    | 100.00                             |
| 118   | KALINADI SUPA HPS     | 1        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 2        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 100.00                   | 0.00                          | 0.00                    | 100.00                             |
| 119   | KODASALI HPS          | 1        | 40.00                    | 4.39                          | 0.00                    | 95.61                              |
|       |                       | 2        | 40.00                    | 1.45                          | 0.00                    | 98.55                              |
|       |                       | 3        | 40.00                    | 9.09                          | 0.00                    | 90.91                              |
|       | TOTAL                 |          | 120.00                   | 4.98                          | 0.00                    | 95.02                              |
| 120   | LIGANAMAKKI HPS       | 1        | 27.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 27.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 55.00                    | 0.00                          | 0.00                    | 100.00                             |
| 121   | MUNIRABAD HPS         | 1        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 10.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 28.00                    | 0.00                          | 0.00                    | 100.00                             |
| 122   | SHARAVATHI HPS        | 1        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 6        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 7        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 8        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 9        | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 10       | 103.50                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 1035.00                  | 0.00                          | 0.00                    | 100.00                             |
| 123   | SIVASAMUNDRUM HPS     | 1        | 3.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 3.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 3.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 3.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 3.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 3.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 7        | 6.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 8        | 6.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 9        | 6.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 10       | 6.00                     | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 42.00                    | 0.00                          | 0.00                    | 100.00                             |
| 124   | VARAHI HPS            | 1        | 115.00                   | 8.85                          | 0.07                    | 91.07                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 2        | 115.00                   | 0.09                          | 0.12                    | 99.79                              |
|       |                       | 3        | 115.00                   | 3.42                          | 0.00                    | 96.58                              |
|       |                       | 4        | 115.00                   | 0.02                          | 0.00                    | 99.98                              |
|       | TOTAL                 |          | 460.00                   | 3.10                          | 0.05                    | 96.85                              |
|       | KSEB                  |          |                          |                               |                         |                                    |
| 125   | IDAMALAYAR HPS        | 1        | 37.50                    | 9.47                          | 0.11                    | 90.42                              |
|       |                       | 2        | 37.50                    | 8.32                          | 0.01                    | 91.67                              |
|       | TOTAL                 |          | 75.00                    | 8.89                          | 0.06                    | 91.05                              |
| 126   | IDUKKI HPS            | 1        | 130.00                   | 12.10                         | 0.04                    | 87.86                              |
|       |                       | 2        | 130.00                   | 7.43                          | 0.11                    | 92.46                              |
|       |                       | 3        | 130.00                   | 16.08                         | 0.08                    | 83.84                              |
|       |                       | 4        | 130.00                   | 6.41                          | 0.40                    | 93.20                              |
|       |                       | 5        | 130.00                   | 5.55                          | 0.66                    | 93.79                              |
|       |                       | 6        | 130.00                   | 15.85                         | 1.63                    | 82.52                              |
|       | TOTAL                 |          | 780.00                   | 10.57                         | 0.49                    | 88.94                              |
| 127   | KAKKAD HPS            | 1        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 25.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
| 128   | KUTTIYADI ADDL EXTN   | 1        | 50.00                    | 10.65                         | 0.79                    | 88.56                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 2        | 50.00                    | 9.61                          | 0.05                    | 90.34                              |
|       | TOTAL                 |          | 100.00                   | 10.13                         | 0.42                    | 89.45                              |
| 129   | KUTTIYADI EXTN HPS    | 4        | 50.00                    | 26.06                         | 0.53                    | 73.40                              |
|       | TOTAL                 |          | 50.00                    | 26.06                         | 0.53                    | 73.40                              |
| 130   | KUTTIYADI HPS         | 1        | 25.00                    | 10.62                         | 0.00                    | 89.38                              |
|       |                       | 2        | 25.00                    | 9.54                          | 0.44                    | 90.02                              |
|       |                       | 3        | 25.00                    | 4.32                          | 0.32                    | 95.36                              |
|       | TOTAL                 |          | 75.00                    | 8.16                          | 0.25                    | 91.58                              |
| 131   | LOWER PERIYAR HPS     | 1        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 180.00                   | 0.00                          | 0.00                    | 100.00                             |
| 132   | NARIAMANGLAM HPS      | 1        | 15.00                    | 100.00                        | 0.00                    | 0.00                               |
|       |                       | 2        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 45.00                    | 33.33                         | 0.00                    | 66.67                              |
| 133   | PALLIVASAL HPS        | 1        | 5.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 5.00                     | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 5.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 7.50                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 7.50                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 7.50                     | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 37.50                    | 0.00                          | 0.00                    | 100.00                             |
| 134   | PANNIAR HPS           | 1        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
| 135   | PORINGALKUTTU HPS     | 1        | 8.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 8.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 8.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 8.00                     | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 32.00                    | 0.00                          | 0.00                    | 100.00                             |
| 136   | SABARIGIRI HPS        | 1        | 50.00                    | 5.27                          | 0.17                    | 94.55                              |
|       |                       | 2        | 50.00                    | 16.99                         | 4.04                    | 78.97                              |
|       |                       | 3        | 50.00                    | 6.46                          | 0.52                    | 93.02                              |
|       |                       | 4        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 50.00                    | 7.21                          | 0.19                    | 92.60                              |

| S.No. | STATION / CORPORATION   | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-------------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                         | 6        | 50.00                    | 0.61                          | 0.81                    | 98.58                              |
|       | TOTAL                   |          | 300.00                   | 6.09                          | 0.96                    | 92.95                              |
| 137   | SENGULAM HPS            | 1        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 2        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 3        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 4        | 12.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 48.00                    | 0.00                          | 0.00                    | 100.00                             |
| 138   | SHOLAYAR HPS            | 1        | 18.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 2        | 18.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 3        | 18.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 54.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TANGEDCO                |          |                          |                               |                         |                                    |
| 139   | ALIYAR HPS              | 1        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
| 140   | BHAWANI BARRAGE-II HPS  | 1        | 15.00                    | 12.78                         | 0.19                    | 87.03                              |
|       |                         | 2        | 15.00                    | 9.33                          | 1.37                    | 89.29                              |
|       | TOTAL                   |          | 30.00                    | 11.05                         | 0.78                    | 88.16                              |
| 141   | BHAWANI BARRAGE-III HPS | 1        | 15.00                    | 1.11                          | 0.00                    | 98.89                              |
|       |                         | 2        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 30.00                    | 0.55                          | 0.00                    | 99.45                              |
| 142   | BHAWANI KATTAL        | 1        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
| 143   | KADAMPARI HPS         | 1        | 100.00                   | 0.00                          | 83.11                   | 16.89                              |
|       |                       | 2        | 100.00                   | 24.24                         | 7.41                    | 68.35                              |
|       |                       | 3        | 100.00                   | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 4        | 100.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 400.00                   | 6.06                          | 47.63                   | 46.31                              |
| 144   | KODAYAR-I HPS         | 1        | 60.00                    | 0.00                          | 11.91                   | 88.09                              |
|       | TOTAL                 |          | 60.00                    | 0.00                          | 11.91                   | 88.09                              |
| 145   | KODAYAR-II HPS        | 2        | 40.00                    | 0.00                          | 56.10                   | 43.90                              |
|       | TOTAL                 |          | 40.00                    | 0.00                          | 56.10                   | 43.90                              |
| 146   | KUNDAH-I HPS          | 1        | 20.00                    | 9.36                          | 0.41                    | 90.23                              |
|       |                       | 2        | 20.00                    | 5.86                          | 0.00                    | 94.14                              |
|       |                       | 3        | 20.00                    | 0.00                          | 0.51                    | 99.49                              |
|       | TOTAL                 |          | 60.00                    | 5.08                          | 0.31                    | 94.62                              |
| 147   | KUNDAH-II HPS         | 4        | 35.00                    | 0.64                          | 0.00                    | 99.36                              |
|       |                       | 5        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 6        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 7        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 8        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 175.00                   | 0.13                          | 0.00                    | 99.87                              |
| 148   | KUNDAH-III HPS        | 9        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 10       | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 11       | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 180.00                   | 0.00                          | 0.00                    | 100.00                             |
| 149   | KUNDAH-IV HPS         | 12       | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 13       | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 100.00                   | 0.00                          | 0.00                    | 100.00                             |
| 150   | KUNDAH-V HPS          | 14       | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 15       | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
| 151   | LOWER METTUR-I HPS    | 1        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
| 152   | LOWER METTUR-II HPS   | 3        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 4        | 15.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
| 153   | LOWER METTUR-III HPS  | 5        | 15.00                    | 10.52                         | 0.00                    | 89.48                              |
|       |                       | 6        | 15.00                    | 5.17                          | 0.00                    | 94.83                              |
|       | TOTAL                 |          | 30.00                    | 7.85                          | 0.00                    | 92.15                              |
| 154   | LOWER METTUR-IV HPS   | 7        | 15.00                    | 9.35                          | 0.00                    | 90.65                              |
|       |                       | 8        | 15.00                    | 5.26                          | 0.00                    | 94.74                              |
|       | TOTAL                 |          | 30.00                    | 7.31                          | 0.00                    | 92.69                              |
| 155   | METTUR DAM HPS        | 1        | 12.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 12.50                    | 8.58                          | 0.00                    | 91.42                              |
|       |                       | 3        | 12.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 12.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 50.00                    | 2.14                          | 0.00                    | 97.86                              |
| 156   | METTUR TUNNEL HPS     | 1        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 50.00                    | 0.00                          | 5.79                    | 94.21                              |
|       | TOTAL                 |          | 200.00                   | 0.00                          | 1.45                    | 98.55                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 157   | MOYAR HPS             | 1        | 12.00                    | 1.10                          | 4.75                    | 94.15                              |
|       |                       | 2        | 12.00                    | 1.10                          | 0.75                    | 98.15                              |
|       |                       | 3        | 12.00                    | 8.67                          | 20.00                   | 71.33                              |
|       | TOTAL                 |          | 36.00                    | 3.63                          | 8.50                    | 87.88                              |
| 158   | PAPANASAM HPS         | 1        | 8.00                     | 0.04                          | 0.00                    | 99.96                              |
|       |                       | 2        | 8.00                     | 0.04                          | 0.00                    | 99.96                              |
|       |                       | 3        | 8.00                     | 7.76                          | 0.00                    | 92.24                              |
|       |                       | 4        | 8.00                     | 9.61                          | 0.00                    | 90.39                              |
|       | TOTAL                 |          | 32.00                    | 4.36                          | 0.00                    | 95.64                              |
| 159   | PARSON`S VALLEY HPS   | 1        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
| 160   | PERIYAR HPS           | 1        | 42.00                    | 0.50                          | 0.00                    | 99.50                              |
|       |                       | 2        | 42.00                    | 3.49                          | 0.00                    | 96.51                              |
|       |                       | 3        | 42.00                    | 5.83                          | 0.00                    | 94.17                              |
|       |                       | 4        | 35.00                    | 11.60                         | 0.00                    | 88.40                              |
|       | TOTAL                 |          | 161.00                   | 5.35                          | 0.00                    | 94.65                              |
| 161   | PYKARA HPS            | 1        | 7.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 7.00                     | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 7.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 13.60                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 13.60                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 11.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 59.20                    | 0.00                          | 0.00                    | 100.00                             |
| 162   | PYKARA ULTMATE HPS    | 1        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 50.00                    | 100.00                        | 0.00                    | 0.00                               |
|       |                       | 3        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 150.00                   | 33.33                         | 0.00                    | 66.67                              |
| 163   | SARKARPATHY HPS       | 1        | 30.00                    | 10.28                         | 0.00                    | 89.72                              |
|       | TOTAL                 |          | 30.00                    | 10.28                         | 0.00                    | 89.72                              |
| 164   | SHOLAYAR HPS (TN)     | 1        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 35.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 70.00                    | 0.00                          | 0.00                    | 100.00                             |
| 165   | SURULIYAR HPS         | 1        | 35.00                    | 8.22                          | 57.05                   | 34.73                              |
|       | TOTAL                 |          | 35.00                    | 8.22                          | 57.05                   | 34.73                              |
|       | TSGENCO               |          |                          |                               |                         |                                    |
| 166   | LOWER JURALA HPS      | 1        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 40.00                    | 0.00                          | 0.17                    | 99.83                              |
|       | TOTAL                 |          | 240.00                   | 0.00                          | 0.03                    | 99.97                              |
| 167   | NAGARJUN SGR HPS      | 1        | 110.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 100.80                   | 0.00                          | 0.79                    | 99.21                              |
|       |                       | 3        | 100.80                   | 0.00                          | 2.40                    | 97.60                              |
|       |                       | 4        | 100.80                   | 0.00                          | 5.61                    | 94.39                              |
|       |                       | 5        | 100.80                   | 0.00                          | 0.08                    | 99.92                              |
|       |                       | 6        | 100.80                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 7        | 100.80                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 8        | 100.80                   | 0.00                          | 2.31                    | 97.69                              |
|       | TOTAL                 |          | 815.60                   | 0.00                          | 1.40                    | 98.60                              |
| 168   | NAGARJUN SGR LBC HPS  | 1        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
| 169   | POCHAMPAD HPS         | 1        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION   | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-------------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                         | 2        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 3        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 4        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
| 170   | PRIYADARSHNI JURALA HPS | 1        | 39.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 2        | 39.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 3        | 39.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 4        | 39.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 5        | 39.00                    | 0.00                          | 50.01                   | 49.99                              |
|       |                         | 6        | 39.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 234.00                   | 0.00                          | 8.34                    | 91.66                              |
| 171   | PULICHINTALA HPS        | 1        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 2        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 3        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 4        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 120.00                   | 0.00                          | 0.00                    | 100.00                             |
| 172   | SRISAILAM LB HPS        | 1        | 150.00                   | 0.00                          | 0.10                    | 99.90                              |
|       |                         | 2        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 3        | 150.00                   | 0.00                          | 12.83                   | 87.17                              |
|       |                       | 4        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 150.00                   | 0.00                          | 14.81                   | 85.19                              |
|       | TOTAL                 |          | 900.00                   | 0.00                          | 4.62                    | 95.38                              |
|       | Eastern               |          |                          |                               |                         |                                    |
|       | APGENCO               |          |                          |                               |                         |                                    |
| 173   | MACHKUND HPS          | 1        | 17.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 17.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 17.00                    | 0.00                          | 0.14                    | 99.86                              |
|       |                       | 4        | 21.25                    | 0.00                          | 0.14                    | 99.86                              |
|       |                       | 5        | 21.25                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 21.25                    | 0.00                          | 0.14                    | 99.86                              |
|       | TOTAL                 |          | 114.75                   | 0.00                          | 0.07                    | 99.93                              |
|       | DEPL                  |          |                          |                               |                         |                                    |
| 174   | JORETHANG LOOP        | 1        | 48.00                    | 13.87                         | 0.08                    | 86.05                              |
|       |                       | 2        | 48.00                    | 0.00                          | 0.09                    | 99.91                              |
|       | TOTAL                 |          | 96.00                    | 6.94                          | 0.09                    | 92.98                              |
|       | DVC                   |          |                          |                               |                         |                                    |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 175   | MAITHON HPS           | 1        | 20.00                    | 0.00                          | 0.67                    | 99.33                              |
|       |                       | 2        | 23.20                    | 0.00                          | 3.78                    | 96.22                              |
|       |                       | 3        | 20.00                    | 8.92                          | 2.03                    | 89.05                              |
|       | TOTAL                 |          | 63.20                    | 2.97                          | 2.16                    | 94.87                              |
| 176   | PANCHET HPS           | 1        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | GIPL                  |          |                          |                               |                         |                                    |
| 177   | CHUZACHEN HPS         | 1        | 55.00                    | 3.06                          | 0.03                    | 96.91                              |
|       |                       | 2        | 55.00                    | 2.14                          | 0.05                    | 97.80                              |
|       | TOTAL                 |          | 110.00                   | 2.60                          | 0.04                    | 97.36                              |
|       | JUUNL                 |          |                          |                               |                         |                                    |
| 178   | SUBERNREKHA-I HPS     | 1        | 65.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 65.00                    | 0.00                          | 0.00                    | 100.00                             |
| 179   | SUBERNREKHA-II HPS    | 2        | 65.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 65.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | MBPC                  |          |                          |                               |                         |                                    |
| 180   | RONGNICHU HPS         | 1        | 56.50                    | 0.36                          | 0.70                    | 98.94                              |
|       |                       | 2        | 56.50                    | 1.56                          | 0.02                    | 98.42                              |
|       | TOTAL                 |          | 113.00                   | 0.95                          | 0.37                    | 98.68                              |

| S.No. | STATION / CORPORATION  | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|------------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | NHPC                   |          |                          |                               |                         |                                    |
| 181   | RANGIT HPS             | 1        | 20.00                    | 6.39                          | 2.26                    | 91.35                              |
|       |                        | 2        | 20.00                    | 7.26                          | 2.36                    | 90.38                              |
|       |                        | 3        | 20.00                    | 7.62                          | 1.32                    | 91.06                              |
|       | TOTAL                  |          | 60.00                    | 7.09                          | 1.98                    | 90.93                              |
| 182   | TEESTA LOW DAM-III HPS | 1        | 33.00                    | 4.64                          | 0.11                    | 95.25                              |
|       |                        | 2        | 33.00                    | 4.38                          | 0.42                    | 95.20                              |
|       |                        | 3        | 33.00                    | 4.65                          | 0.01                    | 95.35                              |
|       |                        | 4        | 33.00                    | 4.41                          | 0.21                    | 95.39                              |
|       | TOTAL                  |          | 132.00                   | 4.52                          | 0.19                    | 95.29                              |
| 183   | TEESTA LOW DAM-IV HPS  | 1        | 40.00                    | 2.93                          | 0.50                    | 96.57                              |
|       |                        | 2        | 40.00                    | 4.77                          | 0.15                    | 95.09                              |
|       |                        | 3        | 40.00                    | 5.14                          | 0.11                    | 94.75                              |
|       |                        | 4        | 40.00                    | 5.13                          | 0.14                    | 94.73                              |
|       | TOTAL                  |          | 160.00                   | 4.49                          | 0.22                    | 95.28                              |
| 184   | TEESTA V HPS           | 1        | 170.00                   | 3.25                          | 0.02                    | 96.73                              |
|       |                        | 2        | 170.00                   | 4.59                          | 0.01                    | 95.40                              |
|       |                        | 3        | 170.00                   | 2.72                          | 0.65                    | 96.63                              |
|       | TOTAL                  |          | 510.00                   | 3.52                          | 0.23                    | 96.25                              |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | OHPC                  |          |                          |                               |                         |                                    |
| 185   | BALIMELA HPS          | 1        | 60.00                    | 100.00                        | 0.00                    | 0.00                               |
|       |                       | 2        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 6        | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 7        | 75.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 8        | 75.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 510.00                   | 12.50                         | 0.00                    | 87.50                              |
| 186   | CH IPLIMA HPS         | 1        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 24.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 72.00                    | 0.00                          | 0.00                    | 100.00                             |
| 187   | HIRAKUD HPS           | 1        | 49.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 49.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 32.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 32.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 5        | 43.65                    | 77.55                         | 0.00                    | 22.45                              |
|       |                       | 6        | 43.65                    | 59.11                         | 0.00                    | 40.89                              |
|       |                       | 7        | 37.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 287.80                   | 19.52                         | 0.00                    | 80.48                              |
| 188   | RENGALI HPS           | 1        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 5        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 250.00                   | 0.00                          | 0.00                    | 100.00                             |
| 189   | UPPER INDRAVATI HPS   | 1        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 150.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 600.00                   | 0.00                          | 0.00                    | 100.00                             |
| 190   | UPPER KOLAB HPS       | 1        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       |                       | 4        | 80.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 320.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | SEPL                  |          |                          |                               |                         |                                    |
| 191   | TASHIDING HPS         | 1        | 48.50                    | 1.27                          | 1.50                    | 97.23                              |
|       |                       | 2        | 48.50                    | 1.27                          | 1.51                    | 97.22                              |
|       | TOTAL                 |          | 97.00                    | 1.27                          | 1.50                    | 97.23                              |
|       | SKPPPL                |          |                          |                               |                         |                                    |
| 192   | DIKCHU HPS            | 1        | 48.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 48.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 96.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TUL                   |          |                          |                               |                         |                                    |
| 193   | TEESTA-III HPS        | 1        | 200.00                   | 2.58                          | 0.01                    | 97.41                              |
|       |                       | 2        | 200.00                   | 3.00                          | 0.00                    | 97.00                              |
|       |                       | 3        | 200.00                   | 2.98                          | 1.24                    | 95.79                              |
|       |                       | 4        | 200.00                   | 5.93                          | 7.37                    | 86.69                              |
|       |                       | 5        | 200.00                   | 4.83                          | 0.00                    | 95.17                              |
|       |                       | 6        | 200.00                   | 0.10                          | 6.89                    | 93.01                              |
|       | TOTAL                 |          | 1200.00                  | 3.24                          | 2.59                    | 94.18                              |
|       | WBSEDCL               |          |                          |                               |                         |                                    |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 194   | JALDHAKA HPS ST-I     | 1        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
| 195   | PURULIA PSS HPS       | 1        | 225.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 225.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 225.00                   | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 225.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 900.00                   | 0.00                          | 0.00                    | 100.00                             |
| 196   | RAMMAM HPS            | 1        | 12.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 12.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 3        | 12.50                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 4        | 12.50                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                 |          | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | North Eastern         |          |                          |                               |                         |                                    |
|       | APGCL                 |          |                          |                               |                         |                                    |
| 197   | KARBI LANGPI HPS      | 1        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                       | 2        | 50.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION   | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-------------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                   |          | 100.00                   | 0.00                          | 0.00                    | 100.00                             |
|       | MeECL                   |          |                          |                               |                         |                                    |
| 198   | KYRDEMKULAI HPS         | 1        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 2        | 30.00                    | 0.00                          | 100.00                  | 0.00                               |
|       | TOTAL                   |          | 60.00                    | 0.00                          | 50.00                   | 50.00                              |
| 199   | MYNTDU(LESHKA) St-1 HPS | 1        | 42.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 2        | 42.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 3        | 42.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 126.00                   | 0.00                          | 0.00                    | 100.00                             |
| 200   | NEW UMTRU HPS           | 1        | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 2        | 20.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 40.00                    | 0.00                          | 0.00                    | 100.00                             |
| 201   | UMIAM HPS ST-I          | 1        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 2        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 3        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 4        | 9.00                     | 0.00                          | 0.00                    | 100.00                             |
|       | TOTAL                   |          | 36.00                    | 0.00                          | 0.00                    | 100.00                             |
| 202   | UMIAM HPS ST-IV         | 7        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |
|       |                         | 8        | 30.00                    | 0.00                          | 0.00                    | 100.00                             |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
|       | TOTAL                 |          | 60.00                    | 0.00                          | 0.00                    | 100.00                             |
|       | NEEPCO.               |          |                          |                               |                         |                                    |
| 203   | DOYANG HPS            | 1        | 25.00                    | 7.88                          | 0.08                    | 92.04                              |
|       |                       | 2        | 25.00                    | 8.64                          | 0.42                    | 90.94                              |
|       |                       | 3        | 25.00                    | 8.07                          | 0.86                    | 91.07                              |
|       | TOTAL                 |          | 75.00                    | 8.20                          | 0.45                    | 91.35                              |
| 204   | KAMENG HPS            | 1        | 150.00                   | 0.73                          | 14.39                   | 84.88                              |
|       |                       | 2        | 150.00                   | 0.71                          | 14.66                   | 84.64                              |
|       |                       | 3        | 150.00                   | 0.72                          | 35.52                   | 63.75                              |
|       |                       | 4        | 150.00                   | 0.00                          | 45.58                   | 54.42                              |
|       | TOTAL                 |          | 600.00                   | 0.54                          | 27.54                   | 71.92                              |
| 205   | KHONDONG HPS          | 1        | 25.00                    | 0.00                          | 0.71                    | 99.29                              |
|       |                       | 2        | 25.00                    | 0.00                          | 1.48                    | 98.52                              |
|       | TOTAL                 |          | 50.00                    | 0.00                          | 1.09                    | 98.91                              |
| 206   | KOPILI HPS            | 1        | 50.00                    | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 2        | 50.00                    | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 3        | 50.00                    | 0.00                          | 100.00                  | 0.00                               |
|       |                       | 4        | 50.00                    | 0.00                          | 100.00                  | 0.00                               |
|       | TOTAL                 |          | 200.00                   | 0.00                          | 100.00                  | 0.00                               |

| S.No. | STATION / CORPORATION | UNIT No. | INSTALLED CAPAPCITY (MW) | PLANNED MAINTENANCE (P.M) (%) | FORCED OUTAGE (F.O) (%) | OPERATING AVAILABILITY (100-FO-PM) |
|-------|-----------------------|----------|--------------------------|-------------------------------|-------------------------|------------------------------------|
| 207   | PARE                  | 1        | 55.00                    | 4.38                          | 0.46                    | 95.15                              |
|       |                       | 2        | 55.00                    | 1.61                          | 0.04                    | 98.35                              |
|       | TOTAL                 |          | 110.00                   | 3.00                          | 0.25                    | 96.75                              |
| 208   | RANGANADI HPS         | 1        | 135.00                   | 2.53                          | 2.11                    | 95.36                              |
|       |                       | 2        | 135.00                   | 2.25                          | 0.00                    | 97.75                              |
|       |                       | 3        | 135.00                   | 0.00                          | 0.30                    | 99.70                              |
|       | TOTAL                 |          | 405.00                   | 1.59                          | 0.80                    | 97.60                              |
| 209   | TUIRIAL HPS           | 1        | 30.00                    | 3.84                          | 0.02                    | 96.15                              |
|       |                       | 2        | 30.00                    | 4.01                          | 0.08                    | 95.92                              |
|       | TOTAL                 |          | 60.00                    | 3.92                          | 0.05                    | 96.03                              |
|       | NHPC                  |          |                          |                               |                         |                                    |
| 210   | LOKTAK HPS            | 1        | 35.00                    | 2.95                          | 0.08                    | 96.97                              |
|       |                       | 2        | 35.00                    | 3.86                          | 0.05                    | 96.09                              |
|       |                       | 3        | 35.00                    | 3.16                          | 1.26                    | 95.59                              |
|       | TOTAL                 |          | 105.00                   | 3.32                          | 0.46                    | 96.21                              |

# CHAPTER-7

## MISCELLANEOUS OUTAGES OF HE UNITS

## CHAPTER-7

### MISCELLANEOUS OUTAGES OF HE UNITS

**7.1** Non-availability of hydel generating units due to reasons other than planned maintenance and forced outages of unit components, auxiliary and other equipments and civil structures has been defined as “Miscellaneous Non-Availability”. This may be due to shortage of water, high silt content in the river, electrical grid disturbance, low system demand, disaster/natural calamity, reserve shutdown, transmission constraints & power evacuation problems, high tailrace level, strikes, etc. constitutes the miscellaneous outages. The station-wise details of miscellaneous non-availability during 2021-22 is given at **Annex-7.1** and summarized below in **Table 7.1**.

**TABLE 7.1**

#### MISCELLANEOUS OUTAGES FOR PERIOD: 2021-22

| S. No. | Causes of Miscellaneous Outage                               | Duration of Outage (Hours) | % of Total Outage |
|--------|--------------------------------------------------------------|----------------------------|-------------------|
|        | <b>NOT ASSOCIATED WITH THE EQUIPMENT AND CIVIL STRUCTURE</b> |                            |                   |
| 1      | Water Constraint                                             | 471,810.30                 | 85.30             |
| 2      | Grid Constraint                                              | 27,968.11                  | 5.06              |
| 3      | Other Miscellaneous                                          | 53,354.20                  | 9.65              |
|        | <b>TOTAL</b>                                                 | <b>553,132.61</b>          | <b>100.00</b>     |

**7.2** The overall non-availability on account of miscellaneous outages has been estimated as 15.12%. It was highest (53.03%) in case of HE Stations from E.P.P.L followed BBMB (30.64%), SJVNL (15.79%), etc. However, miscellaneous non-availability being beyond the control of utilities, does not have not any impact on the operating availability of HE Stations.

**CENTRAL ELECTRICITY AUTHORITY**  
**Hydro WING**  
**Hydro Project Planning & Investigation Division**

**Annex 7.1**

**NON-AVAILABILITY OF HYDROELECTRIC UNITS DUE TO REASONS OTHER THAN PLANNED  
MAINTENANCE AND FORCED OUTAGE DURING 2021-22**

| SL.No.   | UTILITY/STATION     | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|----------|---------------------|----------|----------------------------|----------------------------------------|
|          | Northern            |          |                            |                                        |
|          | ADHPL               |          |                            |                                        |
| <b>1</b> | ALLAIN DUHANGAN HPS | 1        | 96.00                      | 0.00                                   |
|          |                     | 2        | 96.00                      | 0.04                                   |
|          | <b>TOTAL</b>        |          | <b>192.00</b>              | <b>0.02</b>                            |
|          | AHPC (GVK)          |          |                            |                                        |
| <b>2</b> | SHRINAGAR HPS       | 1        | 82.50                      | 0.00                                   |
|          |                     | 2        | 82.50                      | 0.00                                   |
|          |                     | 3        | 82.50                      | 0.00                                   |
|          |                     | 4        | 82.50                      | 0.00                                   |
|          | <b>TOTAL</b>        |          | <b>330.00</b>              | <b>0.00</b>                            |
|          | BBMB                |          |                            |                                        |
| <b>3</b> | BHAKRA LEFT HPS     | 1        | 108.00                     | 2.09                                   |
|          |                     | 2        | 126.00                     | 21.61                                  |
|          |                     | 3        | 126.00                     | 4.55                                   |
|          |                     | 4        | 126.00                     | 21.22                                  |

| SL.No.   | UTILITY/STATION         | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|----------|-------------------------|----------|----------------------------|----------------------------------------|
|          |                         | 5        | 126.00                     | 3.83                                   |
|          | <b>TOTAL</b>            |          | <b>612.00</b>              | <b>10.66</b>                           |
| <b>4</b> | <b>BHAKRA RIGHT HPS</b> | 10       | 157.00                     | 18.18                                  |
|          |                         | 6        | 157.00                     | 12.53                                  |
|          |                         | 7        | 157.00                     | 68.54                                  |
|          |                         | 8        | 157.00                     | 15.13                                  |
|          |                         | 9        | 157.00                     | 21.18                                  |
|          | <b>TOTAL</b>            |          | <b>785.00</b>              | <b>27.11</b>                           |
| <b>5</b> | <b>DEHAR HPS</b>        | 1        | 165.00                     | 14.81                                  |
|          |                         | 2        | 165.00                     | 14.76                                  |
|          |                         | 3        | 165.00                     | 41.01                                  |
|          |                         | 4        | 165.00                     | 82.75                                  |
|          |                         | 5        | 165.00                     | 37.94                                  |
|          |                         | 6        | 165.00                     | 8.62                                   |
|          | <b>TOTAL</b>            |          | <b>990.00</b>              | <b>33.32</b>                           |
| <b>6</b> | <b>GANGUWAL HPS</b>     | 1        | 29.25                      | 2.46                                   |
|          |                         | 2        | 24.20                      | 3.58                                   |
|          |                         | 3        | 24.20                      | 8.21                                   |
|          | <b>TOTAL</b>            |          | <b>77.65</b>               | <b>4.75</b>                            |
| <b>7</b> | <b>KOTLA HPS</b>        | 1        | 29.25                      | 3.70                                   |

| SL.No.    | UTILITY/STATION        | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|------------------------|----------|----------------------------|----------------------------------------|
|           |                        | 2        | 24.20                      | 3.99                                   |
|           |                        | 3        | 24.20                      | 5.82                                   |
|           | <b>TOTAL</b>           |          | <b>77.65</b>               | <b>4.50</b>                            |
| <b>8</b>  | <b>PONG HPS</b>        | 1        | 66.00                      | 20.08                                  |
|           |                        | 2        | 66.00                      | 15.35                                  |
|           |                        | 3        | 66.00                      | 15.00                                  |
|           |                        | 4        | 66.00                      | 14.87                                  |
|           |                        | 5        | 66.00                      | 11.61                                  |
|           |                        | 6        | 66.00                      | 16.36                                  |
|           | <b>TOTAL</b>           |          | <b>396.00</b>              | <b>15.54</b>                           |
|           | <b>E.P.P.L.</b>        |          |                            |                                        |
| <b>9</b>  | <b>MALANA-II HPS</b>   | 1        | 50.00                      | 51.13                                  |
|           |                        | 2        | 50.00                      | 54.93                                  |
|           | <b>TOTAL</b>           |          | <b>100.00</b>              | <b>53.03</b>                           |
|           | <b>GBHPPL</b>          |          |                            |                                        |
| <b>10</b> | <b>BUDHIL HPS</b>      | 1        | 35.00                      | 0.00                                   |
|           |                        | 2        | 35.00                      | 0.00                                   |
|           | <b>TOTAL</b>           |          | <b>70.00</b>               | <b>0.00</b>                            |
|           | <b>GMR BHHPL</b>       |          |                            |                                        |
| <b>11</b> | <b>BAJOLI HOLI HPS</b> | 1        | 60.00                      | 0.00                                   |

| SL.No.    | UTILITY/STATION               | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|-------------------------------|----------|----------------------------|----------------------------------------|
|           |                               | 2        | 60.00                      | 0.00                                   |
|           |                               | 3        | 60.00                      | 0.00                                   |
|           | <b>TOTAL</b>                  |          | <b>180.00</b>              | <b>0.00</b>                            |
|           | <b>HBPCL</b>                  |          |                            |                                        |
| <b>12</b> | <b>BASPA HPS</b>              | 1        | 100.00                     | 0.00                                   |
|           |                               | 2        | 100.00                     | 0.00                                   |
|           |                               | 3        | 100.00                     | 0.00                                   |
|           | <b>TOTAL</b>                  |          | <b>300.00</b>              | <b>0.00</b>                            |
| <b>13</b> | <b>KARCHAM WANGTOO HPS</b>    | 1        | 261.25                     | 0.00                                   |
|           |                               | 2        | 261.25                     | 0.00                                   |
|           |                               | 3        | 261.25                     | 0.00                                   |
|           |                               | 4        | 261.25                     | 0.00                                   |
|           | <b>TOTAL</b>                  |          | <b>1045.00</b>             | <b>0.00</b>                            |
|           | <b>HPPCL</b>                  |          |                            |                                        |
| <b>14</b> | <b>KASHANG INTEGRATED HEP</b> | 1        | 65.00                      | 0.00                                   |
|           |                               | 2        | 65.00                      | 100.00                                 |
|           |                               | 3        | 65.00                      | 0.00                                   |
|           | <b>TOTAL</b>                  |          | <b>195.00</b>              | <b>33.33</b>                           |
| <b>15</b> | <b>SAINJ HPS</b>              | 1        | 50.00                      | 0.00                                   |
|           |                               | 2        | 50.00                      | 0.00                                   |

| SL.No.    | UTILITY/STATION        | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|------------------------|----------|----------------------------|----------------------------------------|
|           | <b>TOTAL</b>           |          | <b>100.00</b>              | <b>0.00</b>                            |
| <b>16</b> | <b>SAWRA KUDDU HPS</b> | 1        | 37.00                      | 0.00                                   |
|           |                        | 2        | 37.00                      | 0.00                                   |
|           |                        | 3        | 37.00                      | 0.00                                   |
|           | <b>TOTAL</b>           |          | <b>111.00</b>              | <b>0.00</b>                            |
|           | <b>HPSEB</b>           |          |                            |                                        |
| <b>17</b> | <b>BASSI HPS</b>       | 1        | 16.50                      | 0.00                                   |
|           |                        | 2        | 16.50                      | 0.00                                   |
|           |                        | 3        | 16.50                      | 0.00                                   |
|           |                        | 4        | 16.50                      | 0.00                                   |
|           | <b>TOTAL</b>           |          | <b>66.00</b>               | <b>0.00</b>                            |
| <b>18</b> | <b>GIRI BATA HPS</b>   | 1        | 30.00                      | 0.00                                   |
|           |                        | 2        | 30.00                      | 0.00                                   |
|           | <b>TOTAL</b>           |          | <b>60.00</b>               | <b>0.00</b>                            |
| <b>19</b> | <b>LARJI HPS</b>       | 1        | 42.00                      | 0.00                                   |
|           |                        | 2        | 42.00                      | 0.00                                   |
|           |                        | 3        | 42.00                      | 0.00                                   |
|           | <b>TOTAL</b>           |          | <b>126.00</b>              | <b>0.00</b>                            |
| <b>20</b> | <b>SANJAY HPS</b>      | 1        | 40.00                      | 0.00                                   |
|           |                        | 2        | 40.00                      | 0.27                                   |

| SL.No.    | UTILITY/STATION        | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|------------------------|----------|----------------------------|----------------------------------------|
|           |                        | 3        | 40.00                      | 10.73                                  |
|           | <b>TOTAL</b>           |          | <b>120.00</b>              | <b>3.67</b>                            |
|           | <b>HSPCL</b>           |          |                            |                                        |
| <b>21</b> | <b>SORANG HPS</b>      | 1        | 50.00                      | 0.00                                   |
|           |                        | 2        | 50.00                      | 0.00                                   |
|           | <b>TOTAL</b>           |          | <b>100.00</b>              | <b>0.00</b>                            |
|           | <b>IAEPL</b>           |          |                            |                                        |
| <b>22</b> | <b>CHANJU-I HPS</b>    | 1        | 12.00                      | 0.00                                   |
|           |                        | 2        | 12.00                      | 0.00                                   |
|           |                        | 3        | 12.00                      | 0.00                                   |
|           | <b>TOTAL</b>           |          | <b>36.00</b>               | <b>0.00</b>                            |
|           | <b>JKSPDC</b>          |          |                            |                                        |
| <b>23</b> | <b>BAGLIHAR HPS</b>    | 1        | 150.00                     | 0.00                                   |
|           |                        | 2        | 150.00                     | 0.00                                   |
|           |                        | 3        | 150.00                     | 0.00                                   |
|           | <b>TOTAL</b>           |          | <b>450.00</b>              | <b>0.00</b>                            |
| <b>24</b> | <b>BAGLIHAR II HPS</b> | 1        | 150.00                     | 0.00                                   |
|           |                        | 2        | 150.00                     | 0.00                                   |
|           |                        | 3        | 150.00                     | 100.00                                 |
|           | <b>TOTAL</b>           |          | <b>450.00</b>              | <b>33.33</b>                           |

| SL.No. | UTILITY/STATION      | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|--------|----------------------|----------|----------------------------|----------------------------------------|
| 25     | LOWER JHELM HPS      | 1        | 35.00                      | 0.00                                   |
|        |                      | 2        | 35.00                      | 0.00                                   |
|        |                      | 3        | 35.00                      | 100.00                                 |
|        | <b>TOTAL</b>         |          | <b>105.00</b>              | <b>33.33</b>                           |
| 26     | UPPER SINDH-II HPS   | 3        | 35.00                      | 0.00                                   |
|        |                      | 4        | 35.00                      | 0.00                                   |
|        |                      | 5        | 35.00                      | 0.00                                   |
|        | <b>TOTAL</b>         |          | <b>105.00</b>              | <b>0.00</b>                            |
|        | <b>JPPVL</b>         |          |                            |                                        |
| 27     | VISHNU PRAYAG HPS    | 1        | 100.00                     | 0.00                                   |
|        |                      | 2        | 100.00                     | 0.00                                   |
|        |                      | 3        | 100.00                     | 0.00                                   |
|        |                      | 4        | 100.00                     | 0.00                                   |
|        | <b>TOTAL</b>         |          | <b>400.00</b>              | <b>0.00</b>                            |
|        | <b>L&amp;T</b>       |          |                            |                                        |
| 28     | SINGOLI BHATWARI HPS | 1        | 33.00                      | 0.00                                   |
|        |                      | 2        | 33.00                      | 0.00                                   |
|        |                      | 3        | 33.00                      | 0.00                                   |
|        | <b>TOTAL</b>         |          | <b>99.00</b>               | <b>0.00</b>                            |
|        | <b>MPCL</b>          |          |                            |                                        |

| SL.No. | UTILITY/STATION | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|--------|-----------------|----------|----------------------------|----------------------------------------|
| 29     | MALANA HPS      | 1        | 43.00                      | 0.00                                   |
|        |                 | 2        | 43.00                      | 0.00                                   |
|        | <b>TOTAL</b>    |          | <b>86.00</b>               | <b>0.00</b>                            |
|        | <b>NHPC</b>     |          |                            |                                        |
| 30     | BAIRA SIUL HPS  | 1        | 60.00                      | 38.30                                  |
|        |                 | 2        | 60.00                      | 39.22                                  |
|        |                 | 3        | 60.00                      | 27.42                                  |
|        | <b>TOTAL</b>    |          | <b>180.00</b>              | <b>34.98</b>                           |
| 31     | CHAMERA-I HPS   | 1        | 180.00                     | 48.88                                  |
|        |                 | 2        | 180.00                     | 50.26                                  |
|        |                 | 3        | 180.00                     | 38.35                                  |
|        | <b>TOTAL</b>    |          | <b>540.00</b>              | <b>45.83</b>                           |
| 32     | CHAMERA-II HPS  | 1        | 100.00                     | 138.99                                 |
|        |                 | 2        | 100.00                     | 36.59                                  |
|        |                 | 3        | 100.00                     | 48.13                                  |
|        | <b>TOTAL</b>    |          | <b>300.00</b>              | <b>74.57</b>                           |
| 33     | CHAMERA-III HPS | 1        | 77.00                      | 50.75                                  |
|        |                 | 2        | 77.00                      | 42.23                                  |
|        |                 | 3        | 77.00                      | 41.37                                  |
|        | <b>TOTAL</b>    |          | <b>231.00</b>              | <b>44.78</b>                           |

| SL.No.    | UTILITY/STATION         | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|-------------------------|----------|----------------------------|----------------------------------------|
| <b>34</b> | <b>CHUTAK HPS</b>       | 1        | 11.00                      | 35.01                                  |
|           |                         | 2        | 11.00                      | 33.89                                  |
|           |                         | 3        | 11.00                      | 33.97                                  |
|           |                         | 4        | 11.00                      | 37.64                                  |
|           | <b>TOTAL</b>            |          | <b>44.00</b>               | <b>35.13</b>                           |
| <b>35</b> | <b>DHAULI GANGA HPS</b> | 1        | 70.00                      | 39.64                                  |
|           |                         | 2        | 70.00                      | 42.36                                  |
|           |                         | 3        | 70.00                      | 52.03                                  |
|           |                         | 4        | 70.00                      | 43.06                                  |
|           | <b>TOTAL</b>            |          | <b>280.00</b>              | <b>44.27</b>                           |
| <b>36</b> | <b>DULHASTI HPS</b>     | 1        | 130.00                     | 18.52                                  |
|           |                         | 2        | 130.00                     | 30.43                                  |
|           |                         | 3        | 130.00                     | 34.56                                  |
|           | <b>TOTAL</b>            |          | <b>390.00</b>              | <b>27.84</b>                           |
| <b>37</b> | <b>KISHANGANGA HPS</b>  | 1        | 110.00                     | 33.31                                  |
|           |                         | 2        | 110.00                     | 25.67                                  |
|           |                         | 3        | 110.00                     | 30.90                                  |
|           | <b>TOTAL</b>            |          | <b>330.00</b>              | <b>29.96</b>                           |
| <b>38</b> | <b>NIMMO BAZGO HPS</b>  | 1        | 15.00                      | 24.82                                  |
|           |                         | 2        | 15.00                      | 26.41                                  |

| SL.No.    | UTILITY/STATION        | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|------------------------|----------|----------------------------|----------------------------------------|
|           |                        | 3        | 15.00                      | 33.19                                  |
|           | <b>TOTAL</b>           |          | <b>45.00</b>               | <b>28.14</b>                           |
| <b>39</b> | <b>PARBATI-III HPS</b> | 1        | 130.00                     | 69.75                                  |
|           |                        | 2        | 130.00                     | 73.38                                  |
|           |                        | 3        | 130.00                     | 75.83                                  |
|           |                        | 4        | 130.00                     | 62.64                                  |
|           | <b>TOTAL</b>           |          | <b>520.00</b>              | <b>70.40</b>                           |
| <b>40</b> | <b>SALAL HPS</b>       | 1        | 115.00                     | 33.69                                  |
|           |                        | 2        | 115.00                     | 46.71                                  |
|           |                        | 3        | 115.00                     | 26.77                                  |
|           |                        | 4        | 115.00                     | 38.21                                  |
|           |                        | 5        | 115.00                     | 48.56                                  |
|           |                        | 6        | 115.00                     | 18.98                                  |
|           | <b>TOTAL</b>           |          | <b>690.00</b>              | <b>35.48</b>                           |
| <b>41</b> | <b>SEWA-II HPS</b>     | 1        | 40.00                      | 0.26                                   |
|           |                        | 2        | 40.00                      | 0.42                                   |
|           |                        | 3        | 40.00                      | 0.03                                   |
|           | <b>TOTAL</b>           |          | <b>120.00</b>              | <b>0.24</b>                            |
| <b>42</b> | <b>TANAKPUR HPS</b>    | 1        | 31.40                      | 8.55                                   |
|           |                        | 2        | 31.40                      | 9.92                                   |

| SL.No.    | UTILITY/STATION             | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|-----------------------------|----------|----------------------------|----------------------------------------|
|           |                             | 3        | 31.40                      | 16.15                                  |
|           | <b>TOTAL</b>                |          | <b>94.20</b>               | <b>11.54</b>                           |
| <b>43</b> | <b>URI-I HPS</b>            | 1        | 120.00                     | 1.11                                   |
|           |                             | 2        | 120.00                     | 2.42                                   |
|           |                             | 3        | 120.00                     | 0.42                                   |
|           |                             | 4        | 120.00                     | 1.03                                   |
|           | <b>TOTAL</b>                |          | <b>480.00</b>              | <b>1.25</b>                            |
| <b>44</b> | <b>URI-II HPS</b>           | 1        | 60.00                      | 5.75                                   |
|           |                             | 2        | 60.00                      | 20.82                                  |
|           |                             | 3        | 60.00                      | 13.53                                  |
|           |                             | 4        | 60.00                      | 9.34                                   |
|           | <b>TOTAL</b>                |          | <b>240.00</b>              | <b>12.36</b>                           |
|           | <b>NTPC Ltd.</b>            |          |                            |                                        |
| <b>45</b> | <b>KOLDAM</b>               | 1        | 200.00                     | 0.00                                   |
|           |                             | 2        | 200.00                     | 0.00                                   |
|           |                             | 3        | 200.00                     | 0.00                                   |
|           |                             | 4        | 200.00                     | 0.00                                   |
|           | <b>TOTAL</b>                |          | <b>800.00</b>              | <b>0.00</b>                            |
|           | <b>PSPCL</b>                |          |                            |                                        |
| <b>46</b> | <b>ANANDPUR SAHIB-I HPS</b> | 1        | 33.50                      | 0.00                                   |

| SL.No.    | UTILITY/STATION              | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|------------------------------|----------|----------------------------|----------------------------------------|
|           |                              | 2        | 33.50                      | 0.00                                   |
|           | <b>TOTAL</b>                 |          | <b>67.00</b>               | <b>0.00</b>                            |
| <b>47</b> | <b>ANANDPUR SAHIB-II HPS</b> | 3        | 33.50                      | 0.00                                   |
|           |                              | 4        | 33.50                      | 0.00                                   |
|           | <b>TOTAL</b>                 |          | <b>67.00</b>               | <b>0.00</b>                            |
| <b>48</b> | <b>MUKERIAN-I HPS</b>        | 1        | 15.00                      | 0.00                                   |
|           |                              | 2        | 15.00                      | 0.00                                   |
|           |                              | 3        | 15.00                      | 0.00                                   |
|           | <b>TOTAL</b>                 |          | <b>45.00</b>               | <b>0.00</b>                            |
| <b>49</b> | <b>MUKERIAN-II HPS</b>       | 4        | 15.00                      | 0.00                                   |
|           |                              | 5        | 15.00                      | 0.00                                   |
|           |                              | 6        | 15.00                      | 0.00                                   |
|           | <b>TOTAL</b>                 |          | <b>45.00</b>               | <b>0.00</b>                            |
| <b>50</b> | <b>MUKERIAN-III HPS</b>      | 7        | 19.50                      | 0.00                                   |
|           |                              | 8        | 19.50                      | 0.00                                   |
|           |                              | 9        | 19.50                      | 0.00                                   |
|           | <b>TOTAL</b>                 |          | <b>58.50</b>               | <b>0.00</b>                            |
| <b>51</b> | <b>MUKERIAN-IV HPS</b>       | 10       | 19.50                      | 0.00                                   |
|           |                              | 11       | 19.50                      | 0.00                                   |
|           |                              | 12       | 19.50                      | 0.00                                   |

| SL.No.    | UTILITY/STATION          | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|--------------------------|----------|----------------------------|----------------------------------------|
|           | <b>TOTAL</b>             |          | <b>58.50</b>               | <b>0.00</b>                            |
| <b>52</b> | <b>RANJIT SAGAR HPS</b>  | 1        | 150.00                     | 0.00                                   |
|           |                          | 2        | 150.00                     | 0.89                                   |
|           |                          | 3        | 150.00                     | 0.00                                   |
|           |                          | 4        | 150.00                     | 0.00                                   |
|           | <b>TOTAL</b>             |          | <b>600.00</b>              | <b>0.22</b>                            |
| <b>53</b> | <b>SHANAN HPS</b>        | 1        | 15.00                      | 0.00                                   |
|           |                          | 2        | 15.00                      | 0.00                                   |
|           |                          | 3        | 15.00                      | 0.00                                   |
|           |                          | 4        | 15.00                      | 0.00                                   |
|           |                          | 5        | 50.00                      | 0.00                                   |
|           | <b>TOTAL</b>             |          | <b>110.00</b>              | <b>0.00</b>                            |
|           | <b>RRVUNL</b>            |          |                            |                                        |
| <b>54</b> | <b>JAWAHAR SAGAR HPS</b> | 1        | 33.00                      | 0.00                                   |
|           |                          | 2        | 33.00                      | 0.00                                   |
|           |                          | 3        | 33.00                      | 0.00                                   |
|           | <b>TOTAL</b>             |          | <b>99.00</b>               | <b>0.00</b>                            |
| <b>55</b> | <b>MAHI BAJAJ-I HPS</b>  | 1        | 25.00                      | 0.00                                   |
|           |                          | 2        | 25.00                      | 0.00                                   |
|           | <b>TOTAL</b>             |          | <b>50.00</b>               | <b>0.00</b>                            |

| SL.No.    | UTILITY/STATION          | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|--------------------------|----------|----------------------------|----------------------------------------|
| <b>56</b> | <b>MAHI BAJAJ-II HPS</b> | 3        | 45.00                      | 100.00                                 |
|           |                          | 4        | 45.00                      | 0.00                                   |
|           | <b>TOTAL</b>             |          | <b>90.00</b>               | <b>50.00</b>                           |
| <b>57</b> | <b>R P SAGAR HPS</b>     | 1        | 43.00                      | 0.00                                   |
|           |                          | 2        | 43.00                      | 0.00                                   |
|           |                          | 3        | 43.00                      | 0.00                                   |
|           |                          | 4        | 43.00                      | 0.00                                   |
|           | <b>TOTAL</b>             |          | <b>172.00</b>              | <b>0.00</b>                            |
|           | <b>SJVNL</b>             |          |                            |                                        |
| <b>58</b> | <b>NATHPA JHAKRI HPS</b> | 1        | 250.00                     | 40.35                                  |
|           |                          | 2        | 250.00                     | 141.81                                 |
|           |                          | 3        | 250.00                     | 45.84                                  |
|           |                          | 4        | 250.00                     | 41.94                                  |
|           |                          | 5        | 250.00                     | 49.11                                  |
|           |                          | 6        | 250.00                     | 146.01                                 |
|           | <b>TOTAL</b>             |          | <b>1500.00</b>             | <b>77.51</b>                           |
| <b>59</b> | <b>RAMPUR HPS</b>        | 1        | 68.67                      | 32.27                                  |
|           |                          | 2        | 68.67                      | 46.36                                  |
|           |                          | 3        | 68.67                      | 50.22                                  |
|           |                          | 4        | 68.67                      | 49.65                                  |

| SL.No.    | UTILITY/STATION            | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|----------------------------|----------|----------------------------|----------------------------------------|
|           |                            | 5        | 68.67                      | 48.79                                  |
|           |                            | 6        | 68.67                      | 33.99                                  |
|           | <b>TOTAL</b>               |          | <b>412.02</b>              | <b>43.55</b>                           |
|           | <b>THDC</b>                |          |                            |                                        |
| <b>60</b> | <b>KOTESHWAR HPS</b>       | 1        | 100.00                     | 0.00                                   |
|           |                            | 2        | 100.00                     | 0.00                                   |
|           |                            | 3        | 100.00                     | 0.00                                   |
|           |                            | 4        | 100.00                     | 0.00                                   |
|           | <b>TOTAL</b>               |          | <b>400.00</b>              | <b>0.00</b>                            |
| <b>61</b> | <b>TEHRI ST-1 HPS</b>      | 1        | 250.00                     | 0.00                                   |
|           |                            | 2        | 250.00                     | 0.00                                   |
|           |                            | 3        | 250.00                     | 0.00                                   |
|           |                            | 4        | 250.00                     | 0.00                                   |
|           | <b>TOTAL</b>               |          | <b>1000.00</b>             | <b>0.00</b>                            |
|           | <b>UJVNL</b>               |          |                            |                                        |
| <b>62</b> | <b>CHIBRO (YAMUNA) HPS</b> | 1        | 60.00                      | 0.00                                   |
|           |                            | 2        | 60.00                      | 0.00                                   |
|           |                            | 3        | 60.00                      | 0.00                                   |
|           |                            | 4        | 60.00                      | 100.00                                 |
|           | <b>TOTAL</b>               |          | <b>240.00</b>              | <b>25.00</b>                           |

| SL.No.    | UTILITY/STATION     | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|---------------------|----------|----------------------------|----------------------------------------|
| <b>63</b> | <b>CHILLA HPS</b>   | 1        | 36.00                      | 0.00                                   |
|           |                     | 2        | 36.00                      | 0.00                                   |
|           |                     | 3        | 36.00                      | 0.00                                   |
|           |                     | 4        | 36.00                      | 0.00                                   |
|           | <b>TOTAL</b>        |          | <b>144.00</b>              | <b>0.00</b>                            |
| <b>64</b> | <b>DHAKRANI HPS</b> | 1        | 11.25                      | 0.00                                   |
|           |                     | 2        | 11.25                      | 0.00                                   |
|           |                     | 3        | 11.25                      | 0.00                                   |
|           | <b>TOTAL</b>        |          | <b>33.75</b>               | <b>0.00</b>                            |
| <b>65</b> | <b>DHALIPUR HPS</b> | 1        | 17.00                      | 0.00                                   |
|           |                     | 2        | 17.00                      | 0.00                                   |
|           |                     | 3        | 17.00                      | 0.00                                   |
|           | <b>TOTAL</b>        |          | <b>51.00</b>               | <b>0.00</b>                            |
| <b>66</b> | <b>KHATIMA HPS</b>  | 1        | 13.80                      | 0.00                                   |
|           |                     | 2        | 13.80                      | 0.00                                   |
|           |                     | 3        | 13.80                      | 0.00                                   |
|           | <b>TOTAL</b>        |          | <b>41.40</b>               | <b>0.00</b>                            |
| <b>67</b> | <b>KHODRI HPS</b>   | 1        | 30.00                      | 24.73                                  |
|           |                     | 2        | 30.00                      | 1.09                                   |
|           |                     | 3        | 30.00                      | 45.20                                  |

| SL.No.    | UTILITY/STATION            | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|----------------------------|----------|----------------------------|----------------------------------------|
|           |                            | 4        | 30.00                      | 14.52                                  |
|           | <b>TOTAL</b>               |          | <b>120.00</b>              | <b>21.38</b>                           |
| <b>68</b> | <b>KULHAL HPS</b>          | 1        | 10.00                      | 0.00                                   |
|           |                            | 2        | 10.00                      | 10.67                                  |
|           |                            | 3        | 10.00                      | 0.00                                   |
|           | <b>TOTAL</b>               |          | <b>30.00</b>               | <b>3.56</b>                            |
| <b>69</b> | <b>MANERI BHALI-I HPS</b>  | 1        | 30.00                      | 0.00                                   |
|           |                            | 2        | 30.00                      | 0.00                                   |
|           |                            | 3        | 30.00                      | 0.00                                   |
|           | <b>TOTAL</b>               |          | <b>90.00</b>               | <b>0.00</b>                            |
| <b>70</b> | <b>MANERI BHALI-II HPS</b> | 1        | 76.00                      | 0.00                                   |
|           |                            | 2        | 76.00                      | 0.00                                   |
|           |                            | 3        | 76.00                      | 0.00                                   |
|           |                            | 4        | 76.00                      | 0.00                                   |
|           | <b>TOTAL</b>               |          | <b>304.00</b>              | <b>0.00</b>                            |
| <b>71</b> | <b>RAMGANGA HPS</b>        | 1        | 66.00                      | 0.00                                   |
|           |                            | 2        | 66.00                      | 13.98                                  |
|           |                            | 3        | 66.00                      | 4.97                                   |
|           | <b>TOTAL</b>               |          | <b>198.00</b>              | <b>6.32</b>                            |
|           | <b>UPJVNL</b>              |          |                            |                                        |

| SL.No.    | UTILITY/STATION     | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|---------------------|----------|----------------------------|----------------------------------------|
| <b>72</b> | <b>KHARA HPS</b>    | 1        | 24.00                      | 0.00                                   |
|           |                     | 2        | 24.00                      | 0.00                                   |
|           |                     | 3        | 24.00                      | 0.00                                   |
|           | <b>TOTAL</b>        |          | <b>72.00</b>               | <b>0.00</b>                            |
| <b>73</b> | <b>MATATILA HPS</b> | 1        | 10.20                      | 0.00                                   |
|           |                     | 2        | 10.20                      | 0.00                                   |
|           |                     | 3        | 10.20                      | 0.00                                   |
|           | <b>TOTAL</b>        |          | <b>30.60</b>               | <b>0.00</b>                            |
| <b>74</b> | <b>OBRA HPS</b>     | 1        | 33.00                      | 0.00                                   |
|           |                     | 2        | 33.00                      | 0.00                                   |
|           |                     | 3        | 33.00                      | 0.00                                   |
|           | <b>TOTAL</b>        |          | <b>99.00</b>               | <b>0.00</b>                            |
| <b>75</b> | <b>RIHAND HPS</b>   | 1        | 50.00                      | 0.00                                   |
|           |                     | 2        | 50.00                      | 0.00                                   |
|           |                     | 3        | 50.00                      | 0.00                                   |
|           |                     | 4        | 50.00                      | 0.00                                   |
|           |                     | 5        | 50.00                      | 0.00                                   |
|           |                     | 6        | 50.00                      | 0.00                                   |
|           | <b>TOTAL</b>        |          | <b>300.00</b>              | <b>0.00</b>                            |
|           | <b>Western</b>      |          |                            |                                        |

| SL.No.    | UTILITY/STATION               | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|-------------------------------|----------|----------------------------|----------------------------------------|
|           | <b>CSPGCL</b>                 |          |                            |                                        |
| <b>76</b> | <b>HASDEOBANGO HPS</b>        | 1        | 40.00                      | 0.00                                   |
|           |                               | 2        | 40.00                      | 0.00                                   |
|           |                               | 3        | 40.00                      | 0.00                                   |
|           | <b>TOTAL</b>                  |          | <b>120.00</b>              | <b>0.00</b>                            |
|           | <b>DLHP</b>                   |          |                            |                                        |
| <b>77</b> | <b>BHANDARDHARA HPS ST-II</b> | 2        | 34.00                      | 0.00                                   |
|           | <b>TOTAL</b>                  |          | <b>34.00</b>               | <b>0.00</b>                            |
|           | <b>GSECL</b>                  |          |                            |                                        |
| <b>78</b> | <b>KADANA HPS</b>             | 1        | 60.00                      | 0.00                                   |
|           |                               | 2        | 60.00                      | 0.00                                   |
|           |                               | 3        | 60.00                      | 0.00                                   |
|           |                               | 4        | 60.00                      | 0.00                                   |
|           | <b>TOTAL</b>                  |          | <b>240.00</b>              | <b>0.00</b>                            |
| <b>79</b> | <b>UKAI HPS</b>               | 1        | 75.00                      | 0.00                                   |
|           |                               | 2        | 75.00                      | 0.00                                   |
|           |                               | 3        | 75.00                      | 0.00                                   |
|           |                               | 4        | 75.00                      | 0.00                                   |
|           | <b>TOTAL</b>                  |          | <b>300.00</b>              | <b>0.00</b>                            |
|           | <b>MAHAGENCO</b>              |          |                            |                                        |

| SL.No. | UTILITY/STATION     | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|--------|---------------------|----------|----------------------------|----------------------------------------|
| 80     | BHIRA TAIL RACE HPS | 1        | 40.00                      | 0.00                                   |
|        |                     | 2        | 40.00                      | 0.00                                   |
|        | <b>TOTAL</b>        |          | <b>80.00</b>               | <b>0.00</b>                            |
| 81     | GHATGHAR PSS HPS    | 1        | 125.00                     | 0.00                                   |
|        |                     | 2        | 125.00                     | 0.00                                   |
|        | <b>TOTAL</b>        |          | <b>250.00</b>              | <b>0.00</b>                            |
| 82     | KOYNA DPH HPS       | 1        | 18.00                      | 0.00                                   |
|        |                     | 2        | 18.00                      | 0.00                                   |
|        | <b>TOTAL</b>        |          | <b>36.00</b>               | <b>0.00</b>                            |
| 83     | KOYNA-I&II HPS      | 1        | 70.00                      | 0.00                                   |
|        |                     | 2        | 70.00                      | 0.00                                   |
|        |                     | 3        | 70.00                      | 0.00                                   |
|        |                     | 4        | 70.00                      | 0.00                                   |
|        |                     | 5        | 80.00                      | 0.00                                   |
|        |                     | 6        | 80.00                      | 0.00                                   |
|        |                     | 7        | 80.00                      | 0.00                                   |
|        |                     | 8        | 80.00                      | 0.00                                   |
|        | <b>TOTAL</b>        |          | <b>600.00</b>              | <b>0.00</b>                            |
| 84     | KOYNA-III HPS       | 1        | 80.00                      | 0.00                                   |
|        |                     | 2        | 80.00                      | 0.00                                   |

| SL.No.    | UTILITY/STATION         | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|-------------------------|----------|----------------------------|----------------------------------------|
|           |                         | 3        | 80.00                      | 0.00                                   |
|           |                         | 4        | 80.00                      | 0.00                                   |
|           | <b>TOTAL</b>            |          | <b>320.00</b>              | <b>0.00</b>                            |
| <b>85</b> | <b>KOYNA-IV HPS</b>     | 1        | 250.00                     | 0.00                                   |
|           |                         | 2        | 250.00                     | 0.00                                   |
|           |                         | 3        | 250.00                     | 0.00                                   |
|           |                         | 4        | 250.00                     | 0.00                                   |
|           | <b>TOTAL</b>            |          | <b>1000.00</b>             | <b>0.00</b>                            |
| <b>86</b> | <b>TILLARI HPS</b>      | 1        | 60.00                      | 0.00                                   |
|           | <b>TOTAL</b>            |          | <b>60.00</b>               | <b>0.00</b>                            |
| <b>87</b> | <b>VAITARNA HPS</b>     | 1        | 60.00                      | 0.00                                   |
|           | <b>TOTAL</b>            |          | <b>60.00</b>               | <b>0.00</b>                            |
|           | <b>MPPGCL</b>           |          |                            |                                        |
| <b>88</b> | <b>BANSAGAR-II HPS</b>  | 1        | 15.00                      | 0.00                                   |
|           |                         | 2        | 15.00                      | 3.71                                   |
|           | <b>TOTAL</b>            |          | <b>30.00</b>               | <b>1.86</b>                            |
| <b>89</b> | <b>BANSAGAR-III HPS</b> | 1        | 20.00                      | 88.55                                  |
|           |                         | 2        | 20.00                      | 55.34                                  |
|           |                         | 3        | 20.00                      | 55.61                                  |
|           | <b>TOTAL</b>            |          | <b>60.00</b>               | <b>66.50</b>                           |

| SL.No. | UTILITY/STATION     | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|--------|---------------------|----------|----------------------------|----------------------------------------|
| 90     | BANSAGAR TONS-I HPS | 1        | 105.00                     | 0.00                                   |
|        |                     | 2        | 105.00                     | 0.00                                   |
|        |                     | 3        | 105.00                     | 0.00                                   |
|        | TOTAL               |          | 315.00                     | 0.00                                   |
| 91     | BARGI HPS           | 1        | 45.00                      | 0.00                                   |
|        |                     | 2        | 45.00                      | 0.00                                   |
|        | TOTAL               |          | 90.00                      | 0.00                                   |
| 92     | GANDHI SAGAR HPS    | 1        | 23.00                      | 60.04                                  |
|        |                     | 2        | 23.00                      | 0.00                                   |
|        |                     | 3        | 23.00                      | 0.00                                   |
|        |                     | 4        | 23.00                      | 60.11                                  |
|        |                     | 5        | 23.00                      | 59.84                                  |
|        | TOTAL               |          | 115.00                     | 36.00                                  |
| 93     | MADHIKHERA HPS      | 1        | 20.00                      | 0.00                                   |
|        |                     | 2        | 20.00                      | 0.00                                   |
|        |                     | 3        | 20.00                      | 0.00                                   |
|        | TOTAL               |          | 60.00                      | 0.00                                   |
| 94     | PENCH HPS           | 1        | 80.00                      | 0.00                                   |
|        |                     | 2        | 80.00                      | 0.00                                   |
|        | TOTAL               |          | 160.00                     | 0.00                                   |

| SL.No.    | UTILITY/STATION         | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|-----------|-------------------------|----------|----------------------------|----------------------------------------|
| <b>95</b> | <b>RAJGHAT HPS</b>      | 1        | 15.00                      | 13.62                                  |
|           |                         | 2        | 15.00                      | 0.00                                   |
|           |                         | 3        | 15.00                      | 13.34                                  |
|           | <b>TOTAL</b>            |          | <b>45.00</b>               | <b>8.99</b>                            |
|           | <b>NHDC</b>             |          |                            |                                        |
| <b>96</b> | <b>INDIRA SAGAR HPS</b> | 1        | 125.00                     | 0.00                                   |
|           |                         | 2        | 125.00                     | 0.00                                   |
|           |                         | 3        | 125.00                     | 0.00                                   |
|           |                         | 4        | 125.00                     | 0.00                                   |
|           |                         | 5        | 125.00                     | 0.00                                   |
|           |                         | 6        | 125.00                     | 0.14                                   |
|           |                         | 7        | 125.00                     | 0.00                                   |
|           |                         | 8        | 125.00                     | 0.00                                   |
|           | <b>TOTAL</b>            |          | <b>1000.00</b>             | <b>0.02</b>                            |
| <b>97</b> | <b>OMKARESHWAR HPS</b>  | 1        | 65.00                      | 0.00                                   |
|           |                         | 2        | 65.00                      | 0.00                                   |
|           |                         | 3        | 65.00                      | 0.00                                   |
|           |                         | 4        | 65.00                      | 0.00                                   |
|           |                         | 5        | 65.00                      | 0.00                                   |
|           |                         | 6        | 65.00                      | 0.00                                   |

| SL.No.     | UTILITY/STATION           | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|---------------------------|----------|----------------------------|----------------------------------------|
|            |                           | 7        | 65.00                      | 0.00                                   |
|            |                           | 8        | 65.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>520.00</b>              | <b>0.00</b>                            |
|            | <b>SSNNL</b>              |          |                            |                                        |
| <b>98</b>  | <b>S SAROVAR CHPH HPS</b> | 1        | 50.00                      | 0.00                                   |
|            |                           | 2        | 50.00                      | 0.00                                   |
|            |                           | 3        | 50.00                      | 0.00                                   |
|            |                           | 4        | 50.00                      | 0.00                                   |
|            |                           | 5        | 50.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>250.00</b>              | <b>0.00</b>                            |
| <b>99</b>  | <b>S SAROVAR RBPH HPS</b> | 1        | 200.00                     | 0.25                                   |
|            |                           | 2        | 200.00                     | 0.31                                   |
|            |                           | 3        | 200.00                     | 0.13                                   |
|            |                           | 4        | 200.00                     | 0.31                                   |
|            |                           | 5        | 200.00                     | 0.31                                   |
|            |                           | 6        | 200.00                     | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>1200.00</b>             | <b>0.22</b>                            |
|            | <b>TATA MAH.</b>          |          |                            |                                        |
| <b>100</b> | <b>BHIRA HPS</b>          | 1        | 25.00                      | 0.00                                   |
|            |                           | 2        | 25.00                      | 0.00                                   |

| SL.No.     | UTILITY/STATION      | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|----------------------|----------|----------------------------|----------------------------------------|
|            |                      | 3        | 25.00                      | 0.00                                   |
|            |                      | 4        | 25.00                      | 0.00                                   |
|            |                      | 5        | 25.00                      | 0.00                                   |
|            |                      | 6        | 25.00                      | 0.00                                   |
|            | <b>TOTAL</b>         |          | <b>150.00</b>              | <b>0.00</b>                            |
| <b>101</b> | <b>BHIRA PSS HPS</b> | 1        | 150.00                     | 0.00                                   |
|            | <b>TOTAL</b>         |          | <b>150.00</b>              | <b>0.00</b>                            |
| <b>102</b> | <b>BHIVPURI HPS</b>  | 1        | 24.00                      | 0.00                                   |
|            |                      | 2        | 24.00                      | 0.00                                   |
|            |                      | 3        | 24.00                      | 0.00                                   |
|            |                      | 4        | 1.50                       | 0.00                                   |
|            |                      | 5        | 1.50                       | 0.00                                   |
|            | <b>TOTAL</b>         |          | <b>75.00</b>               | <b>0.00</b>                            |
| <b>103</b> | <b>KHOPOLI HPS</b>   | 1        | 24.00                      | 0.00                                   |
|            |                      | 2        | 24.00                      | 0.00                                   |
|            |                      | 3        | 24.00                      | 0.00                                   |
|            | <b>TOTAL</b>         |          | <b>72.00</b>               | <b>0.00</b>                            |
|            | <b>Southern</b>      |          |                            |                                        |
|            | <b>APGENCO</b>       |          |                            |                                        |
| <b>104</b> | <b>HAMPI HPS</b>     | 1        | 9.00                       | 0.00                                   |

| SL.No.     | UTILITY/STATION             | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|-----------------------------|----------|----------------------------|----------------------------------------|
|            |                             | 2        | 9.00                       | 0.00                                   |
|            |                             | 3        | 9.00                       | 0.00                                   |
|            |                             | 4        | 9.00                       | 0.00                                   |
|            | <b>TOTAL</b>                |          | <b>36.00</b>               | <b>0.00</b>                            |
| <b>105</b> | <b>LOWER SILERU HPS</b>     | 1        | 115.00                     | 0.00                                   |
|            |                             | 2        | 115.00                     | 0.00                                   |
|            |                             | 3        | 115.00                     | 0.00                                   |
|            |                             | 4        | 115.00                     | 0.00                                   |
|            | <b>TOTAL</b>                |          | <b>460.00</b>              | <b>0.00</b>                            |
| <b>106</b> | <b>NAGARJUN SGR RBC HPS</b> | 1        | 30.00                      | 0.00                                   |
|            |                             | 2        | 30.00                      | 0.00                                   |
|            |                             | 3        | 30.00                      | 0.00                                   |
|            | <b>TOTAL</b>                |          | <b>90.00</b>               | <b>0.00</b>                            |
| <b>107</b> | <b>NAGARJUN SGR TPD</b>     | 1        | 25.00                      | 0.00                                   |
|            |                             | 2        | 25.00                      | 0.00                                   |
|            | <b>TOTAL</b>                |          | <b>50.00</b>               | <b>0.00</b>                            |
| <b>108</b> | <b>SRISAILAM HPS</b>        | 1        | 110.00                     | 0.00                                   |
|            |                             | 2        | 110.00                     | 0.00                                   |
|            |                             | 3        | 110.00                     | 0.00                                   |
|            |                             | 4        | 110.00                     | 0.00                                   |

| SL.No.     | UTILITY/STATION         | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|-------------------------|----------|----------------------------|----------------------------------------|
|            |                         | 5        | 110.00                     | 0.00                                   |
|            |                         | 6        | 110.00                     | 0.00                                   |
|            |                         | 7        | 110.00                     | 0.00                                   |
|            | <b>TOTAL</b>            |          | <b>770.00</b>              | <b>0.00</b>                            |
| <b>109</b> | <b>T B DAM HPS</b>      | 1        | 9.00                       | 0.00                                   |
|            |                         | 2        | 9.00                       | 0.00                                   |
|            |                         | 3        | 9.00                       | 0.00                                   |
|            |                         | 4        | 9.00                       | 0.00                                   |
|            | <b>TOTAL</b>            |          | <b>36.00</b>               | <b>0.00</b>                            |
| <b>110</b> | <b>UPPER SILERU HPS</b> | 1        | 60.00                      | 0.00                                   |
|            |                         | 2        | 60.00                      | 0.00                                   |
|            |                         | 3        | 60.00                      | 0.00                                   |
|            |                         | 4        | 60.00                      | 0.00                                   |
|            | <b>TOTAL</b>            |          | <b>240.00</b>              | <b>0.00</b>                            |
|            | <b>KPCL</b>             |          |                            |                                        |
| <b>111</b> | <b>ALMATTI DPH HPS</b>  | 1        | 15.00                      | 0.00                                   |
|            |                         | 2        | 55.00                      | 0.00                                   |
|            |                         | 3        | 55.00                      | 0.00                                   |
|            |                         | 4        | 55.00                      | 0.00                                   |
|            |                         | 5        | 55.00                      | 0.00                                   |

| SL.No.     | UTILITY/STATION        | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|------------------------|----------|----------------------------|----------------------------------------|
|            |                        | 6        | 55.00                      | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>290.00</b>              | <b>0.00</b>                            |
| <b>112</b> | <b>BHADRA HPS</b>      | 1        | 2.00                       | 0.00                                   |
|            |                        | 2        | 12.00                      | 0.00                                   |
|            |                        | 3        | 12.00                      | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>26.00</b>               | <b>0.00</b>                            |
| <b>113</b> | <b>GERUSUPPA HPS</b>   | 1        | 60.00                      | 0.00                                   |
|            |                        | 2        | 60.00                      | 0.00                                   |
|            |                        | 3        | 60.00                      | 0.00                                   |
|            |                        | 4        | 60.00                      | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>240.00</b>              | <b>0.00</b>                            |
| <b>114</b> | <b>GHAT PRABHA HPS</b> | 1        | 16.00                      | 54.30                                  |
|            |                        | 2        | 16.00                      | 53.24                                  |
|            | <b>TOTAL</b>           |          | <b>32.00</b>               | <b>53.77</b>                           |
| <b>115</b> | <b>JOG HPS</b>         | 1        | 13.20                      | 0.00                                   |
|            |                        | 2        | 13.20                      | 0.00                                   |
|            |                        | 3        | 13.20                      | 0.00                                   |
|            |                        | 4        | 13.20                      | 0.00                                   |
|            |                        | 5        | 21.60                      | 0.00                                   |
|            |                        | 6        | 21.60                      | 0.26                                   |

| SL.No.     | UTILITY/STATION          | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|--------------------------|----------|----------------------------|----------------------------------------|
|            |                          | 7        | 21.60                      | 0.00                                   |
|            |                          | 8        | 21.60                      | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>139.20</b>              | <b>0.03</b>                            |
| <b>116</b> | <b>KADRA HPS</b>         | 1        | 50.00                      | 65.04                                  |
|            |                          | 2        | 50.00                      | 65.46                                  |
|            |                          | 3        | 50.00                      | 64.35                                  |
|            | <b>TOTAL</b>             |          | <b>150.00</b>              | <b>64.95</b>                           |
| <b>117</b> | <b>KALINADI HPS</b>      | 1        | 150.00                     | 0.00                                   |
|            |                          | 2        | 150.00                     | 0.00                                   |
|            |                          | 3        | 150.00                     | 100.00                                 |
|            |                          | 4        | 150.00                     | 100.00                                 |
|            |                          | 5        | 150.00                     | 0.00                                   |
|            |                          | 6        | 150.00                     | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>900.00</b>              | <b>33.33</b>                           |
| <b>118</b> | <b>KALINADI SUPA HPS</b> | 1        | 50.00                      | 0.02                                   |
|            |                          | 2        | 50.00                      | 0.02                                   |
|            | <b>TOTAL</b>             |          | <b>100.00</b>              | <b>0.02</b>                            |
| <b>119</b> | <b>KODASALI HPS</b>      | 1        | 40.00                      | 37.53                                  |
|            |                          | 2        | 40.00                      | 57.56                                  |
|            |                          | 3        | 40.00                      | 55.76                                  |

| SL.No.     | UTILITY/STATION          | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|--------------------------|----------|----------------------------|----------------------------------------|
|            | <b>TOTAL</b>             |          | <b>120.00</b>              | <b>50.28</b>                           |
| <b>120</b> | <b>LIGANAMAKKI HPS</b>   | 1        | 27.50                      | 0.00                                   |
|            |                          | 2        | 27.50                      | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>55.00</b>               | <b>0.00</b>                            |
| <b>121</b> | <b>MUNIRABAD HPS</b>     | 1        | 9.00                       | 29.97                                  |
|            |                          | 2        | 9.00                       | 34.77                                  |
|            |                          | 3        | 10.00                      | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>28.00</b>               | <b>21.58</b>                           |
| <b>122</b> | <b>SHARAVATHI HPS</b>    | 1        | 103.50                     | 0.00                                   |
|            |                          | 10       | 103.50                     | 0.00                                   |
|            |                          | 2        | 103.50                     | 0.00                                   |
|            |                          | 3        | 103.50                     | 0.00                                   |
|            |                          | 4        | 103.50                     | 0.00                                   |
|            |                          | 5        | 103.50                     | 0.00                                   |
|            |                          | 6        | 103.50                     | 0.00                                   |
|            |                          | 7        | 103.50                     | 0.00                                   |
|            |                          | 8        | 103.50                     | 0.00                                   |
|            |                          | 9        | 103.50                     | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>1035.00</b>             | <b>0.00</b>                            |
| <b>123</b> | <b>SIVASAMUNDRUM HPS</b> | 1        | 3.00                       | 0.00                                   |

| SL.No.     | UTILITY/STATION       | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|-----------------------|----------|----------------------------|----------------------------------------|
|            |                       | 10       | 6.00                       | 0.00                                   |
|            |                       | 2        | 3.00                       | 0.00                                   |
|            |                       | 3        | 3.00                       | 0.00                                   |
|            |                       | 4        | 3.00                       | 0.00                                   |
|            |                       | 5        | 3.00                       | 0.00                                   |
|            |                       | 6        | 3.00                       | 0.00                                   |
|            |                       | 7        | 6.00                       | 0.00                                   |
|            |                       | 8        | 6.00                       | 0.00                                   |
|            |                       | 9        | 6.00                       | 0.00                                   |
|            | <b>TOTAL</b>          |          | <b>42.00</b>               | <b>0.00</b>                            |
| <b>124</b> | <b>VARAHI HPS</b>     | 1        | 115.00                     | 8.34                                   |
|            |                       | 2        | 115.00                     | 18.95                                  |
|            |                       | 3        | 115.00                     | 4.54                                   |
|            |                       | 4        | 115.00                     | 8.74                                   |
|            | <b>TOTAL</b>          |          | <b>460.00</b>              | <b>10.14</b>                           |
|            | <b>KSEB</b>           |          |                            |                                        |
| <b>125</b> | <b>IDAMALAYAR HPS</b> | 1        | 37.50                      | 15.85                                  |
|            |                       | 2        | 37.50                      | 14.51                                  |
|            | <b>TOTAL</b>          |          | <b>75.00</b>               | <b>15.18</b>                           |
| <b>126</b> | <b>IDUKKI HPS</b>     | 1        | 130.00                     | 0.02                                   |

| SL.No.     | UTILITY/STATION            | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|----------------------------|----------|----------------------------|----------------------------------------|
|            |                            | 2        | 130.00                     | 0.00                                   |
|            |                            | 3        | 130.00                     | 0.00                                   |
|            |                            | 4        | 130.00                     | 0.11                                   |
|            |                            | 5        | 130.00                     | 0.50                                   |
|            |                            | 6        | 130.00                     | 0.40                                   |
|            | <b>TOTAL</b>               |          | <b>780.00</b>              | <b>0.17</b>                            |
| <b>127</b> | <b>KAKKAD HPS</b>          | 1        | 25.00                      | 0.00                                   |
|            |                            | 2        | 25.00                      | 0.00                                   |
|            | <b>TOTAL</b>               |          | <b>50.00</b>               | <b>0.00</b>                            |
| <b>128</b> | <b>KUTTIYADI ADDL EXTN</b> | 1        | 50.00                      | 0.74                                   |
|            |                            | 2        | 50.00                      | 0.58                                   |
|            | <b>TOTAL</b>               |          | <b>100.00</b>              | <b>0.66</b>                            |
| <b>129</b> | <b>KUTTIYADI EXTN HPS</b>  | 4        | 50.00                      | 0.38                                   |
|            | <b>TOTAL</b>               |          | <b>50.00</b>               | <b>0.38</b>                            |
| <b>130</b> | <b>KUTTIYADI HPS</b>       | 1        | 25.00                      | 0.73                                   |
|            |                            | 2        | 25.00                      | 0.48                                   |
|            |                            | 3        | 25.00                      | 0.46                                   |
|            | <b>TOTAL</b>               |          | <b>75.00</b>               | <b>0.56</b>                            |
| <b>131</b> | <b>LOWER PERIYAR HPS</b>   | 1        | 60.00                      | 0.00                                   |
|            |                            | 2        | 60.00                      | 0.00                                   |

| SL.No.     | UTILITY/STATION          | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|--------------------------|----------|----------------------------|----------------------------------------|
|            |                          | 3        | 60.00                      | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>180.00</b>              | <b>0.00</b>                            |
| <b>132</b> | <b>NARIAMANGLAM HPS</b>  | 1        | 15.00                      | 0.00                                   |
|            |                          | 2        | 15.00                      | 0.00                                   |
|            |                          | 3        | 15.00                      | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>45.00</b>               | <b>0.00</b>                            |
| <b>133</b> | <b>PALLIVASAL HPS</b>    | 1        | 5.00                       | 0.00                                   |
|            |                          | 2        | 5.00                       | 0.00                                   |
|            |                          | 3        | 5.00                       | 0.00                                   |
|            |                          | 4        | 7.50                       | 0.00                                   |
|            |                          | 5        | 7.50                       | 0.00                                   |
|            |                          | 6        | 7.50                       | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>37.50</b>               | <b>0.00</b>                            |
| <b>134</b> | <b>PANNIAR HPS</b>       | 1        | 15.00                      | 0.00                                   |
|            |                          | 2        | 15.00                      | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>135</b> | <b>PORINGALKUTTU HPS</b> | 1        | 8.00                       | 0.00                                   |
|            |                          | 2        | 8.00                       | 0.00                                   |
|            |                          | 3        | 8.00                       | 0.00                                   |
|            |                          | 4        | 8.00                       | 0.00                                   |

| SL.No.     | UTILITY/STATION       | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|-----------------------|----------|----------------------------|----------------------------------------|
|            | <b>TOTAL</b>          |          | <b>32.00</b>               | <b>0.00</b>                            |
| <b>136</b> | <b>SABARIGIRI HPS</b> | 1        | 50.00                      | 0.09                                   |
|            |                       | 2        | 50.00                      | 0.15                                   |
|            |                       | 3        | 50.00                      | 0.08                                   |
|            |                       | 4        | 50.00                      | 0.00                                   |
|            |                       | 5        | 50.00                      | 0.17                                   |
|            |                       | 6        | 50.00                      | 0.16                                   |
|            | <b>TOTAL</b>          |          | <b>300.00</b>              | <b>0.11</b>                            |
| <b>137</b> | <b>SENGULAM HPS</b>   | 1        | 12.00                      | 0.00                                   |
|            |                       | 2        | 12.00                      | 100.00                                 |
|            |                       | 3        | 12.00                      | 100.00                                 |
|            |                       | 4        | 12.00                      | 100.00                                 |
|            | <b>TOTAL</b>          |          | <b>48.00</b>               | <b>75.00</b>                           |
| <b>138</b> | <b>SHOLAYAR HPS</b>   | 1        | 18.00                      | 0.00                                   |
|            |                       | 2        | 18.00                      | 0.00                                   |
|            |                       | 3        | 18.00                      | 0.00                                   |
|            | <b>TOTAL</b>          |          | <b>54.00</b>               | <b>0.00</b>                            |
|            | <b>TANGEDCO</b>       |          |                            |                                        |
| <b>139</b> | <b>ALIYAR HPS</b>     | 1        | 60.00                      | 0.00                                   |
|            | <b>TOTAL</b>          |          | <b>60.00</b>               | <b>0.00</b>                            |

| SL.No.     | UTILITY/STATION                | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|--------------------------------|----------|----------------------------|----------------------------------------|
| <b>140</b> | <b>BHAWANI BARRAGE-II HPS</b>  | 1        | 15.00                      | 28.19                                  |
|            |                                | 2        | 15.00                      | 22.34                                  |
|            | <b>TOTAL</b>                   |          | <b>30.00</b>               | <b>25.26</b>                           |
| <b>141</b> | <b>BHAWANI BARRAGE-III HPS</b> | 1        | 15.00                      | 0.00                                   |
|            |                                | 2        | 15.00                      | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>142</b> | <b>BHAWANI KATTAL</b>          | 1        | 15.00                      | 0.00                                   |
|            |                                | 2        | 15.00                      | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>143</b> | <b>KADAMPARI HPS</b>           | 1        | 100.00                     | 0.00                                   |
|            |                                | 2        | 100.00                     | 0.00                                   |
|            |                                | 3        | 100.00                     | 0.00                                   |
|            |                                | 4        | 100.00                     | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>400.00</b>              | <b>0.00</b>                            |
| <b>144</b> | <b>KODAYAR-I HPS</b>           | 1        | 60.00                      | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>60.00</b>               | <b>0.00</b>                            |
| <b>145</b> | <b>KODAYAR-II HPS</b>          | 2        | 40.00                      | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>40.00</b>               | <b>0.00</b>                            |
| <b>146</b> | <b>KUNDAH-I HPS</b>            | 1        | 20.00                      | 0.00                                   |
|            |                                | 2        | 20.00                      | 0.00                                   |

| SL.No.     | UTILITY/STATION           | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|---------------------------|----------|----------------------------|----------------------------------------|
|            |                           | 3        | 20.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>60.00</b>               | <b>0.00</b>                            |
| <b>147</b> | <b>KUNDAH-II HPS</b>      | 4        | 35.00                      | 0.00                                   |
|            |                           | 5        | 35.00                      | 0.00                                   |
|            |                           | 6        | 35.00                      | 0.00                                   |
|            |                           | 7        | 35.00                      | 0.00                                   |
|            |                           | 8        | 35.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>175.00</b>              | <b>0.00</b>                            |
| <b>148</b> | <b>KUNDAH-III HPS</b>     | 10       | 60.00                      | 0.00                                   |
|            |                           | 11       | 60.00                      | 0.00                                   |
|            |                           | 9        | 60.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>180.00</b>              | <b>0.00</b>                            |
| <b>149</b> | <b>KUNDAH-IV HPS</b>      | 12       | 50.00                      | 0.00                                   |
|            |                           | 13       | 50.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>100.00</b>              | <b>0.00</b>                            |
| <b>150</b> | <b>KUNDAH-V HPS</b>       | 14       | 20.00                      | 0.00                                   |
|            |                           | 15       | 20.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>40.00</b>               | <b>0.00</b>                            |
| <b>151</b> | <b>LOWER METTUR-I HPS</b> | 1        | 15.00                      | 0.00                                   |
|            |                           | 2        | 15.00                      | 0.00                                   |

| SL.No.     | UTILITY/STATION             | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|-----------------------------|----------|----------------------------|----------------------------------------|
|            | <b>TOTAL</b>                |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>152</b> | <b>LOWER METTUR-II HPS</b>  | 3        | 15.00                      | 0.00                                   |
|            |                             | 4        | 15.00                      | 0.00                                   |
|            | <b>TOTAL</b>                |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>153</b> | <b>LOWER METTUR-III HPS</b> | 5        | 15.00                      | 0.00                                   |
|            |                             | 6        | 15.00                      | 0.00                                   |
|            | <b>TOTAL</b>                |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>154</b> | <b>LOWER METTUR-IV HPS</b>  | 7        | 15.00                      | 0.00                                   |
|            |                             | 8        | 15.00                      | 0.00                                   |
|            | <b>TOTAL</b>                |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>155</b> | <b>METTUR DAM HPS</b>       | 1        | 12.50                      | 38.33                                  |
|            |                             | 2        | 12.50                      | 65.80                                  |
|            |                             | 3        | 12.50                      | 45.24                                  |
|            |                             | 4        | 12.50                      | 32.58                                  |
|            | <b>TOTAL</b>                |          | <b>50.00</b>               | <b>45.49</b>                           |
| <b>156</b> | <b>METTUR TUNNEL HPS</b>    | 1        | 50.00                      | 24.38                                  |
|            |                             | 2        | 50.00                      | 30.99                                  |
|            |                             | 3        | 50.00                      | 41.19                                  |
|            |                             | 4        | 50.00                      | 20.64                                  |
|            | <b>TOTAL</b>                |          | <b>200.00</b>              | <b>29.30</b>                           |

| SL.No.     | UTILITY/STATION            | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|----------------------------|----------|----------------------------|----------------------------------------|
| <b>157</b> | <b>MOYAR HPS</b>           | 1        | 12.00                      | 0.00                                   |
|            |                            | 2        | 12.00                      | 0.00                                   |
|            |                            | 3        | 12.00                      | 0.00                                   |
|            | <b>TOTAL</b>               |          | <b>36.00</b>               | <b>0.00</b>                            |
| <b>158</b> | <b>PAPANASAM HPS</b>       | 1        | 8.00                       | 0.00                                   |
|            |                            | 2        | 8.00                       | 0.00                                   |
|            |                            | 3        | 8.00                       | 0.00                                   |
|            |                            | 4        | 8.00                       | 0.00                                   |
|            | <b>TOTAL</b>               |          | <b>32.00</b>               | <b>0.00</b>                            |
| <b>159</b> | <b>PARSON'S VALLEY HPS</b> | 1        | 30.00                      | 0.00                                   |
|            | <b>TOTAL</b>               |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>160</b> | <b>PERIYAR HPS</b>         | 1        | 42.00                      | 0.00                                   |
|            |                            | 2        | 42.00                      | 0.00                                   |
|            |                            | 3        | 42.00                      | 0.00                                   |
|            |                            | 4        | 35.00                      | 0.00                                   |
|            | <b>TOTAL</b>               |          | <b>161.00</b>              | <b>0.00</b>                            |
| <b>161</b> | <b>PYKARA HPS</b>          | 1        | 7.00                       | 0.00                                   |
|            |                            | 2        | 7.00                       | 0.00                                   |
|            |                            | 3        | 7.00                       | 0.00                                   |
|            |                            | 4        | 13.60                      | 0.00                                   |

| SL.No.     | UTILITY/STATION           | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|---------------------------|----------|----------------------------|----------------------------------------|
|            |                           | 5        | 13.60                      | 0.00                                   |
|            |                           | 6        | 11.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>59.20</b>               | <b>0.00</b>                            |
| <b>162</b> | <b>PYKARA ULTMATE HPS</b> | 1        | 50.00                      | 0.00                                   |
|            |                           | 2        | 50.00                      | 0.00                                   |
|            |                           | 3        | 50.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>150.00</b>              | <b>0.00</b>                            |
| <b>163</b> | <b>SARKARPATHY HPS</b>    | 1        | 30.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>30.00</b>               | <b>0.00</b>                            |
| <b>164</b> | <b>SHOLAYAR HPS (TN)</b>  | 1        | 35.00                      | 0.00                                   |
|            |                           | 2        | 35.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>70.00</b>               | <b>0.00</b>                            |
| <b>165</b> | <b>SURULIYAR HPS</b>      | 1        | 35.00                      | 0.00                                   |
|            | <b>TOTAL</b>              |          | <b>35.00</b>               | <b>0.00</b>                            |
|            | <b>TSGENCO</b>            |          |                            |                                        |
| <b>166</b> | <b>LOWER JURALA HPS</b>   | 1        | 40.00                      | 41.64                                  |
|            |                           | 2        | 40.00                      | 31.64                                  |
|            |                           | 3        | 40.00                      | 40.54                                  |
|            |                           | 4        | 40.00                      | 33.70                                  |
|            |                           | 5        | 40.00                      | 68.22                                  |

| SL.No.     | UTILITY/STATION                | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|--------------------------------|----------|----------------------------|----------------------------------------|
|            |                                | 6        | 40.00                      | 55.89                                  |
|            | <b>TOTAL</b>                   |          | <b>240.00</b>              | <b>45.27</b>                           |
| <b>167</b> | <b>NAGARJUN SGR HPS</b>        | 1        | 110.00                     | 23.83                                  |
|            |                                | 2        | 100.80                     | 37.07                                  |
|            |                                | 3        | 100.80                     | 15.26                                  |
|            |                                | 4        | 100.80                     | 21.31                                  |
|            |                                | 5        | 100.80                     | 11.78                                  |
|            |                                | 6        | 100.80                     | 23.01                                  |
|            |                                | 7        | 100.80                     | 28.69                                  |
|            |                                | 8        | 100.80                     | 44.76                                  |
|            | <b>TOTAL</b>                   |          | <b>815.60</b>              | <b>25.71</b>                           |
| <b>168</b> | <b>NAGARJUN SGR LBC HPS</b>    | 1        | 30.00                      | 50.96                                  |
|            |                                | 2        | 30.00                      | 40.27                                  |
|            | <b>TOTAL</b>                   |          | <b>60.00</b>               | <b>45.62</b>                           |
| <b>169</b> | <b>POCHAMPAD HPS</b>           | 1        | 9.00                       | 44.38                                  |
|            |                                | 2        | 9.00                       | 44.67                                  |
|            |                                | 3        | 9.00                       | 50.13                                  |
|            |                                | 4        | 9.00                       | 51.23                                  |
|            | <b>TOTAL</b>                   |          | <b>36.00</b>               | <b>47.60</b>                           |
| <b>170</b> | <b>PRIYADARSHNI JURALA HPS</b> | 1        | 39.00                      | 29.04                                  |

| SL.No.     | UTILITY/STATION         | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|-------------------------|----------|----------------------------|----------------------------------------|
|            |                         | 2        | 39.00                      | 34.25                                  |
|            |                         | 3        | 39.00                      | 35.89                                  |
|            |                         | 4        | 39.00                      | 33.15                                  |
|            |                         | 5        | 39.00                      | 0.00                                   |
|            |                         | 6        | 39.00                      | 43.01                                  |
|            | <b>TOTAL</b>            |          | <b>234.00</b>              | <b>29.22</b>                           |
| <b>171</b> | <b>PULICHINTALA HPS</b> | 1        | 30.00                      | 44.38                                  |
|            |                         | 2        | 30.00                      | 44.93                                  |
|            |                         | 3        | 30.00                      | 17.26                                  |
|            |                         | 4        | 30.00                      | 33.42                                  |
|            | <b>TOTAL</b>            |          | <b>120.00</b>              | <b>35.00</b>                           |
| <b>172</b> | <b>SRISAILAM LB HPS</b> | 1        | 150.00                     | 23.23                                  |
|            |                         | 2        | 150.00                     | 23.01                                  |
|            |                         | 3        | 150.00                     | 18.63                                  |
|            |                         | 4        | 150.00                     | 100.00                                 |
|            |                         | 5        | 150.00                     | 26.57                                  |
|            |                         | 6        | 150.00                     | 37.28                                  |
|            | <b>TOTAL</b>            |          | <b>900.00</b>              | <b>38.12</b>                           |
|            | <b>Eastern</b>          |          |                            |                                        |
|            | <b>APGENCO</b>          |          |                            |                                        |

| SL.No.     | UTILITY/STATION       | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|-----------------------|----------|----------------------------|----------------------------------------|
| <b>173</b> | <b>MACHKUND HPS</b>   | 1        | 17.00                      | 0.00                                   |
|            |                       | 2        | 17.00                      | 0.00                                   |
|            |                       | 3        | 17.00                      | 0.00                                   |
|            |                       | 4        | 21.25                      | 0.00                                   |
|            |                       | 5        | 21.25                      | 0.00                                   |
|            |                       | 6        | 21.25                      | 0.00                                   |
|            | <b>TOTAL</b>          |          | <b>114.75</b>              | <b>0.00</b>                            |
|            | <b>DEPL</b>           |          |                            |                                        |
| <b>174</b> | <b>JORETHANG LOOP</b> | 1        | 48.00                      | 1.23                                   |
|            |                       | 2        | 48.00                      | 0.93                                   |
|            | <b>TOTAL</b>          |          | <b>96.00</b>               | <b>1.08</b>                            |
|            | <b>DVC</b>            |          |                            |                                        |
| <b>175</b> | <b>MAITHON HPS</b>    | 1        | 20.00                      | 43.78                                  |
|            |                       | 2        | 23.20                      | 7.66                                   |
|            |                       | 3        | 20.00                      | 16.02                                  |
|            | <b>TOTAL</b>          |          | <b>63.20</b>               | <b>22.49</b>                           |
| <b>176</b> | <b>PANCHET HPS</b>    | 1        | 40.00                      | 0.00                                   |
|            |                       | 2        | 40.00                      | 0.00                                   |
|            | <b>TOTAL</b>          |          | <b>80.00</b>               | <b>0.00</b>                            |
|            | <b>GIPL</b>           |          |                            |                                        |

| SL.No.     | UTILITY/STATION               | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|-------------------------------|----------|----------------------------|----------------------------------------|
| <b>177</b> | <b>CHUZACHEN HPS</b>          | 1        | 55.00                      | 44.42                                  |
|            |                               | 2        | 55.00                      | 44.67                                  |
|            | <b>TOTAL</b>                  |          | <b>110.00</b>              | <b>44.55</b>                           |
|            | <b>JUUNL</b>                  |          |                            |                                        |
| <b>178</b> | <b>SUBERNREKHA-I HPS</b>      | 1        | 65.00                      | 0.00                                   |
|            | <b>TOTAL</b>                  |          | <b>65.00</b>               | <b>0.00</b>                            |
| <b>179</b> | <b>SUBERNREKHA-II HPS</b>     | 2        | 65.00                      | 0.00                                   |
|            | <b>TOTAL</b>                  |          | <b>65.00</b>               | <b>0.00</b>                            |
|            | <b>MBPC</b>                   |          |                            |                                        |
| <b>180</b> | <b>RONGNICHU HPS</b>          | 1        | 56.50                      | 13.88                                  |
|            |                               | 2        | 56.50                      | 14.40                                  |
|            | <b>TOTAL</b>                  |          | <b>113.00</b>              | <b>14.14</b>                           |
|            | <b>NHPC</b>                   |          |                            |                                        |
| <b>181</b> | <b>RANGIT HPS</b>             | 1        | 20.00                      | 27.59                                  |
|            |                               | 2        | 20.00                      | 19.45                                  |
|            |                               | 3        | 20.00                      | 26.49                                  |
|            | <b>TOTAL</b>                  |          | <b>60.00</b>               | <b>24.51</b>                           |
| <b>182</b> | <b>TEESTA LOW DAM-III HPS</b> | 1        | 33.00                      | 46.24                                  |
|            |                               | 2        | 33.00                      | 35.90                                  |
|            |                               | 3        | 33.00                      | 46.28                                  |

| SL.No.     | UTILITY/STATION              | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|------------------------------|----------|----------------------------|----------------------------------------|
|            |                              | 4        | 33.00                      | 32.69                                  |
|            | <b>TOTAL</b>                 |          | <b>132.00</b>              | <b>40.28</b>                           |
| <b>183</b> | <b>TEESTA LOW DAM-IV HPS</b> | 1        | 40.00                      | 43.89                                  |
|            |                              | 2        | 40.00                      | 37.00                                  |
|            |                              | 3        | 40.00                      | 31.30                                  |
|            |                              | 4        | 40.00                      | 41.72                                  |
|            | <b>TOTAL</b>                 |          | <b>160.00</b>              | <b>38.48</b>                           |
| <b>184</b> | <b>TEESTA V HPS</b>          | 1        | 170.00                     | 33.59                                  |
|            |                              | 2        | 170.00                     | 45.53                                  |
|            |                              | 3        | 170.00                     | 32.16                                  |
|            | <b>TOTAL</b>                 |          | <b>510.00</b>              | <b>37.09</b>                           |
|            | <b>OHPC</b>                  |          |                            |                                        |
| <b>185</b> | <b>BALIMELA HPS</b>          | 1        | 60.00                      | 0.00                                   |
|            |                              | 2        | 60.00                      | 0.00                                   |
|            |                              | 3        | 60.00                      | 0.00                                   |
|            |                              | 4        | 60.00                      | 0.00                                   |
|            |                              | 5        | 60.00                      | 0.00                                   |
|            |                              | 6        | 60.00                      | 0.00                                   |
|            |                              | 7        | 75.00                      | 0.00                                   |
|            |                              | 8        | 75.00                      | 0.00                                   |

| SL.No.     | UTILITY/STATION            | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|----------------------------|----------|----------------------------|----------------------------------------|
|            | <b>TOTAL</b>               |          | <b>510.00</b>              | <b>0.00</b>                            |
| <b>186</b> | <b>CHIJIMA HPS</b>         | 1        | 24.00                      | 0.00                                   |
|            |                            | 2        | 24.00                      | 0.00                                   |
|            |                            | 3        | 24.00                      | 0.00                                   |
|            | <b>TOTAL</b>               |          | <b>72.00</b>               | <b>0.00</b>                            |
| <b>187</b> | <b>HIRAKUD HPS</b>         | 1        | 49.50                      | 0.00                                   |
|            |                            | 2        | 49.50                      | 0.00                                   |
|            |                            | 3        | 32.00                      | 0.00                                   |
|            |                            | 4        | 32.00                      | 0.00                                   |
|            |                            | 5        | 43.65                      | 0.00                                   |
|            |                            | 6        | 43.65                      | 0.00                                   |
|            |                            | 7        | 37.50                      | 0.00                                   |
|            | <b>TOTAL</b>               |          | <b>287.80</b>              | <b>0.00</b>                            |
| <b>188</b> | <b>RENGALI HPS</b>         | 1        | 50.00                      | 0.00                                   |
|            |                            | 2        | 50.00                      | 0.00                                   |
|            |                            | 3        | 50.00                      | 0.00                                   |
|            |                            | 4        | 50.00                      | 0.00                                   |
|            |                            | 5        | 50.00                      | 0.00                                   |
|            | <b>TOTAL</b>               |          | <b>250.00</b>              | <b>0.00</b>                            |
| <b>189</b> | <b>UPPER INDRAVATI HPS</b> | 1        | 150.00                     | 0.00                                   |

| SL.No.     | UTILITY/STATION        | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|------------------------|----------|----------------------------|----------------------------------------|
|            |                        | 2        | 150.00                     | 0.00                                   |
|            |                        | 3        | 150.00                     | 0.00                                   |
|            |                        | 4        | 150.00                     | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>600.00</b>              | <b>0.00</b>                            |
| <b>190</b> | <b>UPPER KOLAB HPS</b> | 1        | 80.00                      | 0.00                                   |
|            |                        | 2        | 80.00                      | 0.00                                   |
|            |                        | 3        | 80.00                      | 0.00                                   |
|            |                        | 4        | 80.00                      | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>320.00</b>              | <b>0.00</b>                            |
|            | <b>SEPL</b>            |          |                            |                                        |
| <b>191</b> | <b>TASHIDING HPS</b>   | 1        | 48.50                      | 0.00                                   |
|            |                        | 2        | 48.50                      | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>97.00</b>               | <b>0.00</b>                            |
|            | <b>SKPPPL</b>          |          |                            |                                        |
| <b>192</b> | <b>DIKCHU HPS</b>      | 1        | 48.00                      | 0.00                                   |
|            |                        | 2        | 48.00                      | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>96.00</b>               | <b>0.00</b>                            |
|            | <b>TUL</b>             |          |                            |                                        |
| <b>193</b> | <b>TEESTA-III HPS</b>  | 1        | 200.00                     | 0.21                                   |
|            |                        | 2        | 200.00                     | 0.26                                   |

| SL.No.     | UTILITY/STATION          | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|--------------------------|----------|----------------------------|----------------------------------------|
|            |                          | 3        | 200.00                     | 0.24                                   |
|            |                          | 4        | 200.00                     | 0.21                                   |
|            |                          | 5        | 200.00                     | 0.21                                   |
|            |                          | 6        | 200.00                     | 0.20                                   |
|            | <b>TOTAL</b>             |          | <b>1200.00</b>             | <b>0.22</b>                            |
|            | <b>WBSEDCL</b>           |          |                            |                                        |
| <b>194</b> | <b>JALDHAKA HPS ST-I</b> | 1        | 9.00                       | 0.00                                   |
|            |                          | 2        | 9.00                       | 0.00                                   |
|            |                          | 3        | 9.00                       | 0.00                                   |
|            |                          | 4        | 9.00                       | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>36.00</b>               | <b>0.00</b>                            |
| <b>195</b> | <b>PURULIA PSS HPS</b>   | 1        | 225.00                     | 0.00                                   |
|            |                          | 2        | 225.00                     | 0.00                                   |
|            |                          | 3        | 225.00                     | 0.00                                   |
|            |                          | 4        | 225.00                     | 0.00                                   |
|            | <b>TOTAL</b>             |          | <b>900.00</b>              | <b>0.00</b>                            |
| <b>196</b> | <b>RAMMAM HPS</b>        | 1        | 12.50                      | 0.00                                   |
|            |                          | 2        | 12.50                      | 0.00                                   |
|            |                          | 3        | 12.50                      | 0.00                                   |
|            |                          | 4        | 12.50                      | 0.00                                   |

| SL.No.     | UTILITY/STATION                | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|--------------------------------|----------|----------------------------|----------------------------------------|
|            | <b>TOTAL</b>                   |          | <b>50.00</b>               | <b>0.00</b>                            |
|            | North Eastern                  |          |                            |                                        |
|            | APGCL                          |          |                            |                                        |
| <b>197</b> | <b>KARBI LANGPI HPS</b>        | 1        | 50.00                      | 0.00                                   |
|            |                                | 2        | 50.00                      | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>100.00</b>              | <b>0.00</b>                            |
|            | MeECL                          |          |                            |                                        |
| <b>198</b> | <b>KYRDEMKULAI HPS</b>         | 1        | 30.00                      | 0.00                                   |
|            |                                | 2        | 30.00                      | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>60.00</b>               | <b>0.00</b>                            |
| <b>199</b> | <b>MYNTDU(LESHKA) St-1 HPS</b> | 1        | 42.00                      | 0.00                                   |
|            |                                | 2        | 42.00                      | 0.00                                   |
|            |                                | 3        | 42.00                      | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>126.00</b>              | <b>0.00</b>                            |
| <b>200</b> | <b>NEW UMTRU HPS</b>           | 1        | 20.00                      | 0.00                                   |
|            |                                | 2        | 20.00                      | 0.00                                   |
|            | <b>TOTAL</b>                   |          | <b>40.00</b>               | <b>0.00</b>                            |
| <b>201</b> | <b>UMIAM HPS ST-I</b>          | 1        | 9.00                       | 0.00                                   |
|            |                                | 2        | 9.00                       | 0.00                                   |
|            |                                | 3        | 9.00                       | 0.00                                   |

| SL.No.     | UTILITY/STATION        | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|------------------------|----------|----------------------------|----------------------------------------|
|            |                        | 4        | 9.00                       | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>36.00</b>               | <b>0.00</b>                            |
| <b>202</b> | <b>UMIAM HPS ST-IV</b> | 7        | 30.00                      | 0.00                                   |
|            |                        | 8        | 30.00                      | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>60.00</b>               | <b>0.00</b>                            |
|            | <b>NEEPCO.</b>         |          |                            |                                        |
| <b>203</b> | <b>DOYANG HPS</b>      | 1        | 25.00                      | 13.39                                  |
|            |                        | 2        | 25.00                      | 9.92                                   |
|            |                        | 3        | 25.00                      | 5.34                                   |
|            | <b>TOTAL</b>           |          | <b>75.00</b>               | <b>9.55</b>                            |
| <b>204</b> | <b>KAMENG HPS</b>      | 1        | 150.00                     | 0.00                                   |
|            |                        | 2        | 150.00                     | 0.08                                   |
|            |                        | 3        | 150.00                     | 0.05                                   |
|            |                        | 4        | 150.00                     | 0.00                                   |
|            | <b>TOTAL</b>           |          | <b>600.00</b>              | <b>0.03</b>                            |
| <b>205</b> | <b>KHONDONG HPS</b>    | 1        | 25.00                      | 0.45                                   |
|            |                        | 2        | 25.00                      | 0.02                                   |
|            | <b>TOTAL</b>           |          | <b>50.00</b>               | <b>0.23</b>                            |
| <b>206</b> | <b>KOPILI HPS</b>      | 1        | 50.00                      | 0.00                                   |
|            |                        | 2        | 50.00                      | 0.00                                   |

| SL.No.     | UTILITY/STATION      | UNIT No. | INSTALLED<br>CAPACITY (MW) | MISCELLANEOUS NON-<br>AVAILABILITY (%) |
|------------|----------------------|----------|----------------------------|----------------------------------------|
|            |                      | 3        | 50.00                      | 0.00                                   |
|            |                      | 4        | 50.00                      | 0.00                                   |
|            | <b>TOTAL</b>         |          | <b>200.00</b>              | <b>0.00</b>                            |
| <b>207</b> | <b>PARE</b>          | 1        | 55.00                      | 0.00                                   |
|            |                      | 2        | 55.00                      | 0.00                                   |
|            | <b>TOTAL</b>         |          | <b>110.00</b>              | <b>0.00</b>                            |
| <b>208</b> | <b>RANGANADI HPS</b> | 1        | 135.00                     | 0.74                                   |
|            |                      | 2        | 135.00                     | 1.10                                   |
|            |                      | 3        | 135.00                     | 0.55                                   |
|            | <b>TOTAL</b>         |          | <b>405.00</b>              | <b>0.80</b>                            |
| <b>209</b> | <b>TUIRIAL HPS</b>   | 1        | 30.00                      | 5.60                                   |
|            |                      | 2        | 30.00                      | 6.94                                   |
|            | <b>TOTAL</b>         |          | <b>60.00</b>               | <b>6.27</b>                            |
|            | <b>NHPC</b>          |          |                            |                                        |
| <b>210</b> | <b>LOKTAK HPS</b>    | 1        | 35.00                      | 51.06                                  |
|            |                      | 2        | 35.00                      | 53.52                                  |
|            |                      | 3        | 35.00                      | 48.96                                  |
|            | <b>TOTAL</b>         |          | <b>105.00</b>              | <b>51.18</b>                           |

# CHAPTER-8

## GENERATION PROGRAMME FOR THE YEAR 2019-20

## CHAPTER 8

### GENERATION PROGRAMME FOR THE YEAR 2022-23

**8.1** As on 31.03.2022, 210 HE Stations (of more than 25 MW capacity) having total installed capacity of 46722.50 MW are being monitored in the country. With the addition of new hydro units during 2022-23, the anticipated installed capacity of H.E. Stations in the country is likely to be 46850.17 MW by 31<sup>st</sup> March, 2023. The overall Generation Programme for H.E. stations for the year 2022-23 has been fixed at 158667 MU comprising 150661 MU from HE Stations in India and 8000 MU import from Bhutan, which is 1340.5 MU less than actual generation during 2021-22 (i.e.159120.5 MU comprising 151627.33 MU from HE Stations in India and 7493.20 MU import from Bhutan).

**8.2** Region-wise summary of likely installed capacity as on 31.03.2023, Generation targets for 2022-23 and the hydro generation during 2021-22 are given in **Table 7.1** below:

**TABLE 8.1**

#### REGION-WISE LIKELY INSTALLED CAPACITY OF HE STATIONS AND HYDRO GENERATION PROGRAMME DURING 2022-23

| Sl. No.                             | Region               | Likely Hydro Installed Capacity (as on 31.03.2023) (MW) | Hydro Generation Programme for 2022-23 (MU) | Hydro Generation during 2021-22 (MU) |           |
|-------------------------------------|----------------------|---------------------------------------------------------|---------------------------------------------|--------------------------------------|-----------|
|                                     |                      |                                                         |                                             | Programme                            | Actual    |
| 1.                                  | Northern             | 19696.27                                                | 76249                                       | 75684.00                             | 73866.02  |
| 2.                                  | Western              | 7392                                                    | 15461                                       | 16042.00                             | 13719.74  |
| 3.                                  | Southern             | 11747.15                                                | 30511                                       | 30439.00                             | 37206.43  |
| 4.                                  | Eastern              | 5987.75                                                 | 20104                                       | 20540.00                             | 20462.33  |
| 5.                                  | North-Eastern        | 2027                                                    | 8342                                        | 6839.00                              | 6372.81   |
| Sub total                           |                      | 46850.17                                                | 150667                                      | 149544                               | 151627.33 |
| 6.                                  | Import – from Bhutan |                                                         | 8000                                        | 8236                                 | 7493.20   |
| Total(Including Import from Bhutan) |                      |                                                         | 158667                                      | 157780                               | 159120.5  |

**8.3** While finalizing the Generation Programme for 2022-23 during last quarter of 2021-22, it was anticipated that 8 nos. H.E. units having installed capacity of 1860 MW would be added during the year 2022-23 and last quarter of 2021-22. Unit-wise details of these units are given in **Annex-8.1**.

**8.4** Sector-wise and Utility-wise details of likely installed Capacity as on 31.03.2023, targets and actual generation during 2021-22, generation target for 2022-23 are given in **Annex-8.2**.

**Generation from Hydro Electric Projects likely to be commissioned in  
2022-23 and during last quarter of 2021-22**

| S. No.                            | Name of Hydro Power Project              | Unit No. | Present Likely date of commissioning as per CEA/Utility | I.C (MW)    | Generation on Target 2021-22 | Generation Target 2022-23 | Present Capacity Addition Programme during |
|-----------------------------------|------------------------------------------|----------|---------------------------------------------------------|-------------|------------------------------|---------------------------|--------------------------------------------|
| <b>Central Sector</b>             |                                          |          |                                                         |             |                              |                           |                                            |
| 1                                 | Lower Subansiri (NHPC-Arunachal Pradesh) | 1 & 2    | Unit-1 & 2 (Aug 22)                                     | 500         | 0                            | 1205                      | 2022-23                                    |
| 2                                 | Parbati-II (NHPC-Himachal Pradesh)       | 1 to 4   | U- 1 to 4 (Mar 2023)                                    | 800         | 450                          | 320                       | 2022-23                                    |
| 3                                 | Naitwar Mori                             | 1&2      | U- 1 & 2 (Jun, 2022)                                    | 60          | 30                           | 23                        | 2022-23                                    |
| <b>Sub Total (Central Sector)</b> |                                          |          |                                                         | <b>1360</b> | <b>480</b>                   | <b>1548</b>               |                                            |
| <b>State Sector</b>               |                                          |          |                                                         |             |                              |                           |                                            |
| 1                                 | Vyasi (UJVNL-Uttarakhand)                | 1&2      | U- 1 & 2 (Mar, 2022)                                    | 120         | 0                            | 353                       | 2021-22                                    |
| 2                                 | Pallivasal (KSEBL-Kerala)                | 1&2      | U- 1& 2 (Dec 2022)                                      | 60          | 0                            | 30                        | 2022-23                                    |
| 3                                 | Thottiyar (KSEBL-Kerala)                 | 1&2      | U- 1& 2 (Dec 2022)                                      | 40          | 0                            | 15                        | 2022-23                                    |
| <b>Sub Total (State Sector)</b>   |                                          |          |                                                         | <b>220</b>  | <b>0</b>                     | <b>398</b>                |                                            |

|                       |                                   |        |                      |             |            |             |         |
|-----------------------|-----------------------------------|--------|----------------------|-------------|------------|-------------|---------|
| <b>Private Sector</b> |                                   |        |                      |             |            |             |         |
| 1                     | Bajoli Holi (GMR-HP)              | 1 to 3 | U- 1 to 3 (Dec 2021) | 180         | 273        | 500         | 2021-22 |
| 2                     | Tindong (Statkraft-HP)            | 1&2    | U- 1& 2 (Oct 2022)   | 100         | 0          | 50          | 2022-23 |
|                       | <b>Sub Total (Private Sector)</b> |        |                      | <b>280</b>  | <b>273</b> | <b>550</b>  |         |
| <b>Grand Total</b>    |                                   |        |                      | <b>1860</b> | <b>753</b> | <b>2496</b> |         |

**SECTOR-WISE PERFORMANCE OF HYDROELECTRIC STATIONS  
DURING 2021-2022 & TARGETS FOR 2022-2023**

| SECTOR/<br>UTILITY                       | Likely Hydro<br>Installed<br>Capacity<br>as on 31.03.2023 | Generation during<br>2021-2022 (MU) |          | Generation<br>Programme for<br>2022-23<br>(MU) |
|------------------------------------------|-----------------------------------------------------------|-------------------------------------|----------|------------------------------------------------|
|                                          |                                                           | Targets                             | Actual   |                                                |
| A. CENTRAL SECTOR                        |                                                           |                                     |          |                                                |
| BBMB                                     | 2938.3                                                    | 9650                                | 9794.82  | 9650.00                                        |
| NHPC Ltd                                 | 5451.2                                                    | 26000                               | 24382.6  | 25663.00                                       |
| SJVN Ltd                                 | 1912.02                                                   | 9111                                | 9048.61  | 8888.14                                        |
| NTPC Ltd                                 | 800                                                       | 3100                                | 3120.14  | 3099.90                                        |
| THDC Ltd                                 | 1400.00                                                   | 4160                                | 4288.75  | 4162.00                                        |
| NHDC Ltd.                                | 1520.00                                                   | 3900                                | 2645.41  | 3265.00                                        |
| DVC                                      | 143.20                                                    | 215                                 | 466.89   | 290.00                                         |
| NEEPCO Ltd.                              | 1500.00                                                   | 4908                                | 4674.39  | 6356.00                                        |
| Sub Total                                | 15664.72                                                  | 61044                               | 58421.61 | 61374.04                                       |
| B. STATE ELECTRICITY BOARDS/CORPORATIONS |                                                           |                                     |          |                                                |
| JKSPDCL                                  | 1110                                                      | 4887                                | 5116.09  | 4866                                           |
| HPPCL                                    | 406                                                       | 821                                 | 649.55   | 772                                            |
| HPSEBL                                   | 372                                                       | 1603                                | 1768.66  | 1628                                           |
| BVPC                                     | 0                                                         | 0                                   | 0        | 0                                              |
| RRVUNL                                   | 411                                                       | 370                                 | 481.84   | 480                                            |
| PSPCL                                    | 1051                                                      | 3969                                | 3007.86  | 3780                                           |
| UPJVNL                                   | 501.6                                                     | 1519                                | 1402.68  | 1519                                           |
| UJVNL                                    | 1372.15                                                   | 4612                                | 4987.18  | 5035                                           |
| SSNNL                                    | 1450                                                      | 2832                                | 1748.01  | 3099                                           |
| GSECL                                    | 540                                                       | 889                                 | 873.5    | 965                                            |
| MAHAGENCO                                | 2406                                                      | 4109                                | 4078.97  | 3963                                           |
| MPPGCL                                   | 875                                                       | 2526                                | 2345.79  | 2389                                           |
| CSPGCL                                   | 120                                                       | 280                                 | 404.13   | 274                                            |
| APGENCO                                  | 1796.75                                                   | 3636                                | 4037.32  | 3600                                           |
| TSGENCO                                  | 2405.6                                                    | 4018                                | 5626.63  | 3852                                           |
| KPCL                                     | 3617.2                                                    | 12409                               | 13731.48 | 12337                                          |
| KSEBL                                    | 1864.15                                                   | 6505                                | 9317.44  | 7414                                           |
| TANGEDCO                                 | 2178.2                                                    | 4483                                | 5212.07  | 3913                                           |
| JUUNL                                    | 130                                                       | 110                                 | 302.49   | 110                                            |
| OHPC                                     | 2039.80                                                   | 5959                                | 4512.12  | 5363                                           |
| TUL                                      | 1200                                                      | 5652                                | 6315.53  | 5652                                           |
| WBSEDCL                                  | 986                                                       | 1578                                | 1630.14  | 1550                                           |
| APGCL                                    | 100                                                       | 380                                 | 401.12   | 380                                            |
| MePGCL                                   | 322                                                       | 1051                                | 841.82   | 1106                                           |
| Sub Total                                | 27254.45                                                  | 74198                               | 78792.42 | 74047                                          |

| SECTOR/<br>UTILITY                                  | Likely Hydro<br>Installed<br>Capacity<br>as on 31.03.2023 | Generation during<br>2021-2022 (MU) |           | Generation<br>Programme for<br>2022-23<br>(MU) |
|-----------------------------------------------------|-----------------------------------------------------------|-------------------------------------|-----------|------------------------------------------------|
|                                                     |                                                           | Targets                             | Actual    |                                                |
| C. PRIVATE SECTOR                                   |                                                           |                                     |           |                                                |
| MPCL                                                | 86.00                                                     | 344                                 | 314.96    | 336.00                                         |
| EPPL                                                | 100.00                                                    | 367                                 | 345.66    | 348.00                                         |
| ADHPL                                               | 192.00                                                    | 676                                 | 637.44    | 658.00                                         |
| GBHPPL                                              | 70.00                                                     | 270                                 | 251.37    | 293.00                                         |
| JSW ENERGY                                          | 1345.00                                                   | 5431                                | 5563.8    | 5431.00                                        |
| IAEPL                                               | 36.00                                                     | 158                                 | 146.54    | 158.00                                         |
| AHPC LTD                                            | 330.00                                                    | 1310                                | 1421.89   | 500.00                                         |
| JPVL                                                | 400.00                                                    | 1590                                | 1801.24   | 392.00                                         |
| DLHP                                                | 34.00                                                     | 36                                  | 33.94     | 50.00                                          |
| GIPL                                                | 110.00                                                    | 500                                 | 514.21    | 1310.00                                        |
| TPCL                                                | 447.00                                                    | 1470                                | 1589.99   | 1590.00                                        |
| DEPL                                                | 96.00                                                     | 408                                 | 424.69    | 402.00                                         |
| SEPL                                                | 97.00                                                     | 421                                 | 453.07    | 36.00                                          |
| SNEHA KINETIC                                       | 96.00                                                     | 460                                 | 481.45    | 537.00                                         |
| NTPGPL                                              | 0.00                                                      | 0                                   | 0         | 1470.00                                        |
| HSPPL                                               | 100.00                                                    | 39                                  | 57.18     | 412.00                                         |
| L&T                                                 | 99.00                                                     | 293                                 | 80.44     | 421.00                                         |
| GMR                                                 | 180                                                       | 273                                 | 0         | 460.00                                         |
| MBPC                                                | 113.00                                                    | 256                                 | 295.43    | 442.00                                         |
| Sub Total                                           | 3931.00                                                   | 14302                               | 14413.3   | 15246.00                                       |
| Total All India                                     | 46850.17                                                  | 149544                              | 151627.33 | 150667                                         |
| Import from Bhutan                                  |                                                           | 8236                                | 7493.20   | 8000                                           |
| Total Hydro generation including import from Bhutan |                                                           | 157780.00                           | 159120.53 | 158667                                         |

# CHAPTER-9

## RENOVATION & MODERNISATION OF HYDRO-ELECTRIC STATIONS

## CHAPTER – 9

### 9. RENOVATION & MODERNISATION OF HYDRO ELECTRIC POWER PROJECTS

#### 9.1 R&M Phase-I Programme

Recognising the benefits of the R&M programme, Govt. of India set up a National Committee in 1987 to formulate strategy on R&M of hydro power projects. Based on the recommendations of the National Committee and subsequent reviews, a programme for Renovation, Modernization and Uprating of Hydro Power Stations was formulated by Central Electricity Authority in which 55 schemes were identified with an aggregate capacity of 9653 MW. The total cost of these schemes was estimated as Rs.1493 Crores with expected benefit of 2531 MW.

#### 9.2 R&M Phase-II Programme

As per the hydro policy of Govt. of India declared in 1998, Renovation & Modernization of Hydro Power Plants was accorded priority. Accordingly, 67 hydro R&M schemes having an aggregate capacity of 10318 MW were identified to be undertaken under Phase-II programme till the end of X Plan to accrue a benefit of 3685 MW at an estimated cost of Rs. 2161 Crores.

#### 9.3 National Perspective Plan

CEA formulated the National Perspective Plan for hydro power stations in the year 2000 and incorporated R&M proposals under Phase-II programme alongwith the left out schemes as recommended in Phase-I programme of National Committee. The left out schemes were those which were either under implementation or were yet to be implemented. This Perspective Plan was for IX, X and XI Plan with 117 schemes having an aggregate installed capacity of 19370 MW with benefit of 7755MW at an estimated cost of Rs.4654 Crores.

##### 9.3.1 Achievements during VIII, IX, X, XI and XII Plan

Under the hydro R&M programme, 104 (21 in Central Sector and 83 in State Sector) hydro electric schemes (13 upto the VIII Plan, 20 in the IX Plan, 32 in the X Plan, 18 in the XI Plan and 21 in XII Plan) with an installed capacity of 20,611 MW at a cost of Rs. 3,138 Crores have been completed by the end of the XII Plan (i.e. by 31.03.2017) & have accrued a benefit of 3,636 MW through Life Extension, Uprating and Restoration. The state-wise list of hydro R&M schemes completed during the VIII, IX, X, XI & XII Plan is given at Annex. I, II, III, IV & V respectively.

##### 9.3.2 Programme during the period 2017-22

The Renovation & Modernization (R&M), Uprating and Life Extension works at 22 Hydro Electric Plants (HEPs) with an aggregate installed capacity of 4847.8 MW was programmed for completion during 2017-22 with its break-up as 3729.60 MW through R&M at 12 HEPs, 433.2 MW through Life Extension at 7 HEPs and 685 MW through Life Extension & Uprating at 3 HEPs. The 3 HEPs where both Life Extension & Uprating were envisaged, the aggregate installed capacity of 685 MW after completion of R&M works would get uprated to 801.2 MW resulting in additional benefit of installed capacity of 116.2 MW. As such, the revised aggregate capacity of these 22 projects on completion of R&M works would be 4964 MW.

Out of these 22 schemes, fourteen (14) schemes with an aggregate installed capacity of about 2023.20 MW have been completed till March, 2022. The benefits accrued include 334.2 MW (6 schemes) through Life Extension and 171.2 MW (2 schemes) through LE & Uprating. The State-wise list of hydro R&M schemes completed as

well as those which were programmed but could not be completed during 2017-22 is given at Annex-VI.

### 9.3.3 Programme during the period 2022-27

The Renovation, Modernization, Upgrading and Life Extension works at 77 Hydro Electric Plants (HEPs) with an aggregate installed capacity of 13192.60 MW is programmed for completion during 2022-27 with its break-up as 3218.15 MW through R&M at 15 HEPs, 8183.45 MW through Life Extension at 51 HEPs and 1791 MW through Life Extension and Upgrading at 11 HEPs. The 11 HEPs where both Life Extension & Upgrading are envisaged, the aggregate installed capacity of 1791 MW shall get upgraded after completion of R&M works to 2017.5 MW resulting in additional benefit of installed capacity of 226.5 MW. As such, the revised aggregate installed capacity after completion of RMU&LE works of these 77 projects would be 13419.10 MW. The State-wise list of hydro R&M schemes expected for completion during 2022-27 is given at Annex-VII.

### 9.3.4 Programme during the period 2027-32


The Renovation, Modernization, Upgrading and Life Extension works at 5 Hydro Electric Plants (HEPs) with an aggregate installed capacity of 1339.20 MW is programmed for completion during 2027-32 through Life Extension. The State-wise list of hydro R&M schemes expected for completion during 2027-32 is given at Annex-VIII.

Plan-wise summary of R&M of H.E. Projects starting from VIII Plan is given below:

## 9.4 Summary of R&M of Hydro Electric Projects (As on 31.03.2022)

### I Hydro R&M schemes completed up to XII Plan

| Sl. No. | Plan Period            | No. of Projects |              |       | Installed Capacity (MW) | Actual Expenditure (Rs. in Crs) | Benefit (MW)                                       |
|---------|------------------------|-----------------|--------------|-------|-------------------------|---------------------------------|----------------------------------------------------|
|         |                        | Central Sector  | State Sector | Total |                         |                                 |                                                    |
| 1.      | Upto VIII Plan Schemes | 2               | 11           | 13    | 1282.00                 | 127.37                          | 429.00<br>[39.00(U) + 54.00(LE) + 336.00(Res.)]    |
| 2.      | IX Plan Schemes        | 8               | 12           | 20    | 4892.10                 | 570.16                          | 1093.03<br>[339.00(U) + 423.00(LE) + 331.03(Res.)] |
| 3.      | X Plan Schemes         | 5               | 27           | 32    | 4446.60                 | 1029.24                         | 829.08<br>[123.40(U) + 701.25 (LE) + 4.43(Res.)]   |
| 4.      | XI Plan Schemes        | 4               | 14           | 18    | 5841.20                 | 294.84                          | 735<br>[12 (U) + 708 (LE) + 15 (Res.)]             |
| 5.      | XII Plan Schemes       | 2               | 19           | 21    | 4149.60                 | 1115.97                         | 549.40<br>[58 (U) + 476.40 (LE) + 15(Res.)]        |
| 6.      | Total                  | 21              | 83           | 104   | 20611.50                | 3137.58                         | 3635.51                                            |



## II Programme & Completion of R&M works during 2017-22

| Sl. No. | Category                                                                | No. of Projects |              |       | Capacity covered under RMU&LE (MW) | Estimated Cost (Rs. in Crs.) | Benefit (MW)                  |
|---------|-------------------------------------------------------------------------|-----------------|--------------|-------|------------------------------------|------------------------------|-------------------------------|
|         |                                                                         | Central Sector  | State Sector | Total |                                    |                              |                               |
| 1.      | Programmed                                                              | 7               | 15           | 22    | 4847.8                             | 1977.62                      | 1234.4 [1118.2(LE) +116.2(U)] |
| 2.      | Completed                                                               | 5               | 9            | 14    | 2023.2                             | 814.37<br>(Actual Cost)      | 505.4 [479.2(LE) + 26.2(U)]   |
| 3.      | Programmed during 2017-22 but delayed and now Programmed during 2022-27 | 2               | 6            | 8     | 2824.6                             | 833.68                       | 729.0 [639(LE) +90(U)]        |

### III Programme of R&M works during 2022-27

| Sl. No. | Category                                      | No. of Projects |              |       | Capacity covered under RMU&LE (MW) | Benefit (MW)                       |
|---------|-----------------------------------------------|-----------------|--------------|-------|------------------------------------|------------------------------------|
|         |                                               | Central Sector  | State Sector | Total |                                    |                                    |
| 1.      | Programmed                                    | 8               | 69           | 77    | 13192.60                           | 10200.95<br>[9974.45(LE)+226.5(U)] |
| 2.      | Under Implementation                          | 3               | 23           | 26    | 5485.15                            | 3047.5<br>[2868 (LE)+ 179.5(U)]    |
| 3.      | Under Tendering                               | 1               | 8            | 9     | 956.75                             | 968.75<br>[956.75LE)+ 12(U)]       |
| 4.      | Under DPR Preparation/ Finalisation/ Approval | 3               | 8            | 11    | 2220.2                             | 1751.2<br>1745.2(LE)+ 6(U)]        |
| 5.      | Under RLA Studies                             | 1               | 30           | 31    | 4530.5                             | 4433.5<br>[4404.5(LE)+ 29(U)]      |

### IV Programme of R&M works during 2027-32

| Sl. No. | Category                                    | No. of Projects |              |       | Capacity covered under RMU&LE (MW) | Benefit (MW)              |
|---------|---------------------------------------------|-----------------|--------------|-------|------------------------------------|---------------------------|
|         |                                             | Central Sector  | State Sector | Total |                                    |                           |
| 1.      | Programmed                                  | 3               | 2            | 5     | 1339.20                            | 1339.20<br>[1339.20 (LE)] |
| 2.      | Under Implementation                        | 0               | 0            | 0     | 0                                  | 0                         |
| 3.      | Under Tendering                             | 0               | 0            | 0     | 0                                  | 0                         |
| 4.      | Under DPR Preparation/Finalisation/Approval | 0               | 0            | 0     | 0                                  | 0                         |
| 5.      | Under RLA Studies                           | 3               | 2            | 5     | 1339.20                            | 1339.20<br>[1339.20 (LE)] |

**Abbreviations:**

MW – Mega Watt;

Res. – Restoration;

U – Upgrading;

LE – Life Extension

RLA- Residual Life Assessment

## 9.5 Achievement during the year 2021-22

R&M works of the following 6 Schemes having with an aggregate installed capacity of about 685 MW have been completed during the year 2021-22 and have achieved benefit of 282.8 MW through Life Extension and 12.2 MW through Upgrading:

| S. No. | Name of Schemes             | Capacity under R&M (in MW) | Cost (in Rs. Crores) | Benefit               | Utility/Agency |
|--------|-----------------------------|----------------------------|----------------------|-----------------------|----------------|
| 1      | Chenani,                    | 5x4.66                     | 21.84                | 23.30 (LE)            | J&KSPDC        |
| 2      | Ganderbal, (Unit-3)         | 1x4.5                      | 3.26                 | 4.5 (LE)              | J&KSPDC        |
| 3      | Dehar Power House, (Unit-3) | 1x165                      | 18.67                | -                     | BBMB           |
| 4      | Baira Siul                  | 3x60                       | 295.69               | 180 (LE)              | NHPC           |
| 5      | Ukai                        | 3x75 (U-1,2,&4)            | 7.30                 | -                     | GSECL          |
| 6      | Hirakud-I                   | 2x37.5 (U5&6)              | 101.83               | 75.00 (LE) + 12.2 (U) | OHPC           |

## 9.6 Programme for the year 2022-23

For the year 2022-23, it is programmed to complete following 16 schemes having an installed capacity of 3695.95 MW. On completion of these schemes, there will be a benefit of about 1470 MW through Life Extension and 90 MW through upgrading.

| S. No. | Name of Schemes                      | Capacity under R&M (in MW) | Cost (in Rs. Crores) | Utility/Agency |
|--------|--------------------------------------|----------------------------|----------------------|----------------|
| 1.     | Bhabha Power House                   | 3x40                       | 90.14                | HPSEB          |
| 2.     | Bhakra LB                            | 5x108                      | 489.77               | BBMB           |
| 3.     | Ranjit Sagar Dam                     | 4x150                      | 82.16                | PSPCL          |
| 4.     | UBDC St.I & St.II                    | 3x15+ 3x15.45              | 23.55                | PSPCL          |
| 5.     | Anandpur Sahib Hydel Project         | 4x33.5                     | 31.65                | PSPCL          |
| 6.     | Mukerian St.I, St.II, St.III & St.IV | 3x15, 3x15, 3x19.5& 3x19.5 | 194.29               | PSPCL          |
| 7.     | Shanan HEP                           | 1x50+ 4x15                 | 37.81                | PSPCL          |
| 8.     | Tiloth                               | 3x30                       | 384.66               | UJVNL          |
| 9.     | Dhalipur                             | 3x17                       | 152.65               | UJVNL          |
| 10.    | Rihand                               | 6x50                       | 132.20               | UPJVNL         |
| 11.    | Obra                                 | 3x33                       | 58.80                | UPJVNL         |
| 12.    | Kadana PSS                           | 4x60                       | 5.44                 | GSECL          |
| 13.    | Nagarjuna Sagar Ph-II                | 1x110+7x100.8              | 22.17                | TSGENCO        |
| 14.    | Munirabad Dam Power House            | 2x9 + 1x10                 | 4.60                 | KPCL           |
| 15.    | Kadra Dam Power House                | 3x50                       | 44.47                | KPCL           |
| 16.    | Kodasalli Dam Power House            | 3x40                       | 50.60                | KPCL           |

## State-wise List of Hydro RMU&amp;LE schemes completed upto the VIII Plan

| Sl. No.          | Project, Agency                  | CS/ SS | Inst. Cap. (MW) | Est. Cost     | Actual Exp. | Benefits (MW)                    | Category | Year of Completion |
|------------------|----------------------------------|--------|-----------------|---------------|-------------|----------------------------------|----------|--------------------|
|                  |                                  |        |                 | (Rs. in Crs.) |             |                                  |          |                    |
| Himachal Pradesh |                                  |        |                 |               |             |                                  |          |                    |
| 1                | Bairasiul, NHPC                  | CS     | 3x60            | 25.98         | 25.98       | 18 (U)                           | RM&U     | 1991-92            |
| 2                | Giri, HPSEB                      | SS     | 2x30            | 9.85          | 7.90        | 6 (U)                            | RM&U     | 1995-96            |
| Punjab           |                                  |        |                 |               |             |                                  |          |                    |
| 3                | UBDC-I, PSPCL                    | SS     | 3x15            | 11.00         | 8.00        | 11 (Res)                         | R&M+Res. | 1991-92            |
| Uttar Pradesh    |                                  |        |                 |               |             |                                  |          |                    |
| 4                | Rihand, UPJVNL                   | SS     | 6x50            | 1.43          | 1.43        | 100(Res.)                        | R&M+Res. | 1995-96            |
| Karnataka        |                                  |        |                 |               |             |                                  |          |                    |
| 5                | Nagjhari, U-2, KPCL              | SS     | 1x135           | 11.97         | 11.32       | 15 (U)                           | RM&U     | 1995-96            |
| 6                | Shivasamudram, VVNL              | SS     | 6x3 + 4x6       | 8.00          | 8.00        | 18 (LE)                          | RM&LE    | N.A.               |
| Kerala           |                                  |        |                 |               |             |                                  |          |                    |
| 7                | Sholayar, KSEB                   | SS     | 3x18            | 7.58          | 7.58        | -                                | R&M      | 1996-97            |
| Tamil Nadu       |                                  |        |                 |               |             |                                  |          |                    |
| 8                | Kadamparai (Units 3&4), TANGEDCO | SS     | 2x100           | 23.17         | 33.69       | 200(Res.)                        | R&M+Res. | 1993-95            |
| 9                | Kundah III (Units 1&2), TANGEDCO | SS     | 2x60            | 5.45          | 3.20        | -                                | R&M      | 1991-92            |
| 10               | Moyar, TANGEDCO                  | SS     | 3x12            | 1.62          | 1.30        | 36.00 (LE)                       | RM&LE    | 1990-91            |
| 11               | Sholayar-I, TANGEDCO             | SS     | 2x35            | 1.40          | 0.85        | -                                | R&M      | 1994-95            |
| Meghalaya        |                                  |        |                 |               |             |                                  |          |                    |
| 12               | Khandong, U-1, NEEPCO            | CS     | 1x25            | 0.62          | 0.62        | 25 (Res)                         | R&M+Res. | 1991-92            |
| Tripura          |                                  |        |                 |               |             |                                  |          |                    |
| 13               | Gumti, TPGL                      | SS     | 3x5             | 17.50         | 17.50       | -                                | R&M      | 1994-95            |
| Total            |                                  |        | 1282            | 125.57        | 127.37      | 429 [39 (U) + 54(LE) + 336(Res)] |          |                    |

Abbreviations: R&M – Renovation & Modernisation; U – Uprating; LE – Life Extension;  
Res – Restoration; MW – Mega Watt; CS-Central Sector; SS- State Sector

**State-wise List of Hydro RMU&LE schemes completed in the IX Plan**

| Sl. No.          | Project, Agency            | CS/ SS | Inst. Cap. (MW) | Est. Cost     | Actual Exp. | Benefits (MW)            | Category  | Year of Completion |
|------------------|----------------------------|--------|-----------------|---------------|-------------|--------------------------|-----------|--------------------|
|                  |                            |        |                 | (Rs. in Crs.) |             |                          |           |                    |
| Himachal Pradesh |                            |        |                 |               |             |                          |           |                    |
| 1                | Bhakra RB BBMB             | CS     | 5x132           | 88.45         | 90.68       | 125.00 (U)               | RM&U      | 2000-01            |
| 2                | Dehra U-2 BBMB             | CS     | 1x165           | 10.74         | 10.74       | 25.00 (Res.)             | R&M+Res.  | 1998-99            |
| 3                | Bairasiul, NHPC            | CS     | 3x66            | 18.45         | 18.45       | -                        | R&M       | 2000-01            |
| 4                | Bassi, HPSEB               | SS     | 4x15            | 5.35          | 4.34        | -                        | R&M       | 2000-01            |
| Jammu & Kashmir  |                            |        |                 |               |             |                          |           |                    |
| 5                | Salal St.I, NHPC           | CS     | 3x115           | 51.50         | 51.50       | -                        | R&M       | 2000-01            |
| 6                | Chenani, J&KSPDC           | SS     | 5x4.66          | 11.00         | 11.00       | 0.93 (Res)               | R&M+Res.  | 2000-01            |
| Punjab           |                            |        |                 |               |             |                          |           |                    |
| 7                | Ganguwal, U-2 BBMB         | CS     | 1x24.2          | 18.90         | 15.00       | 22.00 (LE)+ 2.20 (Res)   | RM&LE+Res | 1997-98            |
| 8                | Kotla, U-3, BBMB           | CS     | 1x24.2          | 18.90         | 16.90       | 22.00 (LE)+ 2.20 (Res)   | RM&LE+Res | 1998-99            |
| 9                | Ganguwal U-3, BBMB         | CS     | 1x24.2          | 25.00         | 43.40       | 22.00 (LE)+ 2.20 (Res)   | RM&LE+Res | 2000-01            |
| 10               | Kotla U-2, BBMB            | CS     | 1x24.2          | 25.00         |             | 22.00 (LE)+ 2.20 (Res)   | RM&LE+Res | 2001-02            |
| Uttarakhand      |                            |        |                 |               |             |                          |           |                    |
| 11               | Chilla U-1, 3& 4, UJVNL    | SS     | 3x36            | 4.25          | 4.11        | -                        | R&M       | 1998-99            |
| 12               | Tiloth, UJVNL              | SS     | 3x30            | 8.02          | 5.51        | 6.00 (U)                 | RM&U      | 1998-99            |
| Andhra Pradesh   |                            |        |                 |               |             |                          |           |                    |
| 13               | Lower Sileru, APGENCO      | SS     | 4x115           | 13.35         | 9.30        | 24.00 (Res)              | R&M+Res.  | 2001-02            |
| 14               | Srisailam RB, APGENCO      | SS     | 7x110           | 16.32         | 11.40       | -                        | R&M       | 2001-02            |
| Karnataka        |                            |        |                 |               |             |                          |           |                    |
| 15               | Sharavathy, U-1 to 8, KPCL | SS     | 8x89.1          | 65.00         | 63.49       | 115.20 (U) +178.20 (Res) | RM&U+Res  | 1997-98            |
| 16               | Sharavathy, U-9&10, KPCL   | SS     | 2x89.1          | 17.96         | 14.68       | 28.80(U) +19.10 (Res)    | RM&U+Res  | 1997-98            |

**Annex-II**  
**(Sheet 2/ 2)**

| Sl. No      | Project, Agency                 | CS/ SS | Inst. Cap. (MW) | Est. Cost     | Actual Exp. | Benefits (MW)                                 | Category                       | Year of Completion |
|-------------|---------------------------------|--------|-----------------|---------------|-------------|-----------------------------------------------|--------------------------------|--------------------|
|             |                                 |        |                 | (Rs. in Crs.) |             |                                               |                                |                    |
| Orissa      |                                 |        |                 |               |             |                                               |                                |                    |
| 17          | Hirakud-I, U1&2, OHPC           | SS     | 2x37.5          | 95.10         | 95.10       | 24.00(U) +75.00(LE)                           | RMU&LE                         | 1997-98            |
| Gujarat     |                                 |        |                 |               |             |                                               |                                |                    |
| 18          | Ukai,U-1&3, GSECL               | SS     | 2x75            | 24.99         | 24.99       | 75.00 (Res.)                                  | R&M+Res.                       | 1997-98            |
| Maharashtra |                                 |        |                 |               |             |                                               |                                |                    |
| 19          | Koyna I&II, MSPGCL              | SS     | 4x65+ 4x75      | 74.91         | 74.91       | 40.00(U) + 260.00(LE)                         | RM&U of St-I & II & LE of St-I | 1999-2000          |
| 20          | Koyna III, U-10, 11 &12, MSPGCL | SS     | 3x80            | 4.65          | 4.65        | -                                             | R&M                            | 1997-98            |
| Total       |                                 |        | 4892.10         | 597.84        | 570.16      | 1093.03 [339.0(U) + 423.0(LE) + 331.03(Res.)] |                                |                    |

Abbreviations: R&M – Renovation & Modernisation;. U – Uprating; LE – Life Extension;  
Res – Restoration; MW – Mega Watt; CS-Central Sector; SS- State Sector

State-wise List of Hydro RMU&LE schemes completed in the X Plan

| Sl. No.          | Project, Agency       | CS/ SS | Inst. Cap. (MW) | Est. Cost     | Actual Exp. | Benefits (MW)          | Category                                    | Year of Completion |
|------------------|-----------------------|--------|-----------------|---------------|-------------|------------------------|---------------------------------------------|--------------------|
|                  |                       |        |                 | (Rs. in Crs.) |             |                        |                                             |                    |
| Himachal Pradesh |                       |        |                 |               |             |                        |                                             |                    |
| 1                | Pong, BBMB            | CS     | 6x60            | 17.70         | 17.79       | 36.00(U)               | RM&U                                        | 2003-04            |
| Punjab           |                       |        |                 |               |             |                        |                                             |                    |
| 2                | Ganguwal,U-1, BBMB    | CS     | 1x29.25         | 51.28         | 81.99       | 25.89 (LE) +2.10       | RM&LE+Res.                                  | 2006-07            |
| 2                | Kotla, U-1, BBMB      | CS     | 1x29.25         | 51.28         |             | 2.33 (Res.)            | RM&LE+Res.                                  | 2006-07            |
| 4                | Shanan Ph.A, PSPCL    | SS     | 4x15+ 1x50      | 11.35         | 10.93       | -                      | R&M                                         | 2003-04            |
| 5                | Shanan, Ph.B, PSPCL   | SS     | 4x15+ 1x50 \$   | 35.95         | 13.34       | 60.00(LE)              | RM&LE(LE for 15 MW units+R&M for 50 MW unit | 2006-07            |
| 6                | Anandpur Sahib, PSPCL | SS     | 4x33.5          | 3.68          | 1.04        | -                      | R&M                                         | 2006-07            |
| 7                | UBDC I&II, PSPCL      | SS     | 3x15+ 3x15.45   | 7.89          | 2.44        | 45.00 (LE)             | RM&LE(LE for 3x15MW&R &M for 3x15.45 MW     | 2006-07            |
| 8                | Mukerian St.I, PSPCL  | SS     | 3x15            | 6.04          | 4.38        | -                      | R&M                                         | 2006-07            |
| Uttarakhand      |                       |        |                 |               |             |                        |                                             |                    |
| 9                | Chibro, UJVNL         | SS     | 4x60            | 10.45         | 10.52       | -                      | R&M                                         | 2006-07            |
| Karnataka        |                       |        |                 |               |             |                        |                                             |                    |
| 10               | Nagjhari, U-1&3,KPCL  | SS     | 2x135           | 26.12         | 21.62       | 30 (U)                 | RM&U                                        | 2002-03            |
| 11               | Supa PH, KPCL         | SS     | 2x50            | 2.64          | 2.47        | -                      | R&M                                         | 2002-03            |
| 12               | Mahatma Gandhi, VVNL  | SS     | 4x12+ 4x18      | 44.66         | 43.13       | 19.20 (U) +120.00 (LE) | RMU&LE                                      | 2002-03            |
| 13               | Munirabad, VVNL       | SS     | 2x9+ 1x10.3     | 3.64          | 3.53        | 28.30 (LE)             | RM&LE                                       | 2002-03            |

**Annex- III  
(Sheet 2/3)**

(Sheet 2/3)

| Sl. No      | Project, Agency           | CS/ SS | Inst. Cap. (MW)   | Est. Cost     | Actual Exp | Benefits (MW)         | Category | Year of Completion |
|-------------|---------------------------|--------|-------------------|---------------|------------|-----------------------|----------|--------------------|
|             |                           |        |                   | (Rs. in Crs.) |            |                       |          |                    |
| 14          | Mani Dam, KPCL            | SS     | 2x4.5             | 1.00          | 1.00       | -                     | R&M      | 2002-03            |
| 15          | Shivasamudram , VVNL      | SS     | 6x3+ 4x6          | 68.38         | 73.17      | 42.00 (LE)            | RM&LE    | 2004-05            |
| 16          | Bhadra, Ph.II, KPCL       | SS     | 1x2               | 3.30          | 2.51       | 2.00 (LE)             | RM&LE    | 2005-06            |
| 17          | Varahi, KPCL              | SS     | 2x115             | 2.57          | 2.66       | -                     | R&M      | 2006-07            |
| 18          | Sharavathy, Ph.A, KPCL    | SS     | 10x103.5          | 5.22          | 3.52       | -                     | R&M      | 2006-07            |
| Kerala      |                           |        |                   |               |            |                       |          |                    |
| 19          | Neriamangalam KSEB        | SS     | 3x15              | 58.00         | 53.05      | 9.00 (U) +45.00(LE)   | RMU&LE   | 2006-07            |
| 20          | Pallivasal, KSEB          | SS     | 3x5+ 3x7.5        | 94.00         | 371.71     | 37.50 (LE)            | RM&LE    | 2002-03            |
| 21          | Sengulam, KSEB            | SS     | 4x12              | 114.00        |            | 48.00 (LE)            | RM&LE    | 2002-03            |
| 22          | Panniar, KSEB             | SS     | 2x15              | 62.00         |            | 30.00 (LE)            | RM&LE    | 2002-03            |
| Tamilnadu   |                           |        |                   |               |            |                       |          |                    |
| 23          | Pykara, TANGEDCO          | SS     | 3x6.65+1x11 +2x14 | 26.06         | 20.147     | 58.95(LE)             | RM&LE    | 2004-05            |
| 24          | Papanasam, TANGEDCO       | SS     | 4x7               | 27.05         | 22.61      | 4.00 (U) + 28.00 (LE) | RMU&LE   | 2005-06            |
| Orissa      |                           |        |                   |               |            |                       |          |                    |
| 25          | Hirakud-I (Sw.yard), OHPC | SS     |                   | 9.85          | 15.88      | -                     | R&M      | 2006-07            |
| 26          | Hirakud-I,U-3&4, OHPC     | SS     | 2x24              | 126.14        | 108.86     | 16.00(U)+ 48.00(LE)   | RMU&LE   | 2005-06            |
| West Bengal |                           |        |                   |               |            |                       |          |                    |
| 27          | Maithon, U-2, DVC         | CS     | 1x20              | 42.08         | 36.94      | 3.20(U)+ 20.00(LE)    | RMU&LE   | 2004-05            |
| Maharastra  |                           |        |                   |               |            |                       |          |                    |
| 28          | Bhira Tail Race, MSPGCL   | SS     | 2x40              | 1.60          | 0.70       | -                     | R&M      | 2003-04            |
| 29          | Tillari, MSPGCL           | SS     | 1x60              | 4.50          | 4.24       | 6.0 (U)               | RM&U     | 2004-05            |

**Annex- III**  
**(Sheet 3/3)**

(Sheet 3/3)

| Sl. No    | Project, Agency            | CS/ SS | Inst. Cap. (MW) | Est. Cost     | Actual Exp | Benefits (MW)                                        | Category | Year of Completion |
|-----------|----------------------------|--------|-----------------|---------------|------------|------------------------------------------------------|----------|--------------------|
|           |                            |        |                 | (Rs. in Crs.) |            |                                                      |          |                    |
| 30        | Koyna Gen. Complex, MSPGCL | SS     | 4x70+4x80+4x80  | 12.00         | 11.50      | -                                                    | R&M      | 2004-05            |
| Meghalaya |                            |        |                 |               |            |                                                      |          |                    |
| 31        | Umium St.I, MePGCL         | SS     | 4x9             | 81.88         | 84.21      | 36(LE)                                               | RM&LE    | 2002-03            |
| 32        | Khandong, NEEPCO           | CS     | 2x25            | 4.00          | 3.35       | -                                                    | R&M      | 2003-04            |
| Total     |                            |        | 4446.60         | 1016.31       | 1029.24    | 829.08<br>[123.40(U)<br>+701.25(LE)<br>+ 4.43(Res.)] |          |                    |

\$ - Installed Capacity of Shanan, Ph.B, at Sl. No. 5 not included in the total, as the same has been accounted for at Sl. No. 4.

Abbreviations: R&M – Renovation & Modernisation;. U – Uprating; LE – Life Extension;  
Res – Restoration; MW – Mega Watt; CS-Central Sector; SS- State Sector

**State-wise List of Hydro RMU&LE schemes completed in the XI Plan**

| Sl. No           | Project, Agency         | CS/ SS | Inst. Cap. (MW) | Est. Cost     | Actual Exp | Benefits (MW)    | Category | Year of Completion |
|------------------|-------------------------|--------|-----------------|---------------|------------|------------------|----------|--------------------|
|                  |                         |        |                 | (Rs . in crs) |            |                  |          |                    |
| Himachal Pradesh |                         |        |                 |               |            |                  |          |                    |
| 1                | Dehar Ph. A BBMB        | CS     | 6x165           | 11.00         | 6.94       | -                | R&M      | 2010-11            |
| 2                | Dehar Ph. B BBMB        | CS     | 6x165           | 49.00         | 24.45      | 330(LE)          | RM&LE    | 2009-10            |
| Uttarakhand      |                         |        |                 |               |            |                  |          |                    |
| 3                | Tanakpur, NHPC          | CS     | 3x31.4          | 10.77         | 11.95      | -                | R&M      | 2007-08            |
| 4                | Khodri Ph.A, UJVNL      | SS     | 4x30            | 5.25          | 6.39       | -                | R&M      | 2008-09            |
| 5                | Chilla Ph.A, UJVNL      | SS     | 4x36            | 23.55         | 21.24      | -                | R&M      | 2008-09            |
| Andhra Pradesh   |                         |        |                 |               |            |                  |          |                    |
| 6                | Upper Sileru, APGENCO   | SS     | 4x60            | 4.20          | 3.34       | -                | R&M      | 2009-10            |
| Karnataka        |                         |        |                 |               |            |                  |          |                    |
| 7                | Nagjhari, U1 to 6, KPCL | SS     | 5x150 + 1x135   | 14.75         | 15.31      | -                | R&M      | 2009-10            |
| 8                | Sharavathy Ph.B, KPCL   | SS     | 10x103.5        | 20.50         | 11.14      | -                | R&M      | 2009-10            |
| 9                | Supa, KPCL              | SS     | 2x50            | 3.45          | 4.90       | -                | R&M      | 2009-10            |
| 10               | Bhadra, KPCL            | SS     | 2x12            | 1.44          | 0.85       | -                | R&M      | 2009-10            |
| 11               | Lingnamakki, KPCL       | SS     | 2x27.5          | 3.81          | 2.62       | -                | R&M      | 2010-11            |
| Tamil Nadu       |                         |        |                 |               |            |                  |          |                    |
| 12               | Mettur Dam, TANGEDCO    | SS     | 4x10            | 30.17         | 24.16      | 10 (U) + 40 (LE) | RMU&LE   | 2007-08            |
| Maharashtra      |                         |        |                 |               |            |                  |          |                    |
| 13               | Koyna St.I&II, MSPGCL   | SS     | 4x70 + 4x80     | 87.50         | 81.82      | -                | R&M      | 2008-09            |



**State-wise list of Hydro RMU&LE schemes completed in the XII Plan**

| Sl. No           | Project, Agency                            | CS/ SS | Inst. Cap. (No.x.MW ) | Est. Cost     | Actual Exp | Benefits (MW)  | Capacity after RMU&LE (MW) | Category  | Year of Completion |
|------------------|--------------------------------------------|--------|-----------------------|---------------|------------|----------------|----------------------------|-----------|--------------------|
|                  |                                            |        |                       | (Rs . in Crs) |            |                |                            |           |                    |
| Himachal Pradesh |                                            |        |                       |               |            |                |                            |           |                    |
| 1                | Bassi, HPSEB                               | SS     | 4x15                  | 124.25        | 158.26     | 6.0(U)+ 60(LE) | 66                         | RMU&LE    | 2013-14            |
| Jammu & Kashmir  |                                            |        |                       |               |            |                |                            |           |                    |
| 2                | Lower Jhelum, J&KSPDC                      | SS     | 3x35                  | 101.3         | 96.10      | 15.00(Res)     | 105                        | R&M+ Res. | 2014-15            |
| 3                | Sumbal Sindh, J&KSPDC                      | SS     | 2x11.3                | 25.00         | 24.59      | -              | 22.6                       | R&M       | 2016-17            |
| Uttarakhand      |                                            |        |                       |               |            |                |                            |           |                    |
| 4                | Pathri, UJVNL                              | SS     | 3x6.8                 | 113.25        | 108.3      | 20.40(LE)      | 20.4                       | RM&LE     | 2014-15            |
| 5                | Khatima, UJVNL                             | SS     | 3x13.8                | 256.77        | 118.83     | 41.40 (LE)     | 41.4                       | RM&LE     | 2016-17            |
| Uttar Pradesh    |                                            |        |                       |               |            |                |                            |           |                    |
| 6                | Matatila, UPJVNL                           | SS     | 3x10.2                | 10.29         | 7.21       | 30.6 (LE)      | 30.6                       | RM&LE     | 2015-16            |
| Andhra Pradesh   |                                            |        |                       |               |            |                |                            |           |                    |
| 7                | Lower Sileru, APGENCO                      | SS     | 4x115                 | 8.75          | 6.77       | -              | 460                        | R&M       | 2013-14            |
| 8                | Srisaillam RB, APGENCO                     | SS     | 7x110                 | 16.70         | 17.60      | -              | 770                        | R&M       | 2015-16            |
| Telangana        |                                            |        |                       |               |            |                |                            |           |                    |
| 9                | Nagarjuna Sagar Ph-I works, TSGENCO        | SS     | 1x110+ 7x100.8        | 33.35         | 13.90      | -              | 815.6                      | R&M       | 2012-13            |
| Karnataka        |                                            |        |                       |               |            |                |                            |           |                    |
| 10               | Supa, KPCL                                 | SS     | 2x50                  | 3.45          | 3.88       | -              | 100                        | R&M       | 2014-15            |
| 11               | Nagihari,U-1 to 6, KPCL                    | SS     | 1x135 (U-6)           | 69.21         | 64.49      | 15 (U)         | 150                        | RM&U      | 2015-16            |
| 12               | Sharavathy Genarating Station (Ph B), KPCL | SS     | 10x103.5              | 20.00         | 29.27      | -              | 1035                       | R&M       | 2016-17            |
| Kerala           |                                            |        |                       |               |            |                |                            |           |                    |
| 13               | Idamalayar, KSEB                           | SS     | 2x37.5                | 14.50         | 13.22      | -              | 75                         | R&M       | 2012-13            |

**Annex- V**  
**(Sheet 2 of 2)**

Sheet 2 of 2

| Sl. No      | Project, Agency        | CS/ SS | Inst. Cap. (No.x.MW ) | Est. Cost     | Actual Exp | Benefits (MW)                          | Capacity after RMU&LE | Category | Year of Completion |
|-------------|------------------------|--------|-----------------------|---------------|------------|----------------------------------------|-----------------------|----------|--------------------|
|             |                        |        |                       | (Rs . in Crs) |            |                                        |                       |          |                    |
| 14          | Sabarigiri, U-4 KSEB   | SS     | 1x55                  | 52.20         | 50.41      | 5(U)                                   | 60                    | RM&U     | 2014-15            |
| 15          | Poringalkuthu, KSEB    | SS     | 4x8                   | 88.63         | 51.90      | 4 (U)+ 32.00 (LE)                      | 36                    | RMU&LE   | 2015-16            |
| Tamil Nadu  |                        |        |                       |               |            |                                        |                       |          |                    |
| 16          | Periyar, TANGEDCO      | SS     | 4x35                  | 161.18        | 133.68     | 28.00(U)+ 140(LE)                      | 168                   | RMU&LE   | 2015-16            |
| Odisha      |                        |        |                       |               |            |                                        |                       |          |                    |
| 17          | Rengali Unit-1 OHPC    | SS     | 1x50                  | 47.50         | 36.76      | 50(LE)                                 | 50                    | RM&LE    | 2012-13            |
| 18          | Rengali Unit-2 OHPC    | SS     | 1x50                  | 25.20         | 20.73      | 50(LE)                                 | 50                    | RM&LE    | 2013-14            |
| West Bengal |                        |        |                       |               |            |                                        |                       |          |                    |
| 19          | Jaldhaka St.I, WBSEDCL | SS     | 3x9                   | 88.62         | 79.97      | 27 (LE)                                | 27                    | RM&LE    | 2016-17            |
| Assam       |                        |        |                       |               |            |                                        |                       |          |                    |
| 20          | Khandong, NEEPCO       | CS     | 1x25                  | 25.05         | 29.18      | 25(LE)                                 | 25                    | RM&LE    | 2014-15            |
| 21          | Kopili, NEEPCO         | CS     | 2x50                  | 50.22         | 50.92      | -                                      | 100                   | R&M      | 2014-15            |
| Total       |                        |        | 4149.60               | 1335.42       | 1115.97    | 549.40 [58(U)+ 476.40 (LE) + 15 (Res)] | 4207.6                |          |                    |

State-wise list of Hydro RMU&LE schemes programmed for completion and achievement during 2017-22

| Sl. No                          | Name of Project, Agency, Inst. Cap. (No. x MW)                 | CS/ SS | Capacity Covered Under RMU&LE (No.x MW) | Est. Cost     | Actual Exp. | Benefits (MW)               | Capacity after RMU&LE (MW) | Category | Year of Completion   |             |
|---------------------------------|----------------------------------------------------------------|--------|-----------------------------------------|---------------|-------------|-----------------------------|----------------------------|----------|----------------------|-------------|
|                                 |                                                                |        |                                         | (Rs. in Crs.) |             |                             |                            |          | Original             | Anticipated |
| A. COMPLETED SCHEMES IN 2017-22 |                                                                |        |                                         |               |             |                             |                            |          |                      |             |
| Jammu & Kashmir (UT)            |                                                                |        |                                         |               |             |                             |                            |          |                      |             |
| 1                               | Salal, NHPC (6x115)                                            | CS     | 5x115                                   | 58.01         | 51.08       | -                           | 575                        | R&M      | Completed in 2019-20 |             |
| 2                               | Chenani, J&KSPDC (5x4.66)                                      | SS     | 5x4.66                                  | 34.28         | 21.84       | 23.30 (LE)                  | 23.3                       | RM&LE    | Completed in 2021-22 |             |
| 3                               | Ganderbal, (Unit-3) J&KSPDC (2x3+2x4.5)                        | SS     | 1x4.5                                   | 18.00         | 3.26        | 4.5 (LE)                    | 4.5                        | RM&LE    | Completed in 2021-22 |             |
| Himachal Pradesh                |                                                                |        |                                         |               |             |                             |                            |          |                      |             |
| 4                               | Ganguwal, BBMB (1x29.25+2x24.2) & Kotla, BBMB (1x29.25+2x24.2) | CS     | 1x24.2 (U-2)<br>1x24.2 (U-3)            | 14.19         | 9.58        | 48.4 (LE)                   | 48.4                       | RM&LE    | Completed in 2017-18 |             |
| 5                               | Dehar Power House (Unit-6), BBMB (6x165)                       | CS     | 1x165                                   | 19.87         | 16.00       | -                           | 165                        | R&M      | Completed in 2017-18 |             |
| 6                               | Dehar Power House (Unit-3), BBMB (6x165)                       | CS     | 1x165                                   | 23.00         | 18.67       | -                           | 165                        | R&M      | Completed in 2021-22 |             |
| 7                               | Baira Siul, NHPC (3x60)                                        | CS     | 3x60                                    | 341.41        | 295.69      | 180 (LE)                    | 180                        | RM&LE    | Completed in 2021-22 |             |
| Gujarat                         |                                                                |        |                                         |               |             |                             |                            |          |                      |             |
| 8                               | Ukai, GSECL (4x75)                                             | SS     | 3x75 (U-1,2,&4)                         | 7.30          | 7.30        | -                           | 225                        | R&M      | Completed in 2021-22 |             |
| Karnataka                       |                                                                |        |                                         |               |             |                             |                            |          |                      |             |
| 9                               | Bhadra River Bed units, KPCL (2x12)                            | SS     | 2x12                                    | 23.55         | 20.12       | -                           | 24                         | R&M      | Completed in 2019-20 |             |
| Tamil Nadu                      |                                                                |        |                                         |               |             |                             |                            |          |                      |             |
| 10                              | Sholayar-I, TANGEDCO (2x35)                                    | SS     | 2x35                                    | 90.44         | 66.94       | 70 (LE) + 14(U)             | 84                         | RMU&LE   | Completed in 2019-20 |             |
| Kerala                          |                                                                |        |                                         |               |             |                             |                            |          |                      |             |
| 11                              | Sholayar, KSEB (3x18)                                          | SS     | 3x18                                    | 199.55        | 84.26       | 54 (LE)                     | 54                         | RM&LE    | Completed in 2020-21 |             |
| 12                              | Idukki 1 <sup>st</sup> stage, KSEB (3x130)                     | SS     | 3x130                                   | 89.90         | 65.76       | -                           | 390                        | R&M      | Completed in 2020-21 |             |
| Odisha                          |                                                                |        |                                         |               |             |                             |                            |          |                      |             |
| 13                              | Hirakud-I OHPL (2x37.5)                                        | SS     | 2x37.5 (U5&6)                           | 158.77        | 101.83      | 75.00 (LE) + 12.2 (U)       | 87.2                       | RMU&LE   | Completed in 2021-22 |             |
| 14                              | Hirakud-II (Chiplima), OHPL (3x24)                             | SS     | 1x24 (U-3)                              | 65.67         | 52.04       | 24.00 (LE)                  | 24                         | RM&LE    | Completed in 2019-20 |             |
| Sub Total (A)                   |                                                                |        | 2023.20                                 | 1143.94       | 814.37      | 505.4 [479.2(LE) + 26.2(U)] | 2049.40                    |          |                      |             |

| Sl. No                                                                                                   | Name of Project, Agency<br>Inst. Cap. (No. x MW)                                 | CS/<br>SS | Capacity<br>Covered<br>Under<br>RMU&LE<br>(No.x MW) | Est.<br>Cost  | Actual<br>Exp. | Benefits<br>(MW)                    | Capacity<br>after<br>RMU&LE<br>(MW) | Category | Year of Completion |             |  |
|----------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------|-----------|-----------------------------------------------------|---------------|----------------|-------------------------------------|-------------------------------------|----------|--------------------|-------------|--|
|                                                                                                          |                                                                                  |           |                                                     | (Rs. in Crs.) |                |                                     |                                     |          | Original           | Anticipated |  |
| B. PROGRAMMED FOR COMPLETION DURING 2017-22 BUT DELAYED AND NOW PROGRAMMED FOR COMPLETION DURING 2022-27 |                                                                                  |           |                                                     |               |                |                                     |                                     |          |                    |             |  |
| Himachal Pradesh                                                                                         |                                                                                  |           |                                                     |               |                |                                     |                                     |          |                    |             |  |
| 15                                                                                                       | Bhakra LB, BBMB<br>(5x108)                                                       | CS        | 5x108                                               | 489.77        | 552.75         | 540.00(LE)+<br>90.00 (U)            | 630                                 | RMU&LE   | 2016-17            | 2021-22     |  |
| 16                                                                                                       | Bhakra RB, BBMB<br>(5x157)                                                       | CS        | 5x157                                               | 20.80         | -              | -                                   | 785                                 | R&M      | 2021-22            | 2021-22     |  |
| Punjab                                                                                                   |                                                                                  |           |                                                     |               |                |                                     |                                     |          |                    |             |  |
| 17                                                                                                       | Mukerian St.I, St.II, St.III &<br>St.IV, PSPCL<br>(3x15, 3x15,<br>3x19.5&3x19.5) | SS        | 3x15, 3x15,<br>3x19.5&<br>3x19.5                    | 194.29        | 63.67          | -                                   | 207                                 | R&M      | 2019-20            | 2021-22     |  |
| 18                                                                                                       | Shanan HEP, PSPCL<br>(1x50+4x15)                                                 | SS        | 1x50+<br>4x15                                       | 37.81         | 20.21          | -                                   | 110                                 | R&M      | 2019-20            | 2021-22     |  |
| Uttar Pradesh                                                                                            |                                                                                  |           |                                                     |               |                |                                     |                                     |          |                    |             |  |
| 19                                                                                                       | Obra, UPJVNL<br>(3x33)                                                           | SS        | 3x33                                                | 58.80         | 44.87          | 99 (LE)                             | 99                                  | RM&LE    | 2017-18            | 2021-22     |  |
| Gujarat                                                                                                  |                                                                                  |           |                                                     |               |                |                                     |                                     |          |                    |             |  |
| 20                                                                                                       | Kadana PSS, GSECL<br>(4x60)                                                      | SS        | 4x60                                                | 5.44          | 3.73           | -                                   | 240                                 | R&M      | 2021-22            | 2021-22     |  |
| Telangana                                                                                                |                                                                                  |           |                                                     |               |                |                                     |                                     |          |                    |             |  |
| 21                                                                                                       | Nagarjuna Sagar Ph-II<br>works, TSGENCO<br>(1x110+7x100.8)                       | SS        | 1x110+7x100<br>.8                                   | 22.17         | 14.34          | -                                   | 815.6                               | R&M      | 2018-19            | 2021-22     |  |
| Karnataka                                                                                                |                                                                                  |           |                                                     |               |                |                                     |                                     |          |                    |             |  |
| 22                                                                                                       | Munirabad Dam Power<br>House, KPCL<br>(2x9 + 1x10)                               | SS        | 2x9 + 1x10                                          | 4.60          | 2.20           | -                                   | 28                                  | R&M      | 2018-19            | 2021-22     |  |
| Sub Total (B)                                                                                            |                                                                                  |           | 2824.60                                             | 833.68        | 701.77         | 729.0<br>[639(LE)<br>+90(U)]        | 2914.60                             |          |                    |             |  |
| Total (A+B)                                                                                              |                                                                                  |           | 4847.80                                             | 1977.62       | 1516.14        | 1234.4<br>[1118.2(LE)<br>+116.2(U)] | 4964.00                             |          |                    |             |  |

@ This cost includes Scheme I only i.e. Rehabilitation of damaged/burnt equipments.

Abbreviations: R&M – Renovation & Modernisation; U – Uprating; LE – Life Extension; Res – Restoration;

MW – Mega Watt; CS-Central Sector; SS- State Sector

## State-wise List of Hydro RMU&amp;LE schemes programmed for completion during 2022-27

| State-wise List of Hydro RMU&LE schemes programmed for completion during 2022-27 |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
|----------------------------------------------------------------------------------|-------------------------------------------------------------------------|-----|----------------------------|-----------------------------------------|---------------|-----------------------|---------------|-----------------------|----------|-------------------|
| Sl. No                                                                           | Name of Project, Agency Inst. Cap. (No.X MW)                            | CS/ | SS                         | Capacity Covered Under RMU&LE (No.x MW) | Est. Cost     | Actual Exp.           | Benefits (MW) | Capacity after RMU&LE | Category | Completion Target |
|                                                                                  |                                                                         |     |                            |                                         | (Rs. in Crs.) |                       |               |                       |          |                   |
| A. Ongoing Schemes – Under Implementation                                        |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| Himachal Pradesh                                                                 |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| 1                                                                                | Pong Power House, BBMB (6x66)                                           | CS  | 6x66                       | 142.25                                  | -             | 396 (LE) + 54 (U)     | 450           | RMU&LE                | 2026-27  |                   |
| 2                                                                                | Bhabha Power House, HPSEB                                               | SS  | 3x40                       | 90.14                                   | 43.01         | 120 (LE)              | 120           | RM&LE                 | 2022-23  |                   |
| 3                                                                                | Bhakra LB, BBMB (5x108)                                                 | CS  | 5x108                      | 489.77                                  | 552.75        | 540.00(LE)+ 90.00 (U) | 630           | RMU&LE                | 2022-23  |                   |
| Punjab                                                                           |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| 4                                                                                | Ranjit Sagar Dam, PSPCL (4x150)                                         | SS  | 4x150                      | 82.16                                   | 7.45          | -                     | 600           | R&M                   | 2022-23  |                   |
| 5                                                                                | UBDC St.I & St.II, PSPCL (3x15+3x15.45)                                 | SS  | 3x15+ 3x15.45              | 23.55                                   | 5.66          | -                     | 91.35         | R&M                   | 2022-23  |                   |
| 6                                                                                | Anandpur Sahib Hydel Project, PSPCL (4x33.5)                            | SS  | 4x33.5                     | 31.65                                   | 0.88          | -                     | 134           | R&M                   | 2022-23  |                   |
| 7                                                                                | Mukerian St.I, St.II, St.III & St.IV, PSPCL (3x15, 3x15, 3x19.5&3x19.5) | SS  | 3x15, 3x15, 3x19.5& 3x19.5 | 194.29                                  | 63.67         | -                     | 207           | R&M                   | 2022-23  |                   |
| 8                                                                                | Shanan HEP, PSPCL (1x50+4x15)                                           | SS  | 1x50+ 4x15                 | 37.81                                   | 20.21         | -                     | 110           | R&M                   | 2022-23  |                   |
| Uttarakhand                                                                      |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| 9                                                                                | Chilla Ph B UJVNL (4x36)                                                | SS  | 4x36                       | 490.56                                  | -             | 144(LE)+ 12(U)        | 156           | RMU&LE                | 2024-25  |                   |
| 10                                                                               | Tiloth, UJVNL (3x30)                                                    | SS  | 3x30                       | 384.66                                  | 153.21        | 90 (LE)               | 90            | RM&LE                 | 2022-23  |                   |
| 11                                                                               | Dhalipur, UJVNL (3x17)                                                  | SS  | 3x17                       | 152.65                                  | 61.76         | 51 (LE)               | 51            | RM&LE                 | 2022-23  |                   |
| Uttar Pradesh                                                                    |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| 12                                                                               | Rihand, UPJVNL (6x50)                                                   | SS  | 6x50                       | 132.20                                  | 109.17        | 300 (LE)              | 300           | RM&LE                 | 2022-23  |                   |
| 13                                                                               | Obra, UPJVNL (3x33)                                                     | SS  | 3x33                       | 58.8                                    | 44.87         | 99 (LE)               | 99            | RM&LE                 | 2022-23  |                   |
| Gujarat                                                                          |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| 14                                                                               | Kadana PSS, GSECL (4x60)                                                | SS  | 4x60                       | 5.44                                    | 3.73          | -                     | 240           | R&M                   | 2022-23  |                   |
| Telangana                                                                        |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| 15                                                                               | Nagarjuna Sagar Left Canal Power House, TSGENCO (2x30.6)                | SS  | 2x30.6                     | 30.99                                   | 2.00          | -                     | 61.2          | R&M                   | 2022-27  |                   |
| 16                                                                               | Nagarjuna Sagar Ph-II works, TSGENCO (1x110+7x100.8)                    | SS  | 1x110+7x100.8              | 22.17                                   | 14.34         | -                     | 815.6         | R&M                   | 2022-23  |                   |
| Andhra Pradesh                                                                   |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| 17                                                                               | Upper Sileru Power House, APGENCO (4x60)                                | SS  | 4x60                       | -                                       | -             | -                     | 240           | R&M                   | 2025-27  |                   |
| 18                                                                               | Nagarjunasagar Right Canal Power House, APGENCO (3x30)                  | SS  | 3x30                       | -                                       | -             | -                     | 90            | R&M                   | 2025-27  |                   |
| Karnataka                                                                        |                                                                         |     |                            |                                         |               |                       |               |                       |          |                   |
| 19                                                                               | Nagjhari (Unit-1 to 3) KPCL (3x150)                                     | SS  | 3x150 (U-1 to 3)           | 222.00                                  | 13.108        | 450 (LE)              | 450           | RM&LE                 | 2023-24  |                   |
| 20                                                                               | Shivasamudram, KPCL (6x3+4x6)                                           | SS  | 6x3+4x6                    | 169.18                                  | 14.01         | 42 (LE)               | 42            | RM&LE                 | 2023-24  |                   |
| 21                                                                               | Munirabad Dam Power House, KPCL (2x9 + 1x10)                            | SS  | 2x9 + 1x10                 | 4.60                                    | 2.20          | -                     | 28            | R&M                   | 2022-23  |                   |

| (Sheet 2 of 4)                                                     |                                                               |        |                                         |               |             |                              |                       |          |                    |
|--------------------------------------------------------------------|---------------------------------------------------------------|--------|-----------------------------------------|---------------|-------------|------------------------------|-----------------------|----------|--------------------|
| Sl. No                                                             | Name of Project, Agency Inst. Cap. (No.X MW)                  | CS/ SS | Capacity Covered Under RMU&LE (No.x MW) | Est. Cost     | Actual Exp. | Benefits (MW)                | Capacity after RMU&LE | Category | Year of Completion |
|                                                                    |                                                               |        |                                         | (Rs. in Crs.) |             |                              |                       |          |                    |
| Tamil Nadu                                                         |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 22                                                                 | Moyar PH, TANGEDCO (3x12)                                     | SS     | 3x12                                    | 67.05         | -           | 36(LE)+ 6(U)                 | 42                    | RMU&LE   | 2022-27            |
| 23                                                                 | Kodayar PH-I, TANGEDCO                                        | SS     | 1x60                                    | 88.48         | -           | 60 (LE)+ 10 (U)              | 70                    | RMU&LE   | 2023-24            |
| Kerala                                                             |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 24                                                                 | Kuttiyadi, KSEB (3x25)                                        | SS     | 3x25                                    | 377.41        | 0.625       | 75.00 (LE) + 7.5 (U)         | 82.5                  | RMU&LE   | 2023-24            |
| Odisha                                                             |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 25                                                                 | Balimela, OHPCL (6x60)                                        | SS     | 6x60                                    | 382.91        | 86.27       | 360(LE)                      | 360                   | RM&LE    | 2023-24            |
| Manipur                                                            |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 26                                                                 | Loktak, NHPC (3x35)                                           | CS     | 3x35                                    | 273.59        | 30.77       | 105 (LE)                     | 105                   | RM&LE    | 2023-24            |
| Sub Total(A)                                                       |                                                               |        | 5485.15                                 | 3954.31       | 1229.69     | 3047.5 [2868 (LE)+ 179.5(U)] | 5664.65               |          |                    |
| B. Ongoing Schemes – Under Tendering                               |                                                               |        |                                         |               |             |                              |                       |          |                    |
| Himachal Pradesh                                                   |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 27                                                                 | Giri, HPSEB (2x30)                                            | SS     | 2x30                                    | 139.80        | -           | 60.00 (LE)                   | 60                    | RM&LE    | 2024-25            |
| Uttarakhand                                                        |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 28                                                                 | Ramganaga, UJVNL (3x66)                                       | SS     | 3x66                                    | 455.20        | -           | 198(LE)                      | 198                   | RM&LE    | 2022-27            |
| 29                                                                 | Dhakrani, UJVNL (3x11.25)                                     | SS     | 3x11.25                                 | 137.31        | 4.91        | 33.75 (LE)                   | 33.75                 | RM&LE    | 2025-26            |
| Karnataka                                                          |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 30                                                                 | Kadra Dam Power House, KPCL (3x50)                            | SS     | 3x50                                    | 44.47         | 1.72        | 150 (LE)                     | 150                   | RM&LE    | 2022-23            |
| 31                                                                 | Kodasalli Dam Power House, KPCL (3x40)                        | SS     | 3x40                                    | 50.60         | 1.72        | 120 (LE)                     | 120                   | RM&LE    | 2022-23            |
| 32                                                                 | Gerusoppa Dam Power House (Sharavathy Tail Race), KPCL (4x60) | SS     | 4x60                                    | 59.66         | 2.21        | 240 (LE)                     | 240                   | RM&LE    | 2023-24            |
| 33                                                                 | Linganamakki Dam Power House, KPCL (2x27.5)                   | SS     | 2x27.5                                  | 56.20         | 1.85        | 55 (LE)                      | 55                    | RM&LE    | 2023-24            |
| Jharkhand                                                          |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 34                                                                 | Panchet U-1, DVC (2x40)                                       | CS     | 1x40 (U-1)                              | 121.85        | 2.19        | 40(LE) + 6(U)                | 46                    | RMU&LE   | 2023-24            |
| Meghalaya                                                          |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 35                                                                 | Umium St.III, (Kyrdekulai) MePGCL (2x30)                      | SS     | 2x30                                    | 408.00        | 1.20        | 60(LE) + 6(U)                | 66                    | RMU&LE   | 2022-27            |
| Sub Total(B)                                                       |                                                               |        | 956.75                                  | 1473.09       | 15.80       | 968.75 [956.75 (LE)+ 12(U)]  | 968.75                |          |                    |
| C. Ongoing Schemes – Under DPR Preparation/ Finalisation/ Approval |                                                               |        |                                         |               |             |                              |                       |          |                    |
| Uttarakhand                                                        |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 36                                                                 | Kulhal, UJVNL (3x10)                                          | SS     | 3x10                                    | 115.24        | -           | 30(LE)                       | 30                    | RM&LE    | 2022-27            |
| Madhya Pradesh                                                     |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 37                                                                 | Gandhi Sagar, MPPGCL                                          | SS     | 5x23                                    | 329.64        | 4.97        | 115 (LE)                     | 115                   | RM&LE    | 2026-27            |
| 38                                                                 | Pench, MPPGCL (2x80)                                          | SS     | 2x80                                    | 13.36         | 0.36        | -                            | 160                   | R&M      | 2024-25            |
| 39                                                                 | Bansagar Ton-I, MPPGCL (3x105)                                | SS     | 3x105                                   | 92.95         | 10.34       | -                            | 315                   | R&M      | 2025-26            |
| Karnataka                                                          |                                                               |        |                                         |               |             |                              |                       |          |                    |
| 40                                                                 | Supa Dam Power House, KPCL (2x50)                             | SS     | 2x50                                    | 47.91         | 2.2         | 100 (LE)                     | 100                   | RM&LE    | 2023-24            |
| 41                                                                 | Sharavathy Generating                                         | SS     | 10x103.5                                | 196.56        | 11.07       | 1035 (LE)                    | 1035                  | RM&LE    | 2023-24            |
| 42                                                                 | MGHE, KPCL (4x21.6+4x13.2)                                    | SS     | 4x21.6+ 4x13.2                          | 97.00         | 7.75        | 139.2 (LE)                   | 139.2                 | RM&LE    | 2023-24            |

| (Sheet 3 of 4)                         |                                              |        |                                         |               |             |                          |                       |          |                    |
|----------------------------------------|----------------------------------------------|--------|-----------------------------------------|---------------|-------------|--------------------------|-----------------------|----------|--------------------|
| Sl. No                                 | Name of Project, Agency Inst. Cap. (No.X MW) | CS/ SS | Capacity Covered Under RMU&LE (No.x MW) | Est. Cost     | Actual Exp. | Benefits (MW)            | Capacity after RMU&LE | Category | Year of Completion |
|                                        |                                              |        |                                         | (Rs. in Crs.) |             |                          |                       |          |                    |
| Tamil Nadu                             |                                              |        |                                         |               |             |                          |                       |          |                    |
| 43                                     | Kodayar PH-II, TANGEDCO (1x40 )              | SS     | 1x40                                    | -             | -           | 40.0(LE)+ 6(U)           | 46                    | RMU&LE   | 2026-27            |
| West Bengal                            |                                              |        |                                         |               |             |                          |                       |          |                    |
| 44                                     | Maithon, DVC (2x20+1x23.2)                   | CS     | 2x20 (U-1&3)                            | 109.29        | 7.76        | 40.00 (LE)               | 40                    | RM&LE    | 2024-25            |
| Assam                                  |                                              |        |                                         |               |             |                          |                       |          |                    |
| 45                                     | Khandong Power Station,                      | CS     | 2x23                                    | 189.81        | 8.03        | 46 (LE)                  | 46                    | RM&LE    | 2024-25            |
| 46                                     | Kopili Power Station, NEEPCO (4x50)          | CS     | 4x50                                    | 1117.07       | 436.46      | 200(LE)                  | 200                   | RM&LE    | 2023-24            |
| Sub Total(C)                           |                                              |        | 2220.20                                 | 2308.83       | 488.94      | 1751.2 1745.2(LE)+ 6(U)] | 2226.20               |          |                    |
| D. Ongoing Schemes – Under RLA Studies |                                              |        |                                         |               |             |                          |                       |          |                    |
| Jammu & Kashmir (UT)                   |                                              |        |                                         |               |             |                          |                       |          |                    |
| 47                                     | Salal Stage-I, (Unit 1,2 &3) NHPC (6x115)    | CS     | 3x115                                   | -             | -           | 345 (LE)                 | 345                   | RM&LE    | 2022-27            |
| Madhya Pradesh                         |                                              |        |                                         |               |             |                          |                       |          |                    |
| 48                                     | Bargi, MPPGCL (2x45)                         | SS     | 2x45                                    | 21.63         | 2.42        | -                        | 90                    | R&M      | 2025-26            |
| Maharashtra                            |                                              |        |                                         |               |             |                          |                       |          |                    |
| 49                                     | Vaitarna, MSPGCL (1x60)                      | SS     | 1x60                                    | -             | -           | 60 (LE)                  | 60                    | RM&LE    | 2022-27            |
| 50                                     | Koyna Dam foot (Right Bank), MSPGCL (2x20)   | SS     | 2x20                                    | -             | -           | 40 (LE)                  | 40                    | RM&LE    | 2022-27            |
| 51                                     | Koyna St-3, MSPGCL (4x80)                    | SS     | 4x80                                    | -             | -           | 320 (LE)                 | 320                   | RM&LE    | 2022-27            |
| 52                                     | Tillari, MSPGCL (1x60)                       | SS     | 1x60                                    | -             | -           | 60 (LE)                  | 60                    | RM&LE    | 2022-27            |
| 53                                     | Bhira Tail race, MSPGCL (2x40)               | SS     | 2x40                                    | -             | -           | 80 (LE)                  | 80                    | RM&LE    | 2022-27            |
| Andhra Pradesh                         |                                              |        |                                         |               |             |                          |                       |          |                    |
| 54                                     | Machkund St.I & St.II,                       | SS     | 3x17+ 3x23                              | 500.00        | -           | 120 (LE) +9 (U)          | 129                   | RMU&LE   | 2025-27            |
| 55                                     | Tungabhadra Dam, APGENCO (4x9)               | SS     | 4x9                                     | 175.00        | -           | 36 (LE)                  | 36                    | RM&LE    | 2025-26            |
| 56                                     | Hampi Canal PH, APGENCO (4x9)                | SS     | 4x9                                     | 175.00        | -           | 36 (LE)                  | 36                    | RM&LE    | 2025-26            |
| 57                                     | Lower Sileru, APGENCO                        | SS     | 4x115                                   | 350.00        | 1.80        | 460(LE)                  | 460                   | RM&LE    | 2025-27            |
| Tamil Nadu                             |                                              |        |                                         |               |             |                          |                       |          |                    |
| 58                                     | Kundah-I, TANGEDCO (3x20)                    | SS     | 3x20                                    | -             | -           | 60 (LE)                  | 60                    | RM&LE    | 2022-27            |
| 59                                     | Kundah-II, TANGEDCO (5x35)                   | SS     | 5x35                                    | -             | -           | 175 (LE)                 | 175                   | RM&LE    | 2022-27            |
| 60                                     | Kundah-III, TANGEDCO (3x60)                  | SS     | 3x60                                    | -             | -           | 180 (LE)                 | 180                   | RM&LE    | 2022-27            |
| 61                                     | Kundah-IV, TANGEDCO (2x50)                   | SS     | 2x50                                    | -             | -           | 100 (LE)                 | 100                   | RM&LE    | 2022-27            |
| 62                                     | Kundah-V, TANGEDCO (2x20)                    | SS     | 2x20                                    | -             | -           | 40 (LE)                  | 40                    | RM&LE    | 2022-27            |
| 63                                     | Mettur Tunnel, TANGEDCO (4x50)               | SS     | 4x50                                    | -             | -           | 200 (LE)                 | 200                   | RM&LE    | 2022-27            |
| 64                                     | Sarkarpathy, TANGEDCO (1x30)                 | SS     | 1x30                                    | -             | -           | 30 (LE)                  | 30                    | RM&LE    | 2022-27            |
| 65                                     | Sholayar-II, TANGEDCO (1x25)                 | SS     | 1x25                                    | -             | -           | 25 (LE)                  | 25                    | RM&LE    | 2022-27            |
| 66                                     | Suruliyar, TANGEDCO (1x35)                   | SS     | 1x35                                    | -             | -           | 35 (LE)                  | 35                    | RM&LE    | 2022-27            |

(Sheet 4 of 9)

| Sl. No          | Name of Project, Agency Inst. Cap. (No.X MW) | CS/ SS | Capacity Covered Under RMU&LE (No.x MW) | Est. Cost     | Actual Exn. | Benefits (MW)                    | Capacity after RMU&LE | Category | Year of Completion |
|-----------------|----------------------------------------------|--------|-----------------------------------------|---------------|-------------|----------------------------------|-----------------------|----------|--------------------|
|                 |                                              |        |                                         | (Rs. in Crs.) |             |                                  |                       |          |                    |
| 67              | Kadamparai, PH TANGEDCO (4x100)              | SS     | 4x100                                   | -             | -           | 400 (LE)                         | 400                   | RM&LE    | 2022-27            |
| 68              | Aliyar, TANGEDCO (1x60)                      | SS     | 1x60                                    | -             | -           | 60 (LE)                          | 60                    | RM&LE    | 2022-27            |
| Kerala          |                                              |        |                                         |               |             |                                  |                       |          |                    |
| 69              | Idukki 2 <sup>nd</sup> stage, KSEB           | SS     | 3x130                                   | -             | -           | 390 (LE)                         | 390                   | RM&LE    | 2022-27            |
| 70              | Sabarigiri, KSEB (Unit-1,2,3, 5 & 6) (4x55+) | SS     | 4x55+ 1x60                              | 155.9         | -           | 280 (LE) + 20 (U)                | 300                   | RMU&LE   | 2022-27            |
| 71              | Idamalayar, KSEB (2x37.5)                    | SS     | 2x37.5                                  | -             | -           | 75 (LE)                          | 75                    | RM&LE    | 2022-27            |
| 72              | Porigalkathu, KSEB (4x9)                     | SS     | 4x9                                     | -             | -           | -                                | 36                    | R&M      | 2022-27            |
| Odisha          |                                              |        |                                         |               |             |                                  |                       |          |                    |
| 73              | Hirakud-I (Burla), OHPC Unit 7 (1x37.5 MW)   | SS     | 1x37.5                                  | -             | -           | 37.5 (LE)                        | 37.5                  | RM&LE    | 2022-27            |
| 74              | Rengali, OHPC                                | SS     | 5x50                                    | -             | -           | 250 (LE)                         | 250                   | RM&LE    | 2022-27            |
| 75              | Upper Kolab, OHPC (4x80)                     | SS     | 4x80                                    | -             | -           | 320 (LE)                         | 320                   | RM&LE    | 2022-27            |
| Jharkhand       |                                              |        |                                         |               |             |                                  |                       |          |                    |
| 76              | Subernrekha, JUUNL                           | SS     | 2x65                                    | -             | -           | 130(LE)                          | 130                   | RM&LE    | 2022-27            |
| Meghalaya       |                                              |        |                                         |               |             |                                  |                       |          |                    |
| 77              | Umiam-umtru Stage-IV,                        | SS     | 2x30                                    | -             | -           | 60(LE)                           | 60                    | RM&LE    | 2022-27            |
| Sub Total(D)    |                                              |        | 4530.50                                 | 1355.90       | 1.80        | 4433.5 [4404.5(LE)+ 29(U)]       | 4559.50               |          |                    |
| Total (A+B+C+D) |                                              |        | 13192.60                                | 9092.13       | 1736.23     | 10200.95 [9974.45(LE)+ 226.5(U)] | 13419.10              |          |                    |

Abbreviations: R&M – Renovation & Modernisation;. U – Uprating; LE – Life Extension; Res – Restoration; MW – Mega Watt; CS-Central Sector; SS- State Sector

## State-wise List of Hydro RMU&amp;LE schemes programmed for completion during 2027-32

| State-wise List of Hydro RMU&LE schemes programmed for completion during 2027-32 |                                              |        |                                         |               |             |                           |                       |          |                   |
|----------------------------------------------------------------------------------|----------------------------------------------|--------|-----------------------------------------|---------------|-------------|---------------------------|-----------------------|----------|-------------------|
| Sl. No                                                                           | Name of Project, Agency Inst. Cap. (No.X MW) | CS/ SS | Capacity Covered Under RMU&LE (No.x MW) | Est. Cost     | Actual Exp. | Benefits (MW)             | Capacity after RMU&LE | Category | Completion Target |
|                                                                                  |                                              |        |                                         | (Rs. in Crs.) |             |                           |                       |          |                   |
| A. Ongoing Schemes – Under RLA Studies                                           |                                              |        |                                         |               |             |                           |                       |          |                   |
| Jammu & Kashmir (UT)                                                             |                                              |        |                                         |               |             |                           |                       |          |                   |
| 1                                                                                | Tanakpur, NHPC 3x31.4 MW                     | CS     | 3x31.4                                  | -             | -           | 94.2 (LE)                 | 94.2                  | RM&LE    | 2027-32           |
| 2                                                                                | Chamera-I, NHPC 3x180 MW                     | CS     | 3x180                                   | -             | -           | 540 (LE)                  | 540                   | RM&LE    | 2027-32           |
| 3                                                                                | Salal Stage-II, (Unit 4,5 &6) NHPC (6x115)   | CS     | 3x115                                   | -             | -           | 345 (LE)                  | 345                   | RM&LE    | 2027-32           |
| Uttarakhand                                                                      |                                              |        |                                         |               |             |                           |                       |          |                   |
| 4                                                                                | Chibro, UJVNL (4x60)                         | SS     | 4x60                                    | 184.88        | -           | 240 (LE)                  | 240                   | RM&LE    | 2027-32           |
| 5                                                                                | Khodri, UJVNL (4x30)                         | SS     | 4x30                                    | 169.63        | -           | 120 (LE)                  | 120                   | RM&LE    | 2027-32           |
| Total (A)                                                                        |                                              |        | 1339.20                                 | 354.51        | 0.00        | 1339.2 [1339.2(LE)+ 0(U)] | 1339.20               |          |                   |

Abbreviations: R&M – Renovation & Modernisation; U – Uprating; LE – Life Extension; Res – Restoration;  
MW – Mega Watt; CS-Central Sector; SS- State Sector

# CHAPTER-10

## DEFINITIONS AND ABBREVIATIONS

## CHAPTER-10

### DEFINITIONS AND ABBREVIATIONS

#### 10.1 DEFINITIONS

The definitions of different performance indices and other terms referred to in this review are as under:

**a) Capacity:** Capacity in MW is the Installed or Uprated/Derated capacity of the unit.

**b) Forced Outage Non-Availability (FO) (%)**

$$= \frac{(Cf1 \times hf1 + Cf2 \times hf2 + \dots + Cfn \times hfn) \times 100}{CxH}$$

Where Cf1, Cf2 ..... Cfn are the capacities in MW of the generating units of the station on forced outage and hf1, hf2 ..... hfn are the duration of each outage in hours during the year. C is the total installed capacity of the station in MW and H is the total period in hours during the year.

**c) Planned Maintenance Non-Availability (PM) (%)**

$$= \frac{(Cp1 \times hp1 + Cp2 \times hp2 + \dots + Cpn \times hpn) \times 100}{CxH}$$

Where Cp1, Cp2 ..... Cfn are the capacities in MW of the generating units of the station on planned shutdown and hp1, hp2 ..... are the duration of each shutdown in hours during the year. C is the total installed capacity of the station in MW and H is the total period in hours during the year.

**d) Operating availability (OA) (%) = (100-FO-PM)**

**e) Miscellaneous Non-Availability:** Non-Availability of generating units due to one or more of the following factors:

- Low reservoir level/poor inflow
- Transmission line faults/constraints
- Excess weeding/silting
- No/reduced system demand
- Too high tail water level
- No irrigation demand
- Grid disturbance/failure
- Reserve shutdown/spinning reserve

- f) **Design Energy:** The quantum of energy which could be generated in a 90% dependable year with 95% availability of installed capacity of the generating station.
- g) **Targeted Energy:** Estimated energy generation during the year based on the likely rainfall data, storage position of the reservoirs and past records of energy generation etc.
- h) **Full Reservoir Level (FRL):** The maximum level up to which the water could normally be stored in the reservoir for conservation and regulation for power generation.
- i) **Minimum Draw Down Level (MDDL):** The minimum level up to which the reservoir could be depleted under normal operating conditions.
- j) **Types of H.E. Scheme:** The H.E. Schemes have been classified into following four categories:
- Run-of-River without pondage
  - Run-of River with pondage
  - Storage Schemes
    - Purely power
    - Multipurpose projects
  - Pumped Storage Schemes

## 10.2 Abbreviations

|             |                         |                     |
|-------------|-------------------------|---------------------|
| <b>MW</b>   | Mega Watt               | ( $10^6$ Watts)     |
| <b>KWH</b>  | Kilo Watt hour (1 unit) | ( $10^3$ Watts-hrs) |
| <b>MU</b>   | Million Units           | ( $10^6$ Units)     |
| <b>MCM</b>  | Million Cubic Meters    | ( $10^6$ Cu.M.)     |
| <b>FRL</b>  | Full Reservoir Level    |                     |
| <b>MDDL</b> | Minimum Draw Down Level |                     |
| <b>HRT</b>  | Head Race Tunnel        |                     |
| <b>F.O.</b> | Forced Outage           |                     |
| <b>P.M.</b> | Planned Maintenance     |                     |

## Abbreviations of Agencies

| <b>Northern Region</b> |                  |               |                                                  |
|------------------------|------------------|---------------|--------------------------------------------------|
| 1                      | Himachal Pradesh | ADHPL         | Allain Duhangan Hydro Power Limited              |
|                        |                  | BVPC Limited  | Beas Valley Power. Corp. Ltd. (BVPC)             |
|                        |                  | EPPL          | Everest Power Private Limited                    |
|                        |                  | GBHPPL        | Greenko Budhil Hydro Power Pvt. Limited          |
|                        |                  | HBPCL         | Himachal Baspa Power Company Limited             |
|                        |                  | HPPCL         | Himachal Pradesh Power Corporation Limited       |
|                        |                  | HPSEB Limited | Himachal Pradesh State Electricity Board Limited |
|                        |                  | HSPCL         | Himachal Sorang Power Private Limited            |
|                        |                  | IAEPL         | IA Hydro Energy Pvt Ltd                          |
|                        |                  | JSW           | JSW Energy Ltd.                                  |
|                        |                  | GMR BHHPL     | GMR Bajoli Holi Hydro Power Private Limited      |
|                        |                  | MPCL          | Malana Power Company Limited                     |
|                        |                  | NTPGPL        | Tidong Power Generation Private Limited          |
|                        |                  | NHPC Limited  | National Hydro Power Corporation Limited         |
|                        |                  | NTPC Limited  | National Thermal Power Corporation Limited       |
|                        |                  | SJVN Limited  | Satluj Jal Vidyut Nigam Limited                  |
| 2                      | Jammu & Kashmir  | JKSPDC        | J&K State Power Development Corporation.         |
| 3                      | Punjab           | BBMB          | Bhakra Beas Management Board                     |
|                        |                  | PSPCL         | Punjab State Power Corporation Limited           |
| 4                      | Rajasthan        | RRVUNL        | Rajasthan Rajya Vidyut Utpadan Nigam Limited     |
| 5                      | Uttar Pradesh    | UPJVNL        | Uttar Pradesh Jal Vidyut Nigam Limited           |
| 6                      | Uttarakhand      | THDC          | Tehri Hydro Development Corporation              |
|                        |                  | UJVNL         | Uttarakhand Jal Vidyut Nigam Limited             |
|                        |                  | JPPVL         | Jaiprakash Power Pvt. Venture Limited            |
|                        |                  | AHPC          | Alaknanda Hydro Power Company                    |
| <b>Western Region</b>  |                  |               |                                                  |
| 1                      | Gujarat          | GSECL         | Gujarat State Electricity Corporation Limited    |
|                        |                  | SSNNL         | Sardar Sarovar Narmada Nigam Limited             |
| 2                      | Madhya Pradesh   | MPPGCL        | Madhya Pradesh Power Generation Co. Limited      |
|                        |                  | NHDC          | Narmada Hydroelectric Development Co. Limited    |
| 3                      | Chhatisgarh      | CSPGCL        | Chhatisgarh State Power Generation Co. Limited   |
| 4                      | Maharashtra      | DLHPPL        | Dodson-Lindblom Hydro Power Private Limited      |

|                             |                |          |                                                        |
|-----------------------------|----------------|----------|--------------------------------------------------------|
|                             |                | MSPGCL   | Maharashtra State Power Generating Co. Limited         |
|                             |                | TPCL     | Tata Power Company Limited                             |
| <b>Southern Region</b>      |                |          |                                                        |
| 1                           | Andhra Pradesh | APGENCO  | Andhra Pradesh Power Generation Corporation Ltd.       |
| 2                           | Karnataka      | KPCL     | Karnataka Power Corporation Limited                    |
| 3                           | Kerala         | KSEBL    | Kerala State Electricity Board Limited                 |
| 4                           | Telangana      | TSGENCO  | Telangana State Power Generation Corporation Ltd.      |
| 5                           | Tamil Nadu     | TANGEDCO | Tamil Nadu Generation & Distribution Co. Limited       |
| <b>Eastern Region</b>       |                |          |                                                        |
| 1                           | Jharkhand      | JUUNL    | Jharkhand Urja Utpadan Nigam Limited                   |
|                             |                | DVC      | Damodar Valley Corporation                             |
| 2                           | Odisha         | OHPC     | Odisha Hydro Power Corporation                         |
| 3                           | Sikkim         | GIPL     | Gati Infrastructure Pvt. Limited                       |
|                             |                | DEPL     | Dans Energy Private Limited                            |
|                             |                | TUL      | Teesta Urja Limited                                    |
|                             |                | SKPPPPL  | Sneha Kinetic Power Projects Pvt. Limited              |
|                             |                | SEPL     | Shiga Energy Pvt. Limited                              |
| 4                           | West Bengal    | WBSEDCL  | West Bengal State Electricity Distribution Co. Limited |
| <b>North Eastern Region</b> |                |          |                                                        |
| 1                           | Assam          | APGCL    | Assam Power Generation Co. Limited                     |
|                             |                | NEEPCO   | North Eastern Electric Power Corporation Limited       |
| 2                           | Meghalaya      | MePGCL   | Meghalaya Power Generation Corporation Limited         |