



भारत सरकार  
Government of India  
विद्युत मंत्रालय  
Ministry of Power  
केन्द्रीय विद्युत प्राधिकरण  
Central Electricity Authority  
प्रोटोकॉल इकाई, सचिव का कार्यालय  
Protocol Unit, Office of Secretary

**विषय:- के.वि.प्रा. की वार्षिक विवरण (Annual Report) 2017-2018 के सम्बन्ध में।**

केन्द्रीय विद्युत प्राधिकरण की वार्षिक रिपोर्ट वर्ष 2017-2018 के अंग्रेजी संस्करण की एक प्रति आपके अवलोकनार्थ संलग्न हैं। यह रिपोर्ट विद्युत क्षेत्र के कार्य निष्पादन तथा देश के विद्युत विकास में के.वि.प्रा.की भूमिका को दर्शाती हैं। इस सन्दर्भ में आप अपने महत्वपूर्ण सुझाव प्रोटोकॉल यूनिट के ई-मेल [protocol.cea@gov.in](mailto:protocol.cea@gov.in) पर प्रेषित कर सकते हैं।

**संलग्न:- वार्षिक विवरण (Annual Report) 2017-2018 - एक प्रति ।**

*अजय आर्या*  
५/१०/१८  
(अजय आर्या)

उप निदेशक एवं प्रोटोकॉल अधिकारी  
e-mail : [protocol.cea@gov.in](mailto:protocol.cea@gov.in)  
011-26101696(Telefax)  
9911373455 (M), IC .NO-2216

**निदेशक (आई टी)- साफ्ट कापी एवं डीवीडी प्रेषित की जा रही है। कृप्या करके इसे के.वि.प्रा.की वेबसाइट पर अपलोड करे ।**

पत्र संख्या- के.वि.प्रा/प्रोटोकॉल/2018-19/595

दिनांक : 04.10.2018



ANNUAL REPORT 2017-2018

# ANNUAL REPORT 2017-18

**INTEGRATED POWER DEVELOPMENT SCHEME (IPDS)**  
PROVIDING RELIABLE AND QUALITY POWER SUPPLY TO CITIES

Solar ₹28,400 Crore Sanctioned

Strengthening of Distribution Network in over 3600 Towns

All Towns to be IT Enabled for Automated Measurement of System Losses

Har ghar bijli... Har ghar paani...  
Gaan-gaan falli khushaali...

Deen Dayal Upadhyaya Gram Jyoti Yojana

Electrification of all remaining HTs  
Outlay: Rs 16,320 Cr.

**सौभाग्य**  
प्रत्येक घर के लिए बिजली हर घर में है या नहीं

DISCOMs at the doorsteps




रेगन टैग हर घर में है या नहीं

**24x7 POWER FOR ALL**

Brighter Lighting  
Energy Saving  
Environment Friendly

**UJALA**  
LED Bulbs Under "UJALA" Scheme

Smart meter  
SCADA/DMS  
Solar Irrigation



GOVERNMENT OF INDIA  
MINISTRY OF POWER  
CENTRAL ELECTRICITY AUTHORITY

# ANNUAL REPORT 2017-18



सत्यमेव जयते

**GOVERNMENT OF INDIA  
MINISTRY OF POWER  
CENTRAL ELECTRICITY AUTHORITY**

# THE AUTHORITY

(As on 31.03.2018)




**Sh. Ravindra Kumar Verma**  
Chairperson and Member (G.O.&D)



**Dr. Somit Dasgupta**  
Member (E&C)



**Sh. K.K. Arya**  
Member (Hydro)



**Sh. Pankaj Batra**  
Member (Planning)




**Sh. P.S.Mhaske**  
Member (Power System)



**Sh. P.D. Siwal**  
Member (Thermal)

**Organization Chart of CEA  
(As on 31.03.2018)**



**CENTRAL ELECTRICITY AUTHORITY**  
**Sewa Bhawan, R. K. Puram, New Delhi-110066**  
**CEA Website: [www.cea.nic.in](http://www.cea.nic.in)**

**Sub ordinate Offices:**

**REGIONAL POWER COMMITTEES (RPCs)**

1. **Member Secretary**, Eastern Regional Power Committee, 14, Golf Club Road, Tollygunje, Kolkata-700033
2. **Member Secretary**, Northern Regional Power Committee, 18-A, Qutab Institutional Area, Shaheed Jeet Singh Marg, Katwaria Sarai, New Delhi-110016
3. **Member Secretary**, North Eastern Regional Power Committee, NERPC Complex, Dong Parmaw, Lapalang, Shillong-793006
4. **Member Secretary**, Southern Regional Power Committee, 29, Race Course Cross Road, Bengaluru-560009
5. **Member Secretary**, Western Regional Power Committee, F-3, MIDC Area, Marol, Opposite SEEPZ, Central Road, Andheri (East), Mumbai-400093

**REGIONAL POWER SURVEY OFFICES (RPSOs)**

1. **Dy. Director, Regional Power Survey Office (East)**, 201, C.G.O. Complex, DF-Block, Salt Lake City, Kolkata-700064
2. **Dy. Director, Regional Power Survey Office (North)**, West Block II, R. K. Puram, New Delhi-110066
3. **Dy. Director, Regional Power Survey Office (South)**, Letter Box No. 38, 6<sup>th</sup> Floor, 'F' Wing, Kendriya Sadan, Koramangala, Bengaluru-560034
4. **Dy. Director, Regional Power Survey Office (West)**, F-3, 5<sup>th</sup> Floor, MIDC Area, Marol, Opposite SEEPZ, Central Road, Andheri (East), Mumbai-400093

**REGIONAL INSPECTORATE OFFICES (RIOs)**

1. **Superintending Engineer, Regional Inspectorate Office (East)**, ERPC Building, 14 Golf Club Road, Tollygunje, Kolkata-700033
2. **Superintending Engineer, Regional Inspectorate Office (North)**, 18-A, Qutab Institutional Area, Shaheed Jeet Singh Marg, Katwaria Sarai, New Delhi-110016
3. **Superintending Engineer, Regional Inspectorate Office (North East)**, NERPC Complex, 3<sup>rd</sup> Floor, Dong Parmaw, Lapalang, Shillong-793006
4. **Superintending Engineer, Regional Inspectorate Office (South)**, Shastri Bhawan, Chennai-600006.
5. **Superintending Engineer, Regional Inspectorate Office (West)**, F-3, MIDC Area, Marol, Opposite SEEPZ, Central Road, Andheri (East), Mumbai-400093

## INDEX


| CHAPTER      | DESCRIPTION                                       | P. NO. |
|--------------|---|--------|
| CHAPTER - 1  | CEA as an Organization                            | 1      |
| CHAPTER - 2  | Planning for Power and Development                | 16     |
| CHAPTER - 3  | Power Systems Planning and Development            | 34     |
| CHAPTER - 4  | Grid Management                                   | 53     |
| CHAPTER - 5  | Hydro Power Development                           | 62     |
| CHAPTER - 6  | Thermal Power Development                         | 71     |
| CHAPTER - 7  | Distribution and Rural Electrification            | 94     |
| CHAPTER - 8  | Design & Engineering Services                     | 108    |
| CHAPTER - 9  | Economic and Commercial Aspects of Power Industry | 112    |
| CHAPTER - 10 | Power Generation                                  | 125    |
| CHAPTER - 11 | Power Development in North-Eastern Region         | 134    |
| CHAPTER - 12 | Training and Human Resource Development           | 148    |

| ANNEXURE    |  | P. NO. |
|-------------|--|--------|
| ANNEXURE-2A | Plant-wise details of the Coal receipt and consumption during 2017-18  | 152    |
| ANNEXURE-3A | Details of the Inter-Regional Capacity up to the end of 2017-18  | 161    |
| ANNEXURE-3B | Issues pertaining to Transmission System Planning taken up during 2017-18  | 163    |
| ANNEXURE-3C | Details of the Schemes notified through Tariff Based Competitive Bidding (TBCB)                                  | 169    |
| ANNEXURE-3D | Issues Pertaining to Transmission System Planning taken up in Empowered Committee on Transmission during 2017-18 | 171    |
| ANNEXURE-3E | Cost of the stated Transmission Schemes estimated by the Cost Committee constituted for this purpose             | 172    |

|                     |  |     |
|---------------------|--|-----|
| <b>ANNEXURE-3F</b>  | Progress under Green Energy Corridor during 2017-18  | 173 |
| <b>ANNEXURE-3G</b>  | Details of Failed Transmission Lines reported to CEA   | 176 |
| <b>ANNEXURE-3H</b>  | List of failures of Transformers and Rectors received in CEA during 2017-18  | 177 |
| <b>ANNEXURE-3I</b>  | Transmission Lines Completed during FY 2017-18   | 178 |
| <b>ANNEXURE-3J</b>  | Substations Completed during FY 2017-18  | 187 |
| <b>ANNEXURE-4A</b>  | Power Supply Position for 2017-18  | 195 |
| <b>ANNEXURE-4B</b>  | Details of Total Share of the States from Central Generating Stations  | 196 |
| <b>ANNEXURE-5A</b>  | PFRS under 50 000 MW Hydroelectric Initiative  | 198 |
| <b>ANNEXURE-5B</b>  | Hydro Capacity addition during 2017-18   | 202 |
| <b>ANNEXURE-5C</b>  | Tentative Programme for Hydro Capacity addition for 2018-19  | 203 |
| <b>ANNEXURE-6A</b>  | Thermal Capacity Addition Target/Achievement (RFD) for the year 2017-18  | 204 |
| <b>ANNEXURE-6B</b>  | Thermal Capacity Addition Target for the year 2017-18  | 206 |
| <b>ANNEXURE-9A</b>  | Outstanding Dues of Power Utilities (Principal And Surcharge) Payable to Central Public Sector Undertakings (CPSUs) as on 31.03.2018 | 207 |
| <b>ANNEXURE-9B</b>  | Estimated Average Rates of Electricity (upto 01.04.2017)   | 211 |
| <b>ANNEXURE-10A</b> | All India Sector wise /Organisation wise Generation Target, Actual Generation & PLF(%) for the year 2017-18                          | 212 |
| <b>ANNEXURE-10B</b> | All India Installed Capacity (in MW) of Power Stations located in the Regions of Main Land and Islands (as on 31.03.2018)            | 217 |
| <b>ANNEXURE-12A</b> | Details of Foreign Tours performed during 2017-18  | 231 |



## From the Chairperson



Recognizing the emphasis of the Government of India on a sustained growth of the country, initiatives have been taken to increase power generation in the country and to provide reliable and quality power to all. With consistent efforts in this direction, the Power Sector in India has achieved a capacity addition of 9.505 GW in conventional power and 11.778 GW of Renewable power during the year 2017-18 raising the Installed Generation Capacity to around 344 GW as on 31.03.2018 comprising of 223 GW of Thermal, 45 GW of Hydro, 7 GW of Nuclear and 69 GW of Renewables.

While the coal based generation is expected to continue being the main stay of electricity generation, the share of generation from Renewables is on a growth trajectory and it was about 20.06% of total Installed Capacity contributing 7.8% of total energy generation in the country during 2017-18. The total electricity supplied in the country during 2017-18 was of the order of 1205 BU and the peak demand met was 161 GW.

Government of India has launched Pradhan Mantri Sahaj Bijli Har Ghar Yojana—“**Saubhagya**” on 11<sup>th</sup> October, 2017 for providing last mile connectivity and electricity connections to all households in rural and urban areas. During the year 2017-18, 40.46 lacs of households have been electrified. Further, 99.94 % of the inhabited villages in the country have been electrified by end of 2017-18. Smart meters which enable two-way communication between the meter and the central system for efficient accounting and control of electricity, have been introduced in the Indian Distribution sector.

One of the functions of CEA is to accord concurrence to hydroelectric projects. During the year 2017-18, CEA had appraised and accorded concurrence to three (3) hydro generation schemes aggregating to 5531 MW capacity.

Besides the statutory obligations, CEA rendered engineering and consultancy to the utilities in India and in the neighboring countries. During the year 2017-18, CEA rendered design and engineering to about 5110 MW of hydro generating capacity comprising four (4) Hydro Electric Projects which include Punatsangchhu Stage-I (6x200 MW) and Punatsangchhu Stage-II (6x170 MW) Projects in Bhutan. Further, technical advice related to transmission system has been rendered to various power utilities and agencies.

Central Electricity Authority (CEA) promotes and assists in the timely completion of transmission projects for improving and augmenting the power system in the country. During the year 2017-18, 23119 CKm of Transmission lines has been laid down and 86193 MVA of Transformation Capacity has been commissioned. The Inter-regional power transmission capacity has increased

from 75 GW to 86 GW during the year 2017-18. CEA has prepared a Compendium of tested tower designs for EHV transmission lines for the use of various power utilities.

Section 3(4) of the Electricity Act 2003 mandates CEA to prepare the National Electricity Plan (NEP) in accordance with the National Electricity Policy and to notify the Plan once in five years. In fulfillment of above obligation, CEA has prepared the **National Electricity Plan (Volume I)-Generation** and has notified the same on 28<sup>th</sup> March, 2018. The NEP covers review of the capacity addition in 12<sup>th</sup> Plan (2012-2017) and perspective planning for the 2017-22 & 2022-27 periods. This Plan is based on the demand forecast of the 19<sup>th</sup> Electric Power Survey (EPS) conducted by CEA. The Revised **National Electricity Plan (Volume II)-Transmission** was prepared and submitted to Ministry of Power for approval.

Large scale integration of renewables is a challenging task and its successful integration requires appropriate solutions. In order to look into various aspects, a Committee of CEA was constituted to study optimal location of various types of balancing energy sources/energy storage devices to facilitate grid integration of Renewable Energy Sources. The Committee submitted Report to Ministry of Power (MoP) on 15.12.2017. The Report covers, among other things, the balancing requirement, Ancillary market development and sharing of cost of the same.

CEA plays a pivotal role in optimal utilization of coal and gas for the power sector. Based on the generation target of coal based plants, CEA estimated total coal requirement of 630 Million Tonnes (MT) for the year 2017-18 with 584 MT for plants designed on domestic coal and remaining 46 MT for plants designed on imported coal. The total coal consumption during 2017-18 was about 608 MT, with the power utilities importing 56.41 MT of coal comprising of 17.04 MT for blending with domestic coal and 39.37 MT for thermal power stations designed on imported coal. The gas allocations committed for power stations were not fulfilled even during 2017-18 with the supply of 30.72 MMSCMD to gas based power plants, as against the requirement of about 114 MMSCMD.

A new transparent coal allocation policy for power sector, 2017 SHAKTI (Scheme for Harnessing and Allocating Koyala Transparently in India) has been issued by Ministry of Coal in May, 2017. This new coal linkage policy would ensure a proper mechanism for sourcing coal by the power plants as per their schedules and would ensure that all projects are supplied coal as per their entitlement.

Coal based generation is likely to fuel and support the targeted GDP growth envisaged by the Government in years to come. Efforts are therefore being focused on improving the efficiency of coal based generation. New Environmental norms have been issued by Ministry of Environment, Forest and Climate Change (MoEF&CC) on 7<sup>th</sup> December 2015 for Thermal Power Stations making norms for Suspended Particulate Matter (SPM) more stringent than existing norms. Norms for SO<sub>x</sub>, NO<sub>x</sub> and Mercury along with norms for water consumption in Thermal Power Stations have been notified for the first time. In respect of complying with norms of SO<sub>2</sub> emission, the thermal power plants are required to be fitted with flue gas desulphurization (FGD) system. In this regard, CEA has prepared a standard technical specification for retrofit of wet limestone based FGD system in a typical 2x500MW power plant. An implementation plan which extends from the year 2018 to 2022 for compliance with above environmental norms has been prepared and submitted to MoEF&CC.

CEA has been playing a proactive role in development of Ultra Mega Power Projects (UMPPs) in respect of selection of sites, preparation of technical documents/studies, tie-up of inputs and the

bidding process. The Standard Bidding Documents (SBDs) for domestic coal & imported coal have been revised and are under approval. The preparation of SBD for coal linkage based UMPP is under process. After the issue of these SBDs by Government, further bidding of UMPPs can be taken up.

On behalf of Ministry of Power (MoP), CEA has been actively monitoring the Fly Ash generation at coal/lignite based thermal power station (TPS) in the country since 1996. The annual Fly ash utilization has remained about 60% of the fly ash generated in recent years and reached to 63.28 % in 2016-17. CEA is actively involved in planning and development of a **web based monitoring system** on which feeding of data by the Thermal Power Stations is under progress. Further, a mobile application “**ASH TRACK**”, which is a GIS-based interface between fly ash generators and potential fly ash users, has been developed and launched on 09.02.2018. This mobile application contains useful information regarding quantum of fly ash available at nearby TPS and contact details of nodal officer of the power station concerned for sending requisition of Ash.

As an impetus to Research and Development in Power Sector, CEA identified thrust areas for undertaking research in future, and organized conference / international conclave as promotional measure. CEA has submitted report on “Technical aspects of Charging Infrastructure for electric vehicle”. Further, as part of BIS Committee, CEA has developed safety/performance standards for Energy Storage System for finalization by the BIS Committee.

All out efforts are being made to enhance the usage of Hindi in official work in all the offices of CEA. This year, Hindi correspondence percentage achieved is 92.49% in Region “A”, 90.01% in Region “B” and 83.48% in Region “C”. In CEA most of the officers and employees are trained in Hindi language. The Hindi Fortnight was organized in CEA from 14.09.2017 to 28.09.2017 and prize distribution ceremony was also held for meritorious services/winners of contests in Hindi on 28.09.2017. During the year, four Hindi workshops were organized in which lectures were delivered by the Guest lecturers on different topics related to official language. CEA was entrusted additional responsibility of monitoring Hindi progress in 66 offices covered in *Nagar Rajbhasha Karvanyan Samiti* (NARAKAS) (South Delhi-II) by Northern Regional Implementation Office-1 (Delhi) of RajbhashaVibhag, MHA.

CEA has been at the forefront for development of **National Power Portal (NPP)** which has been launched on 14<sup>th</sup> November, 2017. NPP is a centralized portal for Indian Power Sector which facilitates online data capture/input (daily, monthly, annually) from generation, transmission and distribution utilities in the country and disseminate Power Sector Information (operational, capacity, demand, supply, consumption etc). A detailed framework for registration of all electricity generating units was prepared by CEA and it was approved by the Ministry of Power. In the framework, there is a provision of mandatory registration of all the electricity generating units of 0.5 MW and above capacity by assigning each of them a unique registration number.

With a view to provide timely and necessary human resource development, the officers/officials of CEA were deputed for various service related refresher training programmes, technical courses, workshops, seminars, conferences etc. During the year 2017-18, Induction Training for 26 CPES officers was completed on 29<sup>th</sup> September, 2017 and Induction Training for another 30 CPES officers was started on 1<sup>st</sup> January, 2018. Further, 15 Graduate and 2 Diploma holder apprentices have undergone training in CEA under the Apprentice Act, 1961 and Summer vacation internship/training was provided for 36 Engineers from various engineering colleges during the

year 2017-18. Besides, seven training institutes/centers were visited and accorded recognition/renewal of recognition in accordance with CEA(Measures Relating to Safety & Electric Supply) Regulation,2010 during the year 2017-18.

An amount of Rs. 114.79 crores has been utilized by CEA out of the allocated budget of Rs. 117.14 crore during the financial year 2017-18 which translates to utilization of 98% . It is heartening to mention that CEA has revised 1612 out of 1800 cases of pension/family pension on the recommendations of 7<sup>th</sup> Central Pay Commission during the year 2017-18. E-office Application has been launched in CEA on 1<sup>st</sup> January, 2018 for achieving the objective of “Less Paper” Office with a simplified, responsive and effective working environment in CEA.

In the end, I take this opportunity to express my deep appreciation for the committed efforts put in by one and all in the power sector especially the officers and staff of CEA in accomplishment of the above tasks. I hope that CEA will continue to work with the same zeal, devotion and co-operation for development of the power sector in the country.



**(Pankaj Batra)**  
**Chairperson, CEA**

## CHAPTER – 1

### CEA AS AN ORGANIZATION

#### 1.1 Organization of CEA

**1.1.1** The Central Electricity Authority (CEA) is a statutory organization originally constituted under Section 3(1) of the repealed Electricity (Supply) Act, 1948 since substituted by Section 70 of the Electricity Act, 2003. It was established as a part-time body in the year 1951 and made a full-time body in the year 1975.

**1.1.2** As per Section 70(3) of the **Electricity Act, 2003**, the Authority shall consist of not more than fourteen members (including its Chairperson) of whom not more than eight shall be full-time Members to be appointed by the Central Government.

**1.1.3** CEA is headed by a Chairperson who as the Chief Executive of the Authority largely oversees the development of Power Sector in the country. A Secretary, appointed by the Authority with the approval of the Central Government under Section 72 of the Electricity Act 2003, assists the Chairperson in discharging of CEA's statutory functions. The Secretary also assists the Chairperson in all matters pertaining to administration and technical matters including concurrence of hydro power projects etc. There are six (6) Wings in CEA namely Planning, Hydro, Thermal, Grid Operation & Distribution, Economic & Commercial and Power System each headed by a Member of the Authority. Under each Member, there are technical Divisions, headed by an officer of the rank of Chief Engineer. At present, there are forty Divisions in CEA headquarter at New Delhi.

#### 1.1.4 Sub-ordinate offices of CEA

There are 14 subordinate offices of CEA viz. five (5) Regional Inspectorate Offices, four (4) Regional Power Survey Offices and five (5)

Regional Power Committees located in various parts of the country.

#### A) Regional Inspectorate Offices (RIO)

Under Chief Engineer (CEI) in Power System Wing, five (5) Regional Inspectorate Offices (RIO), each headed by an officer of the rank of Superintending Engineer, function at New Delhi, Mumbai, Chennai, Kolkata and Shillong to inspect the HV/MV installations of the Central Government.

#### B) Regional Power Survey Offices (RPSO)

Four (4) Regional Power Survey Offices (RPSO), each headed by an officer of the rank of Deputy Director, function at New Delhi, Mumbai, Bangalore and Kolkata under Chief Engineer (PS&LF) in the Planning Wing to carry out surveys to forecast the demand of power in their respective regions.

#### C) Regional Power Committees (RPCs)

Five (5) Regional Power Committees (RPCs), each headed by a Member Secretary, an officer of the rank of the Chief Engineer, are functioning at New Delhi, Mumbai, Bangalore, Kolkata and Shillong to facilitate the integrated operation of the Regional Electricity Grids.

#### 1.2 Functions of CEA

The functions and duties of the Authority are delineated under Section 73 of the Electricity Act, 2003. Besides, CEA has to discharge various other functions as well under Sections 3, 8, 34, 53, 55 and 177 of the Act.

#### Section 73 - Functions and Duties of the Authority

- (a) advise the Central Government on the matters relating to the national electricity policy, formulate short-term and perspective plans for development of the electricity system and coordinate the activities of the planning agencies for the optimal utilization of resources to subserve the interests of the national economy and to provide reliable and affordable electricity to all consumers;
- (b) specify the technical standards for construction of electrical plants, electric lines and connectivity to the grid;
- (c) specify the safety requirements for construction, operation and maintenance of electrical plants and electric lines;
- (d) specify the Grid Standards for operation and maintenance of transmission lines;
- (e) specify the conditions for installation of meters for transmission and supply of electricity;
- (f) promote and assist in the timely completion of schemes and projects for improving and augmenting the electricity system;
- (g) promote measures for advancing the skills of persons engaged in electricity industry;
- (h) advise the Central Government on any matter on which its advice is sought or make recommendation to that Government on any matter if, in the opinion of the Authority, the recommendation would help in improving the generation, transmission, trading, distribution and utilization of electricity;
- (i) collect and record the data concerning the generation, transmission, trading, distribution and utilization of electricity and carry out studies relating to cost, efficiency, competitiveness and such like matters;
- (j) make public from time to time the information secured under this Act, and provide for the publication of reports and investigations;
- (k) promote research in matters affecting the generation, transmission, distribution and trading of electricity;
- (l) carry out, or cause to be carried out, any investigation for the purpose of generating or transmitting or distributing electricity;
- (m) advise any State Government, licensees or the generating companies on such matters which shall enable them to operate and maintain the electricity system under their ownership or control in an improved manner and where necessary, in coordination with any other Government, licensee or the generating company owning or having the control of another electricity system;
- (n) advise the Appropriate Government and the Appropriate Commission on all technical matters relating to generation, transmission and distribution of electricity; and
- (o) discharge such other functions as may be provided under this Act.
- In addition to above functions and duties, CEA has to perform the following functions in terms of the under mentioned Sections of the Electricity Act, 2003: -

### **Section 3- National Electricity Policy and Plan**

- (1) The Central Government shall, from time to time, prepare the National Electricity Policy and Tariff Policy, in consultation with the State Governments and the Authority for development of the power system based on optimal utilization of

resources such as coal, natural gas, nuclear substances or materials, hydro and renewable sources of energy.

- (2) The Central Government shall publish the National Electricity Policy and Tariff Policy from time to time.
- (3) The Central Government may, from time to time, in consultation with the State Governments and the Authority, review or revise the National Electricity Policy and Tariff Policy referred to in sub-section (1).
- (4) The Authority shall prepare a National Electricity Plan in accordance with the National Electricity Policy and notify such plan once in five years.

PROVIDED that the Authority while preparing the National Electricity Plan shall publish the draft National Electricity Plan and invite suggestions and objections thereon from licensees, generating companies and the public within such time as may be prescribed;

PROVIDED FURTHER that the Authority shall –

- (a) notify the plan after obtaining the approval of the Central Government;
  - (b) revise the plan incorporating therein directions, if any, given by the Govt. while granting approval under clause (a).
- (5) The Authority may review or revise the National Electricity Plan in accordance with the National Electricity Policy.

### **Section 8 - Hydro-Electric Generation**

- (1) Notwithstanding anything contained in Section 7, any generating company intending to set up a hydro-generating station shall prepare and submit to the Authority for its concurrence, a scheme estimated to involve a capital expenditure exceeding such sum, as

may be fixed by the Central Government, from time- to time, by notification.

- (2) The Authority shall, before concurring in any scheme submitted to it under sub-section (1) have particular regard to, whether or not in its opinion,-
  - (a) the proposed river-works will prejudice the prospects for the best ultimate development of the river or its tributaries for power generation, consistent with the requirements of drinking water, irrigation, navigation, flood-control, or other public purposes, and for this purpose the Authority shall satisfy itself, after consultation with the State Government, the Central Government, or such other agencies as it may deem appropriate, that an adequate study has been made of the optimum location of dams and other river-works;
  - (b) the proposed scheme meets, the norms regarding dam design and safety.
- (2) Where a multi-purpose scheme for the development of any river in any region is in operation, the State Government and the generating company shall co-ordinate their activities with the activities of the person responsible for such scheme insofar as they are inter-related.

### **Section 34 – Grid Standards**

Every transmission licensee shall comply with such technical standards, of operation and maintenance of transmission lines, in accordance with the Grid Standards, as may be specified by the Authority.

### **Section 53 - Provision relating to Safety and Electricity Supply**

The Authority may, in consultation with the State Governments, specify suitable measures for-

- (a) protecting the public (including the person engaged in the generation, transmission or distribution or trading) from dangers arising from the generation, transmission or distribution or trading of electricity, or use of electricity supplied or installation, maintenance or use of any electric line or electrical plant;
- (b) eliminating or reducing the risks of personal injury to any person, or damage to property of any person or interference with use of such property;
- (c) prohibiting the supply or transmission of electricity except by means of a system which conforms to the specification as may be specified;
- (d) giving notice in the specified form to the Appropriate Commission and the Electrical Inspector, of accidents and failures of supplies or transmission of electricity;
- (e) keeping by a generating company or licensee the maps, plans and sections relating to supply or transmission of electricity;
- (f) inspection of maps, plans and sections by any person authorized by it or by Electrical Inspector or by any person on payment of specified fee;
- (g) specifying action to be taken in relation to any electric line or electrical plant, or any electrical appliance under the control of a consumer for the purpose of eliminating or reducing the risk of personal injury or damage to property or interference with its use.

#### **Section 55 - Use, etc. of Meters**

- (2) For proper accounting and audit in the

generation, transmission and distribution or trading of electricity, the Authority may direct the installation of meters, by a generating company or licensee at such stages of generation, transmission or distribution or trading of electricity and at such locations of generation, transmission or distribution or trading, as it may deem necessary.

#### **Section 177- Powers of Authority to make Regulations**

- (1) The Authority may, by notification, make regulations consistent with this Act and the rules generally to carry out the provisions of this Act.
- (2) In particular and without prejudice to the generality of the power conferred in sub-section (1), such regulations may provide for all or any of the following matters, mainly: -
  - (a) the Grid Standards under section 34;
  - (b) suitable measures relating to safety and electricity supply under section 53;
  - (c) the installation and operation of meters under section 55;
  - (d) the rules of procedure for transaction of business under sub-section (9) of section 70;
  - (e) the technical standards for construction of electrical plants and electric lines and connectivity to the grid under clause (b) of section 73;
  - (f) the form and manner in which and the time at which the State Government and licensees shall furnish statistics, returns or other information under section 74;



- (g) any other matter which is to be, or may be, specified;
- (3) All regulations made by the Authority under this Act shall be subject to the conditions of previous publication.

### **1.3 Broad Functional Areas of work of Chairperson and the Members of the Authority**

#### **Chairperson**

Chairperson is the Chief Executive of the Authority.

#### **Member (Planning)**

Formulation of National Electricity Plan; integrated resource planning; coordinating the activities of planning agencies for optimization of resource utilization; formulation of short, medium and long term power plans; long and short term demand forecast and sensitivity studies; material and manpower planning; surveys for power demand growth; identification and testing of co-lateral parameters for economic model for demand forecasting; collection, compilation and publication of statistics of Power Sector; securitization of resources/fuel availability and fuel efficiency with the support of emerging technologies; modernization of project management; concepts of skill development; pro-active technology forecasting approaches; research and development in Power Sector, co-ordination with multiple agencies involved in research and development activities, coordination of fuel oil/ liquid fuel supplies; coal quantity and quality control; development of renewable energy resources for electricity generation etc.

#### **Member (Thermal)**

Overall thermal power development in the country; updating, development and

evaluation of thermal technologies; design and engineering of thermal projects; quality assurance standards and plans; preparation of model documents and standards; thermal projects investigation and ash utilization; coal, oil and gas linkages to power projects; energy conservation; energy auditing; environmental aspects of thermal projects; monitoring of construction and stabilization of thermal projects and suggesting remedial measures to problems involved; renovation, modernisation and life extension programmes of thermal generating stations; making operating norms for thermal generating stations, development of Ultra Mega Power Projects (UMPPs) etc.

#### **Member (Hydro)**

Overall hydro power development in the country; technical appraisal of hydro-electric projects; integrated planning for utilization of water resources; assessment of hydro potential; assistance to States on investigation and project report preparation; construction & investigation, monitoring of hydro projects and suggesting remedial measures to problems involved; updating, development and evaluation of hydro technologies; environmental aspects of hydro projects; quality assurance plans and standardization, design and engineering of hydro projects; renovation, modernization and up rating of hydro stations; co-operation with neighbouring countries of Nepal, Bhutan and Myanmar for development of water resources for mutual benefits; etc.

#### **Member (Power System)**

Planning and development of transmission system consistent with national power plans; studies for the purpose of appraisal of transmission projects; transmission technology development; design and engineering; standardization and preparation of model document; renovation

and modernization of transmission schemes; construction monitoring of transmission projects; coordination of telecommunication system and power lines; matters related to communication, data acquisition and software support in power sector; inspection of existing electrical installations in Union Territories and Central Government Departments; investigation of accidents on electrical installations and suggesting remedial measures for their minimization and prevention etc.

#### **Member (Grid Operation & Distribution)**

Formulation of policies for safe, secure and economic operation of regional grids; integrated operation, co-ordination of five regional grids through Regional Power Committees(RPCs); monitoring of delivery of shares from Central Sector projects; intra and inter-regional exchange of power; regional energy accounting; load generation balance; investigation of grid disturbances; matters related to distribution planning, policy and regulations; monitoring of rural electrification programme and distribution schemes of the Central Government; all matters relating to power development in union territories; operation monitoring and performance review of thermal power stations; updating of maintenance procedures; generation data collection; performance analysis; maintenance monitoring etc.

#### **Member (Economic & Commercial)**

Economic evaluation of power policies and projects; appraisal of tariff for

Nuclear Power Stations; analysis of financial packages; financial parameters; interest during construction and completed cost; examination of bulk power tariff structure; performance of power sector utilities; scrutiny for import duty exemption; certification of deemed export benefit; co-ordination for externally aided schemes; examination of Power Purchase Agreements, advice on legal matters, amendments in Electricity Act,2003, National Electricity Policy, Tariff Policy and Electricity Rules etc.

#### **Secretary**

The Secretary (CEA) appointed by the Authority with the approval of the Government of India, assists the Authority in discharge of CEA's statutory functions. The Secretary also assists the Chairperson (CEA) in all matters pertaining to administration and technical matters including techno-economic appraisal and concurrence of hydro power projects, planning of budget and expenditure control etc.

### **1.4 Personnel and Administration**

#### **1.4.1 Staff strength of CEA**

The staff strength of CEA as on 31.03.2018 was 773 as against the sanctioned strength of 1462 leaving 689 posts vacant. The summarized position of staff strength is shown in the table below:

| Category              | Sanctioned Strength |            |             | Filled Strength |            |                |
|-----------------------|---------------------|------------|-------------|-----------------|------------|----------------|
|                       | Head-Quarters       | Sub-Office | Total       | Head-Quarters   | Sub-Office | Total Strength |
| Chairperson/Members   | 07                  | -          | 07          | 06              | -          | 06             |
| CPES GROUP-A          | 348                 | 84         | 432         | 219             | 58         | 277            |
| CPES GROUP-B          | 90                  | 19         | 109         | 61              | 15         | 76             |
| <b>Non CPES Group</b> |                     |            |             |                 |            |                |
| Group-A               | 57                  | -          | 57          | 38              | -          | 38             |
| Group-B               | 394                 | 39         | 433         | 126             | 14         | 140            |
| Group-C               | 143                 | 70         | 213         | 65              | 43         | 108            |
| Group-C(MTS)          | 154                 | 57         | 211         | 96              | 32         | 128            |
| <b>Total</b>          | <b>1193</b>         | <b>269</b> | <b>1462</b> | <b>611</b>      | <b>162</b> | <b>773</b>     |

- No vacancies were intimated to UPSC for AD-I (Gr.A) against ESE-2016, hence no AD-I had joined during 2017-18.
- Out of the 109 sanctioned posts of CPES AD-II (Group-B) in CEA, 76 posts are filled. 61 vacancies were intimated to UPSC for the post of AD-II against ESE-2016, out of which 43 nominations were received. Of these 29 candidates have joined during the recruitments years 2017-18 Gr.B AD-II, 04 (SC), 02 (ST), 08 (OBC), 01 (PH). Four numbers of offer of appointment have been cancelled, 09 candidates are yet to join and 01 candidate has denied to join.
- Consequent on 3<sup>rd</sup> Cadre Review of CPES, the Service Rules have been

notified vide Gazette Notification dated 14.02.2015. After 3<sup>rd</sup> Cadre review, 429 posts of the position of CPES Gr.A Service comprise of : 2 – HAG, 42-SAG, 94-JAG, 160-STs and 131- JTS posts. In addition, three posts at SAG level for CPE (Gr.A) officers have also been created one each at Krishna River Management Board, Godavari River Management Board and Polavaram Project Authority at Hyderabad.

#### 4. Subordinate Offices:

- One vacancy of AD (OL) was filled in Decemeber,2017 on deputation basis.
- One vacancy of LDC was filled in December, 2017 on the basis of CHSL, 2015 Examination held by SSC.

#### 1.4.2 No. of Women Employees in CEA (as on 31.03.2018)

| Category              | No. of Govt. Employees |            | No. of Women employees In position | % age         |
|-----------------------|------------------------|------------|------------------------------------|---------------|
|                       | Sanctioned             | Filled     |                                    |               |
| Chairperson/Members   | 07                     | 06         | -                                  | -             |
| CPES GROUP-A          | 432                    | 277        | 29                                 | 10.24%        |
| CPES GROUP-B          | 109                    | 76         | 11                                 | 14.47%        |
| <b>Non CPES Group</b> |                        |            |                                    |               |
| Group-A               | 57                     | 38         | 09                                 | 23.68%        |
| Group-B               | 433                    | 140        | 65                                 | 46.42%        |
| Group-C               | 213                    | 108        | 23                                 | 21.29%        |
| Group-C(MTS)          | 211                    | 128        | 13                                 | 10.15%        |
| <b>Total</b>          | <b>1462</b>            | <b>773</b> | <b>150</b>                         | <b>19.40%</b> |

### 1.4.3 Representation of Scheduled Castes, Scheduled Tribes, OBC & Physically Handicapped Employees (as on 31.03.2018)

| Category           | No. of Govt. Employees |            | No. of SC Govt. employees in position | No. of ST Govt. employees in position | No. of OBC Govt. employees in position | No. of Phy. H. Govt. employees in position |
|--------------------|------------------------|------------|---------------------------------------|---------------------------------------|--|--|
|                    | Sanctioned             | Filled     |                                       |                                       |  |  |
| Chairperson/Member | 07                     | 06         | 03                                    | -                                     | -                                      | -  |
| CPES GROUP-A       | 432                    | 277        | 54                                    | 17                                    | 31                                     | 04   |
| CPES GROUP-B       | 109                    | 76         | 11                                    | 06                                    | 18                                     | 02   |
| Non CPES Group     |                        |            |                                       |                                       |  |  |
| Group-A            | 57                     | 38         | 02                                    | 04                                    | 01                                     | -  |
| Group-B            | 433                    | 140        | 33                                    | 08                                    | 11                                     | 04   |
| Group-C            | 213                    | 108        | 19                                    | 06                                    | 19                                     | 01   |
| Group-C(MTS)       | 211                    | 128        | 47                                    | 02                                    | 07                                     | 03   |
| <b>Total</b>       | <b>1462</b>            | <b>773</b> | <b>169</b>                            | <b>43</b>                             | <b>87</b>                              | <b>14</b>                                  |

### 1.4.4 Representation of Physically Challenged employees (as on 31.03.2018)

| Group                   | Total employees as on 31.03.2018 | Physically Challenged Employees |           |           |           | Percentage of Physically Challenged |
|-------------------------|----------------------------------|---------------------------------|-----------|-----------|-----------|-------------------------------------|
|                         |                                  | VH                              | HH        | OH        | Total     |                                     |
| Group A (CPES+NON-CPES) | 315                              | -                               | 01        | 03        | 04        | 1.26%                               |
| Group B                 | 216                              | -                               | 01        | 04        | 05        | 2.31%                               |
| Group C                 | 108                              | 01                              | -         | -         | 01        | 0.9%                                |
| Group -C(MTS)           | 128                              | 01                              | -         | 02        | 03        | 2.34%                               |
| <b>Total</b>            | <b>767</b>                       | <b>02</b>                       | <b>02</b> | <b>09</b> | <b>13</b> | <b>1.69%</b>                        |

## 1.5 Annual Budget

**1.5.1** During the year 2017-18, against an allocation of Rs. 18.04 Crores (reduced to Rs. 14.04 Crores in the FE 2017-18) under Plan side, an expenditure of Rs. 13.53 Crores has been booked upto 31.03.2018.

On the Non-Plan side, during the year 2017-18 an expenditure of Rs. 100.77 Crores was incurred against an allocation of Rs. 99.10 Crores (increased to Rs. 102.73 Crores in RE 2017-18) during the year 2017-18

### 1.5.2 Revenue Recovered for Consultancy Services by CEA and Recovery of expenses by RPCs from constituents

CEA renders Consultancy Services for design and Engineering of thermal and hydro projects to various SEBs and power utilities. During 2017-18, CEA rendered consultancy services worth Rs. 2.50 Crores and amount of Rs. 2.60 Crores was recovered during the year (upto 31.03.2018). It includes pending payments received for consultancy services rendered by CEA.

### 1.6 Progressive use of Hindi in Official Work of CEA

In Central Electricity Authority the Official Language Implementation Committee (OLIC) meetings are held on regular intervals under the chairmanship of

Chairperson, CEA. Required actions are taken on the decisions taken in these meetings. During 2017-18 four quarterly meetings were held on 27.04.2017, 02.08.2017, 14.11.2017 and 26.02.2018. During the year 2017-18, the percentage of Hindi correspondence was 92.49%, 90.01% and 83.48% in Region 'A', 'B' and 'C' respectively.

All possible efforts are being made at every level to promote the use of Hindi in the official functioning of CEA. All incentive schemes recommended by the Department of Official Language are being implemented in the Authority.

Hindi fortnight was organized from 14.9.2017 to 28.9.2017 in the Authority. Prize distribution ceremony was held on 28.09.2017. During the fortnight, four competitions, i.e. Essay writing, Hindi Noting and Drafting, General Knowledge and Hindi dictation (for MTS employees only) were organized, in which many officers and employees participated enthusiastically. The winners of these competitions were awarded cash prizes and certificates. The ceremony was concluded with the poem recital by the guest poet Shri Satyendra Satyarthi. During the fortnight, *Chal Vijayantis* were awarded to the Grid Management (GM) division and Hydro Engineering and Modernization Division (HERM) for achieving first and second places respectively in doing maximum correspondence in Hindi during the year. Under the Dictation Cash Award Scheme, a prize was awarded to an officer. While ten employees were rewarded under Annual Noting / Drafting cash award scheme for working in Hindi throughout the year.

Internal official language inspection of various sections are performed by Official Language Officers from time to time, so that the shortcomings, if any, could be brought to the notice of the Officers-in-charge of these Sections/Divisions. During 2017-18, 14

Sections/ Divisions of CEA were inspected. In addition to it, 5 subordinate offices of CEA were also inspected. Apart from this, Parliamentary Official Language Committee inspected CEA Headquarters, Delhi this year. Check points were prepared for the implementation of the Official Language policies and the same were signed by the Chairperson, CEA, got laminated and distributed to each Division/Section, to place the same at the appropriate place in the office of the Division / Section heads. These check points were also sent to 14 subordinate offices so that the immediate action could be taken on the main points according to the Official Language Policy.

During the year, four Hindi workshops were organized in which lectures were delivered by the Guest lecturers on different topics related to Official Language. The topics and dates of workshops conducted were- On 07.07.2017, "Google Voice Typing and Google Net Hindi Translation"; On 14.09.2017, "Contribution of the poem in the promotion of Hindi"; On 07.12.2017 "Filling up the quarterly progress report online" and on 19.03.2018 "e-office-introduction and Practicer".

In CEA, most of the officers and employees are either proficient in Hindi or having working knowledge of Hindi. Those who do not have knowledge of Hindi, are being trained in Hindi language courses / Shorthand / Typing classes organized by "Kendriya Hindi Prashikshan Sanshthan", Department of Official Language from time to time. During the year, 11 officers were sent to Central Hindi Training Institute for intensive Hindi workshop training and 1 Junior Translator was sent to the Central Translation Bureau for translation training. In addition, 3 staff members were sent to Hindi Shikshan Yojana, R.K. Puram for basic training course on working in Hindi on computers.

During the year, in July, 2017 and

February, 2018 individual Orders were issued by the Chairperson, CEA under the Section 8 (4), to carry out their complete work in Hindi to 31 officers / employees and 162 officials / employees respectively.

The meeting of NARAKAS (Town Official Language Implementation Committee) (South Delhi-2) was organized by the CEA on 26.10.2017 under the Chairmanship of Shri Ravindra Kumar Verma, Chairperson, CEA and Chairman, NARAKAS (South Delhi-2). In this meeting, 39 HODs and 54 representatives from different offices participated. In the meeting, Hindi work in the offices of the members of NARAKAS (South Delhi-II) was reviewed and suggestions for improvement were given. In addition, an introductory meeting of NARAKAS was also held on 21.08.2017, in which all the Heads of departments and 65 office-bearers were invited and various topics were discussed.

### 1.7 Hiring of Consultants

CEA has acute shortage of technical manpower as well as non-technical staff and to cope up with this situation 16 Consultants were hired in CEA during the year 2017-18.

## 1.8 Welfare Activities in CEA

### 1.8.1 Welfare of SC/ST/OBC

Shri K.S.Babu, Director (IRP Division) has been designated as Liaison Officers in CEA to look after the welfare of SC/ST/OBC and PwD employees.

### 1.8.2 Activities related to Women employees

Women employees of CEA have been participating in various activities viz. sports, recreation & cultural activities. They have also been co-opted as members of CEA Departmental Canteen Management Committee.

An Internal Complaints Committee (ICC) has been constituted in CEA for handling the cases of Sexual Harassment of Women at Workplace (Prevention, Prohibition and Redressal). The 7 member of ICC is headed by Smt. Vandana Singhal, Chief Engineer, CEA as Chairman includes Ms. Asha Sharma, All India Democratic Women's Association as the independent member.

### 1.8.3 Recreation and Sports:

During 2017-18, the CEA Sports team participated in various sports events like Cricket, Carrom, Volley ball, Table Tennis, Badminton, Athletic, Chess etc. and CEA's welfare team participated in Inter-Ministry music and dance competition. The achievements have been as under:

1. The Chess players of CEA had participated in the Inter-CPSU Chess Tournament organized by THDC Ltd. in September, 2017 at Rishikesh. Shri Lalrinsanga, Director, NERPC, Shillong had won the trophy of 3<sup>rd</sup> position in the tournament.
2. Athletic team of Men & Women of CEA had participated in the Inter-CPSU Athletic Tournament organized by BBMB on 26-27 February, 2018 at Nangal (Punjab). The women's team had won several awards/medals in the tournament. Smt. Usha Nayal, ASO got medals at 3<sup>rd</sup> position in 800 mtr. & long jump events, Smt. Jayanthi K. Vasudevan, PA had got medals at 3<sup>rd</sup> position in Discus Throw & Shot Put events, Smt. Asha Lata Gautam, PA had won 3<sup>rd</sup> Position in 200 mtr. event and four women players (Smt. Madhu Sharma, Smt. B. Sandhya, Smt. K.G. Geeta & Smt. Usha Nayal) had won Runners up award in 400 mtr. relay.
3. CEA Jal Tarang team had participated in Inter-Ministry music and dance

competition organized by Central Civil Services Cultural and Sports Board (CCSC&SB). Shri Chandrashekhar, Chief Engineer had won medal at 2<sup>nd</sup> position in Instrumental event and Smt. Usha Nayal, ASO had won medal at 3<sup>rd</sup> position in Light Classical event.

#### 1.8.4 Associations/ Unions in CEA

The Drawing Staff Association is recognized for three years under CCS (RSA) Rules, 1993.

#### 1.8.5 Pension Cases

38 superannuation cases and 2 VRS cases have been settled for Pension during the year 2017-18. In addition, 90 nos. of restoration of one third commuted portion of Pension/Grant of family pension cases were settled. In addition, 2 CAT/Court cases are under process.

#### 1.9 Vigilance Activities / Disciplinary Cases in CEA

The Vigilance Division, CEA is headed by Chief Vigilance Officer (CVO) and is the nodal point in Vigilance set up of the Authority and its Subordinate Offices. The Division deals with various facets of vigilance mechanism and functions for carrying out investigations into complaints, suggesting corrective measures for improving the control system, compliance of laid down procedures and also for carrying out preventive vigilance exercises.

As part of preventive vigilance, the Vigilance Division facilitates in ensuring job rotation in sensitive posts. The Vigilance Division has also taken steps to ensure that website of CEA plays an important role in increasing transparency in its functions. Vigilance Awareness Week-2017 was observed in Central Electricity Authority and its Subordinate Offices from 30.10.2017 to 04.11.2017. The Vigilance Awareness week was celebrated to highlight the theme "My

Vision-Corruption Free India".

Complaints other than anonymous/pseudonymous were taken up for investigation promptly and after completion of investigations, reports submitted to the prescribed competent authority. As on 31.03.2018, two cases of disciplinary action are under process for disciplinary proceedings. Out of these two cases, one case is old and one case has been received during the current year. Thus, at present two cases are pending. Prescribed periodical returns were sent to Ministry of Power and Central Vigilance Commission in time.

#### 1.10 Electric Power Information Society

The Electric Power Information Society (EPIS) was established in June, 1996 under the aegis of Central Electricity Authority on no-loss-no profit basis for bringing out various CEA publications. These are also available on sale for general public.

#### 1.11 Grievance Cell

In accordance with the instructions of Department of Administrative Reforms and Public Grievances (DAR&PG), Shri Hemant Jain, Chief Engineer (Regulatory Affairs), is functioning as Grievance Officer for CEA. The Grievances dealt by CEA are mainly service matters (pension, promotion, administrative etc.) and technical/policy matters related to power sector. Further, the Grievances on matters of public /individual concerns, issues of Research and Development /Inventions /suggestions for Power Sector Development are also dealt with.

During the year 2017-18, 239 Nos. of Grievances were received and 19 Nos. were pending as on 01.04.2017. A total of 243 Nos. Grievances were settled/disposed off during the period 01.04.2017 to 31.03.2018 with average disposal time of 27 days.

### 1.12 Right to Information Act, 2005

Under the Right to Information Act, 2005, the Chief Engineer (Coordination) acts as the Nodal Officer for RTI for CEA. 433 applications were received during the year 2017-18, under the Act and were disposed off by various CPIOs in CEA. Further, 33 applicants filed appeal to the Appellate Authority which were also decided.

### 1.13 Parliament Questions/Assurances, VIP references

(A) Works relating to various assignments given below were carried out:

1. Parliament Questions
2. Parliamentary Assurances
3. Oral evidence
4. VIP references
5. Consultative Committees
6. Standing Committee on Energy
7. Material for 'Calling Attention Motion'
8. Material for Economic Survey 2017-18
9. Major Achievements in Power Sector
10. Annual Report of the MOP for 2017-18
11. Estimates Committee
12. Monitorable targets for the year 2017-18 and Achievements
13. Power Ministers' Conference
14. Material for various speeches.
15. International Cooperation with various countries
16. Inputs for regional meeting relating to power matters of the regions
17. Action taken reports were prepared based on the inputs received from various divisions.
18. PMO/VIP/MOP references
19. Power Minister's briefing to the press
20. Material for President's Address

to both the Houses of Parliament and Finance Minister's Budget Speech.

21. Compilation and processing of material for matters such as:

- Power sector reform
- Private Sector participation including action taken reports
- Notes for Estimates Committee
- Ministers meeting on power scenario etc

(B) During the year 2017-18 there were four Parliament Sessions and the Admitted version of Questions were dealt with as follows:

| S. No. | Particulars             | Starred Question | Unstarred Question |
|--------|-------------------------|------------------|--------------------|
| 1.     | Budget Session 2017-18  | 5                | 46                 |
| 2.     | Monsoon Session 2017-18 | 9                | 130                |
| 3.     | Winter Session 2017-18  | 23               | 247                |
| 4.     | Budget Session 2018-19  | 6                | 24                 |

### 1.14 Monthly Reports

The CEA receives data regularly on various aspects of Indian Power Sector, such as generation, transmission and distribution of power. The information received is incorporated in the following regular reports:

- Report on important developments during the month for Prime Minister's Office
- Summary report for Council of Ministers on important developments in Power Sector during the month.
- Monthly Executive Summary
- Fortnightly Report for P.M.O.
- DO letter from Chairperson, CEA to Secretary (Power)



The Executive Summary is an important reference document containing information regarding installed capacity, power supply position, actual generation vis-à-vis the programme, details of the thermal and hydro generating units commissioned during the month, major transmission lines & sub-stations commissioned, status of the coal position, etc. pertaining to the month in the reference.

### 1.15 Computerization in CEA

All Divisions and Sections of CEA have been equipped with the latest IT infrastructure. The computers of CEA office at Sewa Bhawan, West Block-II and NRPC building are interconnected through wired or wireless network. The important statistics/data/information of CEA is uploaded on the bilingual (English & Hindi) website of Central Electricity Authority ([www.cea.nic.in](http://www.cea.nic.in)) for global access. The CEA website has been designed, developed and maintained in-house by IT Division, CEA. The content of this website is updated on daily basis. A state of the art Data Center is running at Sewa Bhawan building since 2011 for collecting and scrutinizing online data from various power sector utilities/ organizations.

#### 1.15.1 Hardware Facilities

The IT hardware facilities in CEA consist of 5 Rack Servers, Router, Firewall, Core-Switch etc. and various office automation equipment like Multifunctional Printers, Plotters, Workstations, etc. All officials of CEA have been provided with latest desktop computers / laptops with internet facility and associated peripherals under the Plan Scheme “Upgradation of IT facilities in CEA – Phase II” approved by Ministry of Power in July, 2015.

#### 1.15.2 Software facilities

System Software like Red Hat Linux, Oracle, Windows Server, WebSphere are

being used for maintaining the Data-Center and Internet connectivity in CEA.

Application Software like MS Office, Information Management System (IMS), CompDDO are available to facilitate daily official works in CEA. Apart from these, there are a few scientific Application Software like AutoCAD, STAAD.Pro, i-Tower, Power System Analysis Package (PSAP), Integrated System Planning Model (ISPLAN), STATA, etc. being used by different divisions for carrying out specific function of designing, study, analysis and planning etc.

Specific software have also been developed in-house by IT Division like IT (Inventory/Complaint /Bill) Management, Canteen Management, Hindi Data Management, etc.

#### 1.15.3 Other Works

##### 1.15.3.1 National Power Data Management System (NPDMS) / National Power Portal (NPP):

Hon'ble Minister of State (IC) for Power and New & Renewable Energy launched the National Power Portal (NPP) on 14.11.2017. The portal is accessible at <https://npp.gov.in>.

NPP is a centralized system for Indian Power Sector which facilitates online data capture/ input (daily, monthly, annually) from generation, transmission and distribution utilities in the country and disseminate Power Sector Information (operational, capacity, demand, supply, consumption, etc.) through various analyzed reports, graphs, statistics for generation, transmission and distribution at all India, region, state level for central, state and private sector.

The NPP Dashboard has been designed and developed to disseminate analyzed information about the sector through GIS enabled navigation and visualization

chart windows on capacity, generation, transmission, distribution at national, state, DISCOM, town, feeder level and scheme based funding to states. The system also facilitates various types of statutory reports required to be published regularly. The Dashboard acts as single point interface for all Power Sector Apps launched by the Ministry like TARANG, UJALA, VIDYUT PRAVAH, GARV, URJA, MERIT, etc.

NPP is integrated with associated systems of Central Electricity Authority (CEA), Power Finance Corporation (PFC), Rural Electrification Corporation (REC) and other major utilities and serves as single authentic source of power sector information to apex bodies, utilities for the purpose of analysis, planning, monitoring as well as for public users. The system is available 24x7 and ensures effective and timely collection of data. It has standardized data parameters and formats for seamless exchange of data between NPP and respective systems at utilities.

The stakeholders of NPP are Ministry of Power (MoP), CEA, PFC for Integrated Power Development Scheme (IPDS), REC for Deen Dayal Upadhyaya Gram Jyoti Yojana (DDUGJY), other power sector utilities in government as well as private sector, Apex Bodies, other government organizations and public users. The Nodal Agency for implementation of NPP and its operational control is CEA. The system has been conceptualized, designed and developed by National Informatics Centre (NIC).

### **1.15.3.2 E-Office in CEA:**

For conducting file and letter handling processes in more efficient and transparent manner, e-Office (e-File) application has been launched in CEA on 1<sup>st</sup> January 2018. The E-Office application is hosted on the Cloud of National Informatics Centre (NIC) and provides features like e-sign facility for ascertaining authentication & non-

repudiation, integration of E-mail service with the application, role based workflow, tracking and searching facility, etc.

### **1.15.3.3 Cyber Security in Power Sector:**

Chief Engineer (IT), CEA is nominated Chief Information Security Officer (CISO) of Ministry of Power to co-ordinate the activities related to cyber security in Power Sector. IT Division, CEA, in collaboration with four Power Sector Computer Emergency Response Teams (CERTs), i.e., CERT-Distribution, CERT-Thermal, CERT-Hydro and CERT-Transmission, is working on setting up of Information Sharing and Analysis Centre (ISAC) for Power Sector. Regular workshops on cyber security in Power Sector are conducted for power utilities.

### **1.15.3.4 Digitization of Approvals/ Clearances given by CEA:**

As per the direction of Project Monitoring Group of Cabinet Secretariat, online application for the following approvals/clearances, given by Central Electricity Authority, have been implemented by NIC:

- (i) Online Application for Inspection of Electrical Installations
- (ii) DPR Approval Process Monitoring System for Hydro Projects
- (iii) Online Application for prior approval of Government under Section 68 of Electricity Act, 2003

This digitization of approvals/clearances is ensuring transparency and timely approval by CEA. This also facilitates developers to track the status of their application.

### **1.16 ISO 9001:2008 Quality Management System Certification (QMS)**

In order to improve quality of services rendered and competency of the personnel of

CEA, the Quality Management System (QMS) as per ISO 9001:2000 was adopted by CEA in February-March 2004 which was subsequently renewed in year 2007. CEA has adopted ISO 9001:2008 Quality Management System in February, 2010 which was renewed in February, 2013 and November, 2016.

As per the provisions of ISO 9001:2008 prescribed in the Quality Manual,

Monthly, Quarterly and Half Yearly Review Meetings are held in various Divisions/Wings at the level of Chief Engineers, Members and Chairperson respectively.

ISO 9001:2008 Quality Management System certificate of CEA is valid up to 14<sup>th</sup> September, 2018. Now, in order to adopt new QMS certification of CEA as per IS/ISO 9001:2015, Apex Manual of CEA as per ISO 9001:2015 is under preparation in CEA.

## CHAPTER – 2

### PLANNING FOR POWER DEVELOPMENT

#### 2.1 Power Planning

##### 2.1.1 Generation Planning Studies

- i) Generation expansion studies for the preparation of National Electricity Plan using Electric Generation Expansion Analysis System (EGEAS) software, have been carried out in CEA, in which incremental capacity requirement in terms of Thermal, Hydro, Nuclear, etc to meet the projected load and energy requirement as per 19<sup>th</sup> Electric Power Survey Report of CEA for the period 2021-22 and 2026-27 has been worked out. Retirement of old units, Renewables and Captive injection have also been considered.
- ii) After procuring a New Generation Expansion planning model namely ORDENA Software by CEA in December, 2016, the Generation planning studies are being carried out using the Software for 2021-22 and 2026-27. It was found that the results matched with the NEP results.
- iii) To assess the optimal mix of capacity addition for the years 2017-22 and 2022-27, Generation Planning Studies using EGEAS/ORDENA Software were carried out.

##### 2.1.2 National Electricity Plan

Section 3(4) of the Electricity Act, 2003 stipulates that the Authority shall prepare the National Electricity Plan, in accordance with the National Electricity Policy and notify such plan once in five years, after obtaining the approval of the Central Government. The draft National Electricity Plan covering the review of 12<sup>th</sup> Plan, detailed plan for 2017-22 and perspective plan for 2022-2027 was uploaded on CEA website for stakeholder's comments.

Based on the comments received from stakeholders, final National Electricity Plan, Volume I (Generation) has been Notified vide Extra Ordinary Gazette No. 1871, Sl. No. 121 under part-III, Section IV dated 28.03.2018.

##### 2.1.3 Reports brought out

- i) National Electricity Plan, Volume 1 (Generation) was published vide Extra ordinary Gazette No. 1871, Sl. No. 121, under part-III, Section IV dated 28.03.2018.
- ii) Assessment of the optimal mix of capacity addition for the years 2017-22 and 2022-27 and preparation of the report on optimal generation mix keeping in view the INDC targets.
- iii) Detailed analysis for flexible operation of coal based power plants in view of large-scale integration of Renewables.
- iv) Estimation of Solar and Wind contribution during Peak Hours for the State of Madhya Pradesh.
- v) Report of Demand Creation Sub Group constituted by Ministry of Power for in depth analysis of issues related to creation of demand to address the stress in Power sector.

##### 2.1.4 Capacity addition during 12<sup>th</sup> Plan

- i) As against a capacity addition target of 88537 MW, capacity addition of 99209.47 MW was achieved during 12<sup>th</sup> Plan (2012-17).
- ii) As against a capacity addition target of 13,171.15 MW, Capacity addition of 9505 MW was achieved during 2017-18 comprising of 795 MW Hydro, 8710 MW Thermal, 0 MW Nuclear.

##### 2.1.5 Participation of CEA as Committee Member/Interaction Meets etc.

- i) Member (Planning) was the Chairman of Demand Sub Group for in depth analysis

of issues related to creation of demand to address the stress in Power Sector and Chief Engineer (IRP) was the Member Secretary of the Committee constituted by Ministry of Power.

- ii) Chief Engineer (IRP), CEA was Chairman of Expert group to input and consultation to POSOCO on various technical aspects of conducting study on Operational analysis for optimization of Gas based capacity.
- iii) Chief Engineer (IRP) was the Member of the Committee on Optimal Energy mix in power generation on medium and long-term basis.

### 2.1.6 Procurement of Planning Model Software

The New Comprehensive Planning Model Software procured in CEA was successfully commissioned and tested. A fifteen days training program was arranged for CEA officers on familiarization with the Software.



### 2.1.7 National Level Data Registry System

Section 74 of Electricity Act, 2003 and Regulation 4 & 5 of CEA (Furnishing of Statistics, Returns and Information) Regulations, 2007, mandates every licensee, generating company, or person(s) generating electricity for its or his own use to furnish the statistics, returns or other information relating to generation, transmission, distribution, trading to CEA.

In accordance with above provisions, it was

decided that a National Level Data Registry System for all electricity generating units of the country above a specified capacity should be maintained by CEA so that the generating capacity data of all electricity generating units of the country including the Renewables and Captive power plants and their other details should be available with CEA.

Accordingly, a detailed framework, for National Level Data Registry System for registering of all electricity generating units was prepared by CEA and it was approved by the Ministry of Power. In the above framework, there is a provision of mandatory registration of all the electricity generating units of 0.5 MW and above capacity by assigning each of them a unique registration number.

The registration number to be assigned by CEA shall be a unique for each generating unit in the country and the registration number once assigned to a generating unit would not be changed. The status of generating unit may change (planned/ under construction/ commissioned/retired etc.). Even if the generating unit retires, its registration number would not be assigned to any other generating unit.

For implementing the aforementioned National Level Data Registry System, an E-Registration Portal is being prepared by CEA.

## 2.2 Electricity Demand

Electricity demand of the country is reassessed periodically, once in five years, for medium term and long term period. The demand projection exercise is carried out by a National Level Committee of Experts, constituted by CEA with the consent of Ministry of Power, by conducting an exhaustive Electric Power Survey (EPS) of India. Electric Power Survey is undertaken by Power Survey and Load Forecasting Division (erstwhile Data Management and Load Forecast Division), CEA, by obtaining inputs from Regional Power Survey Offices (RPSOs) located in various regions, along with data

obtained from various organizations/utilities. The electricity demand forecast is the basic input for formulation of Developmental Plans and Programmes & Schemes concerning generation, transmission, trading, distribution and utilization of electricity.

The 19<sup>th</sup> Electric Power Survey (EPS) Report of India (Electricity Demand Projection of 45 Mega Cities of the country & 23 districts of National Capital Region (NCR) including Delhi in two separate volumes) is under preparation. The Report shall cover year-wise electricity demand projection for 45 Mega Cities of the country & 23 districts of National Capital Region (NCR) including Delhi for the years 2016-17 to 2026-27. The Reports shall also cover perspective electricity demand projection for Mega cities and districts of National Capital Region including Delhi for the years 2031-32 and 2036-37.

### **2.3 Publication on All India Electricity Statistics – General Review & Growth of Electricity Sector in India**

In fulfillment of its duties and functions under Section 73 (i) & (j) and exercising powers vested under Section 74 of the Electricity Act, 2003, CEA publishes following documents containing annual electricity statistics.

#### **2.3.1 All India Electricity Statistics – General Review**

General Review-2017 covers nationwide electricity statistics relating to Generation, Transmission, Distribution, Consumption and Trading of electricity along with important information relating to growth of the Indian Electricity Sector, organizational structure of Electricity Supply Industry in India and reforms carried out by Utilities. The General Review incorporates important statistics /data on installed capacity, electric energy generation and utilization of electric energy along with the transmission and distribution losses, per capita consumption. This publication covers energy utilization by

various categories of electricity consumers like domestic, commercial, irrigation, industries (LV /MV, HV /EHV), public lighting, public water works, etc. The various Chapters/Tables of the publication indicate the above information State wise / Sector wise/ Category wise/ Mode wise etc. In addition to the above, the General Review contains information on about 4248 Nos. captive plants of HV/EHV industries indicating installed generating capacity and generation by such captive plants. General Review-2017 containing the data for the year 2015-16 was published in April, 2017.

General Review-2018 containing data for the year 2016-17 is under finalization.

#### **2.3.2 Growth of Electricity Sector in India**

Publication titled "Growth of Electricity Sector in India from 1947-2017" was published in May, 2017 containing data for 2015-16 and provisional /estimated data for 2016-17 in respect of Indian Electricity Sector. The data for these publications has been sourced from various Utilities and Non-utilities and various National & International sources. This publication illustrates the growth of vital development indicators like installed generating capacity, electrical energy production, transmission and distribution network, captive power plants in industries and pattern of consumption of electricity etc. The important statistics have been compared with the International data with respect to some of the developed and developing nations. The publication also contains charts indicating state of basin wise and region wise Hydro Electric Potential development in the country.

The booklet contains maps and charts presenting a panoramic view of the growth of Indian Electricity Sector.

#### **2.4 Standing Committee on Derating, Up-rating and Retirement of Installed Capacity of Stations**

A Standing Committee is constituted under the chairmanship of Member (Planning) for considering the proposals of de-rating, up-

rating & retirement of electricity generating units.

The proposals received for **retirement** of the units are placed for the approval of the Chairperson/Authority considering the decisions taken by the utilities based on their own techno-economic reasons.

The Committee considers the performance of the units for **de-rating & up-rating**, analyses the performance data and the overall generation throughout the life of the plant/unit and carries out detailed scrutiny of technical parameters of proposed units. Keeping in view the technical merits of the proposals received from various generating companies, the Committee makes recommendations for the approval of the Chairperson/Authority for **de-rating and up-rating** of the units.

During the year 2017-18, various proposals of de-rating, up-rating and retirement of the generating units were initiated, out of which 38 Nos. of thermal generating units with aggregate capacity of 2550.38 MW were retired, Chuzachen HPS (2 units) was uprated by 11 MW and Ratnagiri CCPP (9 units) was derated by 252.92 MW.

## **2.5 Implementation of initiative of Working Group III on National Mission on Enhance Energy Efficiency (NMEE) for retirement of old and inefficient Thermal Units in 12<sup>th</sup> Plan.**

Ministry of Power, under National Action Plan on Climate Change (NAPCC) has initiated National Mission on Enhanced Energy Efficiency (NMEEE). Working Group -III under NMEEE had inter-alia recommended retirement of old and inefficient Thermal Units. As a follow up of the recommendations of working group III of NMEEE regarding retirement of old and inefficient thermal generating units, CEA has undertaken an exercise of identification of thermal units for phased retirement during 11<sup>th</sup> & 12<sup>th</sup> Plan period. A total of 2398 MW was retired during 11<sup>th</sup> Plan. During 12<sup>th</sup> plan a total of 5082.44 MW has been retired. As per the provisions of National Electricity Plan, a total of 4000 MW was envisaged for retirement during 12<sup>th</sup> plan.

Based on the assessment made by CEA, a coal based capacity of 22,716 MW is considered for retirement during 2017-22 which consists of 5,927 MW of capacity assuming that the normal trend of past retirement process and 16,789 MW which are attaining the age of 25 years and do not have space for installation of FGD (Flue Gas Desulphurization) system to curb SOx emissions in view of the latest environmental norms by MOEF.

A total of 2550.38 MW was retired during the year 2017-18. The list of thermal generating units retired during 2017-18 is given below:

| Sl. No. | Name of Station/Plant     | Unit No.   | Installed Capacity (MW) | Utility/ Agency |
|---------|---------------------------|------------|-------------------------|-----------------|
| 1       | Koradi TPS                | 5          | 200.00                  | MAHAGENCO       |
| 2       | Utran CCPP (uprated Cap.) | 1,2,3,4    | 144.00                  | GSECL           |
| 3       | CHANDRAPUR(ASSAM)         | 1,2        | 60.00                   | APGCL           |
| 4       | UKAI TPS                  | 1,2        | 240.00                  | GSECL           |
| 5       | SIKKA REP. TPS            | 1,2        | 240.00                  | GSECL           |
| 6       | HARDUAGANJ TPS            | 5          | 60.00                   | UPRVUNL         |
| 7       | OBRA TPS (derated Cap.)   | 1,2        | 90.00                   | UPRVUNL         |
| 8       | BHUSAWAL TPS              | 2          | 210.00                  | MAHAGENCO       |
| 9       | CHINAKURI TPS             | 1,2,3      | 30.00                   | DPSCLTD         |
| 10      | Dishergarh TPS            | 1,3,4,5    | 18.00                   | DPSCLTD         |
| 11      | Seebpore TPS              | 1,2,3,4    | 8.38                    | DPSCLTD         |
| 12      | CHANDRAPURA(DVC) TPS      | 2          | 130.00                  | DVC             |
| 13      | BOKARO `B` TPS            | 1,2        | 420.00                  | DVC             |
| 14      | NAMRUP CCPP               | 1          | 20.00                   | APGCL           |
| 15      | LAKWA GT                  | 4          | 15.00                   | APGCL           |
| 16      | PATRATU TPS               | 4,6,7,9,10 | 455.00                  | NTPC            |
| 17      | PANKI TPS                 | 3,4        | 210.00                  | UPRVUNL         |
|         | <b>Total</b>              |            | <b>2550.38</b>          |                 |

## 2.6 Research & Development in Power Sector

### 2.6.1 R&D activities in Power Sector

The Central Power Research Institute (CPRI) is the nodal agency for Research & Development in the power sector. Over the years, the Institute has contributed in research in a number of areas and had also helped to fund utilities and academia for their research in the power related fields. Further, CPSUs like Bharat Heavy Electricals Limited (BHEL), and CPSUs of Ministry of Power like NTPC Ltd., Power Grid Corporation of India Limited (PGCIL), NHPC etc., also carry out R&D activities towards development of technology in areas of operational and application technologies keeping in view their commercial / business interests. Other research Institutions like Electrical Research & Development Association (ERDA), Indian Institute of Technology (IITs), Council of Scientific and Industrial Research (CSIR), Centre for Development of Advanced Computing (C-DAC) etc., also carry out

research towards finding solutions to problem areas in the power sector.

Apart from the above, the Government of India through Ministry of Power has supplemented the efforts of other organisations in the area of R&D through three central schemes viz.,

- i) National Perspective Plan (NPP);
- ii) Research Scheme on Power (RSoP); and
- iii) In-house Research and Development Scheme (IHRD) of CPRI.

The MoP is also supporting the research projects under UAY and IMPRINT scheme/programme of MHRD, where MoP is a stakeholder. Since the research projects under both the scheme/programme are mainly collaborative in nature involving participation of industry and the IITs, these are being considered as R&D proposals/projects under National Perspective Plan (NPP) scheme.

### 2.6.2 R&D Schemes being implemented under the Aegis of MoP

Ministry of Power had approved an outlay under XII<sup>th</sup> Plan of Rs.45 crores for R&D



schemes under NPP, Rs.20 crores for Research Scheme on Power (RSoP) and Rs, 15 crores for In-house Research Scheme of CPRI, totalling to Rs 80 crores. Total 90 projects with an outlay Rs.60.3719 crore were approved during 12<sup>th</sup> Five Year Plan i.e till 2016-17.

SFC Memo of CPRI in respect of continuation of R&D schemes of Ministry of Power being implemented through CPRI beyond March, 2017 is submitted for approval of MoP.

#### **A. Research & Development Scheme under National Perspective Plan (R&DNPP)**

The projects proposed under this scheme are focused on development of New Product / Process Development leading to field implementation. The crucial needs of Power Sector require R&D to bridge the technology gaps in various subsections of power sector (Generation, Transmission & Distribution) trading of electricity. The Research Areas and topics are identified and prioritized. The R&D is to be aimed at either improving design of an individual plant component and/or evolving cost efficient overall process. R&D work needs to take advantage of the advances in IT, electronics and communication to improve the control & instrumentation system, data acquisition system and monitoring of system performance parameters. Normally the collaborator and MOP provide funding of the project in the ratio of 50:50 each (in case the collaborator is from equipment manufacturer or utility). However, in case the collaborator is from Technical/Research Institution, 100% funding can be provided by MOP

The Ministry of Power constituted a Standing Committee on R&D (SCRD) to frame 15 years National Perspective Plan for R&D in Indian Power Sector, in the year 2002. Standing Committee on R&D under the Chairmanship of Chairperson CEA has members drawn from leading organizations like CEA, CPRI, NTPC, NHPC, POWERGRID, BHEL, DIPP, DSIR and MNRE. Director General CPRI is the Member Convener for this committee. The

mandate of this committee is to frame a perspective R&D plan. The Indian Power Sector is facing major challenges today with the introduction of reforms, globalization and liberalization policy of the government. With the increase in system expansion, stability and security problems have become more challenging. It is of vital importance to focus attention on ways and means to build expertise within the country to find solutions for the problems existing in the system and also for the problems that may arise in the future. Research is needed to bridge the knowledge and technology gaps, more so due to the faster pace of technological changes in today's world.

#### **Uchhatar Avishkar Yojana:**

Uchhatar Avishkar Yojana is an initiative of Ministry of Human Resource Development (MHRD) to promote innovation of a high order that directly impacts on and meets the needs of the industry and there, improves the competitive edge of Indian manufacturing. Under this scheme, the Indian Institutes of Technology (IITs) have partnered with industry for research projects that would result in innovative solutions for their problems. IIT, Madras is the National Coordinator for this scheme. The objectives of this scheme are as under:

- i. To promote innovation in areas that are directly of relevance to the manufacturing and design industry
- ii. To spur innovative mind-set in the students and faculty in premier technological institutes
- iii. To bring a coordinated action between academia and industry
- iv. To strengthen the laboratories and research facilities in the premier technological institutions
- v. To have outcome-based research funding

The funding pattern of the projects selected under this scheme would be 25% by industry, 25% by participating Department/ Ministry and 50% by Ministry of Human Resource Development (MHRD). Whereas there would

be no limit on the project size, the overall annual investment would be limited to Rs 250 crores.

### **Impacting Research Innovation & Technology (IMPRINT)**

The IMPRINT is a national initiative of Ministry of Human Resource Development for promoting high quality research and innovation in the higher educational institutions covering 10 domains which address the most relevant engineering challenges faced by the Nation. IMPRINT aims to translate knowledge into viable technology (products or processes) and through that, achieve inclusive growth and self-reliance. One of the domains identified is Energy. Ministry of Power is the host for Energy domain with the participant Departments/Ministries being MNRE, DST, DRDO, DAE, DoS and Diety.

The budget identified for this initiative is Rs. 1000 crores from the year 2016-17. MHRD has budgeted Rs.500 crores for funding research and matching contribution from other Ministries who are stakeholders in R&D is expected.

### **B. Research Schemes on Power (RSOP)**

RSOP schemes are fully funded by MOP and aims to carry out need based research in power sector including research in various operational problems encountered in power system. The RSOP projects are undertaken by organisations including academia such as IITs, NITs, and utilities etc.

### **C. In-house R&D Scheme of CPRI**

Under this Scheme various Divisions and Units of the CPRI take up Research Projects under the In-house R&D scheme for which fund is provided by Ministry of Power, Government of India. These schemes are fully funded by Ministry of Power. The scheme is aimed at: -

- Augmentation of Research and testing facilities.

- Improvements /New techniques in testing /Diagnostic methods /Research studies.
- Product/Process Improvements.
- Improvement in product standardization.

### **2.6.3 Other R&D initiatives and HRD in CEA (MoU with IIT, Delhi)**

CEA, being a Statutory Authority in the Power Sector and the technical arm of Ministry of Power, has been given the mandate to promote research in matters affecting the generation transmission, distribution and trading of electricity.

India is a fast growing economy and power has to grow at a faster pace to sustain the growth of various core sector. It is the need of the hour that many grey areas of generation, transmission, distribution and trading of power may be explored and addressed through R&D initiatives in these fields which may yield sizable benefits to the power sector.

In the light of the above, an MoU was signed between MoP/CEA & IIT Delhi to develop:

- R&D Project in Power Sector; and
- Development of Human Resource relevant to the need of Power Sector to further strengthen R&D initiative in CEA.

The revised MoU has been signed between IIT, Delhi & CEA in July, 2013.

Under the obligation of MoU, two officers, one for M.Tech and another for MBA are currently pursuing their course.

### **2.6.4 High level Committee for assessment and review of R&D activities of Organization/PSUs under the Ministry of Power**

A high level Committee was constituted under the chairmanship of Secretary(Power) in order to have a coordinated approach and proper monitoring of R&D efforts being carried in the power sector by Organisations/PSUs of the MoP. In its first meeting held on 19<sup>th</sup> January 2017, it was resolved to constitute a Sub-

committee under the chairmanship of Chairperson, CEA.

The terms of reference of the Sub-committee were:

- i. To list out all major R&D activities being undertaken by Organizations/ PSUs under the Ministry of Power.
- ii. To identify areas where there is an overlap and possibility for collaboration.
- iii. To identify areas of importance for the power sector and focus areas for research in the next 3 to 4 years.

The sub-committee submitted its report in June 2017. Second meeting of High level committee was held on 19.09.2017 to discuss the report submitted. It was inferred that no significant overlap exists in the research efforts of the Organizations/PSUs. The report also consists of thrust areas of research for the next 3-4 years which will be helpful in shaping the future of Power sector of India.

### **2.6.5 Committee on Technical Aspects of Charging Infrastructure for Electric Vehicles**

Ministry of Power set up the following two Committees with respective terms of reference to address the issues and draw the roadmap for setting up charging infrastructure related to Electric Vehicles:

- (1) Committee on Technical Aspects Terms of reference of the Committee are as follows :
  - Regulations/Standards to be framed for charging infrastructure set up
  - Infrastructure
- (2) Committee on Policy, Planning and Regulatory/Tariff related issues

Terms of reference of the Committee are as follows:

- Regulatory aspects and Policy interventions
- Tariff Issues
- Ownership structure to be adopted for the charging infrastructure
- Subsidies/Incentives for promotion

required

- Planning of roll-out

**Committee on Technical Aspects of Charging Infrastructure for Electric Vehicles** headed by Member(Planning), CEA dealt with the technical and infrastructure related issues for charging infrastructure setup.

The meetings of the Committee were held on 12.02.2018 & 14.03.2018 and decisions on the Terms of Reference were finalized. Final report of the Committee has been submitted to the Ministry of Power.

### **2.6.6 ETD-52 (Committee to develop safety standards for energy storage systems)**

A Committee (ETD-52) has been constituted under the aegis of Bureau of Indian Standards (BIS) to develop safety standards for energy storage systems under the chairmanship of Shri Pankaj Batra, Member (Planning). R&D division is also a part of the Committee and it was assigned the task to examine the proposed draft standards with the corresponding IEC documents and IEEE publications as available and submit its recommendations. The recommendations have been included in the final draft report. The final draft report is under circulation among the members of the Committee for further comments.

### **2.6.7 Conferences and Conclaves organised by R&D, CEA.**

#### **2.6.7.1 Conference on E-mobility to meet India's Electric Vehicles Target**

Central Electricity Authority(CEA) in association with Independent Power Producers Association of India(IPPAAI) organized a Conference on E-Mobility to meet India's Electric Vehicles Target on 24<sup>th</sup> January, 2018 at New Delhi. The conference was inaugurated by the Hon'ble Minister of State(IC) for Power and New and Renewable Energy.

The Conference had discussions and



presentations on the following topics related to Electric Vehicles roll out:

- i. Policy Issues for Creating a Favorable Ecosystem to Meet India's E-Mobility targets and Global Practices
- ii. Regulations including Tariff for E-Mobility
- iii. Types of Chargers & Standards
- iv. Implementation & Roll Out of E-Vehicles & Charging Infrastructure at National, State & Local (Municipal & Panchayat) Level.

#### 2.6.7.2 International R&D Conclave



CEA being a nodal body for the Ministry of Power (MoP), has powers under the Section 73(k) of the Electricity Act, 2003 to promote research in matters affecting the generation, transmission, distribution and trading of electricity, the Research and Development (R&D) Division of CEA has been overseeing and promoting the activities of research in the Indian Power Sector.

In order to direct focus in the area of research in the power sector and to create a platform for

dissemination of knowledge in the field of R&D and to stimulate innovation so that new thrust areas can be identified, an **International R&D conclave** was organized on **20<sup>th</sup> and 21<sup>st</sup> February 2018** for promotion of research in the power sector in the whole country. This is also in view of the new smart grid technology coming up for handling the variability in the power from the renewable sources of energy. The Conclave was a **2-Day event** titled



**“Emerging Opportunities and Challenges of R&D in Indian Power Sector”** held at New Delhi. The Hon'ble Minister of State(IC) for Power and New and Renewable Energy was the Chief Guest at the Conclave.



A total of 48 research papers, spread over seven sessions dealing with Thermal, Hydro, Renewable, Transmission, Grid Operation, Distribution and Trading/Marketing & Tariff were presented at the Conclave with each paper followed by interaction among the participants on various issues and challenges in the matter.

#### 2.7 Fuel Management and Analysis



Central Electricity Authority (CEA) plays a pivotal role in optimal utilization of coal for the power sector. It monitors coal supply to the power plants so that plants have coal stock as per norms. CEA is associated with MoP, MoC, Railways and others stakeholders to closely examine the coal supply to power plants and take necessary steps to improve the coal supply to power plants. With the concerted efforts of all stakeholders, the coal supply to power utilities has improved.

### 2.7.1 Monitoring Mechanism

The coal stock position of all the power plants in the country having coal linkages are being monitored by CEA on a daily basis and daily report is published on CEA website. Moreover, on monthly basis, all the power plants including plants designed on imported coal, plants having dedicated coal block, plants getting coal through e-auctions apart from the plants having coal linkages are monitored and monthly report is published on CEA website. As on 31<sup>st</sup> March 2018, the total coal stock available with the 114 Nos. plants was 16.3 Million Tonnes (MT) and twenty eight (28) power plant were critical in coal stock (coal stock for less than 7 days).

CEA is a member of following committees which review and monitor coal supply and related infrastructural constraints:

- Inter-ministerial subgroup constituted by the Infrastructure Constraints Review Committee under the aegis of

Joint Secretary, Ministry of Coal comprising representatives from Ministry of Railways, Ministry of Power, CEA and Coal India Limited.

- Infrastructure Constraints Review Committee, headed by the Secretary (Coordination), Cabinet Secretariat.

## 2.7.2 Coal Scenario for the Power Sector during 2017-18

### 2.7.2.1 Coal Supply Position for the year 2017-18

For the year 2017-18, coal based generation target was 958.4 BU and accordingly the requirement of coal for the year was estimated to be 630 Million Tonnes (MT). However, the actual coal based generation was 951.5 BU and the actual coal consumption was 608 MT during 2017-18. Coal receipt and consumption for year 2017-18 is given as under:

(Figures in MT)

|   |                     |
|---|---------------------|
| Estimated Requirement (Domestic + Imported) | 630.0<br>(584 + 46) |
| Receipt- Domestic coal (Actual)             | 538.6               |
| Receipt- Imported coal (Actual)             | 56.4                |
| Total Receipt (including Imported Coal)     | 595.0               |
| Consumption (including Imported coal)       | 608.0               |

During the year 2017-18, the coal received by the power plants from domestic sources was 538.6 MT as against 494.7 MT during the year 2016-17. The total coal consumption for the year 2017-18 was 608 MT as against 575 MT over the same period last year i.e. 2016-17. The plant-wise details of the coal receipt and consumed during 2017-18 are enclosed at **Annexure 2A**.

### 2.7.2.2 Source-wise Receipt of Coal during the year 2017-18

During the year 2017-18, source wise break up of coal receipt at the power stations is

given below:

| Source                   | Actual Receipts<br>(Million Tonnes) |
|--------------------------|-------------------------------------|
| CIL & SCCL               | 468.0                               |
| Captive Mines            | 31.6                                |
| E- auction               | 39.0                                |
| <b>Total (Domestic):</b> | <b>538.6</b>                        |
| Import                   | 56.4                                |
| <b>Total:</b>            | <b>595.0</b>                        |

### 2.7.2.3 Import of Coal during year 2017-18

Power Utilities are importing coal to bridge the shortfall in the availability of domestic coal as well as to meet the requirement of coal for the power plants designed on imported coal. Under the guidance of Ministry of Coal, Coal India Ltd. (CIL) has taken initiative for substitution of imported with domestic coal. Coal India, in this pursuit, has devised customized strategy as per suitability of each power station and has already started the process of substitution of imported coal with domestic coal for many power plants.

With the increased production of domestic coal, the coal being imported for blending with domestic coal has been decreasing. The coal imported for blending by the power utilities during 2017-18 was 17.04 Million Tonnes (MT) vis-à-vis 19.76 MT during 2016-17 resulting in reduction of 2.72 MT (13.7%). In addition to above, Power Utilities having plants designed on imported coal have imported 39.4 MT coal during 2017-18 vis-à-vis 46.30 MT coal during 2016-17 against estimated 46 MT during 2017-18.

### 2.7.2.4 Generation Loss

During the year 2017-18, power utilities have reported generation loss of about 15.2 BU (Provisional) due to coal shortage.

### 2.7.2.5 Specific Coal Consumption (kg/k Wh)

During the year 2017-18, the Specific Coal Consumption of the power plants designed on domestic coal was 0.662 kg/kWh and that of

plants designed on imported coal was 0.465 kg/kWh.

### 2.7.2.6 Coal Quality Issues

In order to address quality concern of the coal supplied to power plants, it has been decided that coal samples shall be collected and prepared by a Single Third Party Agency appointed by power utilities and coal companies. Accordingly, it was decided by the Ministry of Power and the Ministry of Coal that the power utilities would appoint a Third Party Sampler namely CIMFR for Third Party Sampling and Analysis of coal at loading-end as well as at unloading-end. On the basis of third party sampling analysis results, in case of difference between declared grade and analysed grade of coal, credit/debit notes are being issued by coal companies.

Third party sampling has been started by CIMFR at loading as well as unloading ends, which has resulted into lower ECR, thus benefiting the end consumers of electricity.

### 2.7.2.7 Estimation of Coal requirement for the year 2018-19

As per the coal based generation target of 1008.3 BU for the year 2018-19, FM division, CEA has estimated the total coal requirement for the year as 656 MT comprising 610 MT domestic coal and it was also taken into account that about 46 MT may be imported by the power plants designed on imported coal. The total coal availability from domestic sources is expected to be around 610 MT (including coal from CIL/SCCL, Captive Coal Blocks, E-Auction) showing no shortfall of domestic coal during 2018-19.

The details are as given below:

**BU: Billion Units MT: Million Tonnes**

| S.No.    | Description   |    |        |
|----------|---|----|--------|
| <b>1</b> | <b>Coal based generation</b>                          |    |        |
| 1.1      | Coal based generation programme for 2018-19           | BU | 1008.3 |
| <b>2</b> | <b>Coal Requirement</b>                               |    |        |
| 2.1      | Coal requirement for plants designed on domestic Coal | MT | 610    |
| 2.2      | Coal requirement for plants designed on imported coal | MT | 46     |
| 2.3      | Total Coal Requirement                                | MT | 656    |
| <b>3</b> | <b>Coal availability from Indigenous sources</b>      |    |        |
| 3.1      | From CIL  | MT | 513    |
| 3.2      | From SCCL   | MT | 53     |
| 3.3      | From Captive Mines                                    | MT | 32     |
| 3.4      | From e-auction  | MT | 12     |
| 3.5      | Total domestic coal availability                      | MT | 610    |
| 3.6      | Shortfall in domestic coal availability               | MT | 0      |
| 3.7      | Requirement of imported coal for blending             | MT | 0      |

It is seen from the above that power plants based on domestic coal would meet their requirement of coal from indigenous sources and may not require import of coal for blending. However, some power utilities/power plants may plan for import of coal for blending for their coastal power plants considering economics in import of coal vis-à-vis domestic coal and Railway logistic constraints etc. Power plants designed on imported coal would continue to import about 46 MT to meet their coal requirement.

### 2.7.2.8 New initiatives for addressing issues related to coal supply to Power Plants

#### A. Flexibility in Utilization of Domestic Coal

The Government, on 04.05.2016, approved the proposal for allowing flexibility in utilization of domestic coal amongst power generating stations to reduce the cost of power generation. Under the scheme, the Annual Contracted Quantity (ACQ) of each individual coal linkage as per Fuel Supply Agreement is to be aggregated as consolidated ACQ for each State and Company owning Central Generating Stations instead of individual generating station. The State/Central Gencos would have flexibility to utilize their coal in most efficient and cost effective manner in their own power plants as well as by transferring coal to other State/Central Gencos Power plants for generation of cheaper power. The methodology for utilizing coal amongst State/Central Generating Stations has been issued on 08.06.2016 by CEA.

Further, the methodology for use of coal transferred by a State to Independent Power Producer (IPP) generating stations has been issued by Ministry of Power, Govt. of India on 20.02.2017. As per the methodology, the State can divert their coal and take equivalent power from IPP generating stations selected from the competing IPPs through an e-bidding process. The guiding principle of the methodology is that the landed cost of power from IPP generating station at the State's periphery should be lower than the variable cost of generation of the State generating station whose power is to be replaced by generation from IPP. The landed cost of power is inclusive of the transmission charges and transmission losses.

All the power utilities have signed supplementary agreement with CIL/

Subsidiaries for aggregation of their Annual Contracted Quantity (ACQ) and they are now giving coal program matrix as per their aggregate requirement. Under the flexibility, Gujarat has selected M/s GMR Chhattisgarh Energy Limited for taking 500 MW power for 8 months by transferring their coal from SECL to the GMR Raikheda plant.

### B. National Power Portal

National Power Portal (NPP) has been developed in CEA for collection of various power sector data and generation of reports. Through this portal, the power plants are furnishing their coal related data and reports are being generated and published. Daily Coal Report, Monthly Coal Report and Monthly Gas Report are being generated through this portal.

### C. New Daily Coal Monitoring Methodology

After the discussion with all stake holders and approved by the Authority, a new methodology was issued in November 2017 to monitor coal stock position of the

power plants on daily basis. New methodology was necessitated as the States/Central power utilities started implementing the flexibility in utilization of domestic coal by allocating their aggregated coal to power plants, irrespective of plant specific ACQ.

#### 2.7.2.9 Gas/Liquid supply to Gas based Power Stations

Out of total 25150 MW Gas/Liquid fuel based installed generating capacity in the country as on 31<sup>st</sup> March 2018, CEA monitored the supply of gas to 62 gas based power stations, using gas as the primary fuel, totaling to a capacity of 23842.7 MW (excluding liquid fuel based power plants).

#### 2.7.2.10 Gas Requirement and Supply Position

The production and supply of gas have not been keeping pace with the growing demand of gas in the country including power sector. Even gas allocations committed for power stations were not fulfilled due to shortage of gas supply in the country. Supply of gas to gas based power plants since 2008-09 has been as under:

#### Supply of gas to gas based power plants since 2008-09 has been as under:

| Sl. No. | Years   | Capacity at the end of year (MW) | Gas Required* (MMSCMD) | Average Gas Supplied (MMSCMD) | Shortfall (%) (MMSCMD) |
|---------|---------|----------------------------------|------------------------|-------------------------------|------------------------|
| (1)     | (2)     | (3)                              | (4)                    | (5)                           | (6)=(4)-(5)            |
| 1.      | 2008-09 | 13,599.62                        | 66.61                  | 37.45                         | 43.8%                  |
| 2.      | 2009-10 | 15,769.27                        | 78.09                  | 55.45                         | 29.0%                  |
| 3.      | 2010-11 | 16,639.77                        | 81.42                  | 59.31                         | 27.2%                  |
| 4.      | 2011-12 | 16,926.27                        | 81.78                  | 55.98                         | 31.5%                  |
| 5.      | 2012-13 | 18,362.27                        | 90.7                   | 40.0                          | 55.9%                  |
| 6.      | 2013-14 | 20385.27                         | 97.9                   | 27.13                         | 72.3%                  |
| 7.      | 2014-15 | 21665.57                         | 104                    | 25.2                          | 75.8%                  |
| 8.      | 2015-16 | 23075.57                         | 113.63                 | 28.26                         | 75.1%                  |
| 9.      | 2016-17 | 24037.17                         | 118.16                 | 30.32                         | 74.3%                  |
| 10.     | 2017-18 | 23842.17                         | 114.50                 | 30.72                         | 73.2%                  |

\* Normative gas requirement at 90% PLF taking GCV of gas= 9000 kCal/SCM (except for Ramgarh CCGT for which GCV is 4150 K Cal/SCM), Station Heat Rate= 2900 kCal/kWh for open cycle and 2000 kCal/kWh for combined cycle.

(MMSCMD – Million Metric Standard Cubic Metres per Day)



## 2.8 Renewable Energy

- i. The Government of India has set a target of achieving Renewable Energy Capacity of 175 GW by the year 2022. This includes 100 GW of Solar, 60 GW of Wind, 10 GW consisting of Biomass & Bagasse and 5 GW of Small Hydro. As per the information received from Ministry of New and Renewable Energy (MNRE), as on 31.3.2018, the total grid connected installed capacity of renewable sources of generation was 69.02 GW.
- ii. The Solar power tariffs in India have fallen in nominal terms from INR 17 /kWh in 2009 to INR 2.44 kWh (levelized tariff in respect of Bhadla Solar Park, Rajasthan) in May 2017, which is mainly due to decline in module prices, improvement in technology and competitive environment. The ever-declining solar power tariffs have encouraged good investments into the sector. The tariff discovered in the auction conducted by Gujarat Urja Vikas Nigam Ltd (GUVNL) for wind power also reduced to Rs 2.43 per kWh in Dec 2017.
- iii. Government of India has increased the power generation capacity to be achieved from Solar Parks installations from the originally set target of 20 GW to 40 GW, through setting up of 50 Solar Parks in the country with a capacity of

500 MW or more concentrated in one area.

### 2.8.1 Issues pertaining to Grid integration of Renewable Energy Sources

As per Regulation 5.2 (u) of the Indian Electricity Grid Code (IEGC) power from the wind or solar power projects enjoys must run status. Renewable generation like solar and wind power is variable in nature and to tackle the variability/intermittency of generation from such sources, the requirement of a suitable balancing mechanism is essential to ensure grid security. Grid integration therefore is the priority item for expanding Renewable Energy generation in India.

A Committee was constituted under the Chairmanship of Member (Planning), CEA to study optimal location of various types of balancing energy sources /energy storage devices to facilitate grid integration of Renewable Energy Sources. The Committee held various Meetings, and the final report was submitted to MoP on 15-12-2017. The report covers, among other things, the balancing requirement, Ancillary market development and sharing of cost on the same.

### 2.8.2 Generation from Renewable Sources

Generation from Renewable Energy Sources for the years 2014-15, 2015-16, 2016-17 & 2017-18 and the graph indicating the installed capacity v/s generation from RE sources for the above period are given below:

| Years   | Non RES Generation | RES Generation (MU) | Total Generation | Percentage of RE to total generation | CAGR (%) from 2014-15 to 2017-18 |                |                    |
|---------|--------------------|---------------------|------------------|--------------------------------------|----------------------------------|----------------|--------------------|
|         |                    |                     |                  |                                      | Total Generation                 | RES Generation | Non RES Generation |
| 2014-15 | 1048673            | 61719               | 1110392          | 5.56                                 | 5.62                             | 18.17          | 4.78               |
| 2015-16 | 1107822            | 65781               | 1173603          | 5.61                                 |                                  |                |                    |
| 2016-17 | 1160141            | 81548               | 1241689          | 6.57                                 |                                  |                |                    |
| 2017-18 | 1206306            | 101839              | 1308146          | 7.79                                 |                                  |                |                    |


Renewable energy generation was about 7.8% of total energy generation in the country during 2017-18. Year wise generation from



renewable energy sources (RES) indicating the growth rates is given below:



**Year wise generation from Renewable Energy Sources (RES) in BU**


| Year    | Generation from RES (BU) | Year on year growth (%) | CAGR from 2014-15 to 2017-18 |
|---------|--------------------------|-------------------------|------------------------------|
| 2014-15 | 61.72                    |                         | 18.17                        |
| 2015-16 | 65.78                    | 6.58                    |                              |
| 2016-17 | 81.55                    | 23.97                   |                              |
| 2017-18 | 101.84                   | 24.88                   |                              |

The generation from various types of renewable energy sources is depicted in the following graphs.









## CHAPTER – 3

### POWER SYSTEMS PLANNING AND DEVELOPMENT

#### 3.1 Transmission Planning

All issues relating to planning and development of Transmission System in the country are dealt in the Power System Wing of CEA. This includes evolving long term and short term transmission plans in coordination with central, state transmission utilities and generating companies. The network expansion plans are optimized based on power system studies. This also involves formulation of specific schemes, evolving a phased implementation plan in coordination with the Central and State transmission utilities and their implementation, issues pertaining to development of national power grid in the country and issues relating to cross border electricity interconnections. Transmission planning studies are being conducted to identify evacuation system from generation projects and to strengthen the transmission system in various regions.

#### 3.2 Inter-regional transmission system in India – National Grid.

A national grid in the country has been developed in phased manner. All the regional grids have been inter-connected synchronously to form one Grid-one Nation- One frequency. Inter-regional transmission capacity by the end of 9th Plan was 5750 MW that increased to 14050 MW by the end of 10th Plan, increased to 27750 MW by end of 11th Plan, and increased to 75,050 MW by the end of 12<sup>th</sup> plan. During the year 2017-18, 11400 MW of Inter-Regional transmission capacity has been added making the total capacity of 86450 MW by end of 31.03.2018.

Details of the Inter-regional transmission capacity in the country as on 31.03.2018 (excluding 132 kV link) are given at **Annexure – 3A**.

#### 3.3 Regional Standing Committees on Power System Planning.

##### 3.3.1 Brief Introduction:

The Regional Standing Committees on Power System Planning constituted by CEA is chaired by Member (PS) ,CEA and have representation of Transmission Utilities of constituent States of the region, Central Transmission Utility (i.e POWERGRID), POSOCO, representative of Central Sector Generating companies and Regional Power Committee. The interstate transmission system for evacuation of generation & system strengthening schemes and some of the major intra-state transmission schemes are firmed up through discussion in the meetings of the Regional Standing Committee of power system planning.

##### 3.3.2 Following Standing Committee Meetings were held during 2017-18:

###### Northern Region:

- 39<sup>th</sup> meeting of the Standing Committee on Power System Planning of Northern Region held on 29-30th May, 2017 .

###### Western Region:

- 42<sup>nd</sup> Meeting of the Standing Committee on Power System Planning in Western Region held on 17.11.2017 .

###### Eastern Region:

- 19<sup>th</sup> Standing Committee Meeting on Power System Planning of Eastern Region held on 01.09.2017.

###### Southern Region:

- 41<sup>st</sup> Meeting of the Standing Committee on Power System Planning of Southern Region held on 22<sup>nd</sup> September, 2017.

The transmission systems firmed-up in these meetings are given in **Annexure – 3B**.

### 3.4 Empowered Committee on Transmission

#### 3.4.1 Brief Introduction:

Promotion of competition in the electricity industry in India is one of the key objectives of the Electricity Act, 2003. As per the provisions under Section 63 of the Electricity Act, 2003 and the Tariff Policy dated 6<sup>th</sup> January, 2006, Ministry of Power, issued “Guidelines for Encouraging Competition in Development of Transmission Projects” and Tariff Based Competitive Bidding Guidelines for Transmission Services”. These guidelines aim at laying down a transparent procedure for facilitating competition in the transmission sector through wide participation in providing transmission services and tariff determination through a process of tariff based competitive bidding.

As envisaged in the Guidelines, Ministry of Power had constituted an Empowered Committee on Transmission to identify inter-state transmission projects to be developed through competitive bidding and to oversee the process of competitive bidding.

As provided in the Guidelines, Ministry of Power has appointed PFC Consulting Limited (PFCCL) and REC Transmission Projects Company Limited (RECTPCL) as the Bid Process Coordinators (BPC) for carrying out the bidding process.

#### 3.4.2 Status of the schemes identified by the Empowered Committee on Transmission for implementation through TBCB:

As on 31.03.2018, twenty three (23) Schemes are under implementation and fourteen (14) schemes had been commissioned by the Transmission Service Providers. In addition, there are two notified schemes for which the bidding process is in progress.

These schemes are given at **Annexure – 3C**.

#### 3.4.3 Following meetings of the Empowered Committee on Transmission were held during 2017-18:

- 37<sup>th</sup> Meeting of Empowered Committee on Transmission was held on 20<sup>th</sup> September, 2017, at CEA.

The transmission schemes and relevant issues taken up in these meetings are given at **Annexure – 3D**.

#### 3.4.4 Cost Committee:

Based on the decision taken in the 32<sup>nd</sup> Empowered Committee on Transmission held on 17<sup>th</sup> January, 2014, a Cost Committee was formed with the representatives from CEA, Powergrid/ CTU and BPCs to work out a matrix for different type of transmission lines which would consider different type of variables for estimating the project cost (for example, type of the terrains, wind zones, etc.). The Cost Committee worked out the cost of the transmission schemes based on the preliminary route survey carried out by the BPCs, details of which are attached at **Annexure-3E**.

### 3.5 Examination of Detailed Project Reports (DPRs) / Feasibility Reports (FRs) of Hydro Power Projects for processing of concurrence by CEA

Following DPRs / FRs of hydropower projects examined for from power evacuations considerations for processing of concurrence by CEA

#### Northern Region :

##### a) Himachal Pradesh

- Revised cost estimation of Parbati III(520 MW) Hydro Electric Project by M/s NHPC.
- DPR examination of Sach Khas(267 MW) by M/s L&T.
- DPR examination of Dugar(449 MW) by M/s Dugar Hydro Power Limited.
- DPR examination of Seli(400

- MW) HEP by M/s Seli Hydro Electric Power Co. Limited.
- (v) DPR examination of Kirthai II(930 MW) HEP by M/s JKSPDC.
- (vi) DPR examination of Sawalkot (1856 MW) HEP by M/s JKSPDC.
- (vii) DPR examination of Luhri – I (210MW) HEP by M/s SJVNL.
- (viii) DPR examination of Kwar (540 MW) HEP by M/s CVPPL.
- (ix) DPR examination of Bursar (800 MW) by M/s NHPC.
- (x) DPR examination of Reoli Dugli (430 MW) by M/s L&T Himachal Hydro Power Ltd..
- (xi) MoC for Vishugad Pipalkoti HEP(444 MW)
- (xii) MoC for Dam Toe Power House of Kishenganga HEP(330 MW) in J&K.

#### North Eastern Region

- i) Attunli HEP (680 MW) in Arunachal Pradesh by M/s Attunli Hydro Electric Power Company Limited
- ii) Tagurshit HEP(3x24.67=74MW) in Arunachal Pradesh by M/s L&T Arunachal Hydropower Limited
- iii) Dibang Multipurpose Project in Arunachal Pradesh (12x240W) by NHPC
- iv) Umngot HEP (210 MW) in Meghalaya by MEPGCL
- v) Mago Chu (3x32=96 MW) HEP, in Arunachal Pradesh by M/s SEW Mago Chu Power Corporation Limited (SMCPCL)

### **3.6 Examination of DPR/FR of Transmission Works.**

#### **Northern Region :**

- i) DPR for revised schemes for intrastate transmission system under Green Energy Corridor

- (GEC) in Himachal Pradesh (Part-B) with estimated cost of Rs.193.56 crores
- ii) DPR for transmission schemes under GEC in Rajasthan for KfW funding in place of deferred schemes with estimated cost of Rs. 218.8 crores

#### **Western Region :**

- i) Transmission scheme proposed under Green Energy Corridor for RES generation projects in Maharashtra as Green Energy Corridor – II (Part-B).

#### **Eastern Region**

Revised DPR of Arun-3 (4x225 MW) ATS between Didin (Nepal) to Bathnaha (India Nepal Border) including Dhalkebar Substation by M/s SAPDC.

#### **Southern Region**

- i) DPR for wind and solar power transmission schemes of APTRANSCO to pose the scheme under 40% NCEF Funding.
- ii) DPR for Intra State scheme of TANTRANSCO under Green Energy Corridor – I, Package – II

### **3.7 Grant of prior approval of Government to transmission proposals under Section 68 of Electricity Act, 2003 during 2017-18.**

The list of transmission proposals examined for approval of the Government of India under Section 68(1) of Electricity Act, 2003 is given below:

#### **Northern Region :**

- Connectivity system of 750 MW Pholadi - Pokhran Solar Power park, Jaisalmer, Rajasthan by M/s Essel Saurya Urja Company of Rajasthan Limited (ESUCRL)
- Transmission system for Ultra



Mega Solar Park in Fatehgarh, distt. Jaisalmer Rajasthan.

#### Western Region :

- POWERGRID works associated with Additional 400 kV Feed To Goa - modification.
- Additional 400 kV Feed to Goa and Additional System for Power Evacuation from Generation Projects pooled at Raigarh (Tamnar) Pool.
- Connectivity system for 300 MW wind power of M/s Ostro Kutch Wind Pvt. Ltd. (OKWPL).
- Connectivity system for Surguja Power Pvt. Ltd. (4x150MW), Parsa, Chattisgarh.
- Additional 2 nos. of 220 kV bays for 1x500MVA, 400/220 kV 3<sup>rd</sup> ICT at Khandwa (PG) S/s.
- Connectivity system for 500 MW wind power of M/s INOX wind infrastructure limited at Dayapur, Kutch, Gujrat (IWISL).
- Connectivity system for Renew Power Ventures Pvt. Ltd. (RPVPL) for its 400MW farm in Kutch, Gujrat.
- Connectivity system of 500 MW wind farms in Walka Mota, Bhuj, Gujrat (WWIL).

#### Eastern Region:

- “Eastern Region Strengthening Scheme - XX (ERSS-XX)” (Returned).
- “Transmission System for Transfer of power from generation projects in Sikkim to NR/WR (Part-B1)” (Returned).

#### Southern Region:

- “Transmission System for Ultra Mega Solar Power Park at Tumkur, Karnataka-Phase-I”
- “Transmission System for Ultra

Mega Solar Power Park at Tumkur, Karnataka - Phase - II” - Modification regarding.

- Construction of 8 Km of 230 kV D/C Transmission line from “Mytrah Wind Farms to Tirunelveli Pooling Station”
- Construction of 230 kV Single Circuit Transmission line from “Orange Sironj Wind Generation Switchyard to Tirunelveli Pooling Station”
- Construction of independent transmission system within Indian territory (400kV Double Circuit overhead transmission line quad AAAC/ACSR conductor) for connecting their coal based thermal power plant (2x800MW) in district Godda of Jharkhand with substation at Bogra in Bangladesh to Adani Power (Jharkhand) Limited (APJL)

#### North Eastern Region:

- North Eastern Region Strengthening Scheme (NERSS-VI)(Modified)

### 3.8 Grant of authorisation to transmission proposals for Section 164 of Electricity Act, 2003 during 2017-18.

#### Northern Region :

- System Strengthening Scheme in Northern Region (NRSS XXXVI)" along with LILO of Sikar – Neemrana 400 kV D/C line at Babai (RRVPL)

#### Western Region :

- Transmission system associated with Gadawara STPS (2X800 MW) of NTPC (Part-A).
- Transmission system associated with Gadawara STPS (2X800MW) of NTPC (Part-B).
- Transmission system strengthening

in WR associated with Khargone TPP(1320MW).

- Connectivity system for 300 MW wind power of M/S Ostro Kutch Wind Pvt. Ltd., Gujarat.

#### **Eastern Region:**

- 400kV Vedanta – Sundargarh/ Jharsuguda pooling station (PGCIL) D/C line of M/s Vedanta Limited (formerly known as Sesa Sterlite Limited / Sterlite Energy Limited).
- “765 kV Strengthening in Eastern Region (ERSS-XVIII)” of POWERGRID Medinipur-Jeerat Transmission Limited

#### **Southern Region:**

- To POWERGRID Southern Interconnector Transmission System Ltd. (PSITSL) for construction of “Strengthening of Transmission system beyond Vemagiri”.
- To M/s Warora - Kurnool Transmission Limited (WKTL) for construction of “Additional Inter-Regional AC link for import into Southern Region i.e. Warora-Warangal and Chilakaluripeta-Hyderabad- Kurnool 765 kV Link”.

#### **North Eastern Region:**

- To M/s Kohima - Mariani Transmission Limited (KMTL) for “North Eastern Region Strengthening Scheme (NERSS-VI).

### **3.9 National Electricity Plan (Transmission)**

As per Section 3 of the Electricity Act 2003, CEA has been entrusted with the responsibility of preparing the National Electricity Plan (Generation & Transmission) in accordance with the National Electricity Policy. Accordingly,

draft National Electricity Plan (Transmission) for the country for the five year period from 2017-18 to 2021-22 has been prepared in consultation with CTU, STU, generating companies and RPCs based on studies carried out for various Load-generation scenarios considering seasonal variations of Load & generations. Draft National Electricity Plan (Transmission) has been submitted to MoP.

The draft document prepared on “National Electricity Plan (Transmission)” covers transmission lines and associated substations including the inter-regional transmission links for the plan period 2017-22 to meet the projected peak demand of 226 GW in the 2021-22 time frame as per 19<sup>th</sup> EPS.

### **3.10 Research & Development Works:**

- (a) Compendium of Tower Design:**  
As per the Resolution of Power Minister's conference held in Vadodara in October 2016, a compendium of approved/tested tower designs (66kV and above voltage level) was prepared and published for the use of various power utilities.
- (b) Pilot Audit of transmission towers of 400kV Abdullapur-Bawana D/C Transmission line, 400 kV D/C Panipat-Dadri-II D/C transmission line and 400 kV Panipat –Kaithal D/C transmission line of PGCIL was carried out in January, 2018.**
- (c) Pilot Audit of transmission towers of 400kV Samaypur-Bamnauli D/C Transmission line & 400 kV Bamnauli-Jatikara D/C transmission line of Delhi Transco Ltd. was carried out in February, 2018.**

### **3.13 Representation/ Nomination in the Committees**

- (a) Member (PS), CEA is representing as member in Joint Steering Committee (JSC) for India-Bangladesh, India –Nepal and India-SriLanka cooperation. Similarly Chief Engineer (PSPA-II) is representing as member in Joint Working Group (JWG) and Joint Technical Team (JTT) in above cooperation.
- (b) PSETD officers are represented in :
  - (i). Technical committees of BIS pertaining to overhead conductor, earth-wire, insulator & hardware, transmission line towers, surge arrestor, power cable, HV switchgear & control gear, transformer, HVDC, solid insulating material, substation automation, high voltage engineering, battery etc.
  - (ii). Task force to formulate Power Sector Council of India (PSCI)
  - (iii). Sub-group for techno-economic appraisal of DPRs for PSDF funding.
  - (iv). Cost Committee and Bid Evaluation Committee for projects to be awarded through Tariff Based Competitive Bidding (TBCB)
  - (v). Preparation of Regulations for communication system in Power Sector.
  - (vi). Task force for issues related to Cyber Security.

### 3.14 Analysis of causes of failure of transmission line towers & substation equipment.

Standing Committee constituted as per provision of Section 73, Clause (1) of the Electricity Act, 2003 taking representation from various power

utilities in the Country investigates causes of failure of Transmission line towers and substation equipment of 220kV and above Voltage Class and suggests remedial measures to avert/minimize the failure.

Standing Committee meetings are organized on regular basis to discuss the failures intimated by various power utilities and remedial measures to minimize such failures in future are recommended.

#### (a) Transmission Line towers:

- (i) As a part of activity of Standing Committee to assess the causes of failure of various Transmission Line Towers of 220kV and above voltage levels, CEA officers visited the failure site for assessment of causes of failure, investigations were carried out. The details of failed transmission lines reported to CEA in the FY 2017-18 is enclosed at **Annexure-3G**.
  - (ii) Report of the standing committee of experts on the failure of EHV Transmission line towers (December 2015 - September, 2016) was finalized and uploaded on CEA website, circulated to MoP & various stake holders.
- #### (b) Substation equipment failures:
- (i) Report of the standing committee of experts on the failure of EHV Substation equipment was finalized and uploaded on CEA website, circulated to MoP & various stake holders.
  - (ii) Failure investigation of 100 MVA, 220/66-33/11 kV Transformer in Naraina substation of DTL, Delhi.
  - (iii) Details of failure of transformers and reactors reported to CEA in the FY 2017-18 is enclosed at **Annexure-3H**

### 3.15 Amendment of CEA Regulations / Miscellaneous Works

- (a) The periodical comprehensive review of chapters of CEA (Technical Standards for construction of Electrical Plants and Electric lines) Regulations 2010 pertaining to 66 kV and above voltage class transmission line and substation was finalized.
- (b) DPR of following projects were examined:
  - (i) Arun-3 ATS between Diding (Nepal) to Bathnaha (India Nepal Border) including Dhalkebar Substation extension.
  - (ii) Kaleshwaram lift irrigation project from power requirement consideration.
  - (iii) Evacuation of power from Wind and Solar projects in Anantapur & Kurnool Districts of Andhra Pradesh.
  - (iv) Power evacuation from Mawphu Hydroelectric Project Stage-II (85 MW), Meghalaya by NEEPCO.
  - (v) Electromechanical work of Dorjilung HEP (Kuri-I) in Bhutan.
  - (vi) Proposals of Punjab, Rajasthan, Haryana, Maharashtra, Karnataka, Tamilnadu, UP, MP, Jharkhand, NE States etc. for grant under PSDF Funding.
- (c) Inputs on RFP documents & replies to bidders queries in respect of the projects to be awarded through TBCB were provided to PFC/REC.
- (d) Meeting of task force to formulate Power Sector Council of India (PSCI) was conducted and preliminary report was prepared.
- (e) The design document and drawing of Demo setup for utilization of transmission line tower infrastructure for mobile telecom purpose was examined.
- (f) Technical Papers on Transmission System were presented in various Conferences/Seminars.
- (g) Visit to Siemens, Bengaluru to assess cyber security testing facility was made.


- (h) The training program for following Software was conducted successfully in the year 2017-18:
  - CDEGS: For Earth mat design in Sub-stations, Electromagnetic interference etc.
  - PSCAD - For System transient analysis.

### 3.16 Power & Telecommunication Co-ordination Committee (PTCC)

PCD Division, CEA continued to follow up cases to expedite PTCC clearance of EHV transmission lines of voltages 220 kV and above through discussions/follow-up with Bharat Sanchar Nigam Ltd. (BSNL), Railways, Defense and SEBs/Power Utilities. The division also rendered assistance to the State Power Utilities in resolving complex PTCC cases of voltage level of 132 kV and below. Based on requests, the division also provided training of Induced Voltage computation to the officers of Power Utilities.


To achieve the objectives of PTCC, two Central PTCC meetings were held viz. 104th Central PTCC meeting at Mysore on 9th June, 2017 chaired by Shri T.V Venkatram, PGM, Bangalore and 105<sup>th</sup> Central PTCC meeting on 10<sup>th</sup> November, 2017 at Cochin chaired by Chief Engineer (PCD), CEA. The meetings were attended by the senior officers of CEA, Central/State Power Utilities, Bharat Sanchar Nigam Ltd. (BSNL), Railways and Defense. In the meetings, many contentious and important issues which are in the interest of Power as well as Communication sector were discussed; and decisions were taken.

During the financial year 2017-18, 183 nos. new cases of EHV power lines (220 kV and above) were received for processing of PTCC route approval. A bar chart indicating the number of cases received/processed for PTCC route approval during the last five financial years is given below:



It may be seen that during 2017-18, computation of Induced Voltage (IV) likely to be developed on the communication / railway circuits in proximity of EHV lines under single line to earth fault current conditions was carried out in respect of 185 nos. CEA forwarded induced voltage details to BSNL, Defense & Railways for issuing the PTCC route approval. It included about 3540 Circuit kilometers of 220 kV lines, about 8037 Circuit kilometers of 400 kV lines and about 6455 Circuit kilometers of 765 kV lines. It is pertinent to mention that during 2017-18, due care has been taken to process PTCC cases of those transmission lines which were required to be charged on urgent basis; and with the result there has been no delay of charging of any line for want of PTCC approval.

A bar chart indicating the Circuit kilometers of 220kV, 400kV and 765kV transmission lines, for which PTCC route approval was accorded during the last five years is given below:



### 3.17 Reliable Telecommunication & Data Acquisition System for Power Sector at 66kV & 33kV level

Ministry of Power has entrusted to CEA the work of coordination with States/UTs in preparation of a Report for ensuring reliable telecommunication and data acquisition system at 66kV and 33kV substations located in disaster prone areas across the country. Accordingly, PCD Division has prepared the Report and submitted to Ministry of Power in Nov., 2016.

### 3.18 Frequency Allocation Co-ordination for Microwave and Power Line Carrier Communication (PLCC)

PCD Division coordinated and followed up with Wireless Planning and Coordination (WPC) Wing of Department of Telecommunications (DoT) to achieve timely frequency allocation for PLCC links of new

power transmission lines of power utilities in the country.

### **3.19 Telecommunication Consultancy and Technical Support**

HE & RM Division, CEA carried out the consultancy assignment for Jigmeling 400kV GIS Substation, Bhutan. PCD Division prepared the Technical Specifications for PLCC System. During execution, PCD division rendered assistance, as and when required.

Similar assistance was provided to HE&TD Division, CEA in regard to telecommunication consultancy assignment for Punatsangchhu-I Hydroelectric Project (6X200MW), Bhutan.

### **3.20 Framing of Central Electricity Authority (Technical Standards for Communication System in Power Sector) Regulations, 2018**

It was noted that in the absence of Standards for Communication Systems, adequate planning of communication systems commensurating with transmission system planning was not being done. The transmission utilities tend to provide need based communication facilities in a non-systematic manner. Therefore, the provision of Communication Standards was considered to be vital for the power sector.

To prepare the Technical Standards of Communication System in Power Sector, a Committee under the chairmanship of Member (Power System), CEA was constituted. The Committee comprises representation from NTPC, NHPC, PGCIL, KPTCL (Karnataka), MSETCL (Maharashtra), OPTCL (Orissa), APTRANSCO (Andhra Pradesh), NLDC (POSOCO), Wind Power Association and CEA.

The Committee finalized the Draft Technical Standards. The objectives of the Communication Standards were to ensure seamless integration, reliable, redundant and secure communication. These standards are

applicable to all Communication Service Provider, Central & State Generating Company including Grid connected Captive Generating Plant, RE Generator, Transmission Licensees, Distribution Licensees, Bulk Consumers, whose electrical system is connected to transmission system, Market Operation Service Providers, Forecast/Weather service provider & Ancillary service providers. The performance and reliability requirements of communication system have also been specified, so that these aspects are taken care by the Communication Service Provider while designing the systems. The security requirements to manage cyber security risks have also been addressed.

The Communication Standards are divided into two parts. First part deals with the General Requirement for the Communication System including Objective, Functional Requirement, Standard Codes and Practices, General Conditions, Performance of the communication system, etc. The second part is in the form of Schedules dealing with the different technological options available for the communication system for Power Sector. In this part, the technical requirement of Interface System, Wideband Communication, PLCC, VSAT and GPRS based communication system have been described.

To seek public comments, the draft Communication Standards were placed in public domain.

### **3.21 Inspection of Electrical Installation**

The Indian Electricity Act, 2003 stipulates the statutory inspection of electrical installations by Central and State Electrical Inspectors in respect of installations within their respective jurisdictions. The Chief Electrical Inspector and Electrical Inspectors appointed by the Central Government under section 162 of EA 2003 discharge the functions described in 'The Qualifications, Powers and Functions of Chief Electrical Inspector and Electrical Inspectors Rules, 2006' as per the procedures provided in Central Electricity Authority (Measures

Relating to Safety and Electric Supply) Regulations, 2010 (as amended). The Chief Engineer of Chief Electrical Inspectorate Division is appointed as Chief Electrical Inspector to the Government of India and is assisted by the officers of Chief Electrical Inspectorate Division and the officers from five Regional Inspectorial Organizations (RIO's) with Headquarters at New Delhi, Chennai, Shillong, Mumbai & Kolkata & they are appointed as Electrical Inspectors to the Government of India in discharging the various responsibilities, briefly described as under:

- (a) Statutory periodic inspection of electrical installations for compliance under Regulation 30 of Central Electricity Authority (Measures Relating to Safety and Electric Supply) Regulations, 2010 (as amended).
- (b) Inspection of new electrical installations under Regulations 43 of Central Electricity Authority (Measures Relating to Safety and Electric Supply) Regulations, 2010 (As amended) for according approval for energization of electrical installation of voltage exceeding 650 Volts.
- (c) Inspection of Electrical installations in Cinema house and issue of no objection certificates for grant of annual license to the cinema house under the respective Cinematography Act in force in the Union Territories.
- (d) Inquiry of fatal and non-fatal electrical accidents and remedial measures to be taken to avoid recurrence of such accidents in future.
- (e) Scrutiny of cases received regarding erection/alteration of building under overhead lines involving infringement of Regulations 60, 61 & 63 of Central Electricity Authority (Measures Relating to Safety and Electric Supply) Regulations, 2010.
- (f) Issue of Electrical Contractor licenses and competency certificates to Supervisors and wireman through the Licensing Board in

respect of Union Territory of Puducherry & Chandigarh.

- (g) As per the Gazette of India notification dated 1st March, 2018, the 2nd amendment of Central Electricity Authority (Measures relating to safety and electric supply) Regulations, 2010 was notified.

### **3.22 MAJOR ACHIEVEMENT IN TERMS OF INSPECTIONS DURING THE YEAR 2017-18 (Important installations inspected) :**

#### **3.22.1 New Electrical Installations/ Apparatus under Regulation 43 of Central Electricity Authority (Measures Relating to Safety and Electric Supply) Regulations, 2010 (as amended) :-**

##### **A) Substations :**

- (I) **765kV Substations:** Wardha, Durg, Singrauli, Indore, Korba, Padghe, Solapur, Jabalpur, Sundargarh, Ranchi, Angul NTPC Sipat, NTPC Gadgarwara, NTPC Narsinghpur, Kotra, Champa, Bilaspur, Bansia-Kotra, Sasan, Tamnar, Sasan (UMPP), Ahmedabad (CWRTL), Vindhyachal (CWRTL), Korba (TRN Power), Ahmedabad (RRWTL), Beed (PGPTL), Orai, Vemagiri, Aligarh, Chittorgarh, Ajmer, Osmanabad (PGPTL), Chandrapur (PGWTL), Bina (NHPTL), Seoni (JPL) , NTPC Darlipalli.
- (ii) **400kV Substations :** Gwalior, Singrauli, Korba, Padghe, Satana, Vindhyachal, Aurangabad, Rewa, Raigarh, Solapur, Ambajogai, Jabalpur, Nagpur, Shajapur, Khandwa, Itarsi, Kudus, NTPC Khargone, Mundra (Adani), Beed (PGPTL), Chandrapur (PGWTL), Ballabhar, Mainpuri , Kaithal, Manesar, Biharsharif, Alipurduar, Rupnarayanpur, Daltonganj, Purnea, Gaya, Pusauli, Rourkela, Jamshedpur, Sundargarh, Angul, Muzaffarpur, Patna, Jharsuguda (OPGCL), Dharbhanga (DMTCL)

,Darlipalli (NTPC), Nabhinagar (NPGCL), Rourkela (PGCIL), Bassi,Kala Amb (PKATL), Gurgaon, Banala, Kurukshetra, Ranchi, Rajarhat, Sundergarh, Motihari, Kameng (NEEPCO), Tuirial HEP, NTPC Bongaigoan, Assam, Kudigi (NTPC), Tumkur, Yelahanka, Tuticorn, Dharwad, Karikudi.

(iii) **220kV Substations:** Bastar, Daman, Satana, Rewa, Itarsi, Ambajogai, Balipara.

(iv) **132kV Substations:** Namasai, Nabhinagar (NTPC), Indore (RRCAT), Gadarwara (NTPC), Haldia-Aiswarya (IOCL), Till-79, Doyang HEP, Zemabawk.

(v) **HVDC Substations:** Champa, Bhadravati, Agra, Kurukshetra, Alipurduar, Vishwanath Chairiyali.

The details of electrical apparatus inspected at different voltage levels during the year 2017-18 is as given below: -

| Apparatus     | Transformers /ICT (MVA) | Reactors (MVAR) | Capacitors(MVAR) | Bays (no.) | Bus (no.) | Statcom (no.) |
|---------------|-------------------------|-----------------|------------------|------------|-----------|---------------|
| Voltage Level |                         |                 |                  |            |           |               |
| 765 kV        | 21698                   | 11710           | Nil              | 173        | 8         | Nil           |
| 400 kV        | 12389                   | 5201            | 1068.54          | 304        | 54        | 5             |
| 220 kV        | 1210                    | Nil             | Nil              | 72         | 31        | Nil           |
| 132 kV        | 302.5                   | 26.8            | Nil              | 33         | 4         | Nil           |
| 33 kV         | 1270.55                 | Nil             | Nil              | 8          | Nil       | Nil           |
| HVDC 800 kV   | 5825.6                  | Nil             | Nil              | Nil        | Nil       | Nil           |

Above data are based on the cumulative inspections carried out by all RIOs.

### B) Generating Units :

Dhobnipali (RKM Power), Singrauli (Essar Power), Raigarh (NTPC), Gadarwara (NTPC), Raigarh (SKS), Champa (KSK), Meja Thermal

Power Project, Kameng HEP, Pare HEP, Tuirial HEP, Kudigi (NTPC).

The region wise summary of generating units inspected during the year 2017-18 is as given below: -

| RIOs               | NR  | SR     | WR   | ER  | NER |
|--------------------|-----|--------|------|-----|-----|
| No. of Inspections | 1   | 5      | 7    | Nil | 4   |
| Gen. Capacity (MW) | 660 | 869.85 | 4000 | Nil | 773 |

### C) Transmission Lines:

(i) **765 kV Lines :** Jabalpur-Orai, Aurangabad-Padghe, Raipur (Pool)-Rajnandgaon, Sipat-Bilaspur, New Parli-Solapur, Sasan UMPP-Vindhyaachal, Hyderabad-Nizamabad, Jharsuguda-Dharamjaygarh, Seoni-Bina (LILO), Ajmer-Chittorgarh, Orai-Aligarh, Kanpur-Jhatikara (LILO), Agra – Meerut (LILO), Satna-Gwalior (LILO).

(ii) **400 kV Lines:** Kurukshetra - Jind, Dehradun-Abdullapur, Allahabad-Kanpur Part-I, RAPP 7&8 - Kota (Part-A), Bhadrekh (UPPTCL)-Orai (PGCIL), Chittorgarh (RRVNL)-Chittorgarh (PGCIL), Ajmer (RRVNL)-Ajmer (PGCIL), Nizamabad – Shankarpalli, Maheswaram - Nizamabad Mahabubnagar, Parli - Parli, Wardha - Parli, Gwalior - Morena, Kala-Kudus, Padghe-Padghe, Solapur NTPC-Solapur PG, Aurangabad - Boisar, Mouda - Betul, Lara-Champa, Gaya-Nabhinagar, Punasantchu-Alipurduar, Daltonganj - Pusauli, Raghunathpur-Ranchi, Kameng Balipara, Karcham Wangtoo – Abdullapur (LILO), Sikar-Neemrana (LILO), Uri - Wagoora line (LILO), Khandwa - Rajgarh (LILO), Dehagam-Pirana (LILO), Rourkela-Raigarh (LILO), DMTCL Barh-Gorakhpur (LILO).



- (iii) **220 kV Lines:** Magarawada - Ringanwada.
- (iv) **132 KV Lines:** Tilla -79 - RC Nagar Line, Nirjuli-Ranganadi, Hailakandi, North Karanpur-Tandwa, Earth Electrode Line at Alipurduar Substation.
- (v) **International 132 KV Transmission Lines:** Katiya (Bihar) - Kusaha (Nepal), Raxaul (Bihar) - Parwanipur (Nepal).

Summary of transmission lines inspected at different voltage levels during the year 2017-18 is given below: -

(Data in Circuit Km)

| RIOs<br>kV  | NR   | SR     | WR   | ER      | NER   |
|-------------|------|--------|------|---------|-------|
| 765 kV      | 1200 | 451    | 1801 | 78.384  | Nil   |
| 400 kV      | 1096 | 552.86 | 1865 | 990.724 | 57    |
| 220 kV      | Nil  | Nil    | 12.2 | Nil     | Nil   |
| 132 kV      | Nil  | Nil    | Nil  | 81.661  | 69.0  |
| 110 kV      | Nil  | 5.32   | Nil  | Nil     | Nil   |
| 66 kV       | Nil  | Nil    | Nil  | Nil     | Nil   |
| 33 kV       | 6.3  | 30.15  | Nil  | 7.90    | 101.6 |
| 11 kV       | 4.7  | Nil    | 2.6  | 3.6     | Nil   |
| 800 kV HVDC | Nil  | Nil    | Nil  | Nil     | Nil   |

**D) Electrical installations of the following were inspected during the year 2017-18:** NTPC, PGCIL, DVC, NHPC, SJVNL, BBMB, NEEPCO, THDC, SAIL, GAIL, IOCL, HPCL, BPCL, ONGC, AAI, NALCO, BALCO, AIR, CPWD, Port Trusts Airports, IITs, BARC, NBCC, AIIMS BEL, BHEL, DRDO, Private sectors in SEZ, UTs, ISTS, ISGS, etc.

### 3.22.2 Inspections done for Renewables :

Solar power plants at following locations: GAIL Petrochemical Complex, Pata, Aligarh Muslim University Aligarh, IIT-BHU Varanasi, BHEL Haridwar, BHEL Jhansi, NLC

India ltd. Tamil Nadu, Jaipur International Airport, BEL Bolangir (Odisha), NSCBI Airport Kolkata, ONGC, IOCL, RCFL, RAF, IISE & R, HUL, CPWD, DHNPDCL (Velugam), Shipping corporation, JNPT, IIT Gandhinagar, etc. Small Hydro Plant at NTPC Singrauli.

Summary of Generation capacity of Renewable Energy Sources inspected during the year 2017-18 is given below: -

| RIOs               | NR   | SR      | WR | ER | NER |
|--------------------|------|---------|----|----|-----|
| Gen. Capacity (MW) | 30.1 | 611.562 | 35 | 25 | Nil |

### 3.22.3 Cinemas/Theatres installations inspected :-

Summary of Cinemas/Theatres installations inspected during the year 2017-18 is given below :

| RIOs               | NR  | SR | WR | ER  | NER |
|--------------------|-----|----|----|-----|-----|
| No. Of Inspections | Nil | 18 | 7  | Nil | Nil |

### 3.22.4 Periodical Inspections (under Regulation 30 of Central Electricity Authority (Measures Relating to Safety and Electric Supply) Regulations, 2010 :-

Major installations inspected :

- a) **Generating plants** - OTPC Palatana, Tripura; Doyang HEP, Nagaland, BSPCL Bokaro, NTPC Talcher, DVC – RTPS & BTPS, NALCO CPP, IOCL Barauni CPP, NSPCL CPP Durgapur, NTPC Barh, Adani Mundra, Seoni (JPL), Chattisgarh (GMR), Sasan, Chattisgarh (RKM), Korba (TRN), Bharuch (TPL), Chattisgarh (SKS), NHPC Parbati-III Hydro Power Station, NTPC Koldam Hydro Power station, etc.

- b) **Substations** – Monarchak (NEEPCO); Doyang HEP Nagaland, Dikrong (NEEPCO), Jamshedpur, Raghunathpur (DVC), Barh (NTPC), Champa, Raigarh, Jabalpur, Kotra, Tamnar, Indore, Korba, Bina, Seoni, Mundra, Tamnar, Damoh, Janjgir Champa, Kutch, Shajapur, Bharuch, PGCIL Panchkula, HVDC Mahendragarh Terminal of Adani Pvt. Ltd.
- c) **Electrical installations** of BPCL, NEEPCO, NTPC, OIL, ONGC, PGCIL, SAIL, IOCL, HPCL, AAI, CPCL, NALCO, AIR, CPWD, Kolkata Port Trust, GAIL, NFL, DVC, NHPC, SJVNL, BBMB, THDC, ISTS, ISGS, etc.

### 3.23 Inspections done in UTs :-

Details of inspections done in UTs during the year 2017-18 is given below: -

AN: Andman & Nicobar, DNH: Dadar & Nagar Haveli, DD: Daman & DIU, PDY: Puducherry.

| UTs                | AN | DNH | DD | PDY |
|--------------------|----|-----|----|-----|
| No. of Inspections | 5  | 172 | 72 | 101 |

### 3.24 Self-certifications approval issued by RIOs:-

No. of self-certifications issued during the year 2017-18 is given below: -

| RIOs | NR | SR  | WR | ER | NER |
|------|----|-----|----|----|-----|
| No.  | 1  | 144 | 5  | 16 | Nil |

### 3.25 Construction Monitoring of Transmission Projects

The monitoring of construction of transmission lines and sub-station (220 kV & above) covered under various transmission projects under central/state/private sector is being carried out with a view to achieve timely completion of transmission projects to ensure evacuation of power from new Generation Projects as well as strengthening of existing transmission network required for

transmission of power to load centers.

As on 31<sup>st</sup> March 2018, 390970 Ckm & 826958 MVA of transmission lines & transformation capacity (220 KV & above) respectively exist in the country.

For the year 2017-18, RFD program for commissioning of 23,086 Ckm of transmission lines comprising of 4927 Ckm of 765 kV, 11424 Ckm of 400 kV and 6735 Ckm of 220 kV transmission lines was envisaged. 100.14% of this target was achieved by commissioning of 23119 CKm of transmission lines, whose break-up is 3819 CKm of 765 kV, 13813 CKm of 400 kV and 5487 CKm of 220 kV. Details of transmission lines commissioned /completed during 2017-18 are given in **Annexure-3I**.

In respect of transformation capacity for the year 2017-18, RFD program of 53978 MVA of transformation capacity comprising of 3000 MW at  $\pm 800$  kV HVDC, 19000 MVA at 765 kV, 20805 MVA at 400 kV and 11173 MVA at 220 kV was envisaged. 159.68% of this target was achieved by adding 86193 MVA transformation capacity comprising of 3000 MW at  $\pm 800$  kV HVDC, 23000 MVA at 765 kV, 41815 MVA at 400 kV and 18378 MVA at 220 kV. Details of Substations commissioned / completed during 2017-18 are given in **Annexure-3J**.

Voltage-wise /Sector-wise actual achievement vis-à-vis RFD program for the year 2017-18 in respect of transmission lines and sub Stations are given in **Charts I to VI and VII to XII** respectively.

For the year 2018-19, RFD Program of 22647 Ckm for transmission lines and 62600 MVA of transformation capacity (Substations) has been finalized. The detail of RFD program at 765 kV, 400 kV and 220 kV is 6285 Ckm, 9431 Ckm & 6931 Ckm respectively. The RFD program for transformation capacity additions at  $\pm 800$  KV HVDC, 765 KV, 400 KV and 220 KV levels is 3,000 MW, 22200 MVA, 21900 MVA and 15500 MVA respectively for FY 2018-19. The progress of all transmission elements is being monitored expeditiously for commissioning as per their schedule.

Chart-I




Chart-II




Chart-III




Chart-IV




Chart-V




Chart-VI




Chart-VII




Chart-VIII




Chart-IX




Chart-X




Chart-XI





Chart-XII





## CHAPTER-4

# GRID OPERATION AND MANAGEMENT

### 4.1 Organizational Structure in Grid Operation and Management

Central Government has established Regional Power Committee (RPC) in each region in accordance with provisions of Electricity Act, 2003 to facilitate integrated operation of the power system in that region. The real time operation of the power system is looked after by the Regional Load Despatch Centres (RLDCs) set up in the five Regions and at the national level by National Load Despatch Centre (NLDC). The Regional Power Committee is a conglomerate of all the players partaking in grid operation, i.e. Regional Load Despatch Centre, generating companies, transmission utilities, distribution utilities, power traders, etc. Its Secretariat is manned by the officers of Central Electricity Authority (CEA).

Regional Power Committee (RPC) operates through a number of Sub-Committees, viz. Operation Sub Committee, Commercial Sub Committee, Protection Sub Committee, System Studies Sub Committee and Technical Coordination Sub Committee. The Operation Sub Committee meets every month to review the grid operation in the previous month and plan grid operation for the next month. The Commercial Sub Committee discusses commercial issues viz. energy accounting related matters, matters pertaining to SEMs, settlement of dues, etc. The Protection Sub Committee discusses and analyses various trippings which took place since its last meeting and recommends/monitors the corrective actions to avoid similar trippings. It also finalises protection schemes including protection coordination. The System Studies Sub Committee meets periodically for the purpose of System Studies. The Technical Coordination Sub Committee (TCC) meets before the Regional Power Committee for putting up matters for decision in the Regional

Power Committee. The RPCs play an important role in planning grid operation, since they are responsible for protection coordination, outage planning of generating units and transmission system, planning reactive compensation etc. Member (Grid Operation & Distribution), CEA is also a Member of the Regional Power Committees and guides the Committees to arrive at amicable solutions in case of disputes between Members of the Committees through unbiased decisions. To evolve a common approach to issues related to reliability and security of the grid, National Power Committee (NPC) has been established vide Ministry of Power (MoP) order dated 25th March, 2013.

CEA monitors the power supply position in the country, prepares the all-India monthly power supply position, coordinates all matters of grid operation and management between the five Regions, coordinates enquiry of grid disturbances, recommends to the Ministry of Power the quantum of allocation from Central Generating Stations and also coordinates the implementation of the allocation through the Regional Power Committees. The anticipated Power Supply Position for the next year known as Load Generation Balance Report is also prepared every year.

### 4.2 POWER SUPPLY POSITION

The Central Electricity Authority brings out the All India Power Supply Position on a monthly basis, both in terms of energy and peak giving the requirement, energy supplied and energy not supplied in Million Units (MUs) as well as in percentage and the peak demand, peak met and demand not met both in terms of Mega Watt (MW) and percentage. The total energy requirement in the country during 2017-18 was 12,13,326 Million Units (MUs) as against 11,42,928 MUs during the previous year, registering an increase of 6.2%. The total energy supplied in the country during


2017-18 was 12,04,697 MUs as against 11,35,332 MUs during the previous year, registering an increase of 6.1%. The energy not supplied during the year 2017-18 was 8,629 MUs (0.7 %) against 7,596 MUs ( 0.7 % ) during the previous year. The peak demand during the year 2017-18 was 1,64,066 Mega Watt (MW) as against 1,59,542 MW during the previous year, registering an increase of 2.8%. The peak demand met during 2017-18 was

1,60,752 MW as against 1,56,934 MW during the previous year, registering an increase of 2.4%. The demand not met during the year 2017-18, increased from 2,608 MW (1.6%) to 3,314 MW (2.0%) as compared to previous year.

The power supply position since beginning of 9<sup>th</sup> Plan is as under:


#### Energy:

| Year    | Energy Requirement (MU) | Energy Supplied (MU) | Energy not Supplied |      |
|---------|-------------------------|----------------------|---------------------|------|
|         |                         |                      | (MU)                | (%)  |
| 1997-98 | 424,505                 | 390,330              | 34,175              | 8.1  |
| 1998-99 | 446,584                 | 420,235              | 26,349              | 5.9  |
| 1999-00 | 480,430                 | 450,594              | 29,836              | 6.2  |
| 2000-01 | 507,216                 | 467,400              | 39,816              | 7.8  |
| 2001-02 | 522,537                 | 483,350              | 39,187              | 7.5  |
| 2002-03 | 545,983                 | 497,890              | 48,093              | 8.8  |
| 2003-04 | 559,264                 | 519,398              | 39,866              | 7.1  |
| 2004-05 | 591,373                 | 548,115              | 43,258              | 7.3  |
| 2005-06 | 631,554                 | 578,819              | 52,735              | 8.4  |
| 2006-07 | 690,587                 | 624,495              | 66,092              | 9.6  |
| 2007-08 | 739,343                 | 666,007              | 73,336              | 9.9  |
| 2008-09 | 777,039                 | 691,038              | 86,001              | 11.1 |
| 2009-10 | 830,594                 | 746,644              | 83,950              | 10.1 |
| 2010-11 | 861,591                 | 788,355              | 73,236              | 8.5  |
| 2011-12 | 937,199                 | 857,886              | 79,313              | 8.5  |
| 2012-13 | 995,557                 | 908,652              | 86,905              | 8.7  |
| 2013-14 | 1,002,257               | 959,829              | 42,428              | 4.2  |
| 2014-15 | 1,068,923               | 1,030,785            | 38,138              | 3.6  |
| 2015-16 | 1,114,408               | 1,090,850            | 23,558              | 2.1  |
| 2016-17 | 1,142,928               | 1,135,332            | 7,596               | 0.7  |
| 2017-18 | 1,213,326               | 1,204,697            | 8,629               | 0.7  |



**Peak:**

| Year    | Peak Demand (MW) | Peak Met (MW) | Demand not Met |      |
|---------|------------------|---------------|----------------|------|
|         |                  |               | (MW)           | (%)  |
| 1997-98 | 65,435           | 58,042        | 7,393          | 11.3 |
| 1998-99 | 67,905           | 58,445        | 9,460          | 13.9 |
| 1999-00 | 72,669           | 63,691        | 8,978          | 12.4 |
| 2000-01 | 78,037           | 67,880        | 10,157         | 13.0 |
| 2001-02 | 78,441           | 69,189        | 9,252          | 11.8 |
| 2002-03 | 81,492           | 71,547        | 9,945          | 12.2 |
| 2003-04 | 84,574           | 75,066        | 9,508          | 11.2 |
| 2004-05 | 87,906           | 77,652        | 10,254         | 11.7 |
| 2005-06 | 93,255           | 81,792        | 11,463         | 12.3 |
| 2006-07 | 100,715          | 86,818        | 13,897         | 13.8 |
| 2007-08 | 108,866          | 90,793        | 18,073         | 16.6 |
| 2008-09 | 109,809          | 96,785        | 13,024         | 11.9 |
| 2009-10 | 119,166          | 104,009       | 15,157         | 12.7 |
| 2010-11 | 122,287          | 110,256       | 12,031         | 9.8  |
| 2011-12 | 130,006          | 116,191       | 13,815         | 10.6 |
| 2012-13 | 135,453          | 123,294       | 12,159         | 9.0  |
| 2013-14 | 135,918          | 129,815       | 6,103          | 4.5  |
| 2014-15 | 148,166          | 141,160       | 7,006          | 4.7  |
| 2015-16 | 153,366          | 148,463       | 4,903          | 3.2  |
| 2016-17 | 159,542          | 156,934       | 2,608          | 1.6  |
| 2017-18 | 164,066          | 160,752       | 3,314          | 2.0  |



The Power Supply Position in terms of energy and Peak during 2017-18 is enclosed at **Annexure-4A**.

Details of the state-wise allocation in the country as on 31.03.2018 is enclosed at **Annexure-4B**.

### 4.3 MERIT (Merit Order Despatch of Electricity for Rejuvenation of Income and Transparency) web portal

A Web Portal 'MERIT' i.e. Merit Order Despatch of Electricity for Rejuvenation of Income and Transparency was launched on 23rd June, 2017. Subsequently, MERIT Mobile App was also launched on 5<sup>th</sup> July 2017. This Mobile App/Web Portal displays the details of power purchased by the states from various power Stations/Sources and the rates thereof on day to day basis transparently and provides opportunity to states for improving their power purchase portfolio. (<http://www.meritindia.in>)

### 4.4 Operation of Regional Grids

#### 4.4.1 Northern Regional Grid

The Northern Region has an installed capacity of 92,967.45 MW as on 31-03-2018 consisting of 58720.46 MW thermal, 19753.77 MW hydro, 1620.00 MW nuclear and

12873.22 MW from renewable energy sources. The Northern Grid faced an energy shortage of 1.7% and a peaking shortage of 3.8% during the year 2017-18 as compared to energy and peak shortages of 1.6% and 1.4% respectively during previous year.

Northern Region is connected to Eastern Region through ± 500kV HVDC back-to-back station at Sasaram, 765 kV Sasaram-Fatehpur S/C line, (New) 765 kV Gaya-Varanasi S/C line, 765 kV Gaya-Balia S/C line, 765 kV Gaya-Varanasi S/C (LILO of 765 kV Fatehpur-Gaya at Varanasi), 400 kV Allahabad-Sasaram D/C line, 400 kV Biharshariff - Balia D/C line, 4 No. of 400 kV Patna - Balia (2 x D/C line), 400 kV Muzaffarpur- Gorakhpur (PG) D/C line (Series compensated), 400 kV Motihari-Gorakhpur D/C line, 400 kV Sasaram – Varanasi D/C line, 400 kV Biharshariff-Varanasi D/C line. ± 800 kV Agra-Bishwanath Chariayali (multipole) HVDC link is also available between Northern region and North Eastern Region with intermediate poles at Alipurduar in Eastern Region facilitating transfer of power between NR, ER and NER. Northern Region is also connected to Western region through back-to-back HVDC Vindhyachal, Pole-1 of ± 800 kV Champa – Kurukshetra HVDC link, ± 500 kV Mundra –

Mohindergarh Bipole HVDC link, 765 kV Agra-Gwalior line 1 & 2, 765 kV Phagi - Gwalior line 1 & 2, 400 kV Bhinmal – Zerda D/C line, 400 kV Kankroli – Zerda D/C line, 400 kV RAPP – Shujalpur D/C line, 220 kV Auraiya – Malanpur D/C line, 220 kV Auraiya – Mehgaon D/C line, 220 kV Modak – Bhanpura D/C line, 220 kV Sakatpura – Badod D/C line.

The commissioning of Pole-III & Pole-IV of  $\pm 800$  kV Agra-Alipurduar has further enhanced transmission capability between NR and ER. The commissioning of Pole-2 of  $\pm 800$  kV Champa – Kurukshetra HVDC link has further enhanced transmission capability between NR and WR.

#### 4.4.2 Western Regional Grid

The Western Region has an installed capacity of 111148.99 MW as on 31-03-2018 consisting of 81415.11 MW thermal, 7447.50 MW hydro, 1840.00 MW nuclear and 20446.38 MW from renewable energy sources. The Western Grid faced an energy shortage of 0.1% and a peaking shortage of 0.8% during the year 2017-18 as compared to Nil energy shortage and peak shortage of 0.4% during previous year.

Total capacity of 4060 MW (including renewables 2141.95 MW ) was added in Western Regional Grid in this year including central sector, state sector & private sector. Total Renewable installed capacity is 20446.38 MW in WR as on 31.03.2018. Capacity growth of Renewable energy is 11.70 % compared to the year 2016-17 (18304.43 MW). On the Renewable front, WR has registered installed capacity addition of 905.5 MW (Wind Energy) and 1236.5 MW (Solar Energy) in the year 2017-18. The annual growth of 7.23 % and 49.0 % was recorded for wind and solar respectively.

Total Transmission lines of 6261 ckt km including 765 kV & 400 kV were added in 2017-18. Transformation capacity of 12345 MVA was added in the year 2017-18. Reactive compensation in the form of line reactors and

bus reactors of 3588 MVAR and 1550 MVAR respectively was added during the year. STATCOM at Satana and Solapur of 675 MVAR was also added during this year.

Western region is connected to Eastern region through 765 kV N. Ranchi-Dharmjaygarh D/C line, 765 kV Jharshuguda-Dharmjaygarh D/C line, 400 kV Ranchi -Sipat D/C line, 400 kV Rourkela -Raigarh D/C line, 400 kV Jharshuguda - Raigarh D/C line, 220 kV Budhipadar – Korba D/C line and 220 kV Budhipadar- Raigarh D/C line : to Northern region through back-to-back HVDC Vindhyachal, Pole-1 of  $\pm 800$  kV Champa – Kurukshetra HVDC link,  $\pm 500$  kV Mundra – Mohindergarh Bipole HVDC link, 765 kV Agra-Gwalior line 1 & 2, 765 kV Phagi - Gwalior line 1 & 2, 400 kV Bhinmal – Zerda D/C line, 400 kV Kankroli – Zerda D/C line, 400 kV RAPP – Shujalpur D/C line, 220 kV Auraiya – Malanpur D/C line, 220 kV Auraiya – Mehgaon D/C line, 220 kV Modak – Bhanpura D/C line, 220 kV Sakatpura – Badod D/C line and to Southern region through HVDC back to back link at Chandrapur in addition to 2xS/C 765kV Sholapur- Raichur, 220kV Kolhapur-Chikkodi D/C line, 765 kV Kudgi – Kolhapur 1&2 (charged at 400 kV level) and 765 kV Wardha – Nizamabad.

Besides, WR-NR inter regional connectivity strengthened with charging of 800 kV HVDC Champa-Kurukshetra pole-II in Sept, 2017, 765kV Jabalpur-Orai D/C and LILO of 765kV Satna-Gwalior-1 at Orai in Mar, 2018. Owing to this, WR-NR ATC has increased to 9800MW from quantum of 8050 MW.

#### 4.4.3 Southern Regional Grid

The Southern Region has an installed capacity of 102514.57 MW as on 31-03-2018 consisting of 53017.26 MW thermal (Coal 45782.02 + Gas 6473.66 + Diesel 761.58), 11808.03 MW hydro, 3320 MW nuclear and 34369.28 MW from renewable energy sources. The Southern Grid faced an energy shortage of 0.2% and a peaking shortage of 0.4% during the year 2017-18 as compared to

an energy shortage of 0.2% and no peaking shortage during previous year 2016-17.

The Talcher Stage-II Super Thermal Power Station (4X500 MW) of NTPC in Eastern Region is a dedicated power station for the Southern Region except for 200 MW power allocation to the home state of Orissa in ER. The Southern Region is connected with the Eastern Region through upgraded Talcher - Kolar HVDC bi-pole link, HVDC back-to-back link at Gajuwaka, Balimela-Upper Sileru 220kV S/C and 765 kV Angul - Srikakulam. Southern Region is also connected with Western Region through HVDC back to back link at Chandrapur in addition to 2xS/C 765kV Sholapur- Raichur, 220kV Kolhapur-Chikkodi D/C line, 765 kV Kudgi – Kolhapur 1&2 (charged at 400 kV level) and 765 kV Wardha – Nizamabad.

#### 4.4.4 Eastern Regional Grid

The Eastern Region has an installed capacity of 34402.16 MW as on 31-03- 2018 consisting of 27421.64 MW thermal, 4942.12 MW hydro and 1038.40 MW from renewable energy sources. The Eastern Region faced energy shortage of 0.8% and peaking shortage of 1.5% during the year 2017-18 as compared to energy and peaking shortages of 0.7% and 0.6% respectively during previous year.

Eastern Region is the only region connected to all other Regions of the country as well as neighbouring countries Bangladesh, Bhutan and Nepal. It is connected to Northern Region through 765 kV Gaya-Varanasi D/C line, 765 kV Gaya-Balia S/C line, 765 kV Sasaram-Fatehpur S/C line, 400 kV Muzaffarpur-Gorakhpur D/C line with TCSC, 400 kV Motihari-Gorakhpur D/C line, 400 kV Patna-Balia Q/C line, 400 kV Biharshariff-Balia D/C line, 400 kV Biharshariff -Varanasi D/C line, 400 kV Sasaram-Allahabad/Varanasi D/C line bypassing HVDC back to back link at Sasaram and 220 kV Sasaram-Sahupuri S/C line; to Western Region through 765 kV N. Ranchi-Dharmjaygarh D/C line, 765 kV Jharshuguda-Dharmjaygarh D/C line, 400 kV Ranchi -Sipat

D/C line, 400 kV Rourkela -Raigarh D/C line, 400 kV Jharshuguda - Raigarh D/C line, 220 kV Budhipadar – Korba D/C line and 220 kV Budhipadar- Raigarh D/C line; to Southern Region through 765 kV Angul-Srikakulam D/C line, Talcher-Kolar HVDC bipole link, HVDC back to back link at Gazuwaka and 220 kV Balimera-Upper Sileru S/C line; and to North-Eastern Region through 400 kV Binnaguri-Bongaigaon D/C line, 400 kV Alipurduar-Bongaigaon D/C line and 220 kV Alipurduar –Salakati D/C lines. It has international connectivity with Bhutan through 400 kV Binaguri-Tala T/C, 400 kV Binaguri-Malbase S/C line, 220 kV Birpara–Chukha D/C line and 220 kV Birpara– Malbase D/C line; with Bangladesh through 400 kV Beharampur– Bheramara D/C line; and with Nepal through 400 kV Muzaffarpur–Dhalkebar S/C line (presently charged at 132 kV level), 132 kV Valmikinagar-Surajpura line, 132 kV Kataiya-Kusaha D/C line and 132 kV Raxaul –Parwanipur line.

#### 4.4.5 North-Eastern Regional Grid

The North-Eastern Region has an installed capacity of 3916.63 MW as on 31-03-2018 consisting of 2292.07 MW thermal, 1342.00 MW hydro and 282.56 MW from renewable energy sources. The North Eastern Grid faced an energy shortage of 2.8% and a peaking shortage of 4.1% during the year 2017-18 as compared to energy and peaking shortage of 2.8% and 0.5% respectively during the previous year, mainly on account of transmission and distribution constraints.

North Eastern Regional Grid is connected directly to the Eastern Regional Grid and Northern Regional Grid. The power transfer from North-Eastern Region to Eastern Region is taking place over following 6 lines: 400 kV Bongaigaon - New Siliguri I & II, 400 kV Bongaigaon - Alipurduar I & II and 220 kV Salakati - Alipurduar I & II and to the Northern Region Grid through +/- 800 kV Biswanath Chariali -Agra Pole-I & Pole-II.

#### 4.5 Role of NPC Division is as follows:

- a) Secretariat to National Power Committee.
- b) All works related to Power System Development Fund (PSDF) including assistance in examination of DPRs for funding from PSDF, preparation of their appraisal report, monitoring of funds, monitoring and supervision of various schemes under implementation from PSDF, etc.
- c) Work related to National Reliability Council for Electricity (NRCE).
- d) Providing assistance to the Grid Study Committee.

##### 4.5.1 National Power Committee (NPC)

Keeping in view the ever growing complexity of Power System, NPC was established by Ministry of Power vide order dated 25<sup>th</sup> March, 2013., to evolve a common approach on issues related to reliability and security of the grid, at National level. Chairperson, CEA is the Chairperson of NPC. Member (GO&D), CEA, Member Secretaries and Chairpersons of RPCs, the Chairpersons of Technical Co-ordination Sub Committees (TCC) in five regions are members of NPC. Chief Engineer (NPC), CEA is Member Secretary of NPC. Since its formation, NPC has commenced several initiatives on improving defense mechanism (like Under Frequency Relay and rate of change of frequency df/dt relay based load shedding scheme and System Protection Scheme) to enhance grid security. The methodology of settlement of accounts for bilateral short term and collective transactions, for the period of Grid Disturbance finalized by NPC was submitted to CERC.

Seventh meeting of the NPC was held during 2017-18. Important decisions like reviewing of Under Frequency Relay (UFR) based load shedding scheme for the whole country were taken by NPC. The methodology / procedure for computing actual drawal / injection of entities in case of non-availability of Main/Check/Standby Meter Data were also

finalized. NPC also impressed upon ensuring the healthiness of protection system of the entire power system of the country.

NPC has been entrusted to prepare Guidelines on availability of communication system in terms of Regulation 7.3(i) of CERC(Communication System for Inter-State Transmission of Electricity) Regulations, 2017. Accordingly, a Working Group has been constituted under Member Secretary, NPC with members from all RPCs, CEA, POSOCO, CTU and NTPC. The Guidelines are under progress and two (02) meetings of the working group have been held during 2017-18.

##### 4.6 Power System Development Fund (PSDF)

- i. Ministry of Power, vide letter No. 29/9/2010-R&R (Vol-II) dated 10<sup>th</sup> January, 2014 circulated a scheme regarding operationalization of the Power System Development Fund (PSDF) and utilization of funds deposited therein. As per this scheme, NLDC has been designated as the Nodal Agency for implementation of this scheme and PSDF has been declared Public money. Therefore, money lying in the PSDF account is being regularly transferred to Public Account. The total fund transferred from regulatory Pool Accounts to PSDF up to 31.03.2018 is Rs.13780.80 Crores.
- ii. A three tier structure has been created under the scheme for operationalization of PSDF as mentioned below:
  - a) Appraisal Committee headed by Chairperson, CEA has been constituted for scrutiny (techno-economic appraisal) and prioritization of the various project proposals for funding from PSDF. The Appraisal Committee is assisted by a Techno-Economic Sub-Group headed by Chief Engineer (NPC), CEA for examining the scheme proposals.
  - b) After scrutinizing the proposals, the

- Appraisal Committee shall submit its Appraisal Report and recommendations in writing to the Central Commission and to the project entity who has submitted the proposal.
- c) A Monitoring Committee headed by Secretary, Ministry of Power will consider the projects for sanction based on Appraisal Report and regulatory approval of the Central Commission in accordance with the extant rules/instructions for sanction/approval and release of funds.
- iii. During 2017-18, eight meetings of techno-economic subgroup, four meetings of Appraisal Committee and three meetings of Monitoring Committee were held for scrutiny/sanction of grant from PSDF.
- iv. As on 31<sup>st</sup> March 2018, a total of 101 schemes have been sanctioned with a total grant amount of Rs. 10,260 Crores from PSDF. These include 44 numbers of schemes with grant amount of Rs. 2992 Crores sanctioned during the year 2017-18. Details are as given below:

| Project Entity | During 2017-18 |                | Previous Years |                | Total      |              |
|----------------|----------------|----------------|----------------|----------------|------------|--------------|
|                | Number         | Grant          | Number         | Grant          | Number     | Grant        |
| State/UT       | 40             | 2443.82        | 48             | 3170.18        | 88         | 5614.00      |
| RPCs           | 1              | 6.50           | 4              | 57.04          | 5          | 63.54        |
| BBMB           | 1              | 23.27          | -              | -              | 1          | 23.27        |
| DVC            | 1              | 140.50         | 1              | 25.96          | 2          | 166.46       |
| PGCIL          | 1              | 378.04         | 3              | 3781.52        | 4          | 4159.56      |
| PGCIL/RECTPCL  | -              | -              | 1              | 233.03         | 1          | 233.03       |
| <b>Total</b>   | <b>44</b>      | <b>2992.13</b> | <b>57</b>      | <b>7267.73</b> | <b>101</b> | <b>10260</b> |

Most of the utilities which have availed funding from PSDF are in various stages of implementation of their schemes. Execution of these projects would enhance the grid security and reliability.

#### 4.7 National Reliability Council for Electricity (NRCE)

Hon'ble CERC vide Order dated 11.12.2013 in Petition No.188/SM/2012 with IA No.11/2013 in the matter of calculation of Total Transfer capability (TTC), Available Transfer Capability (ATC) and Transmission Reliability Margin (TRM) directed CEA to constitute a National Reliability Council which shall approve computation of TTC of various Transmission corridors for the month, for the purpose of reliable operation of the Grid.

Accordingly, CEA vide letter No. CEA/NRC/RA-2014/427-452 dated 21.02.2014 had

constituted National Reliability Council for Electricity (NRCE).

Consequent upon restructuring of CEA, CEA vide letter No.3/NRCE/NPC/CEA/2016/245-270 dated 10.02.2016 reconstituted NRCE with the following members:

1. Member (GO&D), CEA - Chairperson of NRCE.
2. Chief Operating Officer (CTU) - Member,
3. Member Secretaries of all RPCs- Member,
4. Director of TANTRANSCO, WBSETCL, MSETCL, UPPCL & AEGCL - Member,
5. Prof. S.C.Srivastava, IIT, Kanpur- Member,
6. Prof. A.R. Abhyankar, IIT, Delhi - Member,
7. Chief Engineer (PSP&A-I, PSP&A-II CEA) - Member
8. Chief Engineer (NPC, CEA) - Member Secretary.

NRCE has constituted two subgroups, one for



carrying out examination of the System studies for the purpose of calculation of TTC, ATC and TRM and the other one for Preparation of reliability Standards for “Protection System” for Indian Power System.

The 4<sup>th</sup> meeting of sub-group for issues related to TTC/ATC/TRM was held during 2017-18. Issues related to validation of thermal limits of transmission elements, analysis of determination of transmission reliability margin (TRM), utilization of LTA granted for solar plants, TTC/ATC curtailment on account of bus shut downs etc. were discussed.

The 5<sup>th</sup> meeting of sub-Group for Preparation of reliability Standards for “Protection System for Indian Power System” was held during 2017-18 and the draft standards were finalized and has been circulated to RPCs for comments.

#### 4.8 Grid Study Committee

In pursuance of the recommendation of the Enquiry Committee constituted by Ministry of Power after the grid disturbance on 30-31 July, 2012, Ministry of Power vide its order dated 13<sup>th</sup> December, 2012 had formed a Task Force for power system analysis under contingencies. The Task Force had detailed deliberations on issues concerning safe and secure operation of the grid and submitted its report to the Ministry of Power in September, 2013, and accordingly two consultants were appointed for this purpose.

As per the recommendations of the above Task Force, one Consultant (Tractebel, Romania) was appointed to carry out the tasks as given below:

**Task I:** To study the status of implementation of recommendations of enquiry committee and

**Task II:** To study the protection audit report of 762 substations across the country carried out after grid failure of July 2012 and conduct on site Protection audit check of the works already carried out, for at least 10% (76 nos.) of 762 Substations.

The Consultant had completed the task and submitted the final report.

The other Consultant (Powertech Labs Inc., Canada) was appointed to study the following six tasks:

**Task-I:** Examination and Recommendation of Methodology for Optimum Calculation of Transfer Capability (TTC/ATC/TRM) in the Planning and the Operational Horizons.

**Task-II:** Calculation of Transfer Capability (TTC/ATC/TRM) for entire country.

**Task-III:** Guidelines for developing and implementing System Protection Scheme (SPS) and islanding schemes and review existing schemes.

**Task-IV:** Operational Planning and Long term planning for secure and efficient operation of the grid.

**Task-V:** Suitable suggestions in the Regulatory framework to ensure Secure and efficient grid operation.

**Task-VI:** To review the tuning of all Power Electronic Devices (including FACTS and HVDC) and suggest retuning of setting of these devices, as per report of Task Force.

A Grid Study Committee under the chairmanship of Member (GO&D), CEA with representatives from POSOCO, CTU, STUs has been formed to facilitate the Consultant's study/analysis.

Both the Consultants had completed the tasks and submitted the final report of all the tasks. 4<sup>th</sup> meeting of Grid Study Committee was held during 2017-18. The Committee has accepted the Task I & II Report of the Consultant M/s Tractebel and the Task I, II & III Reports of the Consultant M/s Powertech Labs Inc. The Consultancy project is targeted to be completed by June 2018.

\*\*\*\*\*


## CHAPTER – 5

### HYDRO POWER DEVELOPMENT

#### 5.1 Hydro Potential and its Development

The re-assessment studies of hydro-electric potential of the country, completed by Central Electricity Authority in 1987, have assessed the economically exploitable hydro power potential in terms of installed capacity as 148701 MW out of which 145320 MW of capacity is from schemes having capacity above 25 MW. The basin-wise details of

hydroelectric potential development in terms of Installed Capacity are indicated in the table below. As on 31.03.2018, the hydro-electric schemes in operation account for only 27.87% (40507.8 MW) and those under execution for 7.65% (11113.5 MW) of the total potential in terms of installed capacity. Thus, the bulk of the potential (64.48%) remains to be developed.



Further, 63 sites for development of Pumped Storage Schemes (PSS) with probable total installation of about 96524 MW have been identified in the country. At present, 9 Nos. Pumped Storage Projects (above 25 MW) having total installed capacity of 4785.60 MW are in operation and 3 Pumped Storage project (1205 MW) are under construction.

In addition, the study for the assessment of small hydro potential has been completed in June, 1996 by CEA. 1512 small hydro-

electric schemes with aggregate installed capacity of about 6782 MW on canal falls/ river-streams have been identified. Subsequently MNRE has been vested with the responsibility of developing Small Hydro Power (SHP) projects up to 25 MW station capacities.

#### 5.2 50,000 MW Hydro-Electric initiative

Under the 50,000 MW Initiative, preparation of Preliminary Feasibility Reports (PFRs) of

162 hydro-electric projects spreading in 16 states was taken up by CEA as nodal agency in the year 2003-04 with CPSUs/State agencies as Consultants. CEA's role included overall coordination, facilitating collection of data, and quality control by vetting conceptual planning, assessment of power benefits and selection of project parameters, evacuation of power and monitoring of works. National Hydro-Electric Power Corporation Ltd, WAPCOS, North-eastern Electric Power Corporation, Satluj Jal Vidyut Nigam Ltd and number of State Power Utilities were associated to complete these feasibility studies. The PFRs were completed in Sept., 2004 for all these projects with an installation of 47,930 MW. The details of these projects are given at **Annexure -5A**.

Out of 162 schemes (47930 MW), DPRs in respect of 39 schemes (20765 MW) have already been prepared. Out of which, 1 scheme (105 MW) has been commissioned while 7 schemes (1538 MW) are under construction in the country. In addition, DPR of 17 schemes (9248 MW) have been concurred by CEA while DPR for 6 schemes (633 MW) are under examination in CEA. A total of 8 schemes (3055 MW) are under Survey & Investigation for preparation of DPRs. The work of preparation of DPRs of remaining 115 schemes (24110 MW) is held up due to issues related to Environment & Forest Clearance, Law & Order and other issues.

### 5.3 Construction Monitoring of Hydro Projects

Hydro Project Monitoring Division is monitoring the progress of construction of on-going sanctioned hydro power projects (above 25 MW) in pursuance to Sections 73(f), 73(i) and 73(j) of the Electricity Act, 2003.

The progress of each project is monitored continuously through site visits, interaction with the developers & other stake holders. Chairperson, CEA/ Member (Hydro), CEA holds review meetings with the Power

Projects Monitoring Panel (PPMP) and monitoring divisions of CEA.

### 5.4 Hydro additions during 2017-18

Hydro capacity addition of 795 MW was achieved against the targets of 1305 MW for the year 2017-18. Project-wise details are given at **Annexure-5B**.

#### 5.4.1 Hydro capacity programme during 2018-19

Hydro Capacity Addition Monitorable Targets planned for the year 2018-19 is 910 MW (710 MW in Central Sector, 167 MW in State Sector, and 33 MW in Private Sector.). Project-wise details are given at **Annexure-5C**.

#### 5.4.2 Survey & Investigation of Hydro Projects

CEA has been monitoring the progress of Survey and Investigation of all the hydro schemes (above 25 MW capacity) by conducting periodical review meetings with developers. As per the Guidelines for formulation of DPRs for Hydro Electric Schemes, their acceptance and examination for concurrence, CEA provides assistance to various Central/State agencies in the matter of survey, investigation and preparation of DPRs of hydro projects costing more than Rs.1000 Crs.

In addition, the consultation meetings are held by CEA, CWC, GSI and CSMRS with project developer and guidance is provided by the appraising agencies for making a good quality and bankable DPR.

A total of 13 HEPs including 3 Pumped Storage Schemes with aggregate capacity of 6784 MW are presently under Survey & Investigation in the country. A total of 9 No. of DPR (3995 MW) have been prepared under the procedure so far including 4 nos. of DPRs (856 MW) prepared during 2017-18.

### 5.5 Project Planning & Optimization Studies

- Revised Power Potential studies of

Ujh MPP, J&K (62X3 MW+ 4X2.5 MW) with Design Energy of 238.66 MU was carried out considering environment flows as per approved TOR by MoEF & CC.

- Consultancy Services are being rendered for Preparation/ Updation of Detailed Project Report of Kuri-Gongri HEP (2640MW) in Bhutan and Sharavathy Pumped Storage Project (2000MW) in Karnataka and Tlawng HEP in Mizoram.

### 5.6 Studies & Other Activities Related to Hydro Power Planning

- Draft IFC Report on Climate Investment Opportunities in South Asia was examined for comments.
- Final report on Cumulative Impact Assessment and Carrying Capacity Study (CIA & CCS) of Chenab River Basin in Himachal Pradesh, Dibang & Kameng basin in Arunachal Pradesh was examined and commented upon.
- Synthesis Report on a Program of Studies on Low Carbon Development of the People's Republic of China and India was examined and commented upon.
- Draft Note for Cabinet for Constitution of Ganga Management Board as per UP Reorganization Act, 2000 was examined and commented upon.
- Project Proposal from Government of Nagaland for financial assistance from AIIB was examined and commented upon.
- The Draft final report by Expert Body (EB-II) in respect of hydro projects to study Cumulative Impact Assessment (CIA) and carrying capacity of river Ganga in general for development of HEPs in upper reaches of river Ganga and focusing upon likely impacts caused by HEP structures, has been prepared and submitted to MoEF in Sep'17.

- Examined proposal of POSOCO/ CERC for "Implementation of Hydro Generators as Fast Response Ancillary Services (FRAS)".
- Examined proposal regarding flexibility in generation and scheduling of Hydro & Thermal Power Stations.

#### • New Hydro Policy

A Committee to suggest policy intervention for hydro power development was constituted by MoP in Feb, 2016. Subsequently, based on the recommendations of the Committee a proposal for revival of hydro sector has been formulated which is under active consideration with Govt. for achieving faster capacity additions from under construction hydro projects. Ministry of Power had prepared an EFC memo and the views of all the stakeholders were also invited.

#### • Indus Water Treaty (IWT) Matters

- Adequacy of Pondage of Sawalkote, Kirthai-II, & Kwar H.E Projects in J&K and Dugar, Seli & Sachkhas H.E Project in Himachal Pradesh mentioned in their DPRs , as per IWT was examined with reference to IWT provisions.
- Meetings of the World Bank with senior representatives of India and Pakistan on issues related development of Kishenganga and Ratle HEPs in Washington, USA held on 30<sup>th</sup> Jul'2017 to 01<sup>st</sup> Aug' 2017 and 14<sup>th</sup> & 15<sup>th</sup> August, 2017 were attended.
- 114<sup>th</sup> Meeting of Permanent Indus Commission held on 29<sup>th</sup> & 30<sup>th</sup> March, 2018 at New Delhi was attended.

#### • Participation in Other Expert Committees & Assistance in Preparation of Reports

- Expert Committee for “Proper Management of Water Resources in North Eastern Region”.
  - Committee on ‘Flexibilisation of Thermal Power Plants’.
  - Committee constituted under the Chairmanship of Chairperson, CEA, to Improve Hydro Generation by one-third within the existing Capacity.
  - Sub-Committee under the Chairmanship of Chairperson, CEA to study the issue of shifting hydro power stations from Base Station to Peak Station.
  - Committee constituted under the Chairmanship of Chairman, BBMB to study the status and impact of silt upon the Hydro-electric Projects including impact on power generation, flooding etc. across the country.
  - Committee under the Chairmanship of CMD, NHPC on "NHPC to Become Grid Stabilizer using Hydro Power”
- **Issues of importance in Jammu & Kashmir**
    - a) Examined the Power Potential Studies on impact of change in MDDL due to reduction in Pondage carried out by M/s GVK for Ratle HEP.
    - b) Issue of pondage in respect of Kishenganga & Ratle HEP.

## 5.7 Co-operation with Neighboring Countries in Hydro Power

During the year, following works were attended in connection with development of water resources of the common rivers of India and neighboring

countries of Bhutan, Nepal, Myanmar, China and Bangladesh for mutual benefits:

- Rendering Consultancy Services for Preparation of Detailed Project Report(DPR) of Kuri-Gongri HEP (2640 MW) in Bhutan and a team of Officers from CEA & WAPCOS visited site of the project for discussion on layout & other issues with RGOB officials and WAPCOS site team engaged in Survey and Investigation work, for various project component locations such as Dam, Power House, Pot head yard etc.
- DPR of Kuri-I (Dorjiling) (1125 MW) in Bhutan was examined & comments were sent to Bangladesh side in this regard.
- Matters relating to revision of tariff for existing Chukha HEP(336 MW) and Tariff negotiation of upcoming Mangdechhu HEP (720 MW) in Bhutan.
- Rendering review consultancy for Preparation/Updation of DPR of Pancheshwar Multipurpose Project (PMP) including Re-regulating dam at Rupaligad (4800 MW + 240 MW) in Nepal. DPR Chapter on “Benefit Assessment and Project Optimization” of Pancheshwar Multipurpose Project prepared by WAPCOS was examined and observations furnished to MoP/ MoWR, RD & GR/CWC/ WAPCOS.
- 11<sup>th</sup> Meeting of Expert Level Mechanism (ELM) between India and China on 26<sup>th</sup> - 29<sup>th</sup> Mar'2018 at Hongzhou, China to discuss issues relating to Trans-Border Rivers was attended. The MoU and Implementation Plan on provision of hydrological information of Yaluzangbu/ Brahmaputra River was agreed upon in the meeting.

### 5.7.1 International Cooperation

The matters relating to co-operation on hydropower development with the countries

like Canada, Norway, Ethiopia, Croatia and Hungary were attended.

### 5.8 Hydro Power Plants Performance & Operation Monitoring

- The report “Review of Performance of Hydro Power Stations” for the year 2016-17 has been published. Performance of 695 units in 200 Hydro Stations with aggregate Installed Capacity of 44478.42 MW (above 25 MW) was analyzed in respect of their outages & generation in this report.
- Mid-term review of generation performance of hydroelectric stations of the country for the year 2017-18 was carried out in Dec' 2017 after withdrawal of South-West monsoon.

Based on interaction with Power Utilities, the generation targets were reviewed for the remaining part of the year 2017-18.

- Month-wise /station-wise hydro generation targets in respect of HE Stations (above 25 MW) totaling to 130 BU for year 2018-19 were finalized in consultation with various utilities.

### 5.9 Hydel Generation Performance during year 2017-18

The region-wise summary of Hydel Generation performance in the country is as follows:

| Region           | Generation (BU) |               | Deviation (+/-) |
|------------------|-----------------|---------------|-----------------|
|                  | Target          | Actual        | (%)             |
| Northern         | 71.58           | 74.73         | 4.41            |
| Western          | 17.08           | 9.18          | -46.25          |
| Southern         | 28.68           | 19.02         | -33.68          |
| Eastern          | 18.66           | 17.52         | -6.10           |
| N-Eastern        | 5.40            | 5.67          | 4.91            |
| <b>All India</b> | <b>141.40</b>   | <b>126.12</b> | <b>-10.80</b>   |

Against target of 141.40 BU, the actual energy generation during the year 2017-18 was 126.12 BU, which was 10.80% less than the target. The lower generation was primarily on account of less rainfall in the catchment areas of the hydro power stations.

### 5.10 Renovation & Modernisation of Hydro Electric Projects

#### 5.10.1 R&M Phase-I Programme :

Recognizing the benefits of the R&M programme, Govt. of India set up a National Committee in 1987 to formulate strategy on R&M of Hydro Power Projects. Based on the recommendations of the National Committee and subsequent reviews, a programme for renovation, modernization and uprating of

Hydro Power Stations was formulated by Central Electricity Authority in which 55 schemes were identified with an aggregate generating capacity of 9653 MW in Phase-1. The total cost of these R&M schemes was estimated as Rs.1493 Crores with expected benefit of 2531 MW.

#### 5.10.2 R&M Phase-II Programme:

The hydro policy of Govt. of India, declared in 1998, accorded priority to renovation & modernization of Hydro Power Plants. Accordingly, 67 hydro R&M schemes having an aggregate capacity of 10318 MW were identified to be undertaken under Phase-II Programme till the end of X Plan to accrue a benefit of 3685 MW at an estimated cost of Rs.

2161 Crores. Details of achievements are given at 5.11.1.

### 5.11 National Perspective Plan:

CEA formulated the National Perspective Plan for Hydro Power Stations in the year 2000 and integrated R&M proposals under Phase-II programme along with the left out schemes as recommended in Phase-I programme of the National Committee. The left out schemes were those, which were either under implementation or were yet to be taken up for implementation. This Perspective Plan was for R&M during IX, X and XI Plans with 117 schemes having an aggregate installed capacity of 19370 MW with benefits of 7755 MW at an estimated cost of Rs.4654 Crores.

#### 5.11.1 Achievements of VIII, IX, X XI and XII Plans:

The R&M works at 104 (21 in Central and 83 in State Sector) hydro projects (13 upto the VIII Plan, 20 in the IX Plan, 32 in the X Plan, 18 in the XI Plan & 21 in the XII Plan) with an aggregate installed capacity of 19481 MW had been completed at the end of the XII Plan (i.e by 31<sup>st</sup> March 2017). A benefit of 3635 MW through Life Extension, Uprating

and Restoration has been accrued.

During the XII Plan, 21 schemes (2 in central sector & 19 in state sector) with an installed capacity of 4150 MW have accrued a benefit of 549 MW through Life Extension, Uprating and Restoration completed till March, 2017. Summary is given at **Table I**.

#### 5.11.2 Programme for R&M during 2017-22 and 2022-27

An aggregate capacity of 9209.80 MW at 48 Hydro Electric Power Station (7 in Central Sector and 41 in State Sector) is programmed for R&M during 2017-22, which will accrue benefit of about 4725.35 MW through Life Extension, Uprating and Restoration. Out of the 48 schemes expected for completion during 2017-22, 2 schemes in Central Sector with an aggregate capacity of about 213.4 MW have been completed till March, 2018 and have accrued a benefit of 48.4 MW through Life Extension. Summary is given at **Table II**.

During 2022-27, an aggregate capacity of 2058 MW at 20 Hydro Electric Power Station (1 in Central Sector and 19 in State Sector) is programmed for R&M. Summary is given at **Table III**.

### Summary of R&M of Hydro Electric Projects (As on 31.03.2018)

#### I. Hydro R&M schemes completed up to XII Plan

| Sl. No. | Schemes completed in Plan Period | No. of Projects |              |       | Installed Capacity (MW) | Actual Expenditure (Rs. in Crs) | Benefit (MW)                                    |
|---------|----------------------------------|-----------------|--------------|-------|-------------------------|---------------------------------|---|
|         |                                  | Central Sector  | State Sector | Total |                         |                                 |   |
| 1.      | VIII Plan                        | 2               | 11           | 13    | 1282.00                 | 127.37                          | 429.00 [39.00(U) + 336.00 (Res.) +54.00(LE)]    |
| 2.      | IX Plan                          | 8               | 12           | 20    | 4892.10                 | 570.16                          | 1093.03 [339.00(U) + 331.03(Res.) + 423.00(LE)] |
| 3.      | X Plan                           | 5               | 27           | 32    | 4336.60                 | 1029.24                         | 829.08 [123.40(U) + 01.25 (LE) + 4.43(Res.)]    |
| 4.      | XI Plan                          | 4               | 14           | 18    | 4821.20                 | 294.84                          | 735 [12 (U) + 15 (Res.) + 708 (LE)]             |
| 5.      | XII Plan                         | 2               | 19           | 21    | 4149.60                 | 1127.69                         | 549.40 [58 (U)+ 476.40 (LE)+15(Res.)]           |

## II. Hydro R&M schemes Programmed for completion during 2017-22

| Sl. No | Category                                      | No. of Projects |              |       | Capacity (MW) covered under R&M | Estimated Cost (Rs. in Crs.) | Benefit (MW)                       |
|--------|---|-----------------|--------------|-------|---------------------------------|------------------------------|------------------------------------|
|        |   | Central Sector  | State Sector | Total |                                 |                              |                                    |
| 1.     | Programmed                                    | 7               | 41           | 48    | 9209.8                          | 6300.41                      | 4725.35 [149.7(U) + 4575.65(LE)]   |
| 2.     | Under Implementation                          | 3               | 21           | 24    | 4691.10                         | 3012.80                      | 2111.50 [116.20 (U)+ 1995.30 (LE)] |
| 3.     | Under Tendering                               | 1               | 13           | 14    | 2594.10                         | 2207.04                      | 848.25 [27.5 (U) + 820.75 (LE)]    |
| 4.     | Under DPR Preparation/ Finalization/ Approval | 1               | 7            | 8     | 1711.20                         | 1046.51                      | 1717.20 [6 (U) + 1711.20 (LE)]     |
| 5.     | Completed                                     | 2               | 0            | 2     | 213.4                           | 25.34 (Actual Cost)          | 48.4 (LE)                          |

## III. Hydro R&M schemes Programmed for completion during 2022-27

| Sl. No | Category                                      | No. of Projects |              |       | Capacity (MW) covered under R&M | Estimated Cost (Rs. in Crs.) | Benefit (MW)           |
|--------|---|-----------------|--------------|-------|---------------------------------|------------------------------|------------------------|
|        |   | Central Sector  | State Sector | Total |                                 |                              |                        |
| 1.     | Programmed                                    | 1               | 19           | 20    | 2058                            | 1285.79                      | 782 [31(U) + 751(LE)]  |
| 2.     | Under Tendering                               | 0               | 2            | 2     | 66                              | 182.29                       | 72 [6 (U) + 66 (LE)]   |
| 3.     | Under DPR Preparation/ Finalization/ Approval | 1               | 5            | 6     | 685                             | 1103.50                      | 710 [25(U) + 685 (LE)] |
| 4.     | Under RLA Studies                             | -               | 12           | 12    | 1307                            | -                            | -                      |

### Abbreviations:

MW – Mega Watt; Res. – Restoration; U – Uprating; LE – Life Extension



### 5.11.2.1 Achievements under R&M in Hydro during the year 2017-18

Two (2) Hydro R&M schemes namely Ganguwal & Kotla (1x24.2 & 1x24.2 MW) and Dehar Power House (1x165 MW) of BBMB, having an aggregate capacity of about 213.4 MW have been completed during the year 2017-18 at a cost of about Rs.25.34 Crores with accrued benefit of about 48.4 MW through Life Extension of Ganguwal & Kotla HEP.

### 5.11.2.2 Programme for the year 2018-19

For the year 2018-19, it is programmed to complete 10 schemes having capacity under R&M of about 1496 MW. On completion of these schemes, there will be a benefit of about 699 MW through Uprating, Life Extension and Restoration at an estimated cost of about Rs. 494 Crores. The details of these 10 schemes are as under:

| S. No. | Name of Scheme                         | Installed Capacity (No. x MW) | Capacity under R&M (No. x MW) | Cost (Rs. in Cr.) | Agency   |
|--------|--|-------------------------------|-------------------------------|-------------------|----------|
| 1      | Ganderbal                              | 2x3+2x4.5                     | 2x4.5                         | 39.30             | J&KSPDC  |
| 2      | Chenani                                | 5x4.66                        | 5x4.66                        | 39.14             | J&KSPDC  |
| 3      | Rihand                                 | 6x50                          | 6x50                          | 132.2             | UPJVNL   |
| 4      | Nagarjuna Sagar Ph-II works            | 1x110+7x100.8                 | 1x110+7x100.8                 | 22.17             | TSGENCO  |
| 5      | Nagarjuna Sagar Left Canal Power House | 2x30.6                        | 2x30.6                        | 30.99             | TSGENCO  |
| 6      | Bhadra River Bed units                 | 2x12                          | 2x12                          | 28.015            | KPCL     |
| 7      | Sholayar                               | 3x18                          | 3x18                          | 199.55            | KSEB     |
| 8      | Sholayar-I                             | 2x35                          | 2x35                          | 120               | TANGEDCO |
| 9      | Gandhi Sagar                           | 5x23                          | 5x23                          | 21.83             | MPPGCL   |
| 10     | Hirakud-II (Chilima)                   | 3x24                          | 1x24 (U-3)                    | 65.67             | OHPC     |

### 5.12 Concurrence / Appraisal of Hydro Schemes:

During the year 2017-18, CEA appraised and accorded concurrence/ appraisal to 3 Nos. Hydro Electric Schemes aggregating to capacity of 5531 MW as detailed below:

**Hydro Electric Schemes accorded Concurrence / Appraisal by  
Central Electricity Authority during 2017-18**

| S. No. | Name of Scheme/ State/ Executing Agency  | Installed Capacity (MW)     | Estimated Cost                                     | Date of Concurrence/ Appraisal by CEA |
|--------|--|-----------------------------|--|---------------------------------------|
| 1.     | Loktak down stream HEP in Manipur by M/s Loktak Downsteam Hydroelectric Corporation Ltd. | ( 2x33= 66 MW)              | Rs.1352.77 Cr.<br><br>(Price at Feb.2015 level)    | <b>5.5.2017</b>                       |
| 2.     | Sankosh HEP, in Bhutan by M/s.THDC India Limited   | (8x312.5MW+3x28.3= 2585 MW) | Rs.15709.59 Cr.<br><br>(Price at April.2016 level) | <b>6.6.2017</b>                       |
| 3.     | Dibang Multipurpose project in Arunachal Pradesh by M/s. NHPC Limited                    | (12x240=2880 MW)            | Rs 17510.84 Cr.<br><br>(Price at July.2016 level)  | <b>18.9.2017</b>                      |
|        | <b>TOTAL:</b>  | <b>5531 MW</b>              |  |                                       |

## CHAPTER-6

## THERMAL POWER DEVELOPMENT

## 6.1 SETTING UP OF ULTRA MEGA POWER PROJECTS (UMPPs)

The Government of India had launched an initiative for the development of coal-based Ultra Mega Power Projects (UMPPs), each with a capacity of 4,000 MW. The objective behind the initiative is to ensure cheaper tariffs utilizing economies of scale, catering to the need of a number of States and to mitigate the risk relating to tie up of land, fuel, water and other statutory clearances etc. The projects are awarded to the successful developers on the basis of tariff based International competitive bidding route employing Super Critical Technology. To tie-up for necessary inputs and clearances such as land, fuel through captive mining blocks,

water and environment and forest clearances, project-specific shell companies (SPVs) are set up as wholly owned subsidiaries of the Power Finance Corporation (PFC) Ltd. – the nodal agency for these projects. The Operative SPV alongwith the various clearances etc. are subsequently transferred to the successful developer.

Four UMPPs namely Sasan in Madhya Pradesh, Mundra in Gujarat, Krishnapatnam in Andhra Pradesh and Tilaiya in Jharkhand have already been awarded to the successful bidders. Mundra UMPP and Sasan UMPP are fully commissioned and are generating electricity. A brief detail of these projects are as below:

| Sl. | Name of UMPP                   | Type    | Date of Transfer | Levelling Tariff (in Rs. Per kWh) | Successful developer |
|-----|--------------------------------|---------|------------------|-----------------------------------|----------------------|
| 1.  | Mudra, Gujarat                 | Coastal | 23.4.2007        | 2.264                             | Tata Power Ltd.      |
| 2.  | Sasan, Madhya Pradesh          | Pithead | 07.08.2007       | 1.196                             | Reliance Power Ltd.  |
| 3.  | Krishnapatnam*, Andhra Pradesh | Coastal | 29.01.2008       | 2.333                             | Reliance Power Ltd.  |
| 4.  | Tilaiya **, Jharkhand          | Pithead | 07.08.2009       | 1.77                              | Reliance Power Ltd.  |

\* The developer has stopped the work at site citing the new regulation of coal pricing in Indonesia. Procurers have issued Termination Notice. The matter is subjudice.

\*\* The Developer has issued Termination Notice citing non transfer of land by Govt. of Jharkhand. Procurers have decided to terminate PPA with M/s RPL.

## Other UMPPs in Pipeline:

- For Odisha UMPP (village Bedabahal in Sundergarh district) afresh bid would be issued after finalization of SBDs. Reallocation of coal blocks for Odisha UMPP is under progress.
- Initially Cheyyur UMPP (District Kanchipuram, Tamil Nadu) was proposed on imported coal due to coastal location. However, Ministry of Power in

the meeting held on 02.11.2017 with procurers decided that due to lower tariff, Cheyyur UMPP would be developed on domestic coal on the same location having capacity of 4000 MW considering availability of land and other factors. Exploring the possibility of Cheyyur UMPP on domestic coal at existing location is under process.

- A site at Kakwara in Banka dist. has been identified for setting up of UMPP in

- Bihar. ToR for EIA study has been issued by MoEF&CC. Site specific studies and land acquisition are under progress. Power Allocation from this UMPP has been made to Bihar, Jharkhand, Uttar Pradesh and Karnataka.
- A site at Husainabad, Deoghar dist. has been identified for setting up of 2<sup>nd</sup> UMPP in Jharkhand. Water availability is a critical issue. Govt. of Jharkhand was requested to identify alternate source of water or alternate site having sufficient quantity of water for Deoghar UMPP. Power allocation from this UMPP has been made to Jharkhand, Gujarat, Tamil Nadu, Haryana, Kerala, Goa and Karnataka.
  - A site at Bijoypatna in Chandbali Tehsil of Bhadrak district for coastal location and another site at Narla & Kasinga sub division of kalahandi district for inland location have been identified for setting up of additional UMPPs in Odisha. Consent of state govt. is awaited.
  - UMPP in Maharashtra has been closed as of now because site could not be firmed up due to resistance by local people. CEA has requested Govt of Maharashtra to propose new site.
  - The proposed site for 2<sup>nd</sup> UMPP in Tamil Nadu is not environmentally suitable. State Govt. agreed to propose alternate suitable site and proposal is awaited since 2014.
  - Land is not sufficient in the proposed site at Chikhli-kob in Gir-Somnath District for 2<sup>nd</sup> UMPP in Gujarat and private land needs to be acquired. CEA in April 2017 requested Govt. of Gujarat (GoG) to identify Pvt. land adjacent to the site and furnish the details in response of GoG assurance for Pvt. land acquisition. Response from GoG is awaited.
  - For UMPP in UP, proposed at Etah, major portion of land is agricultural land and very far away from coal fields. The matter was discussed in the RPM meeting held on 10.08.2016 with

Secretary (Power) and thereafter no response has been received from Govt. of UP.

- A site at Niddodi village in Karnataka has been identified for UMPP by CEA and Govt. of Karnataka but further progress on this site could not be taken up due to local resistance. CEA has requested Govt of Karnataka to propose new site.

### 6.1.1 SITE INVESTIGATIONS OF UMPPs

#### (i) 1st Odisha UMPP, Sundergarh

Necessary input on Design & Detailing of RCC box Culvert, Design of Plate Girder Bridge at River Crossing, Revised Intake Arrangement Report, R&R Colony for Project Affected Families was communicated to UMPP Division.

#### (ii) Banka UMPP, Bihar

Necessary input on Topographical Survey Report Sheet of Power Plant Area and Plant Layout Super-imposed on Topo-sheet of Banka UMPP was communicated to UMPP Division.

### 6.2 CONSTRUCTION MONITORING OF THERMAL POWER PROJECTS

At present, 69171.15 MW capacity is under construction in the country. CEA closely monitors the progress of various construction activities of thermal power projects under construction in the country. Project monitoring related activities emerge from Section 73 (f) functions and duties of Authority of Electricity Act, 2003 which inter-alia envisages "To Promote and Assist in Timely Completion of Various Schemes and Projects." Regular visits are made by CEA officers to the project sites for assessing the progress of various construction activities and rendering necessary advice/assistance in resolving the problems being faced by the project authorities to meet the schedule of commissioning. Regular review meetings are also held in CEA with project authorities, main plant & equipment manufacturers and

other equipment suppliers to review the progress.

### 6.2.1 Key Initiatives

Based on the past experience, there has been a significant shift in approach in the area of project monitoring. Some key initiatives taken in the recent past as the role of a facilitator include the following:

- Detailed schedules were drawn up for equipment supplies and project milestones commitments from project authorities and equipment suppliers/ executing agencies for on-going projects.
- Participation in various review meetings held in the Ministry of Power, Ministry of Heavy Industries, Project Monitoring Group and Niti Aayog etc.
- Thermal projects visited to assess the progress of various activities at site including Gas based projects.
- Review meetings were held with various implementing agencies including suppliers to review the progress of work and finalizing the completion schedule of under construction thermal power projects.

### 6.3 Coal Block Allocation

After the cancellation of 204 coal blocks by Hon'ble Supreme Court in year 2014, 51 coal blocks catering to 62,330 MW have been allocated to various Power Utilities. Out of this 51 coal blocks, 9 coal blocks have been allocated through e-auction process and 42 coal blocks have been allocated to Government Sector Power Projects as per Coal Mines (Special Provisions) Act, 2015. In addition to above, 14 coal blocks have been allocated to various Central/State utilities under Rule- 4 of the Auction of Coal Mines Rules, 2012 and 01 (one) coal block which was allotted through Screening Committee. Thus total 66 Nos. coal blocks have been allocated to Power sector. Presently 07 (Seven) Nos. Coal Blocks are under production.

### 6.3.1 Coal Linkage Policy–2017 (SHAKTI)

- A New more transparent coal allocation policy for power sector, 2017 SHAKTI Scheme for Harnessing and Allocating Koyala Transparently in India) has been issued by Ministry of Coal in May, 2017. This new coal linkage policy would ensure a proper mechanism for sourcing coal by the power plants as per their schedules and would ensure that all projects are supplied coal as per their entitlement.
- FSA would be signed with pending LOA holders after ensuring that the plants are to be commissioned before 31.03.2022, all specified conditions of LOA fulfilled within specified time frame and nothing adverse is detected against the LOA holders.
- Requests from State and Central Sector power utilities for accord of coal linkage have been received under SHAKTI Policy Para B(i). Thermal Power Projects of State and Central Sector totaling to capacity of 13,800 MW have been accorded coal linkage by SLC(LT) under this Scheme.
- As per SHAKTI Policy Para B(ii) Coal linkages may be granted on notified price on auction basis for power producers/IPPs having already concluded long term PPAs based on domestic coal. Power Producers shall bid for discount on tariff. 10 nos. of such IPPs having 11,549 MW of installed capacity and 9,045 MW of PPA capacity have secured coal linkages for 32.682 MTPA (G13 equivalent) under this scheme. Out of this, FSAs has been signed with 07 nos. of Power Projects, totaling to coal quantity of 31.135 MTPA (G-13 Equiv.).
- As per SHAKTI Policy Para B (iii), future coal linkages may be granted on auction basis for power producers / IPPs without PPAs that are either commissioned or to be commissioned.

Coal drawal will be permitted only against valid long term PPAs, which the successful bidder shall be required to procure and submit within two (2) years of completion of auction process. In this regard an IMC has been constituted to recommend over issues arising during its execution.

- As per SHAKTI Policy Para B(iv) Coal linkage may be earmarked to the states for fresh PPAs, by Pre-declaring the availability of coal linkage with description. States may indicate these linkages to Discoms/SDAs. The states/Discoms may, based on such linkage, undertake tariff based competitive bidding for long-term and medium-term procurement of Power. Applications from four (04) states viz. Gujarat, U.P., M.P. & Maharashtra for a total capacity of 10,860 MW have been received for coal linkage under this policy.
- Power requirement of Group of States can be aggregated and procurement of power on tariff based bidding shall be made by a designated agency under SHAKTI Policy para B(v). Power Finance Corporation Ltd. (PFC) has been nominated as designated agency. Further, PFC Consulting Ltd (PFCCL), (a wholly owned subsidiary of PFC) has been assigned this work on behalf of PFC.
- Linkages shall be granted to Special Purpose Vehicles for setting up Ultra Mega Power Projects under Central Government initiative through tariff based competitive biddings under SHAKTI Policy para B (vi).
- Coal shall be supplied to IPPs having PPAs based on imported coal through auction subject to the availability of coal and the condition that such supply does not adversely impact the availability of coal for plants based on domestic coal with full pass through of cost saving to consumers under SHAKTI Policy para

B(vii). An IMC has been constituted to formulate draft methodology for the same.

## 6.4 Clean Development Mechanism

Central Electricity Authority (CEA), brings out a CO<sub>2</sub> Database for all grid connected Power Stations in the country on annual basis. The objective of this Database is to facilitate the consistent and accurate quantification of CO<sub>2</sub> emissions baseline to be used by CDM project developers in country. Version 12.0 of Database for the year 2015-16 is available on CEA website [www.cea.nic.in](http://www.cea.nic.in) and the Database for the year 2016-17 has been under preparation and likely to be finalized soon.

### 6.4.1 Environment aspects of electricity generation

CEA collected and compiled the monthly environmental data viz. Stack emission, Ambient Air Quality and Effluent Discharge for the year 2016-17 for thermal power stations. This database has been compared and reviewed on Quarterly basis.



### 6.4.2 Performance Award Scheme for Thermal Power Stations

This scheme is a part of the “Comprehensive Award Scheme for Meritorious Performance in Power Sector”. Performance Award Scheme for thermal power stations has been developed with a view to accord recognition to power stations based on their all-round performance by integrating the four operational parameters

viz. Station Heat Rate, Auxiliary Power Consumption, Specific Secondary Fuel Oil Consumption and Peaking PLF. The scheme is in its present form is intended to foster the competitive spirit amongst various power stations so as to encourage them to improve performance in all spheres of their working. The scheme would also help in evolving bench mark for various performance indices. The scheme covers all coal/lignite based & Combined Cycle Gas Turbine (CCGT) thermal power stations of Central, State and Private Sector (excluding captive power plants) having units of size 100 MW or above for coal based power stations whereas CCGT based power stations should have at least one GT of size 30 MW or above. The award scheme envisaged eight number awards for meritorious performance of thermal power stations.

Applications for Performance Awards Scheme for the year 2016-17 were invited from TPSs, requesting them to furnish their all-round performance data. Accordingly, one hundred four applications from Thermal Power Stations were received for participation in Performance Awards Scheme 2016-17. The evaluation of Performance Awards Scheme for the year 2016-17 have been completed.

#### **6.4.3 Environment Management Award Scheme for Coal/Lignite based Thermal Power Stations**

One Environment Management Award Scheme for coal/lignite based thermal power stations was introduced to promote best strategy and management of environmental issues by coal/lignite based thermal power stations. Applications for Environment Management Award 2016-17 were invited from TPSs requesting them to furnish information on various environmental parameters such as CO<sub>2</sub> emission, SPM emissions at stack, Fly Ash Utilization and Effluent Discharge etc. Accordingly, 57 applications from Thermal Power Stations were received for participation in

Environment Management Award Scheme 2016-17 and the evaluation of the same has been completed.

#### **6.4.4 Phasing Plan for Implementation of New Environment Norms**

New Environmental norms have been issued by Ministry of Environment, Forest and Climate Change (MoEF&CC) in December 2015 for Thermal Power Stations making norms for Suspended Particulate Matter (SPM) more stringent than existing norms. Norms for SO<sub>x</sub>, NO<sub>x</sub> and Mercury have also been notified for the first time. Norms for water consumption in Thermal Power Stations have also been issued for the first time. An Implementation Plan for compliance with above environmental norms has been prepared and submitted to MoP which extends from the year 2018 to 2022.

#### **6.4.5 National Energy Conservation Awards 2017**

Ministry of Power had undertaken a scheme to encourage, motivate as well as give recognition through National Energy Conservation Awards to industrial units and other establishments, who have taken extra efforts to reduce energy intensities while maintaining the production levels. The scheme is aimed to create an environment that would spur industries and other establishment in achieving excellence in efficient use of energy and its conservation. The awards were given away for the first time in December, 14, 1991 which is now celebrated as National Energy Conservation Day throughout the country. Chief Engineer (TPE&CC), CEA is a member of Technical Sub-Committee to assist the Award Committee in the finalization of awards. During the year 2016-17 proposals received from three industrial sectors viz., Dairy, Fertilizer, and Thermal Power Stations were evaluated by CEA. The awards to the best performing firms in each of the above three sectors were given during National Energy Conservation Day function held in New Delhi on 14<sup>th</sup> December, 2017.

## 6.5 THERMAL CAPACITY ADDITION PROGRAMME

### 6.5.1 Thermal capacity addition during 2017-18

The thermal capacity addition target for the year 2017-18 was 11366.15 MW, a capacity of 8710 MW was commissioned during the year.

This includes 6710 MW Capacity which was commissioned from the target 2017-18 and 2000 MW additional capacity commissioned. The details of target/achievements for the year 2017-18 is enclosed at **Annexure 6A**. Sector-wise details of target and achievement during the year 2017-18 are as follows :

| SECTOR       | THERMAL (In MW) |             |
|--------------|-----------------|-------------|
|              | Target          | Actual      |
| CENTRAL      | 4880            | 3170        |
| STATE        | 3546.15         | 1760        |
| PRIVATE      | 2940            | 3780        |
| <b>TOTAL</b> | <b>11366.15</b> | <b>8710</b> |

### 6.5.2 Thermal Capacity Addition Programme for the year 2018-19

A thermal capacity addition programme of 8216.15 MW has been finalized for the year

2018-19. The details of the Thermal Capacity Addition programme is enclosed at **Annexure-6B**. The details of programme are as follows:

| SECTOR       | THERMAL (in MW) |
|--------------|-----------------|
|              | Target          |
| CENTRAL      | 2760            |
| STATE        | 4506.15         |
| PRIVATE      | 950             |
| <b>TOTAL</b> | <b>8216.15</b>  |

**NOTE:** It has been decided in the meeting convened on 9<sup>th</sup> March 2018 under the chairmanship of Secretary (Power), that the targets for capacity addition would be identified "Commissioning and COD" with effect from 01.04.2018 onwards. The units for capacity addition will be considered only after achieving COD.

## 6.6 Thermal Technology Development and Design & Engineering

### 6.6.1 Supercritical Technology

CEA has been actively associated in developing road map for introduction of new technologies for thermal power generation.

Govt. of India had approved two bulk orders for Supercritical units in September-2009 (Bulk order I) for 11 number of 660 MW supercritical units and in January-2011 (Bulk order II) for 9 number of 800 MW supercritical units for various NTPC & DVC

power projects. The GoI approval stipulated setting up of a subsidiary or Joint Venture (JV) Company for manufacturing of supercritical boiler (or turbine) in India with firm commitment to indigenize manufacturing in India in a phased manner as per Phased Manufacturing Programme (PMP) laid down in the GoI order and levying of liquidated damages for non-adherence to the pre-agreed schedule (milestones) of PMP. A Committee under Member (Thermal), CEA is monitoring the progress of phased manufacturing program.



A number of 660/ 800MW Units are operational in the country and many more number of supercritical units of 660/800 MW are under construction for likely commissioning in 13<sup>th</sup> Plan and beyond. Initially supercritical units were designed with steam parameters of 247 kg/cm<sup>2</sup>, 537/565 deg C. Subsequently, the parameters of 247 kg/cm<sup>2</sup>, 565/593 deg C and higher are being adopted for supercritical units.

Ultra Supercritical Thermal Power Plants with steam pressure of around 270 kg/cm<sup>2</sup> and temperatures of around 600 deg C are also in the process of being adopted in the country. The improvement in design efficiency of Ultra supercritical plants is around 2% point over that of supercritical plants. Some of the new upcoming power plants viz. Khargone TPP of NTPC and Jawaharpur STPP & Obra-C STPP of UPRVUNL are already with steam parameters of Ultra supercritical class.

### 6.7 Important Activities

Following activities were also undertaken:

- (a) Associated with the “Scheme for utilization of Gas based power generation capacity”. The scheme was approved by Cabinet Committee on Economic Affairs for revival and improvement in utilization of Gas based plants which were lying idle or underutilized due to shortfall in the production of domestic natural gas.
- (b) Standard technical specification for retrofit of wet limestone based flue gas desulphurization (FGD) system in typical 2x500 MW thermal Power Plant was taken up and finalized document uploaded on CEA web site.
- (c) Standard technical specification for retrofit of sea water based flue gas desulphurization (FGD) system in thermal Power Plant was taken up.
- (d) Review of CEA Report of 2012 on Land requirement for thermal Power Station was taken up.
- (e) Preparation of specification on Biomass pellets, based on agro based residue, for co-firing in pulverized coal based thermal power stations and preparation of guidelines for blending of Biomass pellets (5%-10%) with coal in coal based thermal power stations was taken up.
- (f) Various issues arising due to MoEF&CC Notifications related to new emissions norms, specific water consumption and Open/ Closed cooling water system were dealt with.
- (g) Associated with deriving the treated sewage water quality desired by Power Plants for mandatory use of sewage water for thermal power plants as per Tariff Policy, 2016.
- (h) Monitored the progress of manufacturing facilities of indigenous manufacture of power equipment for compliance of PMP milestones under Bulk Tender I & II and reports of the visits performed in this respect were prepared.
- (i) Comprehensive Review of Regulations entitled “Central Electricity Authority (Technical Standard for construction of Electrical plants and Electrical lines) Regulations, 2010 for issue of the amendment is under progress.
- (j) The investigation of three accidents/ failures occurred in Kalisindh STPS as referred by RRVUNL to CEA was carried out and reports were furnished to RRVUNL.
- (k) Investigation of the accident that occurred in 500 MW Unit-6 of NTPC Unchahar TPS on 1.11.2017 was carried out by the committee constituted under Member (Thermal), CEA and report of the Committee was submitted to Ministry of Power.
- (l) Study by Expert Group on CFBC

Technology set up by Ministry of Power under Chairmanship of Member (Thermal), CEA is under progress for its feasibility for Adoption in Power Sector.

(m) Officers of TE&TD Division are represented in the following Committees:

- i. CE (TE&TD) is a member of Standing Committee on PMP under Member (Thermal) CEA for monitoring & imposition of Liquidated Damages (LD) for Phased Manufacturing Programme (PMP) under the Bulk tender –I (660 MW) & Bulk tender- II (800 MW).
- ii. Chief Engineer (TE&TD) is Member-Secretary of “Sub- Committee-9 “key inputs for power sector” with Director(Projects),NTPC as Chairman of the Sub-committee for NEP – 2015.
- iii. Director (TE&TD) is a member of the water tube boiler Sub-Committee constituted by Central Boilers Board (CBB).
- iv. Officer from TE&TD division is nominated as a Member on Board of Directors of Puducherry Power Corporation Limited, Puducherry.
- v. CE(TE&TD) is Member-secretary of Task Force constituted under Chairmanship of Member (Thermal), CEA for review of Regulations titled Central Electricity Authority (Technical Standard for construction of Electrical plants and Electric lines) Regulations, 2010.
- vi. Director (TE&TD) was the member of the Committee under Chairmanship of Member (Thermal) for verification of claims received from Bidders for PSDF Support under the “Scheme for utilization of Gas based power generation capacity”.
- vii. Director (TE&TD) was the member of

the Committee for Periodic Comprehensive review of the Regulations entitled, “Central Electricity Authority (Measures relating to safety and Electric Supply) Regulation, 2010”.

- viii. CE(TE&TD) was member of the Committee constituted by MoP under Chairmanship of Member(Thermal) to investigate into the causes of the accident occurred at 500 MW Unit- 6 of NTPC, Unchahar Thermal Power Plant on 1.11.2017.
- ix. CE(TE&TD) is member of the Committee constituted under chairmanship of Member (Thermal) to prepare specification and guidelines on Biomass pellets, based on agro based residue, for co-firing in pulverized coal based thermal power stations.

## 6.8 Renovation & Modernisation and Life Extension of Thermal Power Plants

The main objective of Renovation and Modernisation (R&M) of thermal generating units is to make the operating units well equipped with modified / augmented latest technology equipment and systems with a view to improving their performance in terms of output, reliability and availability, reduction in maintenance requirements, ease of maintenance and minimizing inefficiencies. The R&M programme is primarily aimed at generation sustenance and overcoming problems. The life extension (LE) programme on the other hand focuses on plant operation beyond their original design life after carrying out specific life assessment studies of critical components.

### 6.8.1 Renovation and Modernisation (R&M) and Life Extension Programme (LEP) from 7th Plan onwards

R&M Programme in a structured manner was initiated in 1984 as a centrally sponsored

programme during 7<sup>th</sup> Plan. The programme continued during the two Annual Plans 1990-91 & 1991-92 and during the 8<sup>th</sup>, 9<sup>th</sup>, 10<sup>th</sup>, 11<sup>th</sup> and 12<sup>th</sup> Plan. The Plan wise achievements are given below:-



| S. No. | Five Year Plan                        | Year                             | No. of TPS / No. of Units               | Capacity (MW)                       | Additional Generation Achieved MU/ Annum* | Equivalent MW** |
|--------|---------------------------------------|----------------------------------|---|-------------------------------------|---|-----------------|
| 1      | 7 <sup>th</sup> Plan & 2 Annual Plans | 85-86 to 89 - 90 & 90 -91, 91-92 | <b>34 / 163</b>                         | <b>13570</b>                        | 10000                                     | 2000            |
| 2      | 8 <sup>th</sup> Plan (R&M) (LEP)      | 1992 to 1997                     | <b>44 / 198</b><br>43/(194)<br>1/(4)    | <b>20869</b><br>(20569)<br>(300)    | 5085                                      | 763             |
| 3      | 9 <sup>th</sup> Plan (R&M) (LEP)      | 1997 to 2002                     | <b>37 / 152</b><br>29/ (127)<br>8/ (25) | <b>18991</b><br>(17306)<br>(1685)   | 14500                                     | 2200            |
| 4      | 10 <sup>th</sup> Plan (R&M) (LEP)     | 2002 to 2007                     | <b>9/25</b><br>5/(14)<br>4/(11)         | <b>3445</b><br>(2460)<br>(985)      | 2000                                      | 300             |
| 5      | 11 <sup>th</sup> Plan (R&M) (LEP)     | 2007 to 2012                     | <b>21/72</b><br>15/(59)<br>6/(13)       | <b>16146</b><br>(14855)<br>(1291)   | 5400                                      | 820             |
| 6      | 12 <sup>th</sup> Plan (R&M) (LEP)     | 2012 to 2017                     | <b>18/37</b><br>8/16<br>10/21           | <b>7202.5</b><br>4560.50<br>2641.76 | ----                                      | ----            |

\*Tentative figure.

\*\* Equivalent MW has been worked out assuming PLF prevailing during that period.

### 6.8.2. R&M/LE Programme during (2017-22)

71 thermal generating units with aggregate capacity of 14929 MW have been identified for implementation of R&M/LE works during 2017-22 period. Out of this a total of 35 nos. thermal generating units with aggregate capacity of 7570 MW for LE works and 37 nos. thermal generating units with aggregate capacity of 7359 MW for R&M works have been identified for the period 2017-22. Break-up summary of LE and R&M

works of 14929 MW to be taken up during 2017-22 in terms of Central/State sector-wise is furnished below:

| Category       | LE/R&M works identified during 2017-22<br>No. of units & capacity (MW) |                | Total<br>(State Sector +<br>Central Sector) |
|----------------|--|----------------|---|
|                | State Sector   | Central Sector |   |
| <b>LE</b>      | 34 (7570)  | --             | 34 (7570)                                   |
| <b>R&amp;M</b> | 30 (7135)  | 07 (224)       | 37 (7359)                                   |
| <b>Total</b>   | 64 (14705)   | 07 (224)       | 71 (14929)                                  |

### 6.9 Achievements of R&M and LE Projects during 12th Plan (upto 31.03.2018)

Life Extension works on 2 thermal

generating units with aggregate capacity of 410 MW were completed in FY 2017-18. The details of achievements of R&M/LE Projects during 2017-22 (upto 31.03.2018) is furnished below:

#### Details of Thermal Power Units where R&M Works have been completed during 2017-22

| Sl. No.             | Name of the TPS | Unit No. | Capacity MW | Utility | State/Centra Sector | Date of Synchronisation after LE Works |
|---------------------|-----------------|----------|-------------|---------|---------------------|--|
| 1.                  | Ukai            | 4        | 200         | GSECL   | State Sector        | 17-05-2017                             |
| 2.                  | Wanakabori      | 3        | 210         | GSECL   | State Sector        | 27-11-2017                             |
| Total State-2 units |                 |          | 410 MW      |         |                     |  |

### 6.10 Monitoring of R&M Projects

The progress of R&M and LE works being implemented at Thermal Power units are monitored by carrying out site visits, holding the review meetings and data / information compiled on Monthly/Quarterly basis. Based on the data/information collected & compiled, Quarterly Review Report on

status of R&M projects were prepared.

### 6.11 Thermal units under shutdown for R&M and LE works

The following 4 Units were under shut down for execution of R&M and Life Extension works:

| Sl.No.       | Name of Project | Utility | State       | Unit No. | Capacity (MW) |
|--------------|-----------------|---------|-------------|----------|---------------|
| 1.           | Obra TPS        | UPRVUNL | U.P.        | 7        | 100           |
| 2.           | Barauni TPS     | BSPGCL  | Bihar       | 6        | 110           |
| 3.           | Koradi TPS      | MSPGCL  | Maharashtra | 6        | 210           |
| 4.           | Obra TPS        | UPRVUNL | U.P.        | 12       | 200           |
| <b>Total</b> |                 |         |             |          | <b>620</b>    |

### 6.12 Implementation of Phasing Plan for FGD installation/ ESP upgradation in respect of new Environmental Norms

Ministry of Environment, Forest &

Climate Change (MoEF&CC) notified "Environment (Protection) Amendment Rules, 2015" for thermal power stations on 07.12.2015. All existing stations are required to comply with the new Standards within 2 years (i.e. by Dec. 2017) and the new stations

including the ones presently under construction are required to meet the new norms by 01.01.2017.

To review the various issues arising out of new environmental norms for thermal power stations, a meeting was held on 01.09.2017 in MoEF&CC among Secretary MoEF & CC, Secretary, MoP and Chairperson, CEA and it was decided that the action plan submitted by MoP to MoEF & CC extending up- to 2024 should commence from 2018 and implemented before 2022.

The MOEFCC gave its concurrence to the revised implementation plan for FGD installation/ESP upgradation vide letter no. F. No. Q-15017/40/2007-CPW dated 07.12.2017

The implementation plan including units commissioned upto 31.08.2017 year-wise FGD Phasing Plan and ESP Upgradation Plan are given below:

#### i) Year wise FGD Phasing Plan

| Year               | Capacity (MW) | No. of units |
|--------------------|---------------|--------------|
| 2018               | 500           | 1            |
| 2019               | 4940          | 8            |
| 2020               | 27230         | 55           |
| 2021               | 64027.5       | 172          |
| 2022               | 64704.5       | 178          |
| Plan not Available | 150           | 1            |
| <b>Total</b>       | <b>161552</b> | <b>415</b>   |

#### ii) Year wise FGD Phasing Plan

| Year               | Capacity     | Units      |
|--------------------|--------------|------------|
| 2018               | 500          | 1          |
| 2019               | 1300         | 2          |
| 2020               | 10705        | 28         |
| 2021               | 23495        | 97         |
| 2022               | 28525        | 94         |
| Plan not Available | 1400         | 9          |
| <b>Total</b>       | <b>65925</b> | <b>231</b> |

To ensure compliance of the new Environmental Norms letters have been issued to concerned utilities for furnishing the details of action taken till date and further plan for FGD installation/ ESP upgradation. In view of the above, CEA has started the monitoring of the implementation of the revised implementation plan.

According to the FGD phasing plan, 1 Unit of 500MW of Trombay TPS is to be completed by 2018. The current Status of FGD installation/ESP Upgradation for **Unit#5 of**

**Trombay TPS of Tata Power** is as follows:

1. FGD Installation-Sea water FGD is installed at Unit#5 and is already in operation to meet the SO<sub>2</sub> emissions norms.
2. ESP Upgradation- Unit#5 ESP refurbishment project is already undertaken. Refurbishment of 2 Streams has been completed. Work on third Stream is in advanced stage of completion which would lead in meeting of the SPM Norms.

For Year 2019, according to the FGD phasing plan a total of 8 Units of Combined Capacity of 4940 MW are to be completed. Under this the status of following Units have been received and is as under.

i) **Mahatma Gandhi STPP, Jhajjar Power Ltd. (JPL), Haryana** has already installed FGD at the time of Project Construction. FGD is now under renovation for both the units in order to meet the parameters set by new MOEFCC guidelines. In this regard, OEM has already made a site visit to assess the suitability of existing system and

improvements to be made to meet new SO<sub>2</sub> emission norms. MGTPS (JPL) has installed ESP and FF hybrid design for control of SPM. With the help of this, JPL is complying with environment norms for SPM and it remains below 50 Mg/Nm<sup>3</sup>.

ii) **Hinduja National Power Corporation Limited for the Vizag TPP** have appointed Tata Consultancy Engineers as their consultants who have visited the site along with a team for survey and collecting necessary inputs Technical and Operating Parameters to conceptualize the FGD requirement.

### 6.12.1 Summary of Current Status of Implementation of phasing plan for FGD Installation

| S.No                  | Description  | Capacity(MW) | Units |
|-----------------------|--|--------------|-------|
| <b>Central Sector</b> |  |              |       |
| 1                     | Central sector where FGD to be installed   | 46905        | 122   |
| 2                     | Finalisation of Specification planned  | 14190        | 29    |
| 3                     | Bids Awarded   | 2480         | 5     |
| 4                     | NIT done   | 840          | 4     |
| 5                     | NIT Planned  | 13740        | 44    |
| 6                     | Bids opened  | 4725         | 9     |
| 7                     | Feasibility study under process  | 10930        | 31    |
| <b>State Sector</b>   |  |              |       |
| 1                     | State sector where FGD to be installed   | 49085        | 156   |
| 2                     | Tendering process to be initiated  | 8880         | 24    |
| 3                     | Requested for FGD implementation date to be revised                              | 1200         | 2     |
| 4                     | Not feasible as per developer  | 200          | 1     |
| 5                     | Feasibility study under process  | 17380        | 58    |
| 6                     | Feasibility study carried out  | 13090        | 37    |
| 7                     | Due to space constraint, alternative options of FGD installations being explored | 1000         | 4     |
| 8                     | Complies with the norms  | 1050         | 5     |
| 9                     | Boiler is CFBC, hence FGD is not required.                                       | 215          | 3     |
| 10                    | Administrative approval is under process.  | 6070         | 22    |
| <b>Private Sector</b> |  |              |       |
| 1                     | Private sector where FGD to be installed   | 57085        | 119   |
| 2                     | Tender Under process   | 11740        | 23    |
| 3                     | Bid under evaluation   | 3270         | 7     |
| 4                     | NIT issued   | 1200         | 2     |
| 5                     | As per developer, FGD Installation is not required.                              | 540          | 2     |
| 6                     | FGD Installed  | 1820         | 3     |
| 7                     | Complies with the norms  | 300          | 1     |
| 8                     | Feasibility study carried out  | 22870        | 41    |
| 9                     | Feasibility under process  | 12165        | 34    |
| 10                    | Need Extension   | 3180         | 6     |

### 6.12.2 FGD- ESP Phasing Plan of Thermal Power Plants located in Delhi NCR

| Sl. No. | Name of Thermal Power Station    | Unit No. | Capacity (MW) | Timeline for FGD |
|---------|----------------------------------|----------|---------------|------------------|
| 1       | Dadri (NCTPP), U.P.              |          | <b>1820</b>   |                  |
|         |                                  | 1        | 210           | 31.12.2019       |
|         |                                  | 2        | 210           | 31.12.2019       |
|         |                                  | 3        | 210           | 31.12.2019       |
|         |                                  | 4        | 210           | 31.12.2019       |
|         |                                  | 5        | 490           | 31.12.2019       |
| 2       | GHTP (Lehra Mohabbat), Punjab    |          | <b>920</b>    |                  |
|         |                                  | 1        | 210           | 31.12.2019       |
|         |                                  | 2        | 210           | 31.12.2019       |
|         |                                  | 3        | 250           | 31.12.2019       |
| 3       | Harduaganj, U.P                  |          | <b>500</b>    |                  |
|         |                                  | 8        | 250           | 31.12.2019       |
| 4       | Indira Gandhi STPP, Haryana      |          | <b>1500</b>   |                  |
|         |                                  | 1        | 500           | 31.12.2019       |
|         |                                  | 2        | 500           | 31.12.2019       |
| 5       | Mahatma Gandhi TPP, Haryana      |          | <b>1320</b>   |                  |
|         |                                  | 1        | 660           | 31.12.2019       |
| 6       | Panipat TPS, Haryana             |          | <b>720</b>    |                  |
|         |                                  | 6        | 210           | 31.12.2019       |
|         |                                  | 7        | 250           | 31.12.2019       |
| 7       | Rajiv Gandhi TPS, Hisar, Haryana |          | <b>1200</b>   |                  |
|         |                                  | 1        | 600           | 31.12.2019       |
| 8       | Yamun anagar (DCTPS), Haryana    |          | <b>600</b>    |                  |
|         |                                  | 1        | 300           | 31.12.2019       |
| 9       | Talwandi Sabo TPS, Mansa, Punjab |          | <b>1980</b>   |                  |
|         |                                  | 1        | 660           | 31.12.2019       |
|         |                                  | 2        | 660           | 31.12.2019       |
| 10      | Nabha Power Ltd, Rajpura, Punjab |          | <b>1400</b>   |                  |
|         |                                  | 1        | 700           | 31.12.2019       |
|         |                                  | 2        | 700           | 31.12.2019       |

### 6.13 “Coal-Fired Generation Rehabilitation Project-India” funded by World Bank.

The World Bank has financed the “Coal-Fired Generation Rehabilitation Project-India” for demonstrating Energy Efficiency

Rehabilitation & Modernization (EE R&M) at coal fired generating units through rehabilitation of 640 MW of capacity across three States-West Bengal, Haryana and Maharashtra. The above project has two components: -

### Component-1: Energy Efficiency R&M at Pilot Projects

This component would fund implementation of Energy Efficient R&M of 640 MW capacity comprising Bandel TPS Unit-5(210 MW) of WBPDC, Koradi TPS Unit-6(210 MW) of Mahagenco and Panipat TPS Unit-3&4 (2x110 MW) of HPGCL. The World Bank has earmarked US \$ 180 million of IBRD loan and US \$ 37.9 million of GEF grants for the Component-1.

### Component-2: Technical Assistance to CEA and Utilities

The Technical Assistance component of the project is aimed at providing support in implementation of EE R&M pilots, developing a pipeline of EE R&M interventions, addressing barriers to EE R&M projects and strengthening institutional capacities of implementing agencies for improved operation and maintenance practices. The World Bank has earmarked US \$ 7.5 million GEF grant for the Component-2.

#### 6.13.1 World Bank Funded Energy Efficiency Pilot R&M Projects (Component-1)

##### (A) Bandel TPS (Unit-5, 210 MW)

WBPDC issued Letter of Award (LOA) to M/s Doosan Heavy Industries & Construction Co. Ltd and their associate on January 10, 2012 and the contract was signed on 29<sup>th</sup> February, 2012. Unit Shut Down was taken on November 17, 2013 and Zero Date of R&M works of BTG package was declared as 2<sup>nd</sup> Dec, 2013. The Zero Date of R&M works of BTG package was declared as 2<sup>nd</sup> Dec, 2013. The R&M project consisted of the major packages, viz., Main Plant Package (BTG - Boiler, Turbine & Generator), Coal Handling System Package (CHP), Ash Handling Package & Water System Package (AHP & Water). R&M works at Unit-5 of Bandel have been completed and the Unit has been synchronized on coal on 21<sup>st</sup> September, 2015.

##### (B) Koradi TPS (Unit-6, 210 MW) Background

The total estimated cost of the project is around US\$ 110.5 Million and the fund allocation for the Koradi TPS is loan of around US \$ 59 million (Loan), grant of around US \$ 12.45 million. In addition to above Technical Assistance of US \$ 3.3 million under GEF Grant has been provided for 10 consultancy studies.

The Commercial Operation Date of the unit is 30.03.1982 & the unit is about 34 years old. The zero date for R&M project is 3rd March, 2014. The unit is under shutdown since 20<sup>th</sup> July, 2015 and targeted synchronization date is 18-02-2018.

Expected date of synchronization is 20-04-2018.

#### Status of Physical Progress

- i) **BTG Package:** Mahagenco issued the Letter of Award to BHEL on May 31, 2013. The contract was signed on December 18, 2013. Overall 89.61% work of BTG package completed.
- ii) **Electrical Package :** Mahagenco issued the Letter of Award to M/s ABB Ltd on March 19, 2012 and the final contract was signed on May 25, 2012. Overall 78.79% work of Electrical package completed.
- iii) **BOP Package:** Letter of Award (LOA) for Cooling Tower Plant Package, Ash Handling Plant package and Fire Detection, Protection & Inert Gas System Package are issued and contract is signed on 23.09.2016, 26.10.2016 & 05.11.2016 respectively. DM Plant & Pre-Treatment System Package has been cancelled. The need based work of DM Plant & Pre-Treatment System shall be carried out separately by O&M section. Under Cooling Tower Plant Package overall 70.47% work completed.

#### 6.14 Japan-India Co-operation for Study on Efficiency and Environmental



### Improvement of Coal Fired Stations

A MOU between Central Electricity Authority and Japan Coal Energy Centre (JCOAL) for preliminary study of Efficiency and Environment improvement study in coal fired power plants was signed on 30.4.2010 to carryout necessary diagnostic activities in few coal-fired power plants pertaining to Energy Efficient Renovation & Modernisation works and suggest measures to overcome barriers for promoting R&M, measurement for environmental improvement of coal-fired power plants in India. Accordingly, generating units are selected from Ukai and Wanakbori TPS (GSECL), Ramagundem STPS (NTPC) and Vijaywada TPS (APGENCO) for pre – primary studies. After Pre-Primary Studies, JCOAL finalized 3 units viz., Vijaywada TPS Unit-1 (210MW) of APGENCO, Wanakbori TPS Unit-1 (200 MW) of GSECL and Kahalgaon STPS Unit-2 (210 MW) of NTPC for full-fledged diagnosis. The final report had been submitted in December 2012.

The 2<sup>nd</sup> Phase MOU between CEA and JCOAL was signed on 11.06.2012 for carrying out detail diagnostic study for energy efficiency oriented R&M activities in three nos. of units. Durgapur TPS unit no.4 (210 MW LMZ Unit) of DVC and one unit each from Badarpur TPS and Unchahar TPS of NTPC were selected for studies during the 2nd phase. JCOAL team visited these stations during December, 2012. The final study report for energy efficiency oriented R&M activities was submitted on 15th April, 2013.

The 3<sup>rd</sup> Memorandum of Understanding (MoU) on India – Japan Cooperation for Project on Efficiency & Environment Improvement for Sustainable, Stable and Low Carbon Supply of Electricity was signed on 22nd January, 2016.

Under Clean Coal Technology (CCT) Programme a study tour to Japan has been organised during current year from 29th Nov, 2017 to 7th Dec, 2017. The participants from

CEA, MoP, DVC, NTPC and State Utilities visited the latest USC power stations at Japan. Total 89 officers from MoP, CEA and different power utilities participated in the study tour under CCT Training Programme

Under CEA- JCOAL Co-operation a study on replacement of old units of Badarpur TPS by highly efficient super critical units of higher size has been carried out. JCOAL team has carried out three site surveys and investigations in the month of Nov, 2015, Jan, 2016 and in March, 2016. The report on the study has been submitted in June, 2016 by JCOAL.

JCOAL has also carried out feasibility study on replacement of Singrauli STPS Stg. I & II units (5x200 MW+2x200 MW) of NTPC between December, 2016 to March, 2017.

Unit-3 of Dadri TPS of NTPC was identified for implementation of full-fledged diagnosis study i.e. Residual Life Assessment (RLA) study. JCOAL team has conducted RLA/Diagnostic Study at Unit-3 Dadri TPS of NTPC from 30th November, 2015 to 10th of December, 2015. The report on RLA/CA study of Unit-3 of Dadri TPS has been submitted by JCOAL. The objective of the RLA Study is to identify the remaining life and the current condition of Unit -3, to constitute the base for formulation of the plan of R&M implementation that is tentatively scheduled in 2018.

One day workshop on " Project on Efficiency and Environmental Improvement for Sustainable, Stable and Low-carbon Supply of Electricity" was held on 11th Nov, 2016 and 10th Nov 2017 at New Delhi by CEA and JCOAL. Various stake holders from Central/State/Private in power sector participated in the workshop.

A Kick-off Meeting on Study on O&M enhancement of existing units of DSTPS, DVC under CEA-JCOAL Cooperation was held among NEDO, JCOAL, CEA and DVC on 13th October 2017 at Kolkata in order to share O&M and safety related best practices. The expert team from Japan also visited

DSTPS, DVC for the purpose of O&M Study from 11.12.2017 to 14.12.2017.

Interim Report of Activities during the Site Study for O&M Study at Durgapur Steel Thermal Power Station has been submitted by JCOAL to CEA on 15th Dec 2017.

Mini-workshops were organized on 30-1-2018 at GSECL(Gujrat) and on 01-02-2018 at APGENCO (Andhra Pradesh) respectively for the year 2017-18 under CEA-JCOAL Cooperation for the project on Efficiency and Environment improvement of Coal Fired Power Stations in India.

Under CEA- JCOAL Co-operation a study is being carried out by JCOAL on adoption of available technologies to meet new environment standards and the economic viability of using such technologies in existing power plants. Combustion test of Indian Coal has been done at Japan. The Report of Combustion test of Indian Coal has been submitted. SCR Pilot test at NTPC's Sipat TPS is being carried out to meet the NOx level in the flue gas as per new environmental norms. A diagnostic study for optimal environmental measures at Dadri TPS was conducted in January, 2018.

### **6.15 Decommissioning of old and inefficient Units**

25 years or more old inefficient Thermal Units in Government Sector aggregating to approximately 10000 MW capacity have been identified in September 2015 for decommissioning in a phased manner. 6075 MW Thermal Units have been retired since September 2015 to till 31<sup>st</sup> March, 2018. In addition to above, 797.32 MW of private sector/ Gas based/ DG Set units have also been retired since Sept., 2015 to March, 2018.

### **6.16 Use of Treated Sewage Water by TPS under NMCG**

As per the Tariff Policy 2016, it is envisaged to explore the possibility of recycle/ reuse of the treated waste water from STP's for non-potable use (cooling purpose) in existing Thermal Power Plants within 50 km radius from STP's. Accordingly, the mapping of thermal power stations within the vicinity of 50 km from STPs across the country has been undertaken. In this regard, nine thermal power stations namely Solapur, Mouda, Meja, Dadri, up-coming Patratu, Rattan India Nasik TPS (Phase-II), Yelanhanka CCPP, Khaperkheda TPS & Chandrapur STPS power stations have been identified for use of treated sewage water. State power utility, MAHAGENCO has tied up with Nagpur Municipality Corporation through a long term agreement for supply of treated sewage water to their Koradi Power station in Maharashtra. The monitoring committee set up by Ministry of Power is monitoring this initiative to provide the STP water to power plants. The Power plants, promoting the use of this STP water, will be provided benefits under the Tariff Policy'2016. As per the mapping done, 7867 MLD STP Water is available. Out of the above 7867 MLD, STP water discharge, the potential water to be utilised in Thermal Power Plants is under exploration.

### **6.17 Orders Placed for New Thermal Power Plants**

During 2017-18, Main Plant orders have been placed on EPC basis for New Thermal Power Projects totaling to 9040 MW. Details of these projects are given below :

| Sl. No. | PROJECT               | Implementing Agency                           | Plant Configuration | Capacity (MW) | Main Plant (BTG) |
|---------|-----------------------|---|---------------------|---------------|------------------|
| 1       | Udangudi TPP Stage -I | TANGEDCO                                      | 2x660               | 1,320         | BHEL             |
| 2       | Bhusawal TPP Unit-6   | MAHAGENCO                                     | 1x660               | 660           | BHEL             |
| 3       | Patratu STPP Ph -I    | M/s Patratu Vidyut Utpadan Nigam Ltd. (PVUNL) | 3x800               | 2,400         | BHEL             |
| 4       | Panki Extn. TPP       | UPRVUNL                                       | 1x660               | 660           | BHEL             |
| 5       | Yadadri TPP           | TSGENCO                                       | 5x800               | 4000          | BHEL             |
|         |                       |   | <b>Total</b>        | <b>9040</b>   |                  |

#### 6.18 Environment Clearance to New Thermal Power Projects:

During the year 2017-18, Environment

Clearance was granted to 5(Five) Nos. projects totaling 10260 MW capacity as per details given below:

| List of Thermal Power Projects accorded Environment Clearance during 2017-18 |   |                 |   |               |                               |
|--|---|-----------------|---|---------------|-------------------------------|
| Sl. No.  | Name of Project                             | Capacity (MW)   | Developer   | State         | Date of Environment Clearance |
| 01.  | Yadadri Thermal Power Station - 5x800 MW    | 4000            | TSGENCO   | Telangana     | 29.06.2017                    |
| 02.  | Panki Ex tension Power Project 1x 660 MW    | 660             | UPRVUNL   | Uttar Pradesh | 29.06.2017                    |
| 03.  | Udupi TPP (Phase-II) 2x800 MW               | 1600            | M/s Udupi Power Corporation Limited (UPCL)                                    | Karnataka     | 01.08.2017                    |
| 04.  | Godda TPP - 2x800 MW                        | 1600            | M/s Adani Power (Jharkhand) Ltd   | Jharkhand     | 31.08.2017                    |
| 05.  | Patratu TPP at Patratu, Phase -I - 3x800 MW | 2400            | M/s Patratu Vidyut Utpadan Nigam Ltd. (PVUNL) JV of NTPC & Govt. of Jharkhand | Jharkhand     | 07.11.2017                    |
|  | <b>Total Capacity</b>                       | <b>10260 MW</b> |   |               |                               |

## 6.19 Fly Ash Generation at Coal/Lignite based Thermal Power Stations & its Utilization

### 6.19.1 Monitoring by CEA

Central Electricity Authority has been monitoring, since 1996, fly ash generation and its utilization at coal/ lignite based thermal power stations in the country. Data on fly ash generation and utilization is obtained from thermal power stations on half yearly and yearly basis. The said data is analyzed and reports bringing out the status of fly ash generation as well as its utilization are prepared. The Reports are forwarded to Ministry of Power and Ministry of Environment, Forest & Climate Change.

The said report is now also being uploaded on website of CEA for bringing the information in public domain.

### 6.19.2 MoEF & CC Notification on Fly Ash Utilization

To address the problem of pollution caused by fly ash and to reduce the requirement of land for disposal of fly ash, MoEF&CC issued notification dated 14<sup>th</sup> September, 1999 on fly ash utilization and subsequently issued amendments to the said notification on 27<sup>th</sup> August, 2003, 3<sup>rd</sup> November, 2009 and 25<sup>th</sup> January, 2016. The 3<sup>rd</sup> November, 2009 notification had stipulated targets for utilization of the fly ash, so as to achieve 100% utilization by all thermal power stations in a phased manner - existing thermal power units within five years and those commissioned after 3<sup>rd</sup> November, 2009 within four years. However, the goal of 100% fly ash utilization could not be achieved within the stipulated timeline. In view of the same, further notification in January, 2016 has followed.

This latest MoEF&CC's Notification of 25<sup>th</sup> January, 2016, emphasizing towards the efforts in the direction of enhancing gainful utilization of fly ash, stipulates mandatory uploading on TPS's website fly ash availability during the current month including stock

in ash pond.; increase in mandatory jurisdiction of area of application from 100 km to 300 km; cost of transportation of fly ash to be borne entirely by TPS up to 100 km and equally shared between user and TPS for more than 100 km and up to 300 km; and mandatory use of fly ash based products in all Government schemes or programmes e.g. Pradhan Mantri Gramin Sadak Yojana, Mahatma Gandhi National Rural Employment Guarantee Act, 2005, Swachh Bharat Abhiyan, etc.

### 6.19.3 Fly Ash as a Resource Material

Traditionally, ash (Fly ash and bottom ash) generated at coal/lignite based thermal power stations has been disposed off in ash ponds as waste material. Ash has now been recognized as a 'resource material' and 'useful commodity' capable of being utilized in most of the civil construction activities in an eco-friendly manner. Fly ash has pozzolanic properties and has large number of applications in various construction activities.

### 6.19.4 Important Areas of Ash Utilization

The important areas in which ash is being presently utilized are as under:

- In manufacturing of Portland Pozzolana cement;
- As a part replacement of cement in concrete;
- In making fly ash based building products like bricks, blocks, tiles, road blocks, Kerb Stones etc.;
- In the construction of roads, flyovers, embankments, ash dykes etc.;
- In construction of Roller Compacted Concrete Dams in Hydropower Sector;
- In reclamation of low lying areas and raising of ground level;
- Backfilling/stowing of mines;
- In agriculture and waste-land development.

### 6.19.5 Status of Ash Generation & Utilization for the Year 2016-17

The report for the year 2016-17 bringing out

the status of fly ash generation and its utilization including status of compliance of MoEF&CC's notification has been prepared.

#### (A) Brief Summary

As per data received from coal/lignite based thermal power stations for the Year 2016-17, the present status of fly ash generation & utilization is given in the table below:

| Description  | Status in Year 2016 -17 |
|--|-------------------------|
| Nos. of Coal/Lignite based Thermal Power Stations from which data was received | 155                     |
| Data received for an installed capacity (MW)                                   | 157377.00               |
| Coal consumed (Million ton)  | 509.46                  |
| Ash content (%)  | 33.22                   |
| Fly Ash Generation (Million ton)   | 169.25                  |
| Fly Ash Utilization (Million ton)  | 107.10                  |
| Percentage Fly Ash Utilization   | 63.28                   |

It may be seen from above that 63.28 % of total ash produced at coal/lignite based thermal power stations has been gainfully utilized in various construction activities and other modes of utilization during 2016-17. This is on higher side from the previous year i.e. 2015-16.


#### (B) Modes of Ash Utilization during year 2016-17

The major modes in which ash was utilized during the year 2016-17 is given in table below:

#### MAJOR MODES OF FLY ASH UTILIZATION DURING THE YEAR 2016-17

| Sl. No.      | Modes of utilization          | Fly ash utilization in the Year 2016-17 |                |
|--------------|-------------------------------|---|----------------|
|              |                               | Quantity (Million-ton)                  | Percentage (%) |
| 1            | Cement                        | 40.5869                                 | 23.98          |
| 2            | Bricks & Tiles                | 14.9110                                 | 8.81           |
| 3            | Ash Dyke Raising              | 11.8888                                 | 7.02           |
| 4            | Mine filling                  | 11.7827                                 | 6.96           |
| 5            | Reclamation of low lying area | 11.0392                                 | 6.52           |
| 6            | Others                        | 7.9840                                  | 4.72           |
| 7            | Roads & flyovers              | 6.1942                                  | 3.66           |
| 8            | Agriculture                   | 1.9243                                  | 1.14           |
| 9            | Concrete                      | 0.7647                                  | 0.45           |
| 10           | Hydro Power Sector            | 0.0197                                  | 0.01           |
| 11           | Unutilized Fly Ash            | 62.1577                                 | 36.72          |
| <b>Total</b> |                               | <b>169.2534</b>                         | <b>100.00</b>  |

The utilization of fly ash in various modes in percentage during 2016-17 in the form of a pie-diagram is given below:




The maximum utilization of fly ash during 2016-17 to the extent of 23.98 % has been in Cement sector, followed by 8.81 % in making of bricks & tiles, 7.02 % in ash dyke raising, 6.96 % in mine filling, 6.52 % in reclamation of low-lying area, 3.66 % in roads & flyovers, etc.

**Utilization during the period from 1996-97 to 2016-17**

The fly ash utilization has increased from 6.64 million tonnes in 1996-97 to a level of 107.10 million tonnes in 2016-17. A graph showing about progressive trend in fly ash generation and its utilization for the period from 1996-97 to 2016-17 is given below.

**6.19.6 Progressive Fly Ash Generation &**



It may be seen from above graph that utilization of fly ash in terms of quantity has been increasing over the years except that there was a dip in fly ash utilization during 2010-11 which has picked up during 2011-12 and 2012-13 and again a slight drop during 2013-14 it picked up in 2014-15 and 2015-16 with miniscule drop in the year 2016-17.

#### 6.19.7 Conclusion

The highest level of fly ash utilization of about 63.28% is achieved during the year 2016-17. It would require a lot of efforts to achieve the target of 100% utilization of fly ash by 31<sup>st</sup> December, 2017 as stipulated in MoEF's Notification of 25<sup>th</sup> January, 2016. The stipulations of notification of 2009 and recent amendment should be effectively implemented. As per this report about 36.72% un-utilized fly ash is lying dumped at the various Thermal Power Stations in the country.

#### 6.19.8 Web Based Monitoring System And A Mobile Application For Utilization Of Fly Ash

Annual Fly ash utilization has remained about 60% of the fly ash generated and therefore, it has become a matter of concern in view of its adverse environmental effect and its progressive accumulation may lead to a situation when ash pond may not be in a position to accommodate fly ash further. In view of seriousness and urgency of the issue, NITI AAYOG has convened several meetings on "Policy Framework on Utilization of Fly Ash and Slag". During one of its meetings on 17.03.2017, NITI AAYOG desired an online repository of the fly ash generated by thermal power plants indicating the following parameters:

- Cumulative amount of fly ash available in the ash ponds as on 31.3.2017
- Quantum of fly ash generated for the respective month (ex. For the month of April 2017)
- Number of ash ponds available and their approved capacity in metric tonne.

- Cumulative stock of fly ash available in the ponds for month as on 30<sup>th</sup> April 2017.
- Total quantum of fly ash disposed to the consuming industries, which is located within the vicinity of 100 kms, 101-500 kms, etc. along with the details of the consumers. In this detail, it should also be indicated whether the transportation was paid by the thermal power or not. Similarly, it should also indicate whether fly ash has been given free or it has been charged. If it has been charged, then the rate should also be indicated for each consumer.
- Balance stock of fly ash available in the ash ponds for month ending April, 2017.

A web based monitoring system and a mobile application have been developed. Login ID and Password have been issued to Power Utilities/Thermal Power Stations for uploading the monthly data of fly ash generation & utilization. A workshop for facilitating the users had been organized on 28<sup>th</sup> August, 2017. Further, two video conferences were organized on the above issues on dated 12.09.2017 & 05.10.2017 with the help of M/s NTPC Limited. Feeding of data by the Thermal Power Stations on the web based monitoring system is under progress. The mobile application "ASH TRACK" is a GIS-based interface between fly ash generators and potential fly ash users. It contains useful information regarding quantum of fly ash available at nearby TPS, contact details of nodal officer of concerned TPS, etc.

### 6.20 PERFORMANCE AWARDS IN POWER SECTOR

#### 6.20.1 Comprehensive Award Scheme for Power Sector

An award scheme was introduced by the Ministry of Power in 1983 for recognizing the meritorious performance of thermal power stations. The scheme was modified over the years in view of evolving requirements. In 2004-05, Comprehensive Award Scheme was introduced by the Ministry of Power covering

various facets of power sector with the objective of developing a spirit of competitiveness among the generating stations in thermal, hydro & nuclear generation, transmission & distribution utilities in operation & maintenance and early completion of thermal, hydro & transmission projects. To promote, encourage and recognize the efforts of rural distribution franchisees, an award was introduced in 2007-08. Recognizing the need to promote environment protection, a category of award was introduced in 2008-09 to be given to best performing coal/lignite-based thermal power station for environment management. Keeping in view the technological developments in equipment and machinery, construction techniques of power projects and transmission lines, recognizing need to

promote environmental protection, to further encourage improvement in operational performance, huge capacity addition through super critical units, the comprehensive award schemes was revised and approved by Ministry of Power for the year 2013-14 onwards. As regards award scheme to be followed for the year 2015- 16, some modifications have been proposed in 7 nos. of schemes concerned Divisions as felt necessary. As regards number of awards, it is to mention that maximum possible number of awards for year 2015- 16 shall increase from previous year's 38 nos. to 40 nos. plus 1 consolation award.

The Comprehensive Award Scheme includes the following ten(10) categories of award with the respective number of awards:

| <b>Award Schemes</b>  | <b>No. of Awards</b> |
|---|----------------------|
| • Thermal power station performance                             | - 8                  |
| • Early completion of Thermal Power Projects                    | - 9                  |
| • Hydro Power Station Performance                               | - 3                  |
| • Early Completion of Hydro Power Projects                      | - 3                  |
| • Transmission System Availability                              | - 3                  |
| • Early Completion of Transmission Projects                     | - 6                  |
| • Nuclear Power Station Performance                             | - 1+1*               |
| • Performance of distribution companies                         | - 3                  |
| • Performance of Rural Distribution Franchises.                 | - 3                  |
| • Environment Management for coal based Thermal Power Stations. | - 1                  |
| <b>Total Award -</b>  | <b>40+1*</b>         |

**\*Consolation award**

### **6.20.2 Awards for the year 2015-16**

The data/inputs received from various power utilities/ Organizations in respect of individual award schemes for the year 2015-16 have been evaluated by CEA & recommended list of awardees has been prepared and sent to Ministry of Power. The award distribution function is yet to be held for the year 2014-15 & 2015-16.

### **6.21 Private Sector participation in Power Sector**

With the enactment of Electricity Act 2003, a new system has evolved with the active participation of Private/Independent power producers (IPPs) in the power sector. This Act has created a legal framework for development of Electricity supply industry through liberalized Generation, Power market development and provided open access to the Generators and Consumers. In order to achieve the set objectives, the Government has issued National Electricity Policy and Tariff Policy. For the purpose of facilitating



procurement of power through competitive bidding, the Government has also issued guidelines for tariff based competitive bidding. The Standard Bid Documents for procurement of power under long term and medium term Power Purchase Agreements were issued for Case-I and Case-II bidding during 2005. Many power utilities in states i.e.

Haryana, Punjab, Uttar Pradesh etc. have already taken initiative to invite bids for development of thermal power projects through tariff based competitive bidding. List of such Case -II tariff based competitive bidding projects, totaling to 7,800 MW since 2005 is given hereunder :

### Projects Commissioned / Under Construction based on Tariff Based Competitive Bidding (Case-II) by States

| S.No.                | Name of the Project | Location                 | Capacity(MW)   | Remarks                  |
|----------------------|---------------------|--------------------------|----------------|--------------------------|
| <b>Haryana</b>       |                     |                          |                |                          |
| 1)                   | Jhajjar             | District Jhajjar         | 2x660          | Project is commissioned. |
| <b>Punjab</b>        |                     |                          |                |                          |
| 2)                   | Talwandi Saboo      | District Mansa           | 3x660          | Project is commissioned. |
| 3)                   | Rajpura             | Rajpura District Patiala | 2x660          | Project is commissioned. |
| <b>Uttar Pradesh</b> |                     |                          |                |                          |
| 4)                   | Anpara 'C'          | Distt. Sonebhadra        | 2x600          | Project is commissioned. |
| 5)                   | Bara TPP            | Distt. Allahabad         | 3x660          | Project is commissioned. |
| <b>Total</b>         |                     |                          | <b>7800 MW</b> |                          |

Many State Utilities and their Discoms have contracted substantial amount of power from IPPs through Case -I bidding. The Government has also set up Special Purpose Vehicles under Power Finance Corporation for collective procurement of power on behalf of the distribution utilities by inviting tariff based bids for supplying power from Ultra Mega Power Projects.

Private sector is showing keen interest in investing and setting up new generating facilities. As a result, the scenario in the Power sector appears quite promising and Government of India is making its best efforts to facilitate Independent Power Producers to overcome various challenges in the way of

project implementation. The Private Sector contributed 2670 MW (Thermal-1970 MW & Hydro-700 MW) to generation capacity during 10<sup>th</sup> Plan Period (2002-07), whereas during 11<sup>th</sup> Plan period (2007-12), the capacity of 23,012 MW (Thermal- 21,720 MW & Hydro- 1292 MW) was commissioned, contributing around 41.87% of total conventional capacity addition. During 12<sup>th</sup> Plan, Private Sector contributed 54279 MW (Thermal 53660 MW and Hydro 619 MW) comprising of 55.8% of total conventional capacity. During the year 2017-18 upto 31.03.2018, Private Sector has contributed 3985 MW (Thermal- 3780 MW & Hydro-205 MW) comprising of 42 % of total conventional capacity addition.

\*\*\*\*\*

## CHAPTER - 7

### DISTRIBUTION AND RURAL ELECTRIFICATION

#### 7.1 Preparation and Monitoring of 24x7- Power For All (PFA) Documents

Government of India had taken up a joint initiative with all States/UTs and prepared States /UTs specific documents for providing 24x7 power supply to all households/homes, industrial & commercial consumers and adequate supply of power to agricultural consumers as per State policy. This initiative aimed at ensuring uninterrupted supply of quality power to existing consumers and providing access to electricity to all unconnected consumers by 2019 in a phased manner except in Bihar and Assam, in which access to unconnected households have been proposed beyond Financial Year 2019.

All these action plan documents were prepared by the Consultants with the guidance of the Committee under Central Electricity Authority (CEA) have been approved and signed by the respective States and UTs between September 2014 to April 2017, and the roll-out plans as identified in these documents are under various stages of implementation by them. All these signed copies of action plan documents are available in the website of Powermin.gov.in and powerforall.co.in.

For monitoring of implementation of Roll out plans/action plans as envisaged in 24x7 PFA documents and to facilitate the States/UTs in reporting the same, MOP has on 8<sup>th</sup> December 2016, set up a Central Programme Monitoring Unit for Power For All (CPMU-PFA), which comprises of the members from REC, NHPC and PFC (with REC Ltd as Nodal officer).

Further, in order to address the implementation issues of Rollout Plan, MoP has also set up an Inter-Ministerial group comprising of Members from Ministry of Power (MoP), Ministry of Coal (MoC), Ministry of Environ-

ment & Forest (MoEF), Ministry of New and Renewable Energy (MNRE), Ministry of Railways (MoR), Ministry of Petroleum & Natural Gas (MoP&NG), Ministry of Agriculture (MoA), Bureau of Energy Efficiency (BEE), Department of Expenditure DoE), Central Electricity Authority (CEA), Rural Electrification Corporation (REC) and Power Finance Corporation (PFC). As a member of Monitoring committee of this initiative, CEA has been attending the meeting of MOP regular basis and contributing for sorting out the issues for achieving the goal of 24x7 power for all.

#### 7.2 Development of SMART GRID in the Country

- Govt. of India launched 'National Smart Grid Mission (NSGM)' in March, 2015 for planning and monitoring the implementation of policies & programmes related to smart grid activities in India.
- The NSGM has a three-tier structure i.e. Governing Council, headed by the Hon'ble Minister of Power, Empowered Committee, headed by the Secretary (Power) and Technical Committee headed by the Chairperson, CEA. The Technical Committee is supporting NSGM on technical aspects, standards development, technology selection guidelines and other technical matters and preparation of model RfP document for Smart Grid project. DP&D Division is the nodal division in CEA dealing with development of smart grid in the country and also assists the technical committee of NSGM in technical examination and evaluation of Smart Grid Projects. Under ongoing NSGM, 3 DPRs for Smart Grid in Cities of Chandigarh, Amravati and Nagpur have been sanctioned at approved project cost of Rs.257.78 crores. Additionally, 10 smart Grid pilot projects are under implementation in the Country.
- To help the distribution utilities for

implementing Smart Grid projects in the Country, NSGM in consultation with CEA and other stake holders have finalized model RfP document for smart metering projects in the Country.

- Proposals received from Korean side for advanced metering infrastructure (AMI) project in cities of Kerala and UT of Chandigarh have been examined.
- A Committee under CE (DP&T) has been constituted by MoP to study the issue of Opex based solutions with special reference to cloud based/server based solutions through GOI capital grants.
- CE(DP&T) is a member of the Committee constituted by MoP to look into the issues regarding smart meter rollout in the Country.

### 7.3 Award Scheme for Meritorious performance of Distribution Companies and Rural Distribution Franchisees

#### ◆ Award Scheme for Distribution Companies

Govt. of India has instituted award schemes for various segments of the Power Sector from the year 2004-05 onwards. The scheme was reviewed during 2016-17 to incorporate the features of various ongoing schemes of Govt of India, and at the same time, to promote more competition among the Distribution companies, the existing award scheme has been segregated for Govt Discoms and Private Discoms to be implemented from 2016-17 and onwards. The eligibility criteria for Private Discoms is made stringent than Govt discoms. The revised award scheme is linked to the performance of Distribution Companies based on various parameters such as:

- AT&C losses
- Financial Turnaround
- Metering of Feeders, DTs and consumers
- Power supply and Reliability
- Consumer care and safety

- Demand Side Management.

On the basis of the final approved scheme, data on above parameters is requested from Distribution Companies across the country. The data received is analyzed and evaluated for the performance of Distribution Companies. Under the scheme for the year 2015-16, the recommendation was submitted to the Nodal officer for onwards submission to MOP.

The data for the performance in the year 2016-17 is being received from Distribution Companies and the analysis for recommendations for awards is under progress.

#### ◆ Award Scheme for Rural Distribution Franchisees (RDFs)

From the year 2007-08 onwards, another award scheme was instituted by Ministry of Power in the area of Distribution for giving awards to Rural Distribution Franchisees for their performance based on various parameters such as:

- Type of Activity undertaken by RDF
- Metered service connections
- Revenue Management
- AT&C Losses.

This scheme is also reviewed every year and the modifications proposed are sent for the approval of Chairperson, CEA. On the basis of final approved scheme, data is requested from Distribution Companies across the country. Under the scheme for the year 2015-16, the recommendation was submitted to the Nodal officer for onwards submission to MOP.

The data for the performance of Rural Distribution Franchisees in the year 2016-17 is being received from Distribution Companies and the analysis for recommendations for awards is under progress.

### 7.4 Research & Development Projects in the Distribution Sector

As a nodal division for examination of distribution sector R&D projects, DP&D Division examined R&D Projects during the year received from CPRI.

## 7.5 Integrated Power Development Scheme (IPDS)

Integrated Power Development Scheme (IPDS) was launched by MoP on 3<sup>rd</sup> December 2014 with the following scope of components in Urban Areas:

- (i) Strengthening of sub-transmission and distribution networks;
- (ii) Metering of distribution transformers / feeders / consumers;
- (iii) IT enablement of distribution sector and strengthening of distribution network for completion of the targets laid down under erstwhile Restructured Accelerated Power Development & Reforms Programme (R-APDRP) for 12<sup>th</sup> and 13<sup>th</sup> Plans.

The components at (i) and (ii) above have an estimated outlay of Rs. 32,612 crore including a budgetary support of Rs. 25,354 crore from Government of India during the entire implementation period.

The component at (iii) above is a component of R-APDRP, which was approved by Govt. of India for continuation in 12<sup>th</sup> and 13<sup>th</sup> Plans amounting to Rs. 44,011 crore including a budgetary support of Rs. 22,727 Crores has been subsumed in this scheme.

This outlay will be carried forward to the new scheme of IPDS in addition to the outlay

indicated above.

The scheme of R-APDRP programme is to facilitate State Power Utilities to reduce the level of AT&C losses to 15%. The programme has two major components under which the investments through this scheme will lead to reduction in loss level. **Part-A (IT enablement and SCADA)** includes projects for establishment of Information Technology based energy accounting and audit system leading to finalization of verifiable base line AT&C loss levels in the project areas, and **Part-B (network strengthening)** for strengthening of distribution networks. The total outlay for the programme is Rs 51,577 crore, out of which the major outlay is Rs. 10,000 Crores for **Part-A** and Rs. 40,000 Crores for **Part-B** of the scheme.

As a member of Monitoring committee of this scheme, CEA has been attending meeting at MOP and providing requisite inputs and support for implementation. The achievement/Progress of the schemes (based on MIS of IPDS as on 31.03.2018) is given as below:

### a) Component wise Status of IPDS;

#### i) Strengthening of sub-Transmission and Distribution:

| Item                         | No. of Circles covered | Towns Covered | Sanctioned Project Cost (in Crores) | Amount Released (in Crores) | Status of Projects                  |
|------------------------------|------------------------|---------------|-------------------------------------|-----------------------------|-------------------------------------|
| Strengthening & Augmentation | 545                    | 3618          | 26637.17                            | 4976.76<br>(18.68 %)        | At various stages of implementation |

#### ii) IT Phase-II

| States/UTs | Utility/ DISCOMs | Towns Covered | Total Approved Cost (Rs. Crores) | Fund Released (Rs. Crores) | Status of Work    |
|------------|------------------|---------------|----------------------------------|----------------------------|-------------------|
| 21         | 43               | 1912          | 961.15                           | 10.23<br>(1.06 %)          | Yet to be awarded |

## iii) Metering of Consumers, Feeders and Distribution transformers

| State | Utility | Consumer Meter (No) |           |           | Feeder / DT / Boundary Meter (No) |           |          | Smart Meter (No) |           |          | Pre-Paid Meter (No) |           |          |
|-------|---------|---------------------|-----------|-----------|-----------------------------------|-----------|----------|------------------|-----------|----------|---------------------|-----------|----------|
|       |         | Sanctioned Qty      | Award Qty | Achieved  | Sanctioned Qty                    | Award Qty | Achieved | Sanctioned Qty   | Award Qty | Achieved | Sanctioned Qty      | Award Qty | Achieved |
| 32    | 54      | 8,531,109           | 8,602,673 | 1,886,089 | 205,281                           | 109,773   | 5,691    | 156,970          | 500       | 0        | 155,485             | 40,855    | 2,007    |

## iv) Solar Panels

| Solar Panels (KWp) |           |          |
|--------------------|-----------|----------|
| Sanctioned Qty     | Award Qty | Achieved |
| 38,316             | 46,748    | 11,174   |

## b) R-APDRP component:

| RAPDRP Status                        | Nos. of Towns covered | Approved Cost (Rs crores) | Disbursement (Rs. Crores) @ | Status of Projects/Go-Live  |
|--------------------------------------|-----------------------|---------------------------|-----------------------------|---|
| Part-A RAPDRP(IT Enabled System)     | 1405                  | 5374.56                   | 3525.17 (65.01 %)           | Go-Live - 1376  |
| Part-A RAPDRP(SCADA)                 | 59                    | 1251.13                   | 445.90 (34.97 %)            | 59 awarded/52 Control Centres Commissioned and 25 SCADA completed |
| Part-B RAPDRP(Network Strengthening) | 1227                  | 30897.47                  | 6491.23 (20.94 %)           | 1218 Awarded/ 1187 Completed                                      |
| Total                                | ---                   | 37,523.16                 | 10462.30 (27.88 %)          | ---   |

@ includes PMA charges

### 7.6 Association with the Central Team constituted by MHA for On-The-Spot Assessment of Damage Caused by Natural Calamities in Various States

- ❖ Officers from DPD division were associated as a member of the Central Team constituted under Team Leader JS(MHA)/ JS (Min of Agriculture) for on-the-spot assessment of Damages caused by natural calamities in various states and attended various Inter-Ministerial Group (IMG) meetings held in MHA / Ministry of Agriculture to finalize the recommendations of the Central Team regarding Calamity Relief Fund(CRF) / National Calamity Contingency Funds (NCCF).

- ❖ Report of the power sector damages for the State of Kerala, Tamil Nadu, Assam, Arunachal Pradesh & Chattisgarh caused by natural calamity were submitted to MHA.

- ❖ Inputs given in respect of distribution sector for the review of National Disaster Management Plan, 2015.

### 7.7 Amendment in existing Regulations

Review of (a) CEA (Construction of Electrical Plants and Electric Lines) Regulation, 2010 and, (b) CEA (Installation & Operation of Meters) regulation 2006 were taken up and under various stages of completion. Amendments in these regulations are in progress.

## 7.8 Works Related to Union Territories (UTs) & States

The following works pertaining to UTs were taken up & completed during 2017-18:

### 7.8.1 UT of Daman & Diu

- Technical clearance for the scheme for establishment of 66/11 KV, 2x20 MVA S/S at Panchal Industrial Area in Daman was accorded.
- Technical clearance of the scheme for normal development and release of service connections (ND&SC) for UT of Daman & Diu during 2017-18.
- Scheme for installation of 6.8 MW wind power plant at Diu, scheme for replacement of 4 No of old 66/11 KV, 10 MVA Power Transformers and scheme for erection of 66 KV D/C line from Kachigam S/S to Zari S/S in UT of Daman & Diu were examined.

### 7.8.2 UT of Andaman & Nicobar Islands

- Ministry of Power vide OM No. 21/2/2014-OM, dated 29<sup>th</sup> February, 2016 constituted a Committee with members from CEA, PGCIL & POSCO to study grid related issues in Andaman and Nicobar Islands due to new solar projects and feasibility of setting up of an Energy Management Center (EMC). The Committee submitted its report to MOP in May 2016. As directed by MoP, the committee finalized additional report on optimal energy mix in Port Blair, A&N Islands and submitted to MOP during 2017-18.
- Technical proposal of A&N Admn for establishing Hybrid Energy Island initiative for replacement of existing diesel Power Plant in Chatham under JICA funding was examined.
- To mitigate the power crisis in Port Blair, Hon'ble MoS for Power &

MNRE took a meeting on 10.1.2018 with Hon'ble LG, other senior officers at A&N Islands and CEA. Based on the recommendation of the committee of CEA, NTPC & PGCIL, it was decided in the meeting that NTPC would construct a 50 MW LNG based power plant and 25 MW solar power plant and NLC Ltd. would construct a 25 MW solar power plant at Port Blair.

### 7.8.3 UT of Puducherry

- DPR for improvement in Distribution system in UT of Puducherry under JICA funding was examined and technical concurrence of CEA was conveyed.

### 7.8.4 UT of Lakshadweep

- Tender documents for procurement of Smart Meters for Kavaratti Islands, UT of Lakshadweep was examined.

### 7.8.5 Technical Appraisal of Distribution Schemes of States

- Distribution project proposal along with cost estimates as submitted by Govt. of Meghalaya under JICA proposal was examined.
- Examined the draft SFC memo on the scheme for setting up of 7 MW SPV projects with battery storage each in Leh and Kargil under J&K PMDP.

## 7.9 Rural Electrification

### 7.9.1 Status of Rural Electrification in the Country

During 2017-18, total number of 4149 (including uninhabited villages) un-electrified villages and 90081 partially electrified villages have been electrified, and electric connections to 5041996 BPL households have been provided under Deendayal Upadhyaya Gram Jyoti Yojna (DDUGJY). Cumulatively, 597121 inhabited villages constituting 99.94 %, out of a total of 5,97,464 inhabited villages

in the country (as per 2011 census) have been electrified at the end of March 2018 leaving a balance of 343 (excluding uninhabited villages) villages for electrification.

As per the data furnished by State Govts, 646722 number of pumpsets/tubewells energized during 2017-18 and cumulatively, 21428411 pump sets/tube wells have been energized at the end of March 2018 in the Country. Overall status of Rural Electrification in the Country is shown under DDUGJY at Para 7.9.2.

The bar charts showing the Plan wise and State wise progress of Village Electrification and Pumpset Energisation as on 31.03.2018 are available at end of Chapter.

### 7.9.2 Deen Dayal Upadhyaya Gram Jyoti Yojna (DDUGJY)

Deen Dayal Upadhyaya Gram Jyoti Yojana (DDUGJY) was launched by MoP on 3<sup>rd</sup> December 2014 with the following components in Rural Areas:

- (i) Separation of agriculture and non-agriculture feeders facilitating judicious rostering of supply to agricultural & non-agricultural consumers; and
- (ii) Strengthening & augmentation of sub-transmission and distribution infrastructure in rural areas, including metering of distribution transformers/feeders/consumers;
- (iii) Rural Electrification for completion of the targets laid down under the erstwhile Rajiv Gandhi Gramin Vidyutikaran Yojana (RGGVY) for 12<sup>th</sup> and 13<sup>th</sup> Plans.

The components at (i) and (ii) of the above scheme have an estimated outlay of Rs. 43,033 crore including a budgetary support of Rs. 33,453 crores from Government of India during the entire implementation period. The scheme of RGGVY will get subsumed in this scheme as a separate Rural Electrification component {component (iii) above}, for which Government has already approved the scheme cost of Rs. 39,275 crore including a budgetary support of Rs. 35447 crores. This outlay will be carried forward to the new scheme of DDUGJY in addition to the outlay indicated as above.

Under the new scheme, 60% of the Project cost will be extended by Govt. of India as Grant in respect of States other than special category (85% for the Special Category States i.e. all North Eastern States including Sikkim, J&K, Himachal Pradesh, Uttarakhand). Minimum 10% (5% for Special Category States) shall be contributed through own sources by the State Govt./ State Power Utility and the balance 30% (10% for Special Category States) may be arranged through Loan or own sources by the State Govt./ State Power Utility. Additional grant upto 15% (5% in case of Special Category States) by conversion of 50% of loan component will be provided by Govt. of India on achievement of prescribed milestones such as timely completion, reduction in AT&C losses & upfront release of revenue subsidy by State Govt.

As a member of Monitoring committee of this scheme, CEA has been attending meeting at MOP and providing requisite inputs and support for implementation. The achievement/ Progress of the schemes (based on MIS of DDUGJY as on 31.03.2018) is given as below:

**Progress of RE Components of DDUGJY (including DDG)**  
(as per MIS of DDUGJY as on 31.03.2018)

| No. of Projects |                 | Funds (Rs. Crore) |                       | Un-electrified Villages (Nos.) |                        | Intensive electrification of Villages (Nos.) |                        | BPL HH Connections (Nos.) |                        |
|-----------------|-----------------|-------------------|-----------------------|--------------------------------|------------------------|--|------------------------|---------------------------|------------------------|
| Covered         | Closed          | Sanction          | Total Release         | Scope                          | Cumulative Achievement | Scope  | Cumulative Achievement | Scope                     | Cumulative Achievement |
| 5934            | 531<br>(8.95 %) | 108496.85         | 58963.46<br>(54.34 %) | 129064                         | 125895<br>(97.54 %)    | 780240                                       | 504644<br>(64.68 %)    | 39072502                  | 30510196<br>(78.09 %)  |

### 7.9.3 Decentralized Distributed Generation (DDG) Projects under RE component of DDUGJY (RGGVY)

Under RGGVY, there was a provision for Rs.540 crores during 11<sup>th</sup> plan for Decentralized Distributed Generation (DDG) which has been revised to Rs.1000 crores during 12<sup>th</sup> and 13<sup>th</sup> plan.

Decentralized Distribution Generation can be from conventional or renewable sources such as Biomass, Biofuels, Biogas, Mini Hydro, Solar etc. for villages where grid connectivity is either not feasible or not cost effective. As per 12<sup>th</sup> and 13<sup>th</sup> plan of RGGVY, DDG has been extended to grid connected areas to supplement the availability of Power in areas where power supply is less than six hours a day.

#### Status of DDG projects sanctioned under RGGVY/DDUGJY as on 31.03.2018:

Under DDG Projects of DDUGJY, 4377 projects covering 3379 un electrified villages, 4583 villages/hamlets covered and Nos. of Households 203166 covered (including BPL Household connections of 162096) in 14 States (Andhra Pradesh, Assam, Arunachal Pradesh, Chhattisgarh, Jharkhand, Karnataka, Kerala, Madhya Pradesh, Meghalaya, Odisha,

Telangana, Uttar Pradesh, Uttarakhand & Manipur) at an estimated cost of Rs. 1368.90 crores (release Rs.488.60 crores) have been sanctioned by the Monitoring Committee and out of which 2548 (58.21 %) projects have been commissioned.

### 7.10 Publication of Distribution Data regarding Reliability Index

As per the mandates available in clause 5.13.1 of National Electricity Policy (NEP), the Appropriate Commission is to regulate the utilities based on pre-determined indices on quality of power supply w.r.t. many parameters including frequency and duration of interruption of feeders. The clause 5.13.2 of NEP stipulates that Reliability Index (RI) of supply of power to consumers should be indicated by the distribution licensee. A road map for declaration of RI for all cities and towns upto the District Headquarter towns as also for rural areas, should be drawn by up SERCs. The data of RI should be compiled and published by CEA”.

Accordingly, based on the data furnished by Discoms/SERCs, the data of Reliability Indices viz System Average Interruption Frequency Index (SAIFI), System Average Interruption Duration Index (SAIDI) and RI for feeders (%) for all the distribution



companies/licensees covering all cities and towns up to the District Headquarter and also for rural areas for 2015-16 (revised) are compiled in the formats of CEA and published on website of CEA during July 2017. The data compilation for same for 2016-17 is under progress.

Further, to align with the requirement of Reliability Indices given in various Standards of Performance of SERCs, the formats for collection of RI data is modified and circulated to all Discoms/Power departments to be effective from 2017-18 and onwards.

### Saubhagya Scheme

Government of India has launched Pradhan Mantri Sahaj Bijli Har Ghar Yojana –“Saubhagya” on 11th October, 2017 with the objective to achieve universal household electrification by providing last mile connectivity and electricity connections to all households in rural and urban areas. This scheme has the fund outlay of Rs. 16,320 crore including a Gross Budgetary Support (GBS) of Rs. 12,320.00 crores from Government of India

Under Saubhagya, all the remaining 300 lakh (estimated) un-electrified households are targeted to be electrified (excluding non poor urban households) throughout the country by 31<sup>st</sup> March, 2019

As a member of Monitoring committee of this scheme, CEA has been attending meeting at MOP and providing requisite inputs and support for implementation. The achievement/Progress of the schemes (based on Suabhagya portal as on 31.03.2018) is given as below:

As on 30.03.2018, a total of 40,46,031 households have been electrified since the launch of the scheme on 11<sup>th</sup> October 2017 and 3,30,24,329 households (18.33 % of total 18,01,82,571 households) are balance for electrification. The statewise details are at **Annexure**. The balance households are targeted for completion by March 2019.

### Monitoring of projects under Prime Ministers development (PMDP) 2015 for J&K

Hon'ble Prime Minister on 07.11.2015 announced a Rs 80,000 crore development package for Jammu and Kashmir, including 11708 Crore package for augmentation of power infrastructure and distribution systems; solar power; small hydro projects. Out of the above package, Total amount sanctioned is Rs 2570.14 Crores for Distribution Strengthening in the state of J&K. The details of the project sanctioned by Government of India for as below:

- a) Rural Area: Projects for 21 districts amounting to Rs 1157.75 Crores for strengthening the Rural distribution area also includes electrification in shrines, Underground cable laying in Tourist Place, and electrical infrastructure in Industrial Area has been sanctioned, for which JKPDD & PGCIL are the nominated Project implementing Agency (PIA).
- b) Urban Area: Project for 12 circles amounting to Rs 1144.59 Crores for strengthening the Urban distribution area which includes establishment of 33 Nos of meter testing labs has been sanctioned, for which JKPDD & RECPDCL are the nominated PIA.
- c) Smart metering projects: Projects for providing meter to 2 lakh consumers at the cost of 126.54 Crores has been sanctioned, for which JKPDD & RECPDCL are the nominated PIA.
- d) Smart Grid projects: Projects worth Rs 141.26 Crores has been sanctioned and PGCIL is the PIA.

CEA is regularly monitoring the progress through PMA/PIA and sending the compiled report to Ministry of Power on monthly basis. All these projects are at various stages of tendering and awards for implementation.

**Annexure****Status of Households Electrification under Saubhagya Scheme(as on 31.03.2018)**

| State             | Total Households   | Electrified Households as on 10th Oct,2017 | Household Electrified w.e.f 11th Oct,2017 | Total Household Electrified, | Household Electrification (%) | Balance Un-electrified Households, Nos |
|-------------------|--------------------|--|---|------------------------------|-------------------------------|--|
| Uttar Pradesh     | 303,42,104         | 155,73,943                                 | 10,13,392                                 | 165,87,335                   | 54.67                         | 13754769                               |
| Maharashtra       | 140,01,920         | 135,58,912                                 | 1,65,565                                  | 137,24,477                   | 98.02                         | 277443                                 |
| West Bengal       | 146,59,597         | 141,68,789                                 | 1,94,153                                  | 143,62,942                   | 97.98                         | 296655                                 |
| Bihar             | 124,86,613         | 86,17,983                                  | 4,42,442                                  | 90,60,425                    | 72.56                         | 3426188                                |
| Madhya Pradesh    | 106,23,591         | 77,10,762                                  | 11,28,491                                 | 88,39,253                    | 83.20                         | 1784338                                |
| Andhra Pradesh    | 113,62,846         | 112,80,763                                 | 81,402                                    | 113,62,165                   | 99.99                         | 681                                    |
| Tamil Nadu        | 102,85,848         | 102,83,678                                 | 2,170                                     | 102,85,848                   | 100.00                        |  |
| Karnataka         | 93,83,498          | 87,27,711                                  | 59,134                                    | 87,86,845                    | 93.64                         | 596653                                 |
| Rajasthan         | 91,82,572          | 70,00,719                                  | 2,12,322                                  | 72,13,041                    | 78.55                         | 1969531                                |
| Odisha            | 85,05,179          | 52,44,064                                  | 1,35,336                                  | 53,79,400                    | 63.25                         | 3125779                                |
| Kerala            | 71,04,123          | 71,04,123                                  |   | 71,04,123                    | 100.00                        |  |
| Gujarat           | 65,29,055          | 65,13,307                                  | 15,748                                    | 65,29,055                    | 100.00                        |  |
| Telangana         | 59,71,952          | 55,74,499                                  | 23,803                                    | 55,98,302                    | 93.74                         | 373650                                 |
| Jharkhand         | 54,91,360          | 24,31,847                                  | 1,25,389                                  | 25,57,236                    | 46.57                         | 2934124                                |
| Assam             | 52,24,540          | 27,81,136                                  | 1,10,836                                  | 28,91,972                    | 55.35                         | 2332568                                |
| Chhattisgarh      | 49,73,713          | 43,04,608                                  | 1,54,562                                  | 44,59,170                    | 89.65                         | 514543                                 |
| Punjab            | 36,89,584          | 36,89,584                                  |   | 36,89,584                    | 100.00                        |  |
| Haryana           | 34,24,992          | 27,42,810                                  | 1,71,561                                  | 29,14,371                    | 85.09                         | 510621                                 |
| Uttarakhand       | 17,37,928          | 15,37,625                                  | 4,960                                     | 15,42,585                    | 88.76                         | 195343                                 |
| Himachal Pradesh  | 14,71,502          | 14,56,888                                  | 1,943                                     | 14,58,831                    | 99.14                         | 12671                                  |
| Jammu & Kashmir   | 12,73,430          | 10,07,155                                  |   | 10,07,155                    | 79.09                         | 266275                                 |
| Tripura           | 7,31,404           | 5,24,308                                   | 1,882                                     | 5,26,190                     | 71.94                         | 205214                                 |
| Meghalaya         | 4,63,022           | 3,23,755                                   |   | 3,23,755                     | 69.92                         | 139267                                 |
| Manipur           | 3,81,181           | 2,78,773                                   | 467                                       | 2,79,240                     | 73.26                         | 101941                                 |
| Arunachal Pradesh | 2,31,968           | 1,50,781                                   |   | 1,50,781                     | 65.00                         | 81187                                  |
| Nagaland          | 2,78,128           | 1,69,693                                   | 473                                       | 1,70,166                     | 61.18                         | 107962                                 |
| Goa               | 1,28,208           | 1,28,208                                   |   | 1,28,208                     | 100.00                        |  |
| Mizoram           | 1,10,386           | 99,430                                     |   | 99,430                       | 90.07                         | 10956                                  |
| Puducherry        | 95,046             | 94,704                                     |   | 94,704                       | 99.64                         | 342                                    |
| Sikkim            | 37,281             | 31,653                                     |   | 31,653                       | 84.90                         | 5628                                   |
| <b>Total</b>      | <b>1801,82,571</b> | <b>1431,12,211</b>                         | <b>40,46,031</b>                          | <b>1471,58,242</b>           | <b>81.67</b>                  | <b>3,30,24,329</b>                     |

(Source-Saubhagya Portal)

### 7.11 Conduct of Mock Test Exercise at Parliament House

To ensure reliability of power supply to Parliament house before onset of each Parliament session, Mock test exercises at CPWD 11 KV Parliament House S/S were organized by CPWD in presence of officers of CEA, CPWD & NDMC before the Monsoon, Winter and Budget Sessions of Parliament and the reports of the Mock Test Exercise were sent to MOP, CPWD & NDMC.

### 7.12 Assistance to BEE / REC / EESL

- a) Assisted BEE on technical issues in PAT-II scheme launched for Discoms

- b) Assisted REC in examination of SBD of DDUGJY/IPDS.
- c) Examined DPR of EESL for 2<sup>nd</sup> line of Credit for US \$ 500 million from ADB.


### 7.13 CERT-Distribution

Ministry of Power constituted CERT-Distribution under Chief Engineer(DPD) CEA to advise Discoms on cyber security issues.


A Cyber Crisis Management Plan (CCMP) for cyber security in distribution sector was prepared and circulated to all distribution companies to adopt and prepare their respective Crisis Management Plans.

\*\*\*\*\*

Villages Electrified Statewise (As on 31st March, 2018)




**No. of Villages Electrified Planwise (Cumulative)**




**PLAN PERIODS (ENDING MARCH)**

\* No. of Villages Electrified reduced to 489699 due to downward revision of data by U.P. as per the definition notified in October 1997  
 \*\* No. of Villages Electrified reduced due to revision of data by States as per 2001 census



No. of Pumpsets Energised Planwise (Cumulative)



## CHAPTER – 8

### DESIGN & ENGINEERING SERVICES

#### 8.1 Design & Engineering of Hydro Electric Projects

During the year 2017-2018, the design and engineering consultancy of electro-

mechanical works of the following HE Projects were carried out:

| Sl. No.          | Name of the H.E. Project | Executing Agency/ State | Capacity |
|------------------|--------------------------|-------------------------|----------|
| Main Consultancy |                          |                         |          |
| 1.               | Punatsangchhu –I HEP     | PHPA-I/ Bhutan          | 6x200 MW |
| 2.               | Punatsangchhu –II HEP    | PHPA-II/ Bhutan         | 6x170 MW |
| 3.               | Ganol HEP                | MePGCL*/ Meghalaya      | 3x7.5 MW |
| 4.               | THDC HEP's               | THDCIL                  | 2868 MW  |

\*Meghalaya Power Generation Corporation Ltd.

#### 8.2 Scrutiny/Examination/Preparation of DPRs of HE Projects

a) Chapters on Electro-Mechanical equipments, related drawings and bill of quantities of 23 nos. (22 nos. in India+ 1 no. in Nepal) of DPR of new H.E Projects aggregating to 17421 MW including clarifications/ drawings/ documents etc. as received from time to time were examined

and commented upon. General layout Plan/Salient features of new HEPs (Total 10 nos.) under Survey & Investigation (S&I) at pre-DPR stage aggregating to about 5738 MW were examined & commented upon. A list of these hydro-electric projects has been indicated below:

##### A. List of DPRs of new HEPs examined for E&M aspects during the year 2017-18

| S. No.                     | Name of the Project | State | Installed Capacity (MW) |
|----------------------------|---------------------|-------|-------------------------|
| a) Hydro Projects in India |                     |       |                         |
| 1.                         | Luhri               | H.P.  | 601                     |
| 2.                         | Parbati-II          | H.P.  | 800                     |
| 3.                         | Parbati-III         | H.P.  | 520                     |
| 4.                         | Sachkhas            | H.P.  | 267                     |
| 6.                         | Dugar               | H.P.  | 421                     |
| 7.                         | Reoli Dogli         | H.P.  | 430                     |
| 8.                         | Sunni Dam           | H.P.  | 355                     |
| 9.                         | Sawalkote           | J&K   | 1856                    |
| 10.                        | UJH Multipurpose    | J&K   | 212                     |
| 11.                        | Kirthai-I           | J&K   | 390                     |



|                                    |                                |                      |        |
|------------------------------------|--------------------------------|----------------------|--------|
| 12.                                | Bursar                         | J&K                  | 800    |
| 13.                                | Bowala Nand Prayag             | Uttarakhand          | 300    |
| 14.                                | Sirkari Bhyol Rupsiabagar      | Uttarakhand          | 120    |
| 15.                                | Goriganga –III A               | Uttarakhand          | 150    |
| 16.                                | Ken Betwa Link Project Phase-I | M.P.                 | 78     |
| 17.                                | Bina Complex HEP               | M.P.                 | 25     |
| 18.                                | Dibang MPP                     | Arunachal Pradesh    | 2880   |
| 19.                                | Oju Subansiri HEP              | Arunachal Pradesh    | 259.25 |
| 20.                                | Kamla HEP                      | Arunachal Pradesh    | 1800   |
| 21.                                | Magochu HEP                    | Arunachal Pradesh    | 96     |
| 22.                                | Par-Tapi Narmda Link Project   | Gujrat & Maharashtra | 21     |
| <b>b) Hydro Projects in Abroad</b> |                                |                      |        |
| 23.                                | Pancheshwar MPP                | Nepal                | 5040   |

**B. List of new HEPs under S&I stage which were examined for E&M aspects during the year 2017-18**

| S. No. | Name of the Project             | State             | Installed Capacity (MW) |
|--------|---------------------------------|-------------------|-------------------------|
| 1.     | Pauk HEP                        | Arunachal Pradesh | 145                     |
| 2.     | Myntdu Leshka ( Stage – II) HEP | Meghalaya         | 210                     |
| 3.     | Oju Subansiri                   | Arunachal Pradesh | (8x231.25 MW + 28 MW)   |
| 4.     | New Milling HEP                 | Arunachal Pradesh | 90                      |
| 5.     | Nakhtan HEP                     | H.P.              | 460                     |
| 6.     | Sunni Dam                       | H.P.              | 355                     |
| 7.     | Sirkari Bhyol Rupsiabagar       | Uttarakhand       | 120                     |
| 8.     | Goriganga-III A                 | Uttarakhand       | 150                     |
| 9.     | Bokang Bailing                  | Uttarakhand       | 330                     |
| 10.    | Sharavathy HEP                  | Karnataka         | 2000                    |

b) Preparation/Revision of Electro-Mechanical Chapter, Drawings and related Bill of Quantities for the following projects:

i) Kirthai-II HEP (6x140+2x35+2x10 MW), J&K

**8.3 Proposals for Foreign Assistance / Bilateral Co-operation.**

The material/inputs were provided for the proposal of bilateral co-operation with different countries in the field of hydro power development as and when received from various ministries as detailed below:

1. Switzerland
2. Serbia
3. Armenia
4. Tajikistan
5. Croatia
6. Vietnam
7. Russia
8. Afghanistan
9. Morocco
10. Colombia
11. Kyoto Protocol
12. China
13. Romania
14. Sri Lanka

#### 8.4 Scrutiny of Innovative Proposals/ Schemes

Various Innovative Proposals / Schemes received in this office were examined and commented upon. Some of the proposals received are as listed below:

- i.) Technical paper on “How Great are 3D Effects in Slope Stability Analysis”.
- ii.) Grievance Petition of Shri Girja Shankar Prasad for Production of Electricity without use of fuel.
- iii.) Grievance Petition of Sh. Naresh Jambhare No. PMOPG/E/2017/ 0409352 dated 30.07.2017 forwarded to CEA on 02.08.2017.
- iv.) Innovative proposal on a system for converting Electrical Power into rotational energy power through driving vehicles.
- v.) Innovative scheme regarding twin generators on single turbine common shaft.
- vi.) Email Petition of Sh. K NATARAJAN on

new invention of energy generation by pumping of water.

- vii.) Grievance Petition of Sh. Rabindra Nath Mandal dated 27.09.2017 forwarded to CEA on 04.10.2017.
- viii.) Article on “Tapping Hydropower potential”-Queries from Power Today Magazine.

#### 8.5 Miscellaneous Works

- i) Work of revision of Regulations under Electricity Act 2003 on the technical standards for construction of Hydro Electrical Plants, Safety requirements for construction, operation & maintenance of Hydro Power Plants was taken up and draft revised. Regulations were finalised for further comments/suggestion.
- ii) Participation in panel meeting of BIS for preparation/amendments in draft of various Indian standards as and when required.

#### 8.6 Design and Engineering of Thermal Projects

The design & engineering issues and assignments pertaining to thermal power plants/ projects as and when referred are taken up by the TCDD Division.

#### 8.7 Design and Consultancy Assignments (Civil Aspects) for Thermal/Hydro/Transmission Projects during 2017-18

TCD Division of CEA carried out the following specific works in respect of thermal/hydro/power transmission projects during 2017-18:

##### 8.7.1 Thermal Power Projects

###### (a) Wet-limestone based FGD Plant Retrofit

Draft Specification of Civil works portion of Wet-limestone based FGD retrofitting of thermal power plant was prepared.

**(b) Buxar Thermal Power Plant**

Draft PIB memo in respect of Investment approval for main plant construction was examined and necessary inputs were provided.

**8.7.2 Hydro Power Projects**

- (a) Punatsangchhu-I HEP (6 X 200 MW), Bhutan
- Analysis of Support Structure for Isolated Phase Bus Duct, Cast in-situ Footing Load test report at pothead yard dumping area, foundation load data of equipment have been examined and necessary advice was communicated to project Authorities.
- (b) Punatsangchhu-II HEP (6X170 MW), Bhutan
- Designs/drawings of Cable supporting structure, Test Cradle for Power House EOT Cranes, GIS hall EOT Crane were examined and necessary advice was communicated to Project Authorities.

**8.7.3 Transmission Line & Sub-Station Projects**

- (a) Compendium of Approved Design of Transmission Line Tower Foundation was prepared.

**8.8 Consultancy services and assistance to various Utilities by Power System Wing****(a) Power Development Department, Govt. of J&K :**

220kV and 132kV Transmission System covered under Hon'ble Prime Minister's Reconstruction Plan (PMRP) which includes number of Transmission Lines and Substations of 220kV and 132kV voltage levels.

- (i) Examination of Tower Structural drawings for leg extension

of 4.5m of 'DC' & 'DD' type towers for 132 kV D/C Bandipora – Badampora transmission line for PDD, J&K.

- (ii) Examination of drawings and details for 132 kV Multi circuit tower to be erected at 220/132/33 kV Grid Station Ramban .

**(b) Damodar Valley Corporation:**

Testing of 33 kV M/C 'C' type tower designed by CEA for DVC at CPRI, Bengaluru.

**(c) Technical Advice to MoP/CPSUs/ State Utilities/CPRI/BIS etc.**

Technical advice related to transmission system in the Country provided from time to time to MoP/ Power utilities/ CPSUs /State Utilities/ Other Ministries/ BIS/ CPRI/ CBIP/ IEEMA.

## CHAPTER – 9

## ECONOMIC AND COMMERCIAL ASPECTS OF POWER INDUSTRY

The Electricity Act, 2003 (hereinafter referred to as 'Act') was notified in June, 2003. The Act replaces the earlier three Acts, namely, the Indian Electricity Act 1910, Electricity (Supply) Act, 1948 and the Electricity Regulatory Commissions Act, 1998. As per the Act, CEA has, inter-alia, been entrusted with duties and functions relating to collection/recording of data/information relating to generation, transmission, distribution, trading and utilization of electricity and to carry out studies relating to cost, efficiency,

competitiveness etc. to evaluate the financial performance of the power sector.

### 9.1 Performance of State Power Utilities

#### 9.1.1 Average realization vis-à-vis Average Cost of Supply

The Table below gives the average cost of supply and average realization covering all sectors in the country on the basis of the data made available by various State Power Utilities:

#### Average Cost of Supply and Average Realization of Electricity from All Sectors

(Figures in paise /unit)

| Year    | Average Cost of Supply | Average Realization | Gap<br>(without Subsidy) |
|---------|------------------------|---------------------|--------------------------|
| 2013-14 | 519                    | 400                 | 119                      |
| 2014-15 | 521                    | 415                 | 106                      |
| 2015-16 | 543                    | 423                 | 120                      |

*Source: PFC Report on the Performance of the State Power Utilities for the years 2013-14 to 2015-16*

#### 9.1.2 Aggregate Losses

Various power utilities in the country have been suffering losses over the years. The losses incurred by the power

utilities (without accounting for subsidy) for the period 2013-14 to 2015-16 are indicated below

#### Aggregate Losses (without subsidy) of Power Utilities

| Year    | Losses (Rs. Crore) |
|---------|--------------------|
| 2013-14 | 1,03,298           |
| 2014-15 | 1,14,007           |
| 2015-16 | 1,47,298           |

*Source: PFC Report on the Performance of the State Power Utilities for the years 2013-14 to 2015-16*

#### 9.1.3 Financial health

The gap between average revenue

realization and average cost of supply remained constantly high over the years, causing erosion in the volume of internal

resources generation by the Distribution Companies (DISCOMs) and led many of them to virtual bankruptcy. The level of commercial losses of the DISCOMs/ utilities depend, inter-alia, on the unaccounted electricity losses, subsidies received towards sales to agriculture and domestic sectors, revenue generation through cross-subsidization etc. The Gross Subsidy on energy sales has been increasing over the years as an outcome of the policy of some of the States to provide electricity at subsidized rates to agriculture and domestic consumers.

Consequently, DISCOMs were unable to make complete payments to Central Power Sector Utilities (CPSUs) for purchase of power and coal, resulting in accumulation of huge outstanding amount. This has adversely affected the growth and performance of CPSUs. The payment deficit continues to rise and threaten the viability of the CPSUs. Further, the poor credit worthiness of DISCOMs has effectively blocked investments by the Private Sector despite the enabling and encouraging framework laid down by the Central Government. Even in the post reform period, the managerial and financial inefficiency in the state sector power utilities, has adversely affected capacity addition and system improvement programmes.

#### **9.1.4 Trend in Outstanding Dues Payable to CPSUs**

CEA has been monitoring the status of the outstanding dues payable by the DISCOMs to CPSUs. Based on the information / data received in CEA from the CPSUs, the total outstanding dues payable by various power utilities to CPSUs, is Rs.13785.97 Crore up to 31<sup>st</sup> March,2018. The details of outstanding dues payable by power utilities to CPSUs is given in **Annexure-9A**.

## **9.2 Electricity Tariff & Duty and Average Rates of Electricity Supply in India**

In-fulfillment of its obligation under Section 73(i) & (j) of the Electricity Act, 2003, CEA brings out a publication titled “Electricity Tariff & Duty and Average Rates of Electricity Supply in India”. The latest edition (March, 2017) contains information on retail electricity tariff applicable in various States / Utilities effective during the year 2016-17.

The publication provides assimilation of regulatory data on notified tariffs of various States/UTs, the estimated data on average rates of electricity supply & electricity duty for different categories of consumers, along with the summarized data on power supply schemes for special categories of consumers. It also provides the details of subsidy support given by the government to various categories of consumers. The estimated average rates of electricity published herein have been computed on the basis of Tariff Orders received from various Electricity Regulatory Commissions.

The effective rates for different consumer categories have been worked out assuming different energy consumption for various sanctioned load keeping in view the urbanization, increase in usage of electricity appliances and improvement in the standard of living. In the March, 2017 edition, tariff revisions subsequent to the last edition of the publication have been incorporated and tariff applicable in 45 Distribution Utilities have been indicated.

The sanctioned load and monthly energy consumption have been assumed for each category of consumer and considering the tariff notified by the respective Regulatory Commissions, the total amount payable by a particular category of consumer is worked out for the assumed load and monthly energy consumption. The Taxes and Duties are then added up to arrive at the average estimated rate of electricity supply in terms of Paise /kWh.

A statement indicating category-wise estimated average rates of electricity for various Distribution Utilities in the country is given at **Annexure-9B**.

### 9.3 References on techno-financial matters in power sector

During the year, comments / recommendations of CEA were furnished on the following important references on issues concerning financial/commercial matters of power sector :

#### i. Examination of Detailed Project Reports(DPRs) and Revised Cost Estimates(RCEs)–

- DPR of Dibang MPP (2880 MW) in Arunachal Pradesh -M/s NHPC.
- DPR of Mawphu HEP Stage-II (85 MW) in Meghalaya - M/s NEEPCO.
- DPR of Renuka Dam Project (40 MW) in Himachal Pradesh-M/s HPPCL.
- DPR of Sawalkot HEP (1856 MW) in J&K - M/s JKPDCL.
- DPR of Tel Multipurpose Project (18 MW) in Odisha – Govt. of Odisha.
- DPR of Reoli Dogli (430 MW) in Himachal Pradesh-M/s L&T Himachal Hydropower Ltd.
- DPR of Thana Plaun HEP (191 MW) in Himachal Pradesh - M/s HPPCL
- DPR of Attunli HEP(680MW) in Arunachal Pradesh - M/s AHEPCL
- RCE of Kishanganga HEP (330MW) - M/s NHPC Ltd.
- RCE of Tehri pumped storage plant HEP (1000MW) in Uttarakhand-M/s THDC
- RCE of Subansiri HEP (2000 MW) in Arunachal Pradesh -M/s NHPC

#### ii. Tariff for power stations of NPCIL for the period 1.4.2017 to 31.3.2022 -

- Tarapur Atomic Power Station

- Unit 1 & 2 and Unit 3 & 4
- Rajasthan Atomic Power Station Unit 2,3 & 4 and Unit 5 & 6
- Madras Atomic Power Station Unit 1&2
- Narora Atomic Power Station Unit 1 & 2
- Kaiga Atomic Power Station Unit 1,2,3 & 4

#### iii. Standing Committee on Energy –

- Examination of the subject “Electricity Policy-A Review”.
- Final Action taken on the recommendation contained in the 29<sup>th</sup> Report of the Standing Committee.
- Selection of subjects for detailed examination during the year 2017.
- Examination of the subject “Evaluation of Power Transmission System / Stressed Assets / Non-Performing Assets in Power Sector”

#### iv. Examination of PIB Proposals -

- Naitwar Mori HEP (60 MW) in Uttarakhand - M/s SJVNL.
- PIB Memo for investment approval of Devasri HEP (252 MW) in Uttarakhand - M/s SJVNL.
- PIB Memo of Buxar TPP (1320 MW) in Bihar - M/s SJVNL.

#### v. Financial options for Pancheshwar Multipurpose Project.

#### vi. Proposal to grant exemption from transmission charges and losses to hydro capacity under construction -Assessment of financial impact.

#### vii. Guidelines for Tariff Based Competitive Bidding Process for procurement of power from grid connected wind power project.

- viii. Stressed Assets in Power Sector.
- ix. Draft EFC Memorandum in respect of grid and decentralized Solar PV applications scheme.
- x. Representations of various associations related to textile sector-reg. subsidy for power loom workers on power tariff.
- xi. Request of Indian Energy Exchange (IEX) for increase in threshold for foreign investment in Power Exchange.
- xii. FICCI's Submission on Revival of Hydro-Power Development.
- xiii. Waiver of inter-state transmission charges and losses on transmission of the electricity generated from solar and wind sources of energy under Para 6.4(6) of the revised Tariff Policy as per Order No. 23/12/2016-R&R dt. 30.09.2016 of MoP.
- xiv. Levy of service tax on activities integral to Generation & Distribution of Electricity.
- xv. Preparation of terms of references (TORs) by the programme implementing Ministries/Departments for carrying out impact evaluation of their programmes.
- xvi. Proposal for revival of hydro power sector in New Hydro Policy 2017.
- xvii. Explore possibility of Cheyyur UMPP.
- xviii. Power potential studies for Sapta Kosi High Dam Multipurpose Project in Nepal.
- xix. Impact of closure of generating units due to non-installation of Flue Gas Desulphurization (FGD) equipments.
- xx. Reference from M/s. Lanco for amendment in short term guidelines used in DEEP e-bidding portal.
- xxi. Simplification of Tariff Categories and rationalization of retail tariff.
- xxii. Power Tariff fixation of Noa Dihing dam project in Arunachal Pradesh.
- xxiii. Fixation of tariff for Mangdechhu HEP (720 MW) in Bhutan.
- xxiv. Rationalisation of fuel cost for cost competitive thermal power generation in India.

#### 9.4 Standard Bidding Documents and Competitive Bidding Guidelines

##### (a) Standard Bidding Documents for UMPPs /Case-II

With a view to address the issues raised by the Association of Power Producers (APP) on the Model Bidding Documents (MBDs) issued on 21.09.2013 for UMPPs and other location specific projects under Case-II bidding route, the Ministry of Power had constituted an Expert Committee under the chairmanship of Shri Pratyush Sinha, former CVC on 28.01.2015 to review the same. The Committee is supported by the Ministry of Power, M/s PFC Consulting, CEA and Legal Consultants. The draft Bidding document for "Procurement of Power on a Long-Term basis for Ultra Mega Power Project sourcing coal from domestic Captive Coal Blocks" has been prepared and submitted during 2015-16. Subsequently, the draft bidding document for "Procurement of Power on a Long-Term basis for Ultra Mega Power Project based on imported coal" has also been prepared and submitted by the Committee. This year, the Committee has finalized bid document for Medium-Term procurement of power for

three (3) years through an aggregator.

**(b) Tariff Based Competitive Bidding Guidelines for Transmission Service**

Ministry of Power (MoP) had vide letter dated 31.08.2015 constituted a Committee headed by Member (E&C), CEA, to finalize the changes and revise the Standard Bidding Documents (SBDs) for transmission projects notified by MoP in October, 2008, mainly due to implementation of the transmission charge sharing Regulations (introduction of point of connection transmission charge), introduction of reverse auction through e-bidding, etc. The Committee has prepared the draft SBDs for inter-state transmission projects and submitted to MoP on 08.04.2016 for approval. The SBDs for intra-state transmission projects has also been prepared by the Committee and the draft documents submitted to MoP on 19.10.2016 for approval. As part of the SBD, Draft Implementation Agreement and Authorization Agreement were got developed by REC Transmission Projects Company Limited (RECTPCL). These documents were uploaded on CEA's website for comments of stakeholders. For wider discussion, meetings were held with Designated ISTS Customers (DICs), STUs and transmission developers on 23rd January, 2018 and 13<sup>th</sup> April, 2018. These documents are under finalization.

**9.5 Financial and Operational turnaround of Power Distribution Companies**

Ministry of Power had vide Office Memorandum (OM) dated 20<sup>th</sup> November 2015 announced UDAY (Ujwal DISCOM Assurance Yojana), a Scheme for the financial and operational turnaround of Power Distribution Companies (DISCOMs). The objective of the scheme is to improve the operational and financial efficiency of the State DISCOMs. One of the primary steps envisaged in the scheme for financial

turnaround was that a substantial debt of the state owned DISCOMs would be taken over by the States.

As per the UDAY scheme, for improving operational efficiencies, the participating States and utilities would have to follow the specified timeline of the targeted activities i.e. compulsory feeder and Distribution Transformer (DT) metering, consumer indexing & GIS mapping of losses, upgrade or change transformers, meters etc., smart metering, Demand Side Management (DSM), quarterly tariff revision, campaign to check power theft and assure increased power supply in areas where the AT&C losses reduce.

The outcome of operational improvements is measured through following indicators:

- (i) Reduction of AT&C loss to 15% in 2018-19 as per the loss reduction trajectory to be finalized by Ministry of Power and States, and
- (ii) Reduction in gap between Average Cost of Supply (ACS) & Average Revenue Realized (ARR) to zero by 2018-19 as finalized by MoP and States.

A Committee has been constituted by MoP vide OM dated 19.01.2016, under the Chairmanship of Secretary, MoP, to ensure close monitoring of performance under UDAY to prevent any slippage. Chairperson, CEA is also a Member of this Monitoring Committee of UDAY.

By 31<sup>st</sup> March, 2018, 32 States/UTs have signed MOUs and joined the UDAY. Out of this, 16 States are participating under UDAY for improvement of both operational and financial efficiency whereas another 11 States & 05 UTs are participating for improving operational efficiency only.

The achievement made under UDAY for operational improvement is as under:



- **Reduction of AT&C loss:** As against All India base year AT&C loss of 20.95% (31.03.2016), the target for 2016-17 was 18.38% whereas actual achievement was 20.31%.
- **Reduction in ACS (Average Cost of Supply)-ARR (Average Revenue Realized) gap:** As against All India base year ACS- ARR gap of Rs. 0.59 per unit (31.03.2016), the target for 2016-17 was Rs. 0.38 per unit whereas actual achievement was Rs. 0.41 per unit.

## 9.6 Economic Analysis of Policy Issues

CEA has been regularly providing analytical inputs on various policy issues referred by the Ministry of Power such as power sector performance, material for the President's Address to both the Houses of the Parliament during the Budget Session, material for the speech of Hon'ble Power Minister at different forums and material for Standing Committee on Energy related to various facets of power sector.

## 9.7 Compilation of Information on Power Purchase Agreement

The information on Power Purchase Agreement (PPA) of Independent Power Producers (IPPs) with their tied and untied capacity, has been compiled based on the information supplied by IPPs. The compiled information is being updated regularly. During the year 2017-18, the information for 115 IPPs with an installed capacity of 86,129 MW, having tied and untied capacity of 63,609 MW & 19,273 MW respectively has been compiled.

## 9.8 Reforms Monitoring Unit

Under Section 3 of the Electricity Act, 2003, the National Electricity Policy and Tariff Policy are notified by the Central Government in consultation with the State Governments and the Central Electricity Authority. In this regard, a 'Reforms Monitoring Unit' has been

set up in the Economic Policy Division under the direction of Ministry of Power to monitor the status of implementation of various provisions of the Electricity Act, 2003, the National Electricity Policy, 2005 and the Tariff Policy, 2016.

## 9.9 Expenditure in Power Sector

Investment expenditure in different segments of the power sector during the years 2015-16 to 2017-18, is shown in the **Table A** hereinafter.

## 9.10 The Electricity Act, 2003 and subsequent developments

### 9.10.1 Electricity (Amendment) Bill, 2014

The Electricity Act, 2003 was enacted on 10<sup>th</sup> June 2003. The Act was further amended in the year 2003 and year 2007 by the Electricity (Amendment) Act, 2003 and the Electricity (Amendment) Act 2007 respectively. In order to further amend the Act, the Electricity (Amendment) Bill, 2014 has been introduced by the Government of India in the Parliament on 19<sup>th</sup> December, 2014. The salient features of the proposed Electricity (Amendment) Bill, 2014 are as under:

- Provision for National Renewable Energy Policy in addition to the existing National Electricity Policy.
- Setting up of Renewable Energy Generating Stations and provision for spinning reserves.
- Separation of carriage and content in electricity by granting separate license for Distribution & Supply and for specific exemptions to promote Renewable Energy.
- To amend Sections 29, 33, 142 & 146 of the said Act so as to enhance penalties.
- To prescribe the manner of collection and realization of any dues under the relevant laws for the time being in force in that State, along with the Electricity dues.

**Table A : Investment Expenditure in Power Sector in India**

(Figures in Rs. Crore)

| Sector/Segment                  | 2015-16          | 2016-17          | 2017-18<br>(Provisional) |
|---------------------------------|------------------|------------------|--------------------------|
| <b>CENTRAL Sector</b>           | <b>53395.27</b>  | <b>51143.46</b>  | <b>7150.77</b>           |
| (i) THERMAL                     | 26015.42         | 24172.04         | 5241.71                  |
| (ii) HYDRO                      | 4631.25          | 4390.52          | 1909.06                  |
| (iii) TRANSMISSION              | 22748.60         | 22580.90         | -                        |
| (iv) DISTRIBUTION               | -                | -                | -                        |
| <b>STATE Sector</b>             | <b>86951.35</b>  | <b>37977.12</b>  | <b>4752.50</b>           |
| (i) THERMAL                     | 19683.43         | 15537.13         | 4572.87                  |
| (ii) HYDRO                      | 2762.92          | 1844.73          | 179.63                   |
| (iii) TRANSMISSION              | 16640.08         | 16332.35         | -                        |
| (iv) DISTRIBUTION               | 47900.92         | 4262.91          | -                        |
| <b>PRIVATE Sector</b>           | <b>27043.79</b>  | <b>13060.82</b>  | <b>574.98</b>            |
| (i) THERMAL                     | 21758.72         | 11030.55         | 472.59                   |
| (ii) HYDRO                      | 3216.35          | 815.98           | 102.39                   |
| (iii) TRANSMISSION              | -                | -                | -                        |
| (iv) DISTRIBUTION               | 2068.72          | 1214.29          | -                        |
| <b>GRAND TOTAL Sector wise</b>  | <b>167390.41</b> | <b>102181.40</b> | <b>12478.25</b>          |
| (i) THERMAL                     | 67457.57         | 50739.72         | 10287.17                 |
| (ii) HYDRO                      | 10574.52         | 7051.23          | 2191.08                  |
| (iii) TRANSMISSION              | 39388.68         | 38913.25         | -                        |
| (iv) DISTRIBUTION               | 49969.64         | 5477.20          | -                        |
| <b>GRAND TOTAL Segment wise</b> | <b>167390.41</b> | <b>102181.40</b> | <b>12478.25</b>          |

**Note:**

- These figures are as reported by the utilities, which are likely to change with the truing up of the figures with audit of their accounts in due course.
- Data on Renewable energy, Nuclear energy and Captive generation is not captured.
- Data on Private Transmission is not available.
- Figures are updated upto Oct./Nov. 2017.

- To promote hydro power and reduction in regulatory assets.
- Insertion of a new Section 109A relating to “Review of performance of Appropriate Commissions” through a Committee to be constituted for reviewing the performance of the said Commissions.

#### 9.10.2 Framing of the CEA Regulations and Amendments notified under the Electricity Act, 2003

The principal Regulations and Amendments which have been framed and notified by the Central Electricity Authority under the Electricity Act, 2003, are listed below:

| Sl. No. | Title of the Regulations  | Date of publication in Gazette of India                   |
|---------|---|---|
| (i)     | Central Electricity Authority (Installation & Operation of Meters) Regulations, 2006  | 22.03.2006  |
| (ii)    | Central Electricity Authority (Procedure for Transaction of Business) Regulations, 2006   | 22.08.2006  |
| (iii)   | Central Electricity Authority (Technical Standards for Connectivity to the Grid) Regulations, 2007  | 09.03.2007  |
| (iv)    | Central Electricity Authority (Furnishing of Statistics, Returns & Information) Regulations, 2007   | 19.04.2007  |
| (v)     | Central Electricity Authority (Grid Standards) Regulations, 2010  | 26.06.2010  |
| (vi)    | Central Electricity Authority (Installation and Operation of meters) (Amendment) Regulations, 2010  | 26.06.2010  |
| (vii)   | Central Electricity Authority (Measures relating to Safety and Electricity Supply) Regulations, 2010  | 24.09.2010  |
| (viii)  | Central Electricity Authority (Technical Standards for Construction of Electrical Plants and Electric Lines) Regulations, 2010                            | 20.08.2010 (English Version) & 07.09.2010 (Hindi Version) |
| (ix)    | Central Electricity Authority (Safety requirements for Construction, Operation and Maintenance of Electrical Plants and Electric Lines) Regulations, 2011 | 14.02.2011  |
| (x)     | Central Electricity Authority (Technical Standards for Connectivity of the Distributed Generation Resources) Regulations, 2013                            | 07.10.2013  |
| (xi)    | Central Electricity Authority (Technical Standards for Connectivity to the Grid) (Amendment) Regulations, 2013  | 15.10.2013  |
| (xii)   | Central Electricity Authority (Installation and Operation of Meters) (Amendment) Regulations, 2014  | 26.11.2014  |
| (xiii)  | Central Electricity Authority (Technical Standards for Construction of Electrical Plants and Electric Lines) (Amendment) Regulations, 2015                | 06.04.2015  |
| (xiv)   | Central Electricity Authority (Measures relating to Safety and Electricity Supply) (Amendment) Regulations, 2015  | 13.04.2015  |
| (xv)    | Central Electricity Authority (Measures relating to Safety and Electricity Supply) (Amendment) Regulations, 2018  | 01.03.2018  |

## 9.11 Status of Power Sector Reforms

Central Electricity Authority has been monitoring the reforms of power sector undertaken by the State Governments/UTs as envisaged under Electricity Act, 2003, by way of collation of pertinent data from the States/UTs. Status of the reforms as per the information/data furnished by States/UTs is as under:

### 9.11.1 Restructuring of State Electricity Boards/Electricity Departments / Power Departments

All the States having State Electricity Boards (SEBs) prior to enactment of Electricity Act, 2003, unbundled their SEBs under Section 131 of the Act.

The Electricity Act, 2003 is silent about State Power Departments. However, State of Tripura has created Tripura State

Electricity Corporation Limited (TSECL) as a single Corporation to look after generation, transmission and distribution, trading and SLDC operations. Manipur has also unbundled and corporatized its Electricity Department into two (2) State owned functionally independent entities - (i) Manipur State Power Company Limited (MSPCL) as State transmission and generation utility and (ii) Manipur State Power Distribution Company Limited (MSPDCL) as distribution licensee. In the States of Goa, Sikkim, Arunachal Pradesh, Mizoram and Nagaland, all matters relating to generation, transmission and distribution of Electricity are managed by the respective Power Departments/Energy Department.

In addition, six Union Territories viz. Chandigarh, Puducherry, Lakshadweep, Andaman & Nicobar Island, Daman & Diu and Dadra & Nagar Haveli, are having their own Power Department.

### 9.11.2 Constitution of Electricity Regulatory Commissions (ERCs)

All the States have constituted their respective State Electricity Regulatory Commission (SERC). The States of Manipur & Mizoram have constituted a Joint ERC. All the SERCs are functional.

A separate Joint Electricity Regulatory Commission (JERC) has been constituted by the Central Government for Union Territories including the State of Goa. The nomenclature of JERC for UTs has been changed to "JERC for Goa and Union Territories".

### 9.11.3 Constitution of Special Courts

So far, 27 States viz. Assam, Andhra Pradesh, Bihar, Chhattisgarh, Gujarat, Haryana, Himachal Pradesh, Jammu & Kashmir, Jharkhand, Karnataka, Kerala,

Madhya Pradesh, Maharashtra, Meghalaya, Manipur, Nagaland, Odisha, Punjab, Rajasthan, Sikkim, Telangana, Tamil Nadu, Tripura, Uttar Pradesh, Uttarakhand, West Bengal and Delhi have set up Special Courts for expeditious disposal of cases relating to the theft of electricity.

### 9.11.4 Constitution of Consumer Grievances Redressal Forums

Consumer Grievances Redressal Forums (CGRF) have been constituted by various distribution licensees for redressal of grievances of consumers in 28 States, namely Assam, Andhra Pradesh, Bihar, Chhattisgarh, Goa, Gujarat, Haryana, Himachal Pradesh, Jharkhand, Karnataka, Kerala, Madhya Pradesh, Maharashtra, Meghalaya, Manipur, Mizoram, Nagaland, Odisha, Punjab, Rajasthan, Sikkim, Telangana, Tamil Nadu, Tripura, Uttar Pradesh, Uttarakhand, West Bengal and Delhi. Ombudsmen have also been appointed in these 28 States to look into the non-redressal of grievances by the CGRF.

### 9.12 Court Cases

Legal Division of CEA is dealing with the number of Court Cases filed in Supreme Court, High Courts, National Green Tribunals (NGTs) and District Courts/Lower Courts across the country, on behalf of Government of India, Ministry of Power and Central Electricity Authority.

Presently, Legal Division is involved in more than 125 court cases which are ongoing/pending at various courts in the country in which Central Electricity Authority or Ministry of Power is/are have been impleaded as respondent(s).

### 9.13 Assistance to Ministry of Power

Comments were furnished to the Ministry of Power on various references / issues with the important ones listed

**hereunder -**

- Amendments proposed in Electricity Rules, 2005.
- Inclusion of National Power Committee in Amendment of Electricity Act, 2003.
- Gazette Notification for appointment of Estate Offices under Public Premises (Eviction of Unauthorized Occupants) Act, 1971 for PGCIL.
- VIP reference regarding waiver of Inter-state transmission charges for Small Hydro projects.
- Note for Committee of Secretaries on notifying Technical Regulations to address the regulatory gap in India.
- Proposal for acquisition of SJVNL by NTPC.
- Draft Cabinet Note on Industrial Policy, 2018.
- Request of M/s. Adani Power Ltd. for approval of competent authority to build independent transmission system for evacuation of power from the proposed 2x800MW Godda thermal project in Jharkhand to Bangladesh.
- Reference from Ministry of Commerce & Industry regarding preparation, adoption and application of Standards and Technical Regulations (TRs) to fulfill certain key public policy objectives.
- Note regarding under-recovery in Energy charges for projects under Case-I bidding.
- Application under Section 86(i)(b) for approval of the source of power i.e, 4000MW of power from Odisha Integrated Power Ltd. (UMPP Project) expected to be available

w.e.f. 2021-2022.

- Supply of power for the proposed pit head power plant in Odisha by NLCIL.
- Material for preparation of Chapter on Climate, Sustainable Development and Energy for the Economic Survey 2017-18.
- 2017 Ministerial Meeting of the International Energy Agency (IEA) with respect to priority areas earmarked for the Joint Program of work during 2018-2021.
- Levy of Additional charge of 1% on account of TCS being violative of extant laws.
- Issues to be considered in 15<sup>th</sup> Finance Commission.

**9.14 Legal Assistance/Advice to Utilities**

**Comments were furnished to the stakeholders/utilities on the following important references/issues -**

- Permanent closure of Badarpur Thermal Power Station.
- Legal opinion for finding out a solution to effect recoveries of amount due from M/s. Suryachakra Power Corporation.
- Reference from Association of Power Producers (APP) regarding “Regulatory overburden of Rs. 8400 Crore on account of faulty Indexation of Coal and Coal Transportation Charges of Railways”.
- Reference from Ministry of Commerce on implementation of SEZ Act, 2005.
- Consideration of open access to Southern Railways as deemed distribution license by TANGEDCO.

- Proposal of NHPC to amend CEA (Technical Standards for construction of Electrical plants and Electric lines) Regulations, 2010 and CEA (Technical Standards for connectivity to the Grid) Amendment Regulations, 2013 with respect to change in power factor of generating units.
- Recommendations of Punchhi Commission on Center-State relations to be discussed in the 13th Standing Committee of the Inter-state Council.
- Reference on flexible operation of NTPC station and other multi-station companies for optimizing Energy Charge Rate (ECR).
- Phasing out of Unit Nos. 1 to 10 of Patratu Thermal Power Station.
- Publication of Reliability Index by CEA in compliance with National Electricity Policy.
- Recommendation for change in status from IPP to CPP for unit 1 of 4x600 MW power plant of M/s. Vedanta Ltd.
- Reference from Association of Power Producers (APP) for allowing various surcharges as pass through under Change in Law.
- Allocation from Inter-state Generating Stations (ISGS) towards Auxiliary power under O&M for all AC Sub-stations in different States.

### 9.15 References on Policy & Regulatory aspects in the Power Sector

The important references on issues concerning draft Regulations of CEA/CERC/SERCs, Implementation of Regulations of CEA/CERC/SERCs and Policy Matters received from Ministry of Power (MoP), Ministry of New and Renewable Energy (MNRE), other Ministries, NITI Aayog,

Industry Associations etc. during the year on which comments/inputs of CEA were sent to MoP/concerned organisations, are listed below:

- Draft CERC (Grant of Connectivity and General Network Access to the inter-state transmission system and other related matters) Regulations, 2017.
- Draft CERC (Cross Border Trade of Electricity) Regulations, 2017.
- Proposal/Request of NTPC for status of a 'Distribution Licensee' to provide electricity to their own charging stations for E-Vehicles.
- Reference from Commerce Secretary regarding the follow up action on the issue of strengthening the regulatory and standards framework across various sectors.
- Background Note for the Standing Committee on Energy on the subject – “Role of Regulators in Electricity Sector”.
- Amendment to Tariff Policy.
- Issues for discussion with Regulators during the meeting of Hon'ble Minister of State (IC) for Power & NRE with Forum of Regulators (FOR).
- Draft Roadmap for Implementation of the SAARC framework agreement on Energy Co-operation.
- Uploading of updated/consolidated status of pending court cases in respect of CEA in the Legal Information Management & Briefing System (LIMBS) Portal developed by the Ministry of Law & Justice.
- Draft Electricity Regulations of Ministry of Energy & Public Utilities,

Republic of Mauritius.

- Assessment of effectiveness of provisions of revised Tariff Policy, 2016.
- Proposal from National Solar Energy Federation of India for amendment in Ministry of Commerce & Industry and Department of Revenue Notifications dated 16.02.2016 regarding Guidelines for Power Generation, Transmission and Distribution in Special Economic Zones (SEZs).
- Inputs for the Standing Committee on Energy on the subjects viz., Demands for Grants, Contribution of Central Electricity Authority in the balanced development of Electricity Sector.
- Draft National Energy Policy formulated by NITI Aayog.
- Drafting of Clarification to be issued for no requirement of license by the Charging Stations for E-Vehicles.

#### **9.16 Implementation issues related to Regulations / Standards of CEA/ CERC/SERCs**

- Reference from Ministry of Commerce and Industry regarding formulation of Regulations/ Standards and high cost of electricity for SEZ.
- Publication of the Central Electricity Authority (Measures relating to Safety and Electricity Supply) (Amendment) Regulations, 2018 in the Gazette of India.
- Inputs for Committee on Subordinate Legislation, Rajya Sabha, on issue of CERC Regulations for Renewables.
- Reference from Ministry of Steel on suggestions for optimizing input cost for steel making viz. "Recognition of waste heat/gas based power generation as cogeneration facilities in the

integrated Steel plant in category of renewable power", "Granting of deemed licensee status to SAIL, on similar lines with Railways", etc.

- Uploading of CEA Regulations/ Notifications in India Code Portal developed by the Ministry of Law & Justice.
- Request from Government of Andhra Pradesh regarding grant of waiver of ISTS charges and losses to Renewable Energy Projects (solar and wind) using ISTS network in terms of Clause 6.4 (6) of the Tariff Policy, 2016.
- Reference from Principal Secretary (Energy), Govt. of Rajasthan on CERC (Sharing of ISTS Charges and Losses), Regulations.
- Proposal of NTPC regarding "Restriction in procurement under Short Term Open Access (STOA) by defaulting entities as provided to transmission licensee".
- Second Amendment of CEA (Measures Relating to Safety and Electricity Supply) Regulations, 2010.
- Reference from M/s. ITC Limited regarding Inter State Open Access (ISOA) for 46 MW Wind Energy Project, for meeting the captive power requirements of ITC units located across the unified State of Andhra Pradesh.

#### **9.17 Nomination to the Important Committees**

- (i) Member (E&C), CEA nominated as the Chairman with Chief Engineer (F&CA), CEA, as one of the Members of the Committee constituted by Ministry of Power (MoP) to develop provisions for Joint Bids between RE and non RE players for integrated

- power needs.
- (ii) Nomination of Member (E&C), CEA, as a Member of the Committee constituted by MoP on Policy Planning and Regulatory/Tariff related issues of Charging Infrastructure for Electric Vehicles.
  - (iii) Member (E&C), CEA nominated as the Chairman with Chief Engineer (F&CA), CEA, as one of the Members of the Committee constituted by MoP to formulate long term strategy for giving concessional power for value addition of Raw Material (Alumina and others). The Committee has submitted its Report to MoP in December 2017.
  - (iv) An Inter-Ministerial Group was constituted by MoP for analyzing Stressed Projects in Power Sector and making policy recommendations. In this regard a Financial Sub Group was constituted headed by Member (E&C), CEA and Chief Engineer (F&CA) was co-opted as Member of this subgroup. This Subgroup had submitted its Report to MoP in September 2017.
  - (v) CEA has constituted a Standing Committee for periodic review of Tariff Policy with Member (E&C), CEA nominated as the Chairman of this Committee and Chief Engineer (F&CA) as the Convener.
  - (vi) MoP has constituted a Committee for implementation of Time of Day (ToD) Tariff under the Chairmanship of Addl. Secretary, MoP. Chief Engineer (F&CA), CEA has been nominated as a member of this Committee.
  - (vii) Chief Engineer (F&CA), CEA has been nominated as the Chairman of the Drafting Committee constituted by MoP for carrying out necessary drafting for the proposed amendments in the Tariff Policy.
  - (viii) MoP has constituted a Committee for drafting of the proposed Amendments in Electricity Act, 2003. Chief Engineer (Legal), CEA has been nominated as a member of this Committee.
  - (ix) Chief Engineer (F&CA), CEA has been nominated as a member of the Tariff Negotiation Committee constituted by MoP for Mangdechhu HEP, Bhutan.
  - (x) Chief Engineer (Legal), CEA has been nominated as a member of the Committee constituted by MoP for the proposed Amendments in Electricity Rules, 2005.
  - (xi) MoP has constituted a Committee on Efficient Regulation of Electricity Derivatives. Director (F&CA), CEA has been nominated as a member of this Committee.
  - (xii) Nomination of Sh. Pankaj Kumar Verma, Assistant Director (RA) and Ms. Bhoomika Banga, Assistant Director (F&CA) to deliver a Country Presentation and represent India in the workshop organized by the SAARC in collaboration with Indian Energy Exchange at New Delhi.

\*\*\*\*\*



## CHAPTER – 10

### POWER GENERATION

#### 10.1 Power Generation

Generation of power by the Central Sector, State Sector, Pvt. utilities & IPPs was about 1206306.25 Million Units during the

year 2017-18. This represents a growth of about 3.98% over the same period during previous year 2016-17 as per details given below:

#### Power Generation during 2017-18

| Category          | Programme (MU) | Actual (MU)       | Shortfall (-)/<br>Excess(+) | % of Programme | Growth (%) with respect to previous year Actual Gen. |
|-------------------|----------------|-------------------|-----------------------------|----------------|--|
| <b>Thermal</b>    | 1042028        | 1037059.10        | -4968.90                    | 99.52          | 4.31   |
| <b>Nuclear</b>    | 40972          | 38346.12          | -2625.88                    | 93.59          | 1.13   |
| <b>Hydro</b>      | 141400         | 126122.70         | -15277.3                    | 89.20          | 3.06   |
| <b>Bhutan Imp</b> | 5000           | 4778.33           | -221.67                     | 95.57          | -14.94   |
| <b>TOTAL</b>      | <b>1229400</b> | <b>1206306.25</b> | <b>-23093.75</b>            | <b>98.12</b>   | <b>3.98</b>  |

**Note:** Generation from stations having installed capacity less than 25MW is not being monitored in CEA since 01.04.2010.

The highlights / achievements of operation performance of generating stations in the country during the year 2017-18 are as under:

- Gross annual generation of the country was 1206.31 BU.
- The annual growth in the energy generation during the year was 3.98%.
- Thermal, Nuclear, Hydro and Import from Bhutan achieved a growth rate of 4.31%, 1.13%, 3.06% and -14.94% respectively. The electricity generation during the year 2017-18 from coal based thermal power stations was 951.75 BU showing a growth rate of

4.57% against 5.58% over same period last year.

- In North region the growth in thermal generation was 8.48% with respect to last year highest amongst all other regions.
- The national average PLF for thermal stations was 60.72% and 83 Stations with an aggregate installed capacity of 104629.5MW, achieved PLF above national average.

06 number of thermal power stations with an aggregate installed capacity of 7320 MW achieved above 90% PLF.

The sector wise Generation and PLF during 2017-18 is given below:

| Category / Sectors      | Programme (MU) | Actual            | PLF (%) |
|-------------------------|----------------|-------------------|---------|
|                         |                | (MU)              |         |
| <b>CENTRAL SECTOR</b>   |                |                   |         |
| THERMAL                 | 339749         | 356130.05         | 72.38   |
| NUCLEAR                 | 40972          | 38346.12          | 64.56   |
| HYDRO                   | 55028          | 55036.09          |         |
| <b>TOTAL</b>            | <b>435749</b>  | <b>449512.26</b>  |         |
| <b>STATE SECTOR</b>     |                |                   |         |
| THERMAL                 | 339494         | 320736.93         | 56.90   |
| HYDRO                   | 73005          | 56988.95          |         |
| <b>TOTAL</b>            | <b>412499</b>  | <b>377725.88</b>  |         |
| <b>PVT. SECTOR IPP</b>  |                |                   |         |
| THERMAL*                | 344239         | 341387.76         | 55.09   |
| HYDRO                   | 11917          | 12581.78          |         |
| <b>TOTAL</b>            | <b>356156</b>  | <b>353969.54</b>  |         |
| <b>PVT. SECTOR UTL.</b> |                |                   |         |
| THERMAL                 | 18546          | 18804.36          | 60.42   |
| HYDRO                   | 1450           | 1515.88           |         |
| <b>TOTAL</b>            | <b>19996</b>   | <b>20320.24</b>   |         |
| <b>TOTAL PVT</b>        | <b>376152</b>  | <b>374289.78</b>  |         |
| <b>BHUTAN IMP</b>       | 5000           | 4778.33           |         |
| <b>ALL INDIA REGION</b> |                |                   |         |
| THERMAL                 | 1042028        | 1037059.10        | 60.72   |
| NUCLEAR                 | 40972          | 38346.12          | 64.56   |
| HYDRO                   | 141400         | 126122.70         |         |
| BHUTAN IMP              | 5000           | 4778.33           |         |
| <b>TOTAL</b>            | <b>1229400</b> | <b>1206306.25</b> |         |

\*Includes import from some of the Captive Plants

## 10.2 Plant Load Factor of Thermal Power Stations

During the year 2017-18 the average PLF of Thermal Power Stations was 60.72 % and for Nuclear Power Stations was 64.56%.

83 thermal power plants achieved PLF higher than the All India average PLF of 60.72% as per details given in the table below:


**List of Thermal Power Stations which have achieved PLF above National Average  
of 60.72 % during the year 2017-18**

| S. No. | NAME OF THE STATION      | Installed Capacity (MW) | SECTOR  | State          | PLF (%) |
|--------|--------------------------|-------------------------|---------|----------------|---------|
| 1      | AMARKANTAK EXT TPS       | 450                     | STATE   | MADHYA PRADESH | 93.94   |
| 2      | TALCHER (OLD) TPS        | 460                     | CENTRAL | ORISSA         | 93.82   |
| 3      | DSPM TPS                 | 500                     | STATE   | CHHATTISGARH   | 92.31   |
| 4      | BUDGE BUDGE TPS          | 750                     | PVT     | WEST BENGAL    | 91.83   |
| 5      | SASAN UMTTP              | 3960                    | PVT     | MADHYA PRADESH | 91.65   |
| 6      | SINGARENI TPP            | 1200                    | STATE   | TELANGANA      | 91.09   |
| 7      | VINDHYACHAL STPS         | 4760                    | CENTRAL | MADHYA PRADESH | 89.92   |
| 8      | KORBA STPS               | 2600                    | CENTRAL | CHHATTISGARH   | 89.91   |
| 9      | RIHAND STPS              | 3000                    | CENTRAL | UTTAR PRADESH  | 89.54   |
| 10     | BHILAI TPS               | 500                     | CENTRAL | CHHATTISGARH   | 88.53   |
| 11     | NEYVELI ( EXT) TPS       | 420                     | CENTRAL | TAMIL NADU     | 88.26   |
| 12     | SIPAT STPS               | 2980                    | CENTRAL | CHHATTISGARH   | 88.14   |
| 13     | TALCHER STPS             | 3000                    | CENTRAL | ORISSA         | 87.43   |
| 14     | RAMAGUNDEM - B TPS       | 62.5                    | STATE   | TELANGANA      | 86.73   |
| 15     | HALDIA TPP               | 600                     | PVT     | WEST BENGAL    | 86.11   |
| 16     | CHAKABURA TPP            | 30                      | PVT     | CHHATTISGARH   | 85.49   |
| 17     | TANDA TPS                | 440                     | CENTRAL | UTTAR PRADESH  | 85.05   |
| 18     | PAINAMPURAM TPP          | 1320                    | PVT     | ANDHRA PRADESH | 85.04   |
| 19     | BANDAKHAR TPP            | 300                     | PVT     | CHHATTISGARH   | 84.62   |
| 20     | SINGRAULI STPS           | 2000                    | CENTRAL | UTTAR PRADESH  | 84.37   |
| 21     | SABARMATI (D-F STATIONS) | 362                     | PVT     | GUJARAT        | 83.21   |
| 22     | RAMAGUNDEM STPS          | 2600                    | CENTRAL | TELANGANA      | 82.84   |
| 23     | KOTHAGUNDEM TPS (NEW)    | 1000                    | STATE   | TELANGANA      | 81.41   |
| 24     | BAKRESWAR TPS            | 1050                    | STATE   | WEST BENGAL    | 81.40   |
| 25     | DAHANU TPS               | 500                     | PVT     | MAHARASHTRA    | 80.69   |
| 26     | KASAIPALLI TPP           | 270                     | PVT     | CHHATTISGARH   | 80.56   |
| 27     | BARH II                  | 1320                    | CENTRAL | BIHAR          | 80.19   |
| 28     | ANPARA C TPS             | 1200                    | PVT     | UTTAR PRADESH  | 79.88   |
| 29     | MAITHON RB TPP           | 1050                    | PVT     | JHARKHAND      | 79.86   |
| 30     | NEYVELI TPS-II           | 1470                    | CENTRAL | TAMIL NADU     | 79.70   |
| 31     | KAHALGAON TPS            | 2340                    | CENTRAL | BIHAR          | 79.60   |
| 32     | KORBA-WEST TPS           | 1340                    | STATE   | CHHATTISGARH   | 79.09   |
| 33     | PATHADI TPP              | 600                     | PVT     | CHHATTISGARH   | 78.76   |
| 34     | SGPL TPP                 | 1320                    | PVT     | ANDHRA PRADESH | 77.58   |
| 35     | IB VALLEY TPS            | 420                     | STATE   | ORISSA         | 77.20   |

|    |                       |      |         |                |       |
|----|-----------------------|------|---------|----------------|-------|
| 36 | JOJOBERA TPS          | 240  | PVT     | JHARKHAND      | 76.98 |
| 37 | KAKATIYA TPS          | 1100 | STATE   | TELANGANA      | 76.72 |
| 38 | MUNDRA UMTTP          | 4000 | PVT     | GUJARAT        | 75.67 |
| 39 | BARSINGSAR LIGNITE    | 250  | CENTRAL | RAJASTHAN      | 75.29 |
| 40 | SURAT LIG. TPS        | 500  | PVT     | GUJARAT        | 74.70 |
| 41 | RAJPURA TPP           | 1400 | PVT     | PUNJAB         | 74.28 |
| 42 | DURGAPUR STEEL TPS    | 1000 | CENTRAL | WEST BENGAL    | 74.24 |
| 43 | RAYALASEEMA TPS       | 1650 | STATE   | ANDHRA PRADESH | 73.95 |
| 44 | TORANGALLU TPS(SBU-I) | 260  | PVT     | KARNATAKA      | 73.54 |
| 45 | ROSA TPP Ph-I         | 1200 | PVT     | UTTAR PRADESH  | 73.43 |
| 46 | RATIJA TPS            | 100  | PVT     | CHHATTISGARH   | 73.20 |
| 47 | UNCHAHAH TPS          | 1550 | CENTRAL | UTTAR PRADESH  | 73.14 |
| 48 | FARAKKA STPS          | 2100 | CENTRAL | WEST BENGAL    | 72.61 |
| 49 | JALIPA KAPURDI TPP    | 1080 | PVT     | RAJASTHAN      | 72.47 |
| 50 | ANPARA TPS            | 2630 | STATE   | UTTAR PRADESH  | 72.13 |
| 51 | RAICHUR TPS           | 1720 | STATE   | KARNATAKA      | 71.91 |
| 52 | CHHABRA TPP           | 1660 | STATE   | RAJASTHAN      | 71.37 |
| 53 | GMR WARORA TPS        | 600  | PVT     | MAHARASHTRA    | 71.27 |
| 54 | PARAS TPS             | 555  | STATE   | MAHARASHTRA    | 71.15 |
| 55 | HARDUAGANJ TPS        | 720  | STATE   | UTTAR PRADESH  | 70.32 |
| 56 | Dr. N.TATA RAO TPS    | 1760 | STATE   | ANDHRA PRADESH | 70.19 |
| 57 | GANDHI NAGAR TPS      | 870  | STATE   | GUJARAT        | 67.80 |
| 58 | KODARMA TPP           | 1000 | CENTRAL | JHARKHAND      | 67.48 |
| 59 | SIMHADRI              | 2000 | CENTRAL | ANDHRA PRADESH | 67.20 |
| 60 | SANTALDIH TPS         | 980  | STATE   | WEST BENGAL    | 67.16 |
| 61 | BOKARO TPS `A` EXP    | 500  | CENTRAL | JHARKHAND      | 66.76 |
| 62 | NIGRI TPP             | 1320 | PVT     | MADHYA PRADESH | 66.49 |
| 63 | KOTA TPS              | 1240 | STATE   | RAJASTHAN      | 66.40 |
| 64 | CHANDRAPURA(DVC) TPS  | 1120 | CENTRAL | JHARKHAND      | 66.15 |
| 65 | YAMUNA NAGAR TPS      | 600  | STATE   | HARYANA        | 65.60 |
| 66 | MARWA TPS             | 1000 | STATE   | CHHATTISGARH   | 65.30 |
| 67 | UKAI TPS              | 1350 | STATE   | GUJARAT        | 64.92 |
| 68 | PARICHAH TPS          | 1140 | STATE   | UTTAR PRADESH  | 64.36 |
| 69 | NEYVELI TPS- I        | 600  | CENTRAL | TAMIL NADU     | 64.30 |
| 70 | SANJAY GANDHI TPS     | 1340 | STATE   | MADHYA PRADESH | 64.26 |
| 71 | JSW RATNAGIRI TPP     | 1200 | PVT     | MAHARASHTRA    | 64.03 |
| 72 | KALISINDH TPS         | 1200 | STATE   | RAJASTHAN      | 63.65 |
| 73 | MAHATMA GANDHI TPS    | 1320 | PVT     | HARYANA        | 63.35 |
| 74 | BUTIBORI TPP          | 600  | PVT     | MAHARASHTRA    | 62.91 |
| 75 | NORTH CHENNAI TPS     | 1830 | STATE   | TAMIL NADU     | 62.77 |
| 76 | DADRI (NCTPP)         | 1820 | CENTRAL | UTTAR PRADESH  | 62.30 |
| 77 | BARADARHA TPS         | 1200 | PVT     | CHHATTISGARH   | 62.18 |
| 78 | AKRIMOTA LIG TPS      | 250  | STATE   | GUJARAT        | 61.97 |

|                        |                     |                 |         |             |       |
|------------------------|---------------------|-----------------|---------|-------------|-------|
| 79                     | TUTICORIN (JV) TPP  | 1000            | CENTRAL | TAMIL NADU  | 61.79 |
| 80                     | MAHADEV PRASAD STPP | 540             | PVT     | JHARKHAND   | 61.52 |
| 81                     | KOTHAGUDEM TPS      | 720             | STATE   | TELANGANA   | 61.38 |
| 82                     | MEJIA TPS           | 2340            | CENTRAL | WEST BENGAL | 60.88 |
| 83                     | TIRORA TPS          | 3300            | PVT     | MAHARASHTRA | 60.87 |
| <b>TOTAL CAPACITY:</b> |                     | <b>104629.5</b> |         |             |       |

The trend in All India PLF of coal and Lignite based thermal power stations from 1994-95 onwards is shown below:



All India Sector-wise/Organization-wise target, actual generation and PLF (%) for the year 2017-18 is at **Annexure-10A**.


### 10.3 Generating Capacity Addition

During the year 2017-18, a total of 9505 MW generation capacity was added (excluding Renewable Energy Sources). The

capacity addition during the last 10 years Sector-wise and mode-wise are given below:


**Capacity addition during the last 10 years – Sector-wise**

| Year    | Central Sector | State Sector | Private Sector | Total    |
|---------|----------------|--------------|----------------|----------|
| 2007-08 | 3240.00        | 5273.00      | 750.00         | 9263.00  |
| 2008-09 | 750.00         | 1821.20      | 882.50         | 3453.70  |
| 2009-10 | 2430.00        | 3418.00      | 3737.00        | 9585.00  |
| 2010-11 | 3330.00        | 2209.00      | 6621.50        | 12160.50 |
| 2011-12 | 4770.00        | 3761.00      | 11971.00       | 20502.00 |
| 2012-13 | 5397.30        | 3977.00      | 11257.50       | 20631.80 |
| 2013-14 | 2574.01        | 3367.00      | 11884.00       | 17825.01 |
| 2014-15 | 4395.21        | 4886.10      | 13285.00       | 22566.31 |
| 2015-16 | 3775.60        | 7070.00      | 13131.00       | 23976.60 |
| 2016-17 | 4310.50        | 5177.30      | 4722.00        | 14209.80 |
| 2017-18 | 3560.00        | 1960.00      | 3985.00        | 9505.00  |



## Capacity addition during the last 10 years – Mode-wise

| Year    | Thermal  | Hydro   | Nuclear | Total           |
|---------|----------|---------|---------|-----------------|
| 2007-08 | 6620.00  | 2423.00 | 220     | <b>9263.00</b>  |
| 2008-09 | 2484.70  | 969.00  | 0.00    | <b>3453.70</b>  |
| 2009-10 | 9106.00  | 39.00   | 440.00  | <b>9585.00</b>  |
| 2010-11 | 11250.50 | 690.00  | 220.00  | <b>12160.50</b> |
| 2011-12 | 19079.00 | 1423.00 | 0.00    | <b>20502.00</b> |
| 2012-13 | 20121.8  | 510.00  | 0.00    | <b>20631.80</b> |
| 2013-14 | 16767.00 | 1058.01 | 0.00    | <b>17825.01</b> |
| 2014-15 | 20830.30 | 736.00  | 1000.00 | <b>22566.31</b> |
| 2015-16 | 22460.60 | 1516.00 | 0.00    | <b>23976.60</b> |
| 2016-17 | 11550.80 | 1659.00 | 1000.00 | <b>14209.80</b> |
| 2017-18 | 8710.00  | 795.00  | 0.00    | <b>9505.00</b>  |

Capacity addition during the year 2017-18 -  
Mode wise

#### 10.4 Installed Electricity Generating Capacity

The Total All India Installed Electricity Generating Capacity as on 31.03.2018 is 344002.39 MW comprising of Thermal 222906.59 MW, Hydro 45293.42 MW,

Nuclear 6780.00 MW and 69022.39 MW from Renewable Energy Sources (RES). The details are shown in the Table given below:

## All India Installed Electricity Generating Capacity- Sector-wise

| Type         | Central Sector (MW) | State Sector (MW) | Private Sector (MW) | Total (MW)       |
|--------------|---------------------|-------------------|---------------------|------------------|
| THERMAL      | 64192.91            | 72113.38          | 86600.30            | 222906.59        |
| HYDRO        | 12041.42            | 29858.00          | 3394.00             | 45293.42         |
| NUCLEAR      | 6780.00             | 0.00              | 0.00                | 6780.00          |
| RES          | 1502.30             | 2003.37           | 65516.72            | 69022.39         |
| <b>Total</b> | <b>84516.63</b>     | <b>103974.75</b>  | <b>155511.02</b>    | <b>344002.39</b> |

The State-wise/ Region-wise/ Sector-wise and prime mover wise summary of installed capacity under utilities is at **Annexure-10B**. The mode-wise growth of installed generating capacity in the country is shown in the Table below:

## Growth of Installed generating capacity in the country- Mode wise

| Year        | Thermal | Nuclear | Hydro | RES*  | Total  |
|-------------|---------|---------|-------|-------|--------|
| Dec.1947    | 854     | -       | 508   | -     | 1362   |
| Dec.,1955   | 1755    | -       | 940   | -     | 2695   |
| March, 1961 | 2736    | -       | 1917  | -     | 4653   |
| March, 1966 | 4903    | -       | 4124  | -     | 9027   |
| March, 1974 | 9058    | 640     | 6966  | -     | 16664  |
| March, 1980 | 16424   | 640     | 11384 | -     | 28448  |
| March, 1985 | 27030   | 1095    | 14460 | -     | 42585  |
| March, 1990 | 43764   | 1565    | 18307 | -     | 63636  |
| March, 1991 | 45768   | 1565    | 18753 | -     | 66086  |
| March, 1992 | 48086   | 1785    | 19194 | -     | 69065  |
| March, 1996 | 60083   | 2225    | 20986 | -     | 83294  |
| March, 1997 | 61012   | 2225    | 21658 | 900   | 85795  |
| March, 1998 | 64005   | 2225    | 21904 | 968   | 89102  |
| March, 1999 | 67566   | 2225    | 22479 | 1024  | 93294  |
| March, 2000 | 70193   | 2680    | 23857 | 1155  | 97885  |
| March, 2001 | 72343   | 2860    | 25153 | 1270  | 101626 |
| March, 2002 | 74429   | 2720    | 26269 | 1628  | 105046 |
| March, 2003 | 76762   | 2720    | 26767 | 1628  | 107877 |
| March, 2004 | 77969   | 2720    | 29507 | 2488  | 112684 |
| March, 2005 | 80902   | 2770    | 30942 | 3812  | 118426 |
| March, 2006 | 82410   | 3360    | 32326 | 6191  | 124287 |
| March, 2007 | 86015   | 3900    | 34654 | 7760  | 132329 |
| March, 2008 | 91907   | 4120    | 35909 | 11125 | 143061 |
| March, 2009 | 93725   | 4120    | 36878 | 13242 | 147965 |



|             |        |      |       |       |        |
|-------------|--------|------|-------|-------|--------|
| March, 2010 | 102454 | 4560 | 36863 | 15521 | 159398 |
| March, 2011 | 112824 | 4780 | 37567 | 18455 | 173626 |
| March, 2012 | 131603 | 4780 | 38990 | 24504 | 199877 |
| March, 2013 | 151531 | 4780 | 39491 | 27542 | 223344 |
| March, 2014 | 168255 | 4780 | 40531 | 34988 | 248554 |
| March, 2015 | 188898 | 5780 | 41267 | 38959 | 274904 |
| March, 2016 | 210675 | 5780 | 42783 | 45924 | 305163 |
| March, 2017 | 218330 | 6780 | 44478 | 57244 | 326833 |
| March, 2018 | 222907 | 6780 | 45293 | 69022 | 344002 |

**\*Renewable Energy Sources (RES) includes Wind, Small Hydro Project, Biomass Gasifier ,Biomass Power, Urban & Industrial Waste Power & solar power**

\*\*\*\*\*

## CHAPTER – 11

## POWER DEVELOPMENT IN NORTH-EASTERN REGION

## 11.1 Hydro-electric Potential in North Eastern (N.E.) Region

As per Re-assessment studies carried out by CEA, hydro potential of the North Eastern Region in terms of installed capacity has been estimated as 58971 MW (58356 MW- above 25 MW capacity). Out of the above, 1342

MW (above 25 MW capacity) have been harnessed so far while projects amounting to 2854 MW (above 25 MW capacity) are under construction. State-wise identified hydro-electric potential (above 25 MW) of North-Eastern Region and its status of development is given below:

| Region / State     | Identified potential as per Re-assessment Study (MW) |               | H. E. Schemes Developed (Above 25 MW) | H.E. Schemes Under Construction (Above 25 MW) |
|--------------------|--|---------------|---------------------------------------|---|
|                    | Total  | (Above 25 MW) |                                       |   |
| Meghalaya          | 2394   | 2298          | 322                                   | 0   |
| Tripura            | 15   | 0             | 0                                     | 0   |
| Manipur            | 1784   | 1761          | 105                                   | 0   |
| Assam              | 680  | 650           | 375                                   | 0   |
| Nagaland           | 1574   | 1452          | 75                                    | 0   |
| Ar. Pradesh        | 50328  | 50064         | 405                                   | 2854  |
| Mizoram            | 2196   | 2131          | 60                                    | 0   |
| <b>Total(NER):</b> | <b>58971</b>   | <b>58356</b>  | <b>1342</b>                           | <b>2854</b>                                   |

| Region /State     | H. E. Schemes Concurred by CEA (MW) | H. E. Schemes Under Examination in CEA (MW) | H. E. Schemes Returned to Project authorities (MW) | H. E. Schemes under S&I (MW) | H. E. Schemes for which S&I is held up (MW) | H. E. Schemes yet to be allotted for development (MW) |
|-------------------|-------------------------------------|---|--|------------------------------|---|---|
| Meghalaya         | 270                                 | 85  | 210  | 210                          | 620   | 581   |
| Tripura           | 0                                   | 0   | 0  | 0                            | 0   | 0   |
| Manipur           | 66                                  | 0   | 0  | 0                            | 0   | 1590  |
| Assam             | 120                                 | 0   | 60   | 0                            | 0   | 95  |
| Nagaland          | 186                                 | 0   | 0  | 0                            | 0   | 1191  |
| Ar. Pradesh       | 16952                               | 0   | 6329   | 3707                         | 9462  | 10355   |
| Mizoram           | 0                                   | 0   | 0  | 0                            | 0   | 2071  |
| <b>Total(NER)</b> | <b>17594</b>                        | <b>85</b>                                   | <b>6599</b>  | <b>3917</b>                  | <b>10082</b>                                | <b>15883</b>  |

## 11.2 Survey &amp; Investigation(S&amp;I) of Hydro Projects

The Government approved a Three Stage Clearance procedure for hydro projects to be executed by CPSUs in

consultation with MoF and MoEF. Under Stage-I, the CPSUs will incur expenditure on survey & investigation and preparation of pre-feasibility report.

Under Stage-II, the CPSUs will undertake activities relating to detailed investigation and preparation of Detailed Project Report (DPR). During this Stage, pre-construction activities and infrastructure development including land acquisition will also be undertaken. Under Stage-III, approval of PIB/CCEA would be sought for

investment decision in respect of construction of the projects.

### 11.3 Status of development

Some of the major Hydro Electric Projects being planned in the North Eastern Region are as under :

| S. No. | Name of Project         | Basin  | Agency                                      | State             | Present Status  |
|--------|-------------------------|--------|---|-------------------|---|
| 1      | Tawang-I (600 MW)       | Tawang | NHPC  | Arunachal Pradesh | Concurrence accorded by CEA on 10.10.2011. Environment clearance accorded on 10.06.2011. Forest clearance awaited.  |
| 2      | Tawang-II (800 MW)      | Tawang | NHPC  | Arunachal Pradesh | Concurrence accorded by CEA on 22.09.2011. Environment clearance accorded on 10.06.2011. Stage-I Forest clearance accorded on 08.01.2014 and Stage-II Forest clearance awaited.   |
| 3      | Nyamjungchu (780 MW)    | Tawang | NJCHPL                                      | Arunachal Pradesh | Concurrence accorded by CEA on 24.03.2011. Environment clearance accorded on 19.04.2012. Stage-I Forest clearance accorded on 09.04.2012 & Stage-II Forest clearance awaited.   |
| 4      | Naying (1000 MW)        | Siang  | D.S. Construction Ltd                       | Arunachal Pradesh | Concurrence accorded by CEA on 11.09.2013. Environment & Forest clearance awaited. Impacted by Siang Basin Study.   |
| 5      | Siang Lower (2700 MW)   | Siang  | Jaiprakash Associates Ltd.                  | Arunachal Pradesh | Concurrence accorded by CEA on 16.02.2010. Environment & Forest clearance awaited. Impacted by Siang Basin Study.   |
| 6      | Hirong (500 MW)         | Siang  | Jaiprakash Associates Ltd.                  | Arunachal Pradesh | Concurrence accorded by CEA on 10.04.2013. Environment & Forest clearance awaited. Impacted by Siang Basin Study.   |
| 7      | Dibang (2880MW)         | Dibang | NHPC  | Arunachal Pradesh | Concurrence accorded by CEA on 18.09.2017. Environment clearance accorded on 19.05.15. Stage-I Forest clearance accorded on 15.04. Revised DPR with 10 m reduced dam height as recommended by MoEF being prepared by NHPC.                |
| 8      | Kalai-II (1200 MW)      | Lohit  | Kalai Power Pvt. Ltd. (Reliance Power Ltd.) | Arunachal Pradesh | Concurrence accorded by CEA on 27.03.2015. Environment & Forest clearance awaited.  |
| 9      | Demwe (Lower) (1750 MW) | Lohit  | Athena Energy Venture (P) Ltd.              | Arunachal Pradesh | Concurrence accorded by CEA on 20.11.2009. Environment clearance obtained in Feb., 2010. Stage-I & Stage-II Forest clearance accorded on 01.03.2012 & 03.05.2013 respectively. Case challenging Forest clearance has been filed with NGT. |

|    |   |           |  |                   |   |
|----|---|-----------|--|-------------------|---|
| 10 | Etalin<br>(3097 MW)                       | Dibang    | Jindal Power Ltd.<br>(JV with HPDCAPL)<br>- Etalin H.E. Power Co. Ltd. | Arunachal Pradesh | Concurrence accorded by CEA on 12.07.2013. Environment & Forest clearance awaited.  |
| 11 | Attunli<br>(680 MW)                       | Dibang    | Jindal Power Ltd.<br>(JV with HPDCAPL)<br>-Attunli H.E. Power Co. Ltd. | Arunachal Pradesh | Concurrence accorded by CEA on 15.03.2018. Both EC and FC are yet to be obtained by developer.  |
| 12 | Subansiri Middle<br>(Kamala)<br>(1800 MW) | Subansiri | Kamala HECL<br>(Jindal Power Ltd.)                                     | Arunachal Pradesh | Returned on 29.01.2018. All the partial clearances issued till date were rescinded as no progress has been made by the Developer towards resolving the issues pending with various appraising groups. |
| 13 | Hutong- II<br>(1200 MW)                   | Lohit     | Mountain Fall India Pvt. Ltd.  | Arunachal Pradesh | DPR returned in May, 2012. DPR to be revised considering the project as Storage scheme.   |
| 14 | Kalai-I<br>(1352 MW)                      | Lohit     | Mountain Fall India Pvt. Ltd.  | Arunachal Pradesh | DPR returned in May, 2012. DPR to be revised considering the project as Storage scheme.   |
| 15 | Demwe (Upper)<br>(1080 MW)                | Lohit     | Athena Energy Venture (P) Ltd.   | Arunachal Pradesh | DPR returned by CEA in March, 2015 for resubmission after finalization of dam type.   |
| 16 | Oju<br>(1878 MW)                          | Subansiri | Navayuga Engg. Co. Ltd.  | Arunachal Pradesh | Under S&I.  |
| 17 | Subansiri Upper<br>(2000 MW)              | Subansiri | KSK Energy Ventures Pvt. Ltd.  | Arunachal Pradesh | Under S&I.  |
| 18 | Bhareli-II<br>(Kameng-II)<br>(600 MW)     |           | Mountain Falls Ltd.  | Arunachal Pradesh | S&I held up.  |
| 19 | Kameng Dam(600MW)                         |           | KSK Energy Ventures Ltd.   | Arunachal Pradesh | S&I held up.  |
| 20 | Naba<br>(1000 MW)                         | Subansiri | Abir Infrastructure Pvt. Ltd.  | Arunachal Pradesh | S&I held up.  |
| 21 | Niare<br>(800 MW)                         | Subansiri | Coastal Infrastructure Pvt. Ltd.                                       | Arunachal Pradesh | S&I held up.  |
| 22 | Dengser<br>(552 MW)                       | Subansiri | Coastal Infrastructure Pvt. Ltd.                                       | Arunachal Pradesh | S&I held up.  |

|    |                                |           |  |                   |  |
|----|--------------------------------|-----------|--|-------------------|--|
| 23 | Nalo (635 MW)                  | Subansiri | Indus Hydro Power Pvt. Ltd.                        | Arunachal Pradesh | S&I held up.   |
| 24 | Siang Upper St.I (6000 MW)     | Siang     | JV of NHPC & NEEPCO                                | Arunachal Pradesh | S&I held up.   |
| 25 | Siang Upper St.II (3750 MW)    | Siang     | NEEPCO   | Arunachal Pradesh | S&I held up.   |
| 26 | Emini (500 MW)                 | Dibang    | Emini Hydro Power Pvt. Ltd. (Reliance Energy Ltd.) | Arunachal Pradesh | S&I held up.   |
| 27 | Kimi (535 MW)                  | Kameng    |  | Arunachal Pradesh | Yet to be allotted.  |
| 28 | Siyom (Siang Middle) (1000 MW) | Siang     | SIYOM Hydro Power Pvt. Ltd. (Reliance Energy Ltd.) | Arunachal Pradesh | IC of the project will revise due to change in e-flows recommended in BSR and hence fresh DPR to be prepared by developer. |
| 29 | Tato-II (700 MW)               | Siang     | Tato Hydro Power Pvt. Ltd. (Reliance Energy Ltd.)  | Arunachal Pradesh | IC of the project will revise due to change in e-flows recommended in BSR and hence fresh DPR to be prepared by developer. |

#### 11.4 Status of various Under Construction Hydro Power Projects in North Eastern Region

##### 11.4.1 Central Sector Projects

###### (A) NEEPCO Project (Hydro)

###### (i) Kameng HEP (4 x 150 = 600 MW), Arunachal Pradesh

Kameng H.E. Project is located in West Kameng District of Arunachal Pradesh with an installed capacity of 4x150 MW. The project is being executed by NEEPCO Ltd. The project envisages utilization of flows of Bichom & Tenga rivers (both tributaries of river Kameng) at a head of about 500 m available in an U – bend of the river, downstream of confluence of river Bichom with Kameng. The TEC was accorded by CEA on 11.10.1991. The CCEA

clearance was accorded on 02.12.2004. The approved cost of the project is Rs. 2496.90 crores (March, 2003 price level). The design annual energy is 3353 GWh in a 90% dependable year. The environmental and forest clearance was obtained on 29.03.2001 & 03.8.2000 respectively. The proposed revised cost of the project is Rs. 6179.96 crores (March 2015 price level).

The project envisages construction of 2 nos. concrete gravity dams i.e. Bichom Dam and Tenga Dam, Head Race Tunnel, surge shaft, and surface power house having vertical Francis Turbines for 4 units of 150 MW each. All major Civil works related to commissioning of project almost completed. Erection of Radial Gates of Bichom Dam completed. All Units Boxed up. Leakage observed in penstocks during water filling. The

project is scheduled for commissioning in year 2018-19.

**(ii) Pare HEP (2x55 = 110 MW), Arunachal Pradesh**

The Pare H E Project is located in the Papum Pare District of Arunachal Pradesh on river Dikrong which is tributary of river Brahmaputra. The CEA concurrence was accorded on 24<sup>th</sup> Sept., 2007. The CCEA clearance was accorded on 4.12.2008 at an estimated cost of Rs. 573.99 crores. The project would generate annual energy of 506.42 GWh. The proposed revised cost of the project is Rs. 1337.76 crores (January, 2016 price level).

The project envisages construction of concrete gravity Dam, HRT, diversion tunnel and surface power house having Vertical Francis turbine for 2 units of 55 MW each.

Civil works have been awarded on 31.8.2009 to M/s H.C.C. HM works have been awarded to M/s Precision Infratech Ltd, Ahmedabad and EM work has been awarded to M/s Andritz Hydro Pvt. Ltd. & M/s Areva T&D India Ltd.

All major Civil works related to commissioning of project almost completed. Erection of Radial Gates of Dam (2 nos.) is in progress. One gate erected. All Units Boxed up. Leakage observed in Diversion Tunnel during water filling.

The project is scheduled for commissioning in year 2018-19.

**(A) NHPC Projects (Hydro)**

**(I) Subansiri Lower HEP (8x250 = 2000 MW), Arunachal Pradesh**

The project is located in the districts of Lower Subansiri/Dhemaji in Arunachal

Pradesh/Assam on river Subansiri. The project was Techno-Economically cleared by CEA on 13.01.2003. The CCEA clearance was accorded on 09.09.2003 for an estimated cost of Rs. 6285.33 crores with the schedule commissioning of the project in September, 2010. The design energy is 7421.59 GWh. The anticipated cost of the project is Rs. 18559 crores at April-2017 price level.

The Project envisages construction of concrete gravity dam, horse shoe type head race tunnels, circular steel lined pressure shaft and surface power house having Francis turbine driven 8 nos. generating sets of 250 MW each.

Major civil works have been awarded to M/s. BGS-SGS-Soma Joint Venture and Larsen & Toubro Ltd. Chennai respectively on 19.12.2003. E&M works has been awarded to Consortium of M/s Alstom Power Hydraulique, France and Alstom Projects India Ltd. New Delhi on 11.02.2005. Hydro-Mechanical Package awarded to Texmaco on 19.06.2006.

River diverted on 25.12.2007. Civil works of Dam, HRT, surge tunnel, presume shaft, Power House etc. were in progress.

Work stopped since 16.12.11 due to agitation launched by various activists against construction of Subansiri Lower HE Project. In this regard, as decided in the tripartite meeting dated 06.12.13, discussions between Expert Group formed at the request of AASU (All Assam Students Union) and Experts of Govt. of India & NHPC was held on 23.12.13. Last meeting between Expert Group of Assam and Experts of Govt. of India was held on 02.06.14 at Guwahati. Thereafter, meetings with Expert Group of Assam on 10.12.2014 and with various

Stakeholders of Subansiri Lower Project on 11.12.2014 were held to discuss the issues. The meetings were Co-chaired by Hon'ble MOS (I/C) for Power, Coal and New & Renewable Energy and Hon'ble MOS (I/C) for Skill Development, Entrepreneurship, Youth Affairs & Sports.

As decided in stakeholders meeting on 11.12.2014, a Project oversight Committee (POC) was constituted vide MoP's OM dated 13.01.2015. Due to difference in opinion on some issues mainly seismic issues, the Expert Group of Assam has submitted the final report to MoP & members of POC from Government of India have also submitted a separate report to MoP in Jan / Feb'2016.

Matter related to Subansiri Lower HEP was being heard by Hon'ble National Green Tribunal (NGT), Kolkata. The judgment has been pronounced by NGT Kolkata on 16.10.2017.

“In this judgement, NGT has directed MOEF&CC to constitute a committee of three expert members from the field of Seismology, Geology and Hydrology and one of these members shall be from Northeast to examine the entire matter and reports of various committees constituted. The Terms of Reference (TOR) of the committee will be same as made to POC as contained in OM no. 2/5/2002-NHPC dated 13.01.2005. The MOEF&CC shall constitute the Committee within one month and the committee shall give its report in three months from the constitution of the committee to MOEF&CC which will be placed before Expert Appraisal Committee (EAC) for appraisal under Environment Impact Assessment (EIA) Notification 2006. EAC shall complete the appraisal within 60 days and place it

before the competent authority for final decision.”

Subsequently, MoEF&CC has constituted a Committee consisting of three expert members vide order dated 27.11.2017. The Committee has to give its report within 3 months from date of issue of order. The Committee held its first meeting on 21.12.2017 and 22.12.2017 at New Delhi with NHPC and members of POC of Govt. of India and second meeting on 16.01.2018 at New Delhi with representatives from CEA, CWC, GSI & CSMRS.

In the meantime, the Applicant (Sh. Aabhijeet Sharma) raised objection in NGT, Kolkata on the constitution of committee by Ministry of Environment, Forest & Climate Change (MoEF &CC). The matter was heard by NGT, Kolkata on 10.01.2018.

NGT directed the MoEF to consider those objections and place on record their contention on the wisdom in the continuing with the committee and directed to file an affidavit before next date of hearing.

Signing of MOA with Govt. of Assam is still pending. NHPC had sent the draft MOA, approved by MOP, to the States of Assam and Arunachal Pradesh in April-03 for their consent / signing of Agreement. The MOA with Arunachal Pradesh Government has already been signed on 27.1.2010.

The project is now scheduled for commissioning in year 2022-23 (Subject to re-start of works).

#### 11.4.2 Private Sector Projects

- (I) **Gongri HEP (2x72 = 144 MW), Arunachal Pradesh, M/s Dirang Energy Pvt. Ltd.**

Gongri H.E. Project is located in West Kameng District of Arunachal Pradesh. The project is under execution by M/s Dirang Energy Pvt. Ltd.(M/s DEPL). Estimated cost of the project is Rs. 1436.27 crores at May-2012 price level.

The Project envisages construction of a Barrage, Modified horseshoe type HRT, Surge Shaft, Pressure Shaft and a surface power house having Francis turbine for 2 units of 72MW each.

EPC contract for all works have been awarded to M/s Patel Engineering Ltd. in December, 2011. Works could be started only in May/June, 2014 after obtaining consent to establish from State Pollution Control Board in May, 2014.

Civil works of barrage & Power house were in progress. Construction works stalled since October, 2016 due to fund constraints with the developer.

The project is likely to be commissioned in year 2021-22 (subject to restart of works).

## 11.5 Status of Various Hydro Power Projects in North-Eastern Region Appraised by CEA

### 11.5.1 Central Sector Projects

#### (A) Sanctioned Projects

##### (i) Kameng HEP (4 x 150 = 600 MW), Arunachal Pradesh, NEEPCO.

Kameng H.E. Project was accorded TEC by CEA on 30.04.1991. The CCEA clearance was accorded on 02.12.2004. The approved cost of the project is Rs. 2496.90 crores (at March, 2004 price level). The design annual energy is 3353 GWh in a 90% dependable year. The environmental and forest clearance was obtained on 29.03.2001 & 03.8.2000 respectively.

Revised cost estimates at March, 2015 price level submitted by NEEPCO was vetted by CEA amounting to Rs. 4724.67 crores as Hard Cost and Total Cost as Rs. 6179.96 crores vide CEA letter dated 18.03.2016.

##### (ii) Tuirial HEP (2x30=60 MW), Mizoram, NEEPCO

The project was cleared by CEA in July, 1998 at an estimated cost of Rs.368.72 crores with likely completion by 2006-07. Project was to be financed substantially under Loan assistance of 11,695 Million Japanese Yen from Japan Bank of International Co-operation (JICA). This project was under execution and subsequently put on hold since June, 2004 due to poor law & order conditions and agitation by claimants of crop compensation.

Continuation or otherwise of the project was reviewed due to increase in the project cost and resumption of work was dependent upon viability of the project. CEA on 3.11.05 informed MOP that the present day cost of the project at October 2004 price level was likely to be Rs.687.80 crores (including IDC of Rs. 40.05 crores and financing charges Rs. 0.16 crores). The first year tariff at this cost being Rs. 3.69/Kwh., project at this cost/tariff appeared unviable. In the meantime, JICA discontinued loan and requested for prepayment of entire outstanding amount.

Efforts were made to revive the project and the revised cost estimates were vetted by CEA a number of times and lastly vetted on 26.4.10 for the Present day Hard cost of Rs. 877.06 Crs at March, 10 P.L. PIB meeting was held on 4<sup>th</sup> June 2010 which recommended the project for CCEA approval.



CCEA approval was accorded to the project on 14.1.2011 for Rs.913.63 crores including IDC of Rs.36.57 crores at March, 2010 Price Level. The financial pattern of Rs.913.63 crores comprises of (i) Equity of Rs. 137.04 Crs. (ii) Loan from financial institutions amounting to Rs. 184.63 Crs. (iii) Subordinate loan from Govt. of India amounting to Rs. 291.96 Crs. and (iv) Grant from DoNER amounting to Rs.300 Crs.

Revised cost estimates of the project at December, 2014 price level submitted by NEEPCO was vetted by CEA vide letter dated 19.02.2016 amounting to Rs.1294.75 crores as Hard Cost.

Revised cost estimates at December, 2015 price level submitted by NEEPCO was vetted by CEA amounting to Rs. 1263.33 crores as Hard Cost vide CEA letter dated 20.01.2017.

**(iii) Pare HEP(2x55=110MW), Arunachal Pradesh, NEEPCO.**

Pare HEP was accorded concurrence by CEA on 24<sup>th</sup> Sept. 2007 for an estimated present day cost of Rs.553.25 crores including IDC & FC of Rs.49.26 crores at June 2007 Price Level.

CCEA approval was accorded to the project on 4.12.2008 for Rs.573.99 crores including IDC of Rs.67.66 crores and FC of Rs.0.40 crores at June, 2007 Price Level. The completion cost considering 44 months as construction period is estimated as Rs.674.45 crores including IDC as Rs.76.52 crores and FC as Rs.0.47 crores. The project is currently under execution.

Revised cost estimates at December, 2014 price level submitted by NEEPCO was vetted by CEA vide letter dated 30.10.2015 amounting to Rs. 1163.02

crores as Hard Cost and Total Cost as Rs. 1262.27 crores vide letter dated 28.12.2015.

Revised cost estimates at January,2016 price level submitted by NEEPCO was vetted by CEA vide letter dated 26.09.2016 amounting to Rs. 1192.00 crores as Hard Cost and Total Cost as Rs. 1337.76 crores vide letter dated 30.11.2016.

**(iv) Subansiri Lower (8x250=2000 MW), Arunachal Pradesh, NHPC.**

Subansiri Lower HE Project located in Lower Subansiri District of Arunachal Pradesh was accorded concurrence of CEA on 13.01.2003 for an estimated cost of Rs. 6608.68 Crores including IDC and FC of Rs. 705.58 Crores at December, 2002 price level.

CCEA approval was accorded to the project on 9.09.2003 for Rs. 6285.33 Crores including IDC and FC of Rs. 670.92 Crores at December, 2002 price level.

After CCEA approval the project was taken up for construction however, construction works of project works are stopped since December, 2011 due to agitation by various activists fearing dam safety and downstream impacts of dam. Case in Hon'ble NGT, Kolkata Bench. Likely commissioning of the project is 4 years after restart of works.

Memorandum of Changes (MoC) has been approved by CEA on dated 15.03.2018. Revised cost estimates at April,2017 price level has been taken up for examination on 21.03.2018.

**(B) CEA concurred Projects, yet to be taken under construction.**

**(i) Loktak Down Stream (66 MW), Manipur, LDHCL**

The project to be executed by NHPC, was cleared by CEA for an Installed Capacity of (3x30=90 MW) on 31.12.1999 at an estimated cost of Rs.78.62 crores including IDC of Rs.46.95 crores (April 1999 price level). The environmental clearance was granted by MoEF on 4.2.99 and forest clearance on 3.1.97.

The project is now proposed to be executed by a Joint Venture between NHPC and Government of Manipur with revised capacity of 66 MW. CEA accorded concurrence on 15.11.2006 to the revised proposal with reduced capacity of 66 MW.

MoU and Promoters' Agreement for implementation of the project on joint venture basis were signed by Govt. of Manipur with NHPC on 14.9.2007 and 26.9.2008 respectively. The "Loktak Downstream Hydroelectric Corporation Limited (LDHCL)" has also been incorporated on 23.10.2009.

Concurrence was transferred from NHPC to LDHCL on 06.08.2012. The validity of concurrence was extended by CEA upto 14.11.14 vide letter dated 24.01.13

Environment clearance was accorded by MOEF on 16.01.2013. In-principle forest clearance stage-I was accorded by MOEF on dated 03.03.11 and Forest clearance Stage-II accorded on 22.12.2014.

The revised DPR was submitted on 25.3.2015 for fresh concurrence. The DPR has been concurred by CEA on 05.05.2017 at estimated present day

cost of Rs. 1352.77 Crores (including IDC&FC) at February, 2015 price level.

**(ii) Tawang H.E Project St-I (3x200=600 MW) in Ar. Pradesh by NHPC Ltd.**

Project was accorded concurrence by CEA on 10.10.2011 at an estimated cost of Rs. 4824.01 Crores (including IDC & FC) at May, 2010 price level.

Environment clearance was accorded on 10.06.2011. Forest clearance Stage-I & II yet to be obtained.

**(iii) Tawang H.E Project St.-II (4x200=800 MW) in Ar. Pradesh by NHPC Ltd.**

The project was concurred by CEA on 22.9.2011 at an estimated cost of Rs. 6112.3 crores (including IDC & FC) at May, 2010 price level.

Project was accorded environment clearance on 10.06.2011.

MoEF vide letter dated 08.01.2014 has accorded Forest Clearance (Stage – I) for diversion of 116.62 ha forest land for the project. Forest clearance stage-II yet to be obtained.

**(iv) Dibang Multipurpose Project (12x240 = 2880 MW) – Arunachal Pradesh**

Dibang MPP was accorded concurrence by CEA with IC of 3000 MW on 23.1.2008. The estimated present day cost of the project at Nov., 2007 price level including IDC and FC without provision for external roads and bridges is Rs.15886.39 crores and with external roads and bridges is Rs. 16425.65 crores.

**E&F clearance:** Environment clearance was accorded on 19.5.2015.

MoEF & CC accorded Forest Clearance Stage – I on 15.4.2015, with reduction of Dam height by 10 m in order to reduce the submergence area. FAC has recommended the proposal with 10 m reduction in Dam height, necessitating fresh DPR and fresh TEC by CEA.

The fresh DPR was submitted by NHPC in September, 2016. The DPR has been concurred by CEA on 18.09.2017 at estimated present day cost of Rs. 25732.79 Crores (July, 2016 price level) including Power Component of Rs. 17510.84 Crs., Flood Moderation component Rs. 4627.8 Crs., IDC of Rs. 3557.22 Crs. and FC of Rs. 36.93 Crores.

#### **11.5.2 State Sector – CEA concurred Projects, yet to be taken under construction.**

##### **(i) Lower Kopili HE Project (2x55+1x5+2x2.5 = 120MW) in Assam by M/s APGCL**

Lower Kopili H.E. Project was accorded concurrence by CEA on 24.5.2016 at an estimated completed cost of Rs. 1115.91 Crores.

EC & FC are yet to be obtained.

#### **11.5.3 Private Sector- CEA concurred Projects, yet to be taken under construction.**

##### **i) Demwe Lower HE Project (5x342 + 1x40=1750 MW), Arunachal Pradesh by M/s ADPL**

Demwe Lower HE Project was accorded concurrence by CEA on 20.11.2009 for an estimated cost of Rs. 13144.91 Crores (Completion Cost).

MoEF has accorded environmental clearance to the project on 12.2.10.

Forest clearances stage-II has been accorded on 03.05.2013.

As per NGT order dated 24.10.2017, NBWL issue to be reconsidered by MoEF&CC.

##### **ii) Lower Siang HE Project (9x300=2700 MW), Ar. Pradesh by M/s JAPL**

Lower Siang HE Project was accorded concurrence by CEA on 15.02.2010 for an estimated cost of Rs. 19990.74 Crores (Completion Cost).

EC & FC yet to be obtained. TOR was approved for IC of 2700 MW on 03.08.10. Public hearing could not be conducted due to local protest.

##### **iii) Dibbin H.E. Project (2x60=120MW) in Arunachal Pradesh by M/s KSK Dibbin Hydro Power Private Limited**

Dibbin H.E. Project was accorded concurrence on 4.02.2009 for an estimated completed cost of Rs. 728.54 Crores.

MoEF has accorded environmental clearance to the project on 23.7.2012. Forest clearance (Stage-I) was accorded by MoEF on 7<sup>th</sup> Feb, 2012. FC Stage – II is awaited.

##### **iv) Nafra H.E. Project (2x60=120 MW) - Arunachal Pradesh by M/s SEW Nafra Power Corporation Private Limited**

Nafra H.E. Project was accorded concurrence by CEA on 11<sup>th</sup> February, 2011 at an Estimated completed cost of 848.22 Crores including IDC & FC of 106.60 Crores and 5.94 Crores.

Project was accorded environmental clearance by MOE&F on 17.01.2011 and Forest clearance in June, 2012.

- v) **Nyamjang Chhu H.E. Project (6x130=780MW) in Arunachal Pradesh by M/s NJC Hydro power Limited**
- Nyamjang Chhu H.E. Project was accorded concurrence by CEA on 24.03.2011 for an estimated completed cost of Rs. 6268.26 Crores (without Mega Power Project status) and Rs. 6115.60 Crores (with Mega Power Project status).
- MoEF accorded environmental clearance on 19.04.2012. Forest clearance (Stage-I) was accorded by MoEF on 9.4.2012. Stage – II clearance awaited
- 31.01.17. Letter will be issued after FC-I, FC-I & FC-II yet to be obtained.
- ix) **Talong Londa HE Project (3x75 = 225 MW) in Arunachal Pradesh by GMR**
- Talong Londa H.E. Project was accorded concurrence by CEA on 16<sup>th</sup> Aug , 2013 at an estimated completed cost of Rs. 2172.88 Crores.
- EC accorded on 07.08.2015. FC-I & FC-II yet to be obtained.
- x) **Naying HE Project (4x250 =1000 MW) in Arunachal Pradesh by NDSCPL**
- Naying H.E. Project was accorded concurrence by CEA on 11<sup>th</sup> Sept , 2013 at an estimated completed cost of Rs. 9301.11 Crores.
- EC & FC yet to be obtained.
- vi) **Tato-II H.E Project (4x175= 700MW) in Arunachal Pradesh by M/s THPPL**
- Tato-II H.E. Project was accorded concurrence by CEA on 22<sup>nd</sup> May, 2012 at an Estimated completed cost of Rs. 5616.20 Crores.
- xi) **Siyom HE Project (6x166.67=1000 MW) in Arunachal Pradesh by SHPPL**
- Siyom H.E. Project was accorded concurrence by CEA on 17<sup>th</sup> Dec , 2013 at an estimated completed cost of Rs. 12100.00 Crores.
- EC accorded on 31.01.08. FC yet to be obtained.
- MoEF accorded environmental clearance on 27.6.2011. Forest clearance Stage-I is awaited.
- vii) **Hirong HE Project (4x125=500 MW) in Arunachal Pradesh by M/s JAPL**
- Hirong H.E. Project was accorded concurrence by CEA on 10<sup>th</sup> April , 2013 at an estimated completed cost of Rs. 5532.63 Crores. EC & FC are yet to be obtained.
- xii) **Kalai-II HE Project (6x200=1200 MW) in Arunachal Pradesh by KPPL**
- Kalai – II H.E. Project was accorded concurrence by CEA on 27<sup>th</sup> March , 2015 at an estimated completed cost of Rs. 14199.64 Crores.
- EC has been accorded on 20.05.2015. FC-I&II are yet to be obtained.
- viii) **Etalin HE Project (10x307 +1x9.6 + 1x7.4 = 3097 MW) in Arunachal Pradesh by M/s EHEPCL**
- Etalin H.E. Project was accorded concurrence by CEA on 12<sup>th</sup> July , 2013 at an Estimated completed cost of Rs. 25296.95 Crores.
- EC recommended by EAC on
- xiii) **Kynshi-I HE Project (2x135=270 MW) in Meghalya by M/s AKPPL**
- Kynshi –I H.E. Project was accorded

concurrency by CEA on 31st March, 2015 at an estimated completed cost of Rs. 3154.37 Crores.

EC & FC are yet to be obtained.

**xiv) Heo HE Project (3x80 = 240MW) in Ar. Pradesh by M/s HHPPL**

Heo H.E. Project was accorded concurrency by CEA on 28.07.2015 at an estimated completed cost of Rs. 1614.35 Crores.

Environmental Clearance accorded on 10.11.15. FC-I accorded on 27.10.15. FC-II yet to be obtained.

**xv) Tato – I HE Project (3x62 = 186MW) in Ar. Pradesh by M/s SHPPL**

Tato–I H.E. Project was accorded concurrency by CEA on 28.10.2015 at an estimated completed cost of Rs. 1493.55 Crores.

Environmental Clearance accorded on 10.11.15. FC-I accorded on 27.10.15. FC-II yet to be obtained.

**xvi) Attunli HE Project (4x170 = 680 MW) in Ar. Pradesh By M/s AHPCL**

Attunli H.E. Project was accorded concurrency by CEA on 15.03.2018 at an estimated completed cost of Rs. 6111.28 Crores.

EC & FC yet to be obtained.

**11.6 Thermal Power Development Activities in North Eastern Region - Proposed Thermal Power Projects in North Eastern Region**

The following thermal schemes are proposed in North Eastern region:

**(i) Margherita TPP – 2x800 MW by M/s. APGCL in Assam**

M/s. Assam Power Generation

Corporation (APGCL) has a proposal to set up a 2x800 MW Thermal Power Project at Margherita in Assam. DPR for the project is under preparation and coal linkage is yet to be tied-up.

**(ii) Amguri TPP - 100 MW by M/s. APGCL in Assam**

M/s APGCL had a proposal to set up a Gas Based Thermal Power Plant in Assam. Implementation of this proposed 100MW Gas Based Power Project is stalled due to fuel tie up issues. M/s APGCL has now initiated setting up of 80 MW Solar Power Park at the available land under their possession. However, 30 Acres of land is kept reserved for development of the Gas Based Power Project

**11.7 Development of Transmission System in N.E. Region**

**11.7.1 Examination of Detailed Project Reports (DPRs) for transmission system of Hydro Power Projects as part of concurrence by CEA**

**Following DPRs were examined**

- I) Attunli HEP (680 MW) in Arunachal Pradesh by M/s Attunli Hydro Electric Power Company Limited
- ii) Tagurshit HEP (3x24.67=74MW) in Arunachal Pradesh by M/s L&T Arunachal Hydropower Limited
- iii) Dibang Multipurpose Project in Arunachal Pradesh (12x240W) by NHPC
- iv) Umngot HEP (210 MW) in Meghalaya by MEPGCL
- v) Mago Chu (3x32=96 MW) HEP, in Arunachal Pradesh by M/s SEW Mago Chu Power Corporation Limited

**11.7.2 Grant of prior approval of**

### Government to transmission proposals under Section 68 of Electricity Act, 2003 during 2017-18.

- North Eastern Region Strengthening Scheme (NERSS-VI) (Modified)

### 11.7.3 Grant of authorization to transmission proposals for Section 164 of Electricity Act, 2003 during 2017-18.

- To M/s Kohima - Mariani Transmission Limited (KMTL) for “North Eastern Region Strengthening Scheme (NERSS-VI)

### 11.8 Hydro Power Generation Performance

Hydro Power generation in the North Eastern Region during the year 2017-18 was 5666.08 MU against a target of 5401 MU, which is 4.91 % more.

### 11.9 R&M Schemes (Hydro) of North Eastern Region

Eleven (11) existing hydro schemes of North Eastern Region with an aggregate installed capacity of 539 MW have been identified for R&M works to accrue a benefit of 292 MW. The R&M activities of eight (8) schemes have already been completed at an actual expenditure of about Rs. 277 Crores to accrue a benefit of 121 MW. The remaining three (3) schemes having an aggregate installed capacity of 180 MW are under various stages of implementation and are likely to accrue a benefit of 171 MW at an estimated cost of about Rs. 663 Crores. The scheme-wise status of the R&M works of the hydro schemes of North Eastern Region **as on 31.03.2018** is given hereunder :

| S. No.                                   | Name of Scheme, Agency, State                 | Installed Cap.(MW) | Actual Cost (Rs. Crs.) | Benefits (MW)  | Status   |
|--|---|--------------------|------------------------|----------------|--|
| <b>A. Schemes Completed</b>              |   |                    |                        |                |  |
| 1.                                       | Khandong, U-1, NEEPCO, Meghalaya              | 1x25               | 0.62                   | 25 (Res.)      | U-1 Restoration works completed in 1991-92   |
| 2.                                       | Gumti, TPGL, Tripura                          | 3x5                | 17.50                  | -              | R&M works completed in 1994-95   |
| 3.                                       | Khandong, NEEPCO, Meghalaya                   | 2x25               | 3.35                   | -              | R&M works completed in 2003-04   |
| 4.                                       | Umium St.I, MePGCL, Meghalaya                 | 4x9                | 84.21                  | 36 (LE)        | RM&LE works completed in 2002-03   |
| 5.                                       | Loktak, NHPC, Manipur                         | 3x30 (Derated)     | 18.55                  | 15(Res.)       | R&M works completed in 2011-12   |
| 6.                                       | Umium St.II, MePGCL, Meghalaya                | 2x9                | 90.46                  | 18(LE) + 2 (U) | R&M works completed in 2011-12   |
| 7.                                       | Kopili, NEEPCO, Assam                         | 2x50               | 50.92                  | -              | R&M works completed in 2014-15   |
| 8.                                       | Khandong, NEEPCO, Assam                       | 1x25               | 29.18                  | 25(LE)         | R&M works completed in 2014-15   |
| <b>Sub Total(A):</b>                     |   | <b>359</b>         | <b>294.79</b>          | <b>121</b>     |  |
| <b>B. Ongoing – Under Implementation</b> |   |                    |                        |                |  |
| 9.                                       | Kyrdemkulai (Umium St.III), MePGCL, Meghalaya | 2x30               | 344                    | 60(LE) + 6(U)  | DPR for life extension is under preparation. R&M works planned for completion in 2021-22 |

|     |                       |            |               |            |   |   |
|-----|-----------------------|------------|---------------|------------|---|---|
| 10. | Gumti, TPGL, Tripura  | 3x5        | 58.61         | -          | - | DPR for life extension is under preparation. R&M works planned for completion in 2021-22  |
| 11. | Loktak, NHPC, Manipur | 3x35       | 260.47        | 105 (LE)   |   | DPR for life extension is under examination. R&M works planned for completion in 2022-23. |
|     | <b>Sub Total(B):</b>  | <b>180</b> | <b>663.08</b> | <b>171</b> |   |   |
|     | <b>Total(A+B):</b>    | <b>539</b> | <b>957.87</b> | <b>292</b> |   |   |

Abbreviations: MW – Mega Watt; Res. – Restoration; U – Uprating; LE – Life Extension

### 11.10 Installed Capacity in the N.E. Region

The total installed capacity in the Region as on 31.03.2018 is as under:

| Sector       | Installed Capacity (MW) |
|--------------|-------------------------|
| Hydro        | 1342.00                 |
| Thermal      | 2292.07                 |
| RES          | 282.56                  |
| Nuclear      | -                       |
| <b>Total</b> | <b>3916.63</b>          |

## CHAPTER – 12

# TRAINING AND HUMAN RESOURCE DEVELOPMENT

### 12.1 Training of Manpower in CEA

Human Resource is essential for carrying out any business or service of an organization and the same is required to be developed to produce a quality product/service at a reasonable price. To attain this objective, the technical, managerial and behavioral competencies of the human resources are developed and enhanced through training. Keeping this objective in view, HRD Division, CEA has been organizing various training programmes in technical, managerial, IT, health and other areas to keep the personnel abreast of the latest technological breakthrough and bringing about attitudinal changes in consonance with the need of rapidly changing era of globalization. HRD Division has also been making efforts to keep stock of the infrastructure available for the development of human resources in the power sector. CEA has been following up with the utilities/organizations on the status of implementation of the National Training Policy for the power sector. To fulfill its statutory duty under Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations 2010, CEA has been sending teams to power sector institutes for their evaluation in terms of infrastructure, utilization & quality of training programmes and facilitate CEA's accreditation for them in line with the CEA Guidelines for recognition for training institutes for power sector. CEA has been advising /recommending various measures to the training institutes/power sector organizations for improvement in the training infrastructure and methodologies for enhancing the skills and productivity of the personnel.

It has been the endeavor of CEA management to impart at least one-week

training annually to each employee of CEA.

### 12.2 Preparation of Training Policy/ Cadre Training Policy for Central Power Engineering Service (CPES) officers of CEA

Training Policy for technical Group A & B officers of CEA is being prepared in line with the draft National Training Policy for Power Sector. This Policy broadly covers the training needs as well as field exposure for officers of all levels in the Central Electricity Authority (CEA). The objective of this training programme is to enable officers of CEA to sharpen their skills and improve their effectiveness in discharging the tasks and responsibilities, covering the following broad areas :

- Providing practical exposure to the officers in the area of the power sector construction, operation & maintenance (O&M) for further enhancing the technical competencies.
- Enabling the officers to draw plan, advise and monitor power sector projects with the strong background knowledge/experience of the sector.
- Enhancing the managerial competencies of the officers.
- Familiarizing the officers with the best practices in the application of advanced technologies.

### 12.3 Induction Training programme

Induction Training programme has been organized for the 30 nos. Assistant Directors of the CEA during the year 2017-18. This training programme was conducted for 34 weeks from January,2018 to August, 2018. Under this training programme the officers have undergone classroom training at National Power Training Institute, Faridabad,



On-Job Training at various organizations like NTPC Dadri, BBMB Nangal, PGCIL Agra, etc. and plant visits to Thermal, Hydel, Solar & Wind power plants and power distribution sub-stations etc. This training has given the officers an immense theoretical and practical exposure to the latest technology and trends in the power sector.

#### 12.4 Refresher Training programme

Various refresher training programmes for CEA officers were conducted at professional institutes of national and international repute like CBIP, ISTM, CIGRE and ESCI.

The officers/officials were deputed for various in-service refresher training programmes, technical courses, workshops, seminars, conferences etc., at ISTM, CBIP, NPTI, ESCI, CIGRE, CPU, IEEE etc.

The Man-days for all programmes conducted in 2017-18 were 669.

#### 12.5 In-house training programme-

Presentations were given by various industries/ organizations to keep the CEA officers abreast of latest technologies. The details are as under -

1. Presentation on “Technology Innovations taking place in the Transmission sector (Including global best practices)” by M/s. Sterlite Power Transmission Limited in October 2017
2. Presentation on “Use of Vibration Recorder to counter Aeolian vibration on transmission lines” by M/s. Telegence Powercomm Pvt. Ltd in November 2017.
3. Presentation on “Solutions for Remote Monitoring of Energy Meters” by M/s. Wise Things Solutions Pvt. Ltd., in November-2017.

4. Presentation on “New Technology AdvX™ – for Air Preheaters – in Thermal Power Plants” by M/s LJUNSTRÖM., in November 2016.
5. Presentation on “Anticorrosion/ erosion resistant coating of absorbers, ducts, chimney etc. in Flue Gas Desulphurization in Thermal Power Plants” by M/s Arudra Engineers Pvt Ltd., in February 2018.
6. Presentation on “Floating Solar Technology – an innovation” by M/s Yellow Tropus Pvt. Ltd., in February 2018.
7. Presentation on “On-line condition monitoring of Hydro Power Generating Systems” by M/s Logic Plus Plus India Pvt. Ltd., in February 2018.
8. Presentation on “Implementation of Smart Security Seals and Software as a Service for Power Sector” by M/s Secure Seals Pvt Ltd., in March 2018.

#### 12.6 Foreign Visits/Training programmes for CEA Officers

Foreign training programmes were planned, processed and conducted during the year 2017 -18 for CEA engineers to give them exposure to technological trends/ bench marking followed in developed countries. A total of 38 nos. officers of CEA at various levels visited foreign nations and the details of officers who visited foreign countries during the year 2017 -18 are given in **Annexure 12A**.

#### 12.7 Training Under Apprentice Act, 2015

17 Graduate (Engineering), and 2 Diploma apprentices have undergone training in CEA under the Apprentice Act, 2015 during the year 2017-18.

### 12.8 Recognition of Training Institutes

For ensuring the development of the training infrastructure in the Power Sector and the implementation of statutory requirements of training as per Central Electricity Authority (Measures relating to the Safety and Electric Supply) Regulations 2010, Power Training

Institutes/Centres of various SEBs/Utilities are visited by CEA officers, appraised, graded and then issued recognition on meeting the prescribed norms. The following seven (7) nos. Training Institutes/Centres were inspected and recommended for recognition/renewal of recognition to Ministry of Power during the year 2017-18:

| S.No | Name of the Institute/Centre   |
|------|--|
| 1.   | Distribution Training Institute, CESC, Kolkata   |
| 2.   | Regional Training Centre, MSETCL, Padhge, Maharashtra  |
| 3.   | Power Generating Training Institute, Korba TPS, Chattisgarh SEB, Korba (East) Chhatisgarh      |
| 4.   | Regional Training Centre, MSETCL, Bableshwar, Maharashtra                                      |
| 5.   | Rosa Learning and Development Centre, Shahjahanpur, UP   |
| 6.   | MERC Training Academy, Chennai   |
| 7.   | Swami Vivekananda Institute of Power Training and Applied Science Research, Pokhariput, Odisha |

\*\*\*\*\*

**Annexure 2A**

**Plant-wise details of the Coal receipt and consumption during 2017-18**

| Region          | Name of the Plant  | Capacity (MW) | Receipt  |         |           |        |        | Total Receipt | Total Consumption |
|-----------------|--------------------|---------------|----------|---------|-----------|--------|--------|---------------|-------------------|
|                 |                    |               | CIL/SCCL | Captive | E-Auction | Import | Others |               |                   |
| <b>Northern</b> |                    |               |          |         |           |        |        |               |                   |
| 1               | ANPARA C TPS       | 1200          | 4899     | 0       | 1         | 0      | 0      | 4900          | 5051              |
| 2               | ANPARA TPS         | 2630          | 11332    | 0       | 0         | 0      | 0      | 11332         | 11297             |
| 3               | BADARPUR TPS       | 705           | 1103     | 0       | 0         | 0      | 0      | 1103          | 1129              |
| 4               | BARKHERA TPS       | 90            | 99       | 0       | 0         | 0      | 0      | 99            | 154               |
| 5               | CHHABRA TPP        | 1660          | 1356     | 2994    | 0         | 0      | 0      | 4350          | 3736              |
| 6               | DADRI (NCTPP)      | 1820          | 6156     | 0       | 0         | 0      | 0      | 6156          | 6568              |
| 7               | GH TPS (LEH.MOH.)  | 920           | 1494     | 0       | 0         | 0      | 0      | 1494          | 1795              |
| 8               | GND TPS(BHATINDA)  | 440           | 123      | 0       | 0         | 0      | 0      | 123           | 174               |
| 9               | GOINDWAL SAHIB TPP | 540           | 151      | 0       | 740       | 0      | 0      | 891           | 931               |
| 10              | HARDUAGANJ TPS     | 605           | 2088     | 0       | 0         | 0      | 0      | 2088          | 2354              |
| 11              | INDIRA GANDHI STPP | 1500          | 4630     | 0       | 0         | 0      | 0      | 4630          | 5073              |
| 12              | KALISINDH TPS      | 1200          | 191      | 3501    | 0         | 0      | 0      | 3692          | 3788              |
| 13              | KAWAI TPS          | 1320          | 80       | 0       | 637       | 1662   | 0      | 2379          | 2562              |
| 14              | KHAMBARKHERA TPS   | 90            | 91       | 0       | 0         | 0      | 0      | 91            | 147               |
| 15              | KOTA TPS           | 1240          | 4163     | 336     | 0         | 0      | 0      | 4499          | 4935              |
| 16              | KUNDARKI TPS       | 90            | 112      | 0       | 0         | 0      | 0      | 112           | 145               |
| 17              | LALITPUR TPS       | 1980          | 0        | 0       | 5311      | 0      | 0      | 5311          | 5213              |
| 18              | MAHATMA GANDHI TPS | 1320          | 3619     | 0       | 0         | 0      | 0      | 3619          | 4400              |

| Region                   | Name of the Plant | Capacity (MW) | Receipt       |             |             |             |          | Total Receipt | Total Consumption |
|--------------------------|-------------------|---------------|---------------|-------------|-------------|-------------|----------|---------------|-------------------|
|                          |                   |               | CIL/SCCL      | Captive     | E-Auction   | Import      | Others   |               |                   |
| 19                       | MAQSOODPUR TPS    | 90            | 85            | 0           | 0           | 0           | 0        | 85            | 138               |
| 20                       | OBRA TPS          | 1188          | 3498          | 0           | 0           | 0           | 0        | 3498          | 3283              |
| 21                       | PANIPAT TPS       | 920           | 1287          | 0           | 0           | 0           | 0        | 1287          | 1714              |
| 22                       | PANKI TPS         | 210           | 175           | 0           | 0           | 0           | 0        | 175           | 305               |
| 23                       | PARICHHA TPS      | 1140          | 4178          | 0           | 0           | 0           | 0        | 4178          | 4324              |
| 24                       | PRAYAGRAJ TPP     | 1980          | 3154          | 0           | 620         | 0           | 0        | 3774          | 3583              |
| 25                       | RAJGHAT TPS       | 135           | 0             | 0           | 0           | 0           | 0        | 0             | 0                 |
| 26                       | RAJIV GANDHI TPS  | 1200          | 2720          | 0           | 0           | 0           | 0        | 2720          | 3216              |
| 27                       | RAJPURA TPP       | 1400          | 4128          | 0           | 0           | 514         | 0        | 4642          | 4714              |
| 28                       | RIHAND STPS       | 3000          | 14363         | 0           | 0           | 0           | 0        | 14363         | 14336             |
| 29                       | ROPAR TPS         | 1260          | 1120          | 0           | 0           | 0           | 1        | 1121          | 1522              |
| 30                       | ROSA TPP Ph-I     | 1200          | 3877          | 0           | 256         | 0           | 0        | 4133          | 4848              |
| 31                       | SINGRAULI STPS    | 2000          | 10034         | 0           | 0           | 0           | 0        | 10034         | 10033             |
| 32                       | SURATGARH TPS     | 1500          | 2596          | 132         | 0           | 0           | 0        | 2728          | 3059              |
| 33                       | TALWANDI SABO TPP | 1980          | 4748          | 0           | 0           | 826         | 0        | 5574          | 5830              |
| 34                       | TANDA TPS         | 440           | 1820          | 0           | 0           | 0           | 0        | 1820          | 2108              |
| 35                       | UNCHAHAR TPS      | 1550          | 4277          | 0           | 410         | 0           | 0        | 4687          | 4706              |
| 36                       | UTRAULA TPS       | 90            | 118           | 0           | 0           | 0           | 0        | 118           | 150               |
| 37                       | YAMUNA NAGAR TPS  | 600           | 1816          | 0           | 0           | 0           | 0        | 1816          | 2292              |
| <b>Total of Northern</b> |                   | <b>41233</b>  | <b>105681</b> | <b>6963</b> | <b>7975</b> | <b>3002</b> | <b>1</b> | <b>123622</b> | <b>129613</b>     |

| Region  | Name of the Plant            | Capacity (MW) | Receipt  |         |           |        |        | Total Receipt | Total Consumption |
|---------|------------------------------|---------------|----------|---------|-----------|--------|--------|---------------|-------------------|
|         |                              |               | CIL/SCCL | Captive | E-Auction | Import | Others |               |                   |
| Western |                              |               |          |         |           |        |        |               |                   |
| 38      | AKALTARA TPS                 | 1200          | 0        | 0       | 2758      | 35     | 161    | 2954          | 3623              |
| 39      | AMARAVATI TPS                | 1350          | 2689     | 0       | 0         | 108    | 0      | 2797          | 2837              |
| 40      | AMARKANTAK EXT TPS           | 210           | 985      | 0       | 0         | 0      | 0      | 985           | 957               |
| 41      | ANUPPUR TPP                  | 1200          | 4020     | 0       | 31        | 0      | 0      | 4051          | 4175              |
| 42      | AVANTHA BHANDAR              | 600           | 106      | 0       | 508       | 0      | 0      | 614           | 433               |
| 43      | BALCO TPS                    | 600           | 973      | 0       | 644       | 0      | 0      | 1617          | 1640              |
| 44      | BANDAKHAR TPP                | 300           | 926      | 0       | 689       | 0      | 74     | 1689          | 1688              |
| 45      | BARADARHA TPS                | 1200          | 1770     | 0       | 2923      | 0      | 0      | 4693          | 4649              |
| 46      | BHILAI TPS                   | 500           | 2249     | 0       | 0         | 0      | 0      | 2249          | 2322              |
| 47      | BHUSAWAL TPS                 | 1210          | 5085     | 0       | 0         | 0      | 0      | 5085          | 5106              |
| 48      | BINA TPS                     | 500           | 1226     | 0       | 246       | 0      | 0      | 1472          | 1597              |
| 49      | BUTIBORI TPP                 | 600           | 1266     | 0       | 655       | 83     | 0      | 2004          | 2065              |
| 50      | CHANDRAPUR(MAHARASHTRA) STPS | 2920          | 9890     | 0       | 557       | 0      | 0      | 10447         | 10657             |
| 51      | DAHANU TPS                   | 500           | 1649     | 0       | 0         | 434    | 0      | 2083          | 2170              |
| 52      | DHARIWAL TPP                 | 600           | 1064     | 0       | 220       | 0      | 0      | 1284          | 1319              |
| 53      | DSPM TPS                     | 500           | 2446     | 0       | 0         | 0      | 0      | 2446          | 2549              |
| 54      | GANDHI NAGAR TPS             | 630           | 2122     | 0       | 0         | 208    | 0      | 2330          | 2493              |
| 55      | GMR WARORA TPS               | 600           | 1625     | 0       | 586       | 0      | 0      | 2211          | 2274              |
| 56      | JSW RATNAGIRI TPP            | 1200          | 0        | 0       | 0         | 2535   | 0      | 2535          | 2862              |

| Region | Name of the Plant     | Capacity (MW) | Receipt  |         |           |        |        | Total Receipt | Total Consumption |
|--------|-----------------------|---------------|----------|---------|-----------|--------|--------|---------------|-------------------|
|        |                       |               | CIL/SCCL | Captive | E-Auction | Import | Others |               |                   |
| 57     | KHAPARKHEDA TPS       | 1340          | 4943     | 0       | 0         | 0      | 0      | 4943          | 5235              |
| 58     | KORADI TPS            | 2400          | 6580     | 0       | 0         | 0      | 0      | 6580          | 6895              |
| 59     | KORBA-II              | 440           | 1772     | 0       | 0         | 0      | 0      | 1772          | 1730              |
| 60     | KORBA STPS            | 2600          | 12928    | 0       | 0         | 0      | 0      | 12928         | 13111             |
| 61     | KORBA-WEST TPS        | 1340          | 6447     | 0       | 0         | 0      | 0      | 6447          | 6505              |
| 62     | MAHAN TPP             | 600           | 0        | 0       | 1872      | 0      | 0      | 1872          | 1921              |
| 63     | MARWA TPS             | 1000          | 3831     | 0       | 0         | 0      | 0      | 3831          | 3726              |
| 64     | MAUDA TPS             | 2320          | 4659     | 0       | 909       | 0      | 0      | 5568          | 5655              |
| 65     | MUNDRA TPS            | 4620          | 0        | 0       | 0         | 10966  | 0      | 10966         | 11196             |
| 66     | MUNDRA UMTTP          | 4000          | 0        | 0       | 0         | 11138  | 0      | 11138         | 10799             |
| 67     | NASIK TPS             | 630           | 2211     | 0       | 0         | 0      | 0      | 2211          | 2288              |
| 68     | NAWAPARA TPP          | 600           | 1032     | 0       | 1075      | 0      | 36     | 2143          | 2204              |
| 69     | NIGRI TPP             | 1320          | 0        | 2799    | 1573      | 0      | 0      | 4372          | 4437              |
| 70     | OP JINDAL TPS         | 1000          | 0        | 0       | 3111      | 0      | 0      | 3111          | 3175              |
| 71     | PARAS TPS             | 500           | 2177     | 0       | 0         | 0      | 0      | 2177          | 2293              |
| 72     | PARLI TPS             | 1170          | 2149     | 0       | 0         | 0      | 0      | 2149          | 2231              |
| 73     | PATHADI TPP           | 600           | 2188     | 0       | 449       | 0      | 0      | 2637          | 2605              |
| 74     | RAIKHEDA TPP          | 1370          | 342      | 276     | 227       | 0      | 0      | 845           | 877               |
| 75     | SABARMATI (C STATION) | 422           | 1042     | 0       | 0         | 426    | 0      | 1468          | 1532              |
| 76     | SALAYA TPP            | 1200          | 0        | 0       | 0         | 1169   | 0      | 1169          | 1286              |

| Region                  | Name of the Plant | Capacity (MW) | Receipt       |              |              |              |            | Total Receipt | Total Consumption |
|-------------------------|-------------------|---------------|---------------|--------------|--------------|--------------|------------|---------------|-------------------|
|                         |                   |               | CIL/SCCL      | Captive      | E-Auction    | Import       | Others     |               |                   |
| 77                      | SANJAY GANDHI TPS | 1340          | 5127          | 0            | 0            | 0            | 0          | 5127          | 5143              |
| 78                      | SASAN UMTTP       | 3960          | 0             | 18130        | 0            | 0            | 0          | 18130         | 17983             |
| 79                      | SATPURA TPS       | 1330          | 3273          | 0            | 0            | 0            | 0          | 3273          | 3561              |
| 80                      | SEIONI TPP        | 600           | 892           | 0            | 155          | 0            | 0          | 1047          | 1055              |
| 81                      | SHRI SINGHAJI TPP | 1200          | 2605          | 0            | 0            | 0            | 0          | 2605          | 2604              |
| 82                      | SIKKA REP. TPS    | 500           | 0             | 0            | 0            | 1325         | 0          | 1325          | 1335              |
| 83                      | SIPAT STPS        | 2980          | 13923         | 0            | 0            | 0            | 0          | 13923         | 14055             |
| 84                      | SOLAPUR           | 660           | 606           | 55           | 93           | 0            | 0          | 754           | 776               |
| 85                      | TAMNAR TPP        | 2400          | 2678          | 0            | 2384         | 59           | 0          | 5121          | 5132              |
| 86                      | TIRORA TPS        | 3300          | 8936          | 0            | 811          | 1233         | 0          | 10980         | 11007             |
| 87                      | TROMBAY TPS       | 1250          | 0             | 0            | 0            | 2485         | 0          | 2485          | 2452              |
| 88                      | UCHPINDA TPP      | 1080          | 183           | 0            | 0            | 0            | 0          | 183           | 186               |
| 89                      | UKAI TPS          | 1110          | 3698          | 0            | 0            | 394          | 0          | 4092          | 4285              |
| 90                      | VINDHYACHAL STPS  | 4760          | 25025         | 0            | 0            | 0            | 0          | 25025         | 24489             |
| 91                      | WANAKBORI TPS     | 1470          | 4099          | 0            | 0            | 211          | 0          | 4310          | 5077              |
| 92                      | WARDHA WARORA TPP | 540           | 738           | 0            | 79           | 0            | 0          | 817           | 786               |
| <b>Total of Western</b> |                   | <b>74372</b>  | <b>164175</b> | <b>21260</b> | <b>22555</b> | <b>32809</b> | <b>271</b> | <b>241070</b> | <b>245043</b>     |

| Region          | Name of the Plant         | Capacity (MW) | Receipt  |         |           |        |        | Total Receipt | Total Consumption |
|-----------------|---------------------------|---------------|----------|---------|-----------|--------|--------|---------------|-------------------|
|                 |                           |               | CIL/SCCL | Captive | E-Auction | Import | Others |               |                   |
| <b>Southern</b> |                           |               |          |         |           |        |        |               |                   |
| 93              | BELLARY TPS               | 1700          | 2380     | 0       | 0         | 0      | 0      | 2380          | 2460              |
| 94              | DAMODARAM SANJEEVAIAH TPS | 1600          | 2490     | 0       | 0         | 379    | 0      | 2869          | 2921              |
| 95              | Dr. N.TATA RAO TPS        | 1760          | 8164     | 0       | 0         | 0      | 0      | 8164          | 8536              |
| 96              | ENNORE TPS                | 900           | 0        | 0       | 0         | 0      | 0      | 0             | 0                 |
| 97              | ITPCL TPP                 | 1200          | 0        | 0       | 0         | 3013   | 0      | 3013          | 3114              |
| 98              | KAKATIYA TPS              | 1100          | 4142     | 0       | 0         | 0      | 0      | 4142          | 4561              |
| 99              | KOTHAGUEDEM TPS           | 720           | 4375     | 0       | 0         | 0      | 0      | 4375          | 4077              |
| 100             | KOTHAGUEDEM TPS (NEW)     | 1000          | 5532     | 0       | 0         | 0      | 0      | 5532          | 5321              |
| 101             | KUDGI STPP                | 1600          | 2046     | 125     | 0         | 0      | 0      | 2171          | 2124              |
| 102             | METTUR TPS                | 840           | 3365     | 0       | 0         | 300    | 0      | 3665          | 3680              |
| 103             | METTUR TPS - II           | 600           | 1384     | 0       | 0         | 229    | 0      | 1613          | 1577              |
| 104             | MUTHIARA TPP              | 1200          | 0        | 0       | 0         | 2386   | 0      | 2386          | 2430              |
| 105             | NORTH CHENNAI TPS         | 1830          | 6557     | 0       | 0         | 891    | 0      | 7448          | 7469              |
| 106             | PAINAMPURAM TPP           | 1320          | 2466     | 0       | 0         | 2866   | 0      | 5332          | 5281              |
| 107             | RAICHUR TPS               | 1720          | 7363     | 0       | 0         | 0      | 0      | 7363          | 6932              |
| 108             | RAMAGUNDEM - B TPS        | 63            | 108      | 0       | 0         | 0      | 0      | 108           | 339               |
| 109             | RAMAGUNDEM STPS           | 2600          | 12025    | 0       | 0         | 0      | 0      | 12025         | 11906             |
| 110             | RAYALASEEMA TPS           | 1050          | 4888     | 0       | 0         | 0      | 0      | 4888          | 4992              |
| 111             | SGPL TPP                  | 1320          | 0        | 0       | 4         | 4304   | 0      | 4308          | 4183              |



| Region                   | Name of the Plant      | Capacity (MW) | Receipt      |            |           |              |          | Total Receipt | Total Consumption |
|--------------------------|------------------------|---------------|--------------|------------|-----------|--------------|----------|---------------|-------------------|
|                          |                        |               | CIL/SCCL     | Captive    | E-Auction | Import       | Others   |               |                   |
| 112                      | SIMHADRI               | 2000          | 8417         | 0          | 0         | 0            | 0        | 8417          | 8642              |
| 113                      | SIMHAPURI TPS          | 600           | 0            | 0          | 0         | 70           | 0        | 70            | 13                |
| 114                      | SINGARENI TPP          | 1200          | 5931         | 0          | 0         | 0            | 0        | 5931          | 5743              |
| 115                      | THAMMINAPATNAM TPS     | 300           | 0            | 0          | 0         | 359          | 0        | 359           | 396               |
| 116                      | TORANGALLU TPS(SBU-I)  | 260           | 0            | 0          | 0         | 354          | 0        | 354           | 354               |
| 117                      | TORANGALLU TPS(SBU-II) | 600           | 0            | 0          | 0         | 1076         | 0        | 1076          | 1044              |
| 118                      | TUTICORIN (JV) TPP     | 1000          | 3082         | 0          | 0         | 432          | 0        | 3514          | 3529              |
| 119                      | TUTICORIN TPS          | 1050          | 3228         | 0          | 0         | 293          | 0        | 3521          | 4060              |
| 120                      | UDUPI TPP              | 1200          | 0            | 0          | 0         | 2493         | 0        | 2493          | 2613              |
| 121                      | VALLUR TPP             | 1500          | 5252         | 0          | 0         | 303          | 0        | 5555          | 5221              |
| 122                      | VIZAG TPP              | 1040          | 2621         | 0          | 0         | 85           | 0        | 2706          | 2618              |
| 123                      | YERMARUS TPP           | 1600          | 608          | 0          | 0         | 0            | 0        | 608           | 559               |
| <b>Total of Southern</b> |                        | <b>36473</b>  | <b>96424</b> | <b>125</b> | <b>4</b>  | <b>19833</b> | <b>0</b> | <b>116386</b> | <b>116695</b>     |
| <b>Eastern</b>           |                        |               |              |            |           |              |          |               |                   |
| 124                      | BAKRESWAR TPS          | 1050          | 3945         | 0          | 370       | 7            | 0        | 4322          | 4336              |
| 125                      | BANDEL TPS             | 450           | 1222         | 0          | 46        | 0            | 0        | 1268          | 1421              |
| 126                      | BARAUNI TPS            | 210           | 0            | 0          | 0         | 0            | 0        | 0             | 0                 |
| 127                      | BARH II                | 1320          | 3898         | 1981       | 0         | 17           | 0        | 5896          | 5995              |
| 128                      | BOKARO `B` TPS         | 710           | 1994         | 0          | 0         | 0            | 0        | 1994          | 2038              |
| 129                      | BUDGE BUDGE TPS        | 750           | 1514         | 1230       | 738       | 18           | 0        | 3500          | 3586              |

| Region | Name of the Plant    | Capacity (MW) | Receipt  |         |           |        |        | Total Receipt | Total Consumption |
|--------|----------------------|---------------|----------|---------|-----------|--------|--------|---------------|-------------------|
|        |                      |               | CIL/SCCL | Captive | E-Auction | Import | Others |               |                   |
| 130    | CHANDRAPURA(DVC) TPS | 630           | 2108     | 0       | 0         | 0      | 0      | 2108          | 2417              |
| 131    | DERANG TPP           | 1200          | 844      | 0       | 2354      | 0      | 0      | 3198          | 2972              |
| 132    | D.P.L. TPS           | 660           | 1530     | 0       | 0         | 0      | 0      | 1530          | 1585              |
| 133    | DURGAPUR STEEL TPS   | 1000          | 4151     | 0       | 0         | 0      | 0      | 4151          | 4088              |
| 134    | DURGAPUR TPS         | 210           | 643      | 0       | 0         | 0      | 0      | 643           | 656               |
| 135    | FARAKKA STPS         | 2100          | 8186     | 0       | 0         | 301    | 0      | 8487          | 8803              |
| 136    | HALDIA TPP           | 600           | 2482     | 0       | 372       | 78     | 0      | 2932          | 3065              |
| 137    | IB VALLEY TPS        | 420           | 2584     | 0       | 0         | 0      | 0      | 2584          | 2588              |
| 138    | JOJOBERA TPS         | 240           | 0        | 0       | 75        | 0      | 681    | 756           | 782               |
| 139    | KAHALGAON TPS        | 2340          | 12401    | 0       | 0         | 0      | 0      | 12401         | 12485             |
| 140    | KAMALANGA TPS        | 1050          | 2257     | 0       | 1163      | 344    | 162    | 3926          | 3926              |
| 141    | KODARMA TPP          | 1000          | 3320     | 0       | 0         | 0      | 0      | 3320          | 3493              |
| 142    | KOLAGHAT TPS         | 1260          | 3085     | 0       | 230       | 0      | 0      | 3315          | 3747              |
| 143    | MAHADEV PRASAD STPP  | 540           | 0        | 0       | 1842      | 0      | 0      | 1842          | 1961              |
| 144    | MAITHON RB TPP       | 1050          | 3803     | 0       | 408       | 0      | 0      | 4211          | 4218              |
| 145    | MEJIA TPS            | 2340          | 7879     | 0       | 0         | 0      | 0      | 7879          | 7933              |
| 146    | MUZAFFARPUR TPS      | 610           | 1312     | 0       | 0         | 0      | 0      | 1312          | 1401              |
| 147    | PATRATU TPS          | 770           | 0        | 0       | 0         | 0      | 0      | 0             | 0                 |
| 148    | NABI NAGAR TPP       | 500           | 606      | 0       | 0         | 0      | 0      | 606           | 599               |
| 149    | RAGHUNATHPUR TPP     | 1200          | 1162     | 0       | 260       | 0      | 0      | 1422          | 1422              |

| Region                         | Name of the Plant  | Capacity (MW) | Receipt       |              |              |              |             | Total Receipt | Total Consumption |
|--------------------------------|--------------------|---------------|---------------|--------------|--------------|--------------|-------------|---------------|-------------------|
|                                |                    |               | CIL/SCCL      | Captive      | E-Auction    | Import       | Others      |               |                   |
| 150                            | SAGARDIGHI TPS     | 1600          | 3314          | 0            | 406          | 3            | 0           | 3723          | 3918              |
| 151                            | SANTALDIH TPS      | 500           | 1523          | 0            | 159          | 0            | 0           | 1682          | 1828              |
| 152                            | SOUTHERN REPL. TPS | 135           | 201           | 0            | 7            | 0            | 0           | 208           | 211               |
| 153                            | STERLITE TPP       | 1200          | 1550          | 0            | 0            | 0            | 0           | 1550          | 1392              |
| 154                            | TALCHER (OLD) TPS  | 460           | 3070          | 0            | 0            | 0            | 0           | 3070          | 3150              |
| 155                            | TALCHER STPS       | 3000          | 18469         | 0            | 0            | 0            | 0           | 18469         | 18299             |
| 156                            | TENUGHAT TPS       | 420           | 743           | 0            | 0            | 0            | 0           | 743           | 1413              |
| 157                            | TITAGARH TPS       | 240           | 0             | 0            | 0            | 0            | 0           | 0             | 0                 |
| <b>Total of Eastern Region</b> |                    | <b>31765</b>  | <b>99796</b>  | <b>3211</b>  | <b>8430</b>  | <b>768</b>   | <b>843</b>  | <b>113048</b> | <b>115728</b>     |
| <b>North Eastern</b>           |                    |               | 0             | 0            | 0            | 0            | 0           | 0             | 0                 |
| 158                            | BONGAIGAON TPP     | 500           | 888           | 0            | 0            | 0            | 0           | 888           | 918               |
| <b>Total of North Eastern</b>  |                    | <b>500</b>    | <b>888</b>    | <b>0</b>     | <b>0</b>     | <b>0</b>     | <b>0</b>    | <b>888</b>    | <b>918</b>        |
| <b>Total All INDIA</b>         |                    | <b>184343</b> | <b>466964</b> | <b>31559</b> | <b>38964</b> | <b>56412</b> | <b>1115</b> | <b>595014</b> | <b>607997</b>     |

**ANNEXURE-3A**

(Item no. 3.2)

**Detail of the inter-regional capacity up to the end of 2017-18**

(Transmission capacity in MW)

| <b>Detail of the inter-regional Transmission Lines</b>  | <b>As on 31.03.2018</b> |
|---|-------------------------|
| <b>EAST-NORTH</b>   |                         |
| Dehri-Sahupuri 220 kV S/c   | 130                     |
| Muzaffarpur-Gorakhpur 400 kV D/c (with Series Cap+TCSC)   | 2,000                   |
| Patna – Balia 400kV D/c (Quad)  | 1,600                   |
| Biharshariff – Balia 400kV D/c(Quad)  | 1,600                   |
| Barh – Balia 400kV D/c (Quad)   | 1,600                   |
| Gaya - Balia 765kV S/c  | 2,100                   |
| Sasaram-Allahabad/Varanasi 400kV D/C line (Sasaram HVDC back to back has been bypassed)   | 1,000                   |
| Sasaram - Fatehpur 765kV2x S/c  | 4,200                   |
| Barh-II-Gorakhpur 400kV D/c (Quad) line   | 1,600                   |
| Gaya-Varanasi 765 kV S/c line   | 2,100                   |
| LILO of Biswanath Chariali - Agra +/- 800 kV, 3000 MW HVDC Bi-pole at new pooling station in Alipurduar and addition of second 3000 MW module | 3,000                   |
| Biharsharif-Varanasi 400kV D/c line (Quad)  | 1,600                   |
| <b>Sub-total</b>  | <b>22,530</b>           |
| <b>EAST-WEST</b>  |                         |
| Budhipadar-Korba 220 kV 3 ckts.   | 390                     |
| Rourkela-Raipur 400 kV D/c with series comp.+TCSC   | 1,400                   |
| Ranchi –Sipat 400 kV D/c with series comp.  | 1,200                   |
| Rourkela-Raipur 400 kV D/c (2 <sup>nd</sup> ) with series comp.   | 1,400                   |
| Ranchi - Dharamjayagarh - WR Pooling Station 765kV S/c line   | 2,100                   |
| Ranchi - Dharamjayagarh 765kV 2nd S/c   | 2,100                   |
| Jharsuguda-Dharamjayagarh 765kV D/c line  | 4,200                   |
| <b>Sub-total</b>  | <b>12,790</b>           |
| <b>WEST- NORTH</b>  |                         |
| Auriya-Malanpur 220 KV D/c  | 260                     |
| Kota - Ujjain 220 KV D/c  | 260                     |

| <b>Detail of the inter-regional Transmission Lines</b>     | <b>As on 31.03.2018</b> |
|--|-------------------------|
| Vindhyachal HVDC back-to-back                              | 500                     |
| Gwalior-Agra 765 kV 2 x S/c                                | 4,200                   |
| Zerda-Kankroli 400kV D/c                                   | 1,000                   |
| Champa Pool- Kurukshetra HVDC Bipole                       | 3,000                   |
| Gwalior-Jaipur 765kV 2xS/c lines                           | 4,200                   |
| RAPP-Sujalpur 400kV D/c                                    | 1,000                   |
| Adani(Mundra) - Mahendranagar HVDC bipole                  | 2,500                   |
| Jabalpur - Orai 765kV D/c line                             | 4,200                   |
| LILO of Satna - Gwalior 765kV 2xS/c line at Orai           | 4,200                   |
| <b>Sub-total</b>   | <b>25,320</b>           |
| <b>EAST- SOUTH</b>   |                         |
| Balimela-Upper Sileru 220kV S/c                            | 130                     |
| Gazuwaka HVDC back-to-back                                 | 1,000                   |
| Talcher-Kolar HVDC bipole                                  | 2,000                   |
| Upgradation of Talcher-Kolar HVDC Bipole                   | 500                     |
| Angul - Srikakulum   | 4,200                   |
| <b>Sub-total</b>   | <b>7,830</b>            |
| <b>WEST- SOUTH</b>   |                         |
| Chandrapur HVDC back-to-back                               | 1,000                   |
| Kolhapur-Belgaum 220kV D/c                                 | 260                     |
| Ponda – Nagajhari 220kV D/c                                | 260                     |
| Raichur - Sholapur 765kV S/c line (PG)                     | 2,100                   |
| Raichur - Sholapur 765kV S/c line (Pvt. Sector)            | 2,100                   |
| Narendra - Kolhapur 765kV D/c (ch at 400kV)                | 2,200                   |
| Wardha - Hyderabad 765kV D/c line                          | 4,200                   |
| <b>Sub-total</b>   | <b>12,120</b>           |
| <b>EAST- NORTH EAST</b>                                    |                         |
| Birpara-Salakati 220kV D/c                                 | 260                     |
| Malda - Bongaigaon 400 kV D/c                              | 1,000                   |
| Siliguri - Bongaigaon 400 kV D/c (Quad) line               | 1,600                   |
| <b>Sub-total</b>   | <b>2,860</b>            |
| <b>NORTH EAST-NORTH</b>                                    |                         |
| Biswanath Chariali - Agra +/- 800 kV, 3000 MW HVDC Bi-pole | 3000                    |
| <b>Sub-total</b>   | <b>3,000</b>            |
| <b>TOTAL</b>   | <b>86,450</b>           |

**ISSUES PERTAINING TO TRANSMISSION SYSTEM PLANNING  
TAKEN UP DURING 2017-18****A. 39<sup>th</sup> Standing Committee Meeting on Power System Planning in Northern Region.**

1. Review of intra state transmission scheme for evacuation of power from western part of Rajasthan.
2. Delinking of up-gradation of Tehri Pooling Station–Meerut 765kV 2xS/c lines (operated at 400 kV) at its rated voltage with the commissioning of Tehri PSS generation scheme.
3. Two number of 132kV bays at PGCIL's Balia (765) S/S.
4. Requirement of 1 (one) no. additional 220kV bay at 400/220kV substation at Roorkee (Puhana), POWERGRID.
5. Requirement of 2 (two) nos. of additional 220kV bay at 400/220kV S/s at Patran.
6. Requirement of 4 nos. of 220kV bays and augmentation by 1x500MVA, 400/220kV transformer at 400kV Substation at Sonepat (Jajji), POWERGRID.
7. 220kV bays at Prithla 400/220kV sub-station being implemented through TBCB route.
8. Two nos. of 220kV bays at 400/220kV substation Abdullapur (PG), Yamunanagar for HVPNL.
9. Connectivity to Dhaulasidh Hydro Electric Power Project (66MW) of M/s SJVNL in Himachal Pradesh.
10. 400/220kV substations at Rajghat (Maharanibagh-II) and Karampura in NCT of Delhi
11. UT of Chandigarh's proposal regarding handing over of 220/66kV substation at Kishangarh (Manimajra) to PGCIL and to treat it as ISTS point.
12. Loading at Raebareli 220/132 kV Substation
13. Transmission system for Ultra Mega Solar Park in Fatehgarh, distt. Jaisalmer Rajasthan.
14. Grant of Long Term Access (Revised) to NTPC Ltd. for its Tanda TPS Stage-II (2x660 MW) for 395.42 MW to NR Beneficiaries
15. Establishment of 220/66kV, 2x160MVA GIS Substation at Hallo Majra, Chandigarh.
16. Development of Transmission scheme for Solar Power Parks in Bhadla, Rajasthan
17. Reconductoring of Badarpur–Ballabhgarh 220kV D/C line
18. Connectivity (6x660 MW) and LTA (4x660MW) Application of Barethi STPS of NTPC Ltd.
19. Operational Feedback (NR Region)
20. Power evacuation plan for Nakhtan HEP (4x115 MW)
21. Creation of 220kV substation at Deoli Ahir (Mohindergarh) and associated transmission system
22. Issues related to transmission system for evacuation of power for Bajoli Holi HEP (180MW) of M/s GMR Energy Ltd. in Himachal Pradesh.
23. Agenda proposed by PTCUL for consideration of Transmission Network up to 400kV S/s Srinagar of UITP Scheme developed by PTCUL as part of System Strengthening of Northern Region and modifications in the UITP scheme for Alakhnanda Basin.
24. Evacuation of New Generation Project in 13th Plan (2017-2022) in Uttar Pradesh
25. Study to limit high Short Circuit level of various Substations in NR (Phase 2)
26. Reactive Power Compensation Requirement Studies in Northern Region and High voltage at Kurukshetra.
27. Installation of 400kV and 220kV Shunt Bus Reactors in Rajasthan

28. Early Commissioning of 400kV D/C Samba-Amargarh Transmission Line, 400/220 kV GIS Substation at Amargarh and LILO of both circuits of 400kV Uri- Wagoora at Amargath under NRSS-XXIX Transmission Limited Project.
29. Transmission system for connectivity to Bilhaur TPS (2x660MW) of NTPC
30. Prime Minister Development Package for the state of J&K (PMDP-2015) / PMRRP-2015
31. Modification in scope of Intra-State transmission schemes under Green Energy Corridor planned for evacuation of Renewable energy addition in Renewable rich states.
32. Strengthening of Intra-State Transmission System - Operational Constraints
33. Connectivity & LTA to GHAVP Nuclear power plant (2x700MW) of M/s NPCIL in Haryana
34. Power Evacuation of the projects in Chenab Basin and establishment of 400/132kV Substation at Kishtwar
35. Down Stream network by State utilities from ISTS Station
36. 400kV bays at 400kV substation Bhinmal and Sikar
37. Evacuation of power from 1x800 MW supercritical unit- 9 at PTPS, Panipat
38. Interconnection of Manimajra and Hallomajra 220/66kV substations of UT Chandigarh
39. Connectivity of Railways' TSS with ISTS Network for Delhi – Bharuch route
40. Connectivity of Railways' TSS with ISTS Network for Ludhiana-Delhi-Sonagar Route.
41. Second 400kV high capacity India – Nepal cross border corridor viz. New Butwal (Nepal) – Gorakhpur (New)
42. UITP Scheme by PTCUL and Grant of Connectivity and LTA to various generators in Uttarakhand (Agenda by CTU).
43. Connectivity to Luhri Hydro Electric Power Project (210 MW) of SJVN Ltd. in Himachal Pradesh (Agenda by CTU)
44. Capacity enhancement of Rihand- Dadri HVDC from 1500MW to 2500MW
45. Converting Fixed Line Reactors into Switchable Line Reactors in Over Compensated lines
46. Ownership of newly installed 63MVA Reactor, GIS bay & 4x105MVA ICT BBMB Dehar Power House
47. Creation of 400/220kV Substation at Etawah
48. 765kV D/c interconnection of Lalitpur TPS with Bina(PG)
49. Connectivity of UPPTCL Moradnagar-II (new), 400/220 kV, 2x240 MVA substation by shifting of 400,220 kV lines from Moradnagar 400 kV UPPTCL S/S to Moradnagar –II
50. Connectivity of 400/220/33 kV 2x500, 3x60 MVA Indrapuram (Ghaziabad) substation
51. Augmentation of transformation capacity at Gorakhpur, Lucknow and Fatehpur
52. Upgradation of existing 220/132 kV Sahupuri Substation to 400/220 kV, 2x500 MVA.
53. Compilation of ICT augmentations and 220 kV line bays agreed in the meeting
54. Various LTA/ Connectivity applications discussed in 10th Connectivity/Long-Term Access meeting of Northern Region held along with 39th SCM of NR.

## **B. 42<sup>nd</sup> Meeting of Standing Committee on Power System Planning in Western Region**

1. Early commissioning of TBCB schemes of M/s Adani Transmission Ltd.
2. Provision of Bus Reactors at High Voltage Nodes in Western Region
3. Second 400 kV D/C transmission line for BALCO Complex and 400 kV Grid connectivity for the proposed new smelter plant of 0.51 MTPA at Balco Complex

4. LILO of SSP–Dhule 400 kV D/C at Shivaji Nagar (Balsane) 400 kV S/s
5. Additional feed to Goa: interconnection of Xeldam (GED) and Xeldam (New) 400/220 kV sub-stations
6. Progress of dedicated transmission lines of IPPs which are connected through interim arrangement – Extension of Essar Power (Mahan) interim connectivity
7. Connectivity of Railways’ TSS with ISTS Network
8. Transmission System for Solar Power Parks in Madhya Pradesh
9. Additional ISTS feed to Navi Mumbai 400/220 kV substation of POWERGRID
10. Interim arrangement of Koradi II–Wardha 400 kV D/C quad line and power evacuation beyond Warora
11. High fault level at 400 kV Korba STPS (NTPC)
12. Reviewing the intra state transmission system and 220 kV interconnection with Vapi – II DNH
13. Charging of 400 kV Solapur PG – Karad line on 220 kV Level for resolving low voltage problems in Solapur District
14. Progress of downstream network whose terminating bays are under construction by POWERGRID
15. Requirement of Transformer Augmentation in Western Region
16. Provision of Bus Reactor at Champa Pool Split Section –A
17. Transmission System associated with DGEN TPS (4x300MW) under implementation by DGEN Transmission Co. Ltd.
18. Charging of 2x330 MVAR Line Reactors of Dharamjaygarh – Jharsuguda 765kV 2nd D/c line as Bus Reactor at 765/400 kV Dharamjaygarh Substation
19. Interconnection of MSETCL lines with PGCIL lines or S/s
20. Declaration of 132 kV Nepanagar (Madhya Pradesh)–Dharni (Maharashtra) line as ISTS line
21. Advancement in schedule of 2 no. of 220 kV line bays at Khandwa (PG) 400/220 kV S/s associated with 1 x 500 MVA, 400/220 kV, 3rd ICT
22. Provision of 400/220 kV, 2x500 MVA ICT at Kakrapar Nuclear Power Station
23. Installation of 2x50MVA, 220/33kV transformer with 10 Nos. 33kV feeder bays at 220kV Jabalpur substation
24. Retention of LILO of 400kV Khandwa- Rajgarh at Khargone
25. Signing of Transmission Service Agreement (TSA) by Long Term Transmission Customers (LTTC) for the transmission scheme “Additional 400 kV Feed to Goa and Additional System for Power Evacuation from Generation Projects pooled at Raigarh (Tamnar) Pool”
26. Extension of Essar Power Gujarat Ltd (EPGL) - Bhachau 400 kV D/c (Triple) line of POWERGRID upto Bhogat substation
27. Operational feedback of NLDC period from Jul’2017 to Sep’2017
28. Implementation modalities on provision of 400/220 kV, 315 MVA or 500 MVA ICT along with one no. of 400 kV ICT bay and one no. of 220 kV bay ICT bay at M/s CGPL Switchyard
29. Implementation of the future GIS bay along-with the planned GIS bay in the same diameter in view of complexities involved with interfacing different manufacturer make GIS bay modules
30. Converting Fixed Line Reactors into Switchable Line Reactors in Kankroli – Zerda line at Kankroli end
31. Submission of data for Geospatial Energy Portal being developed by ISRO



### **C. 19<sup>th</sup> Meeting of the Standing Committee on Power System Planning in Eastern Region**

1. Termination of 400kV lines at Jeerat (WBSETCL) S/s under the ERSS-XV and ERSS-XVIII schemes.
2. Creation of 220kV level at the under construction 400/132kV Motihari (TBCB).
3. Modifications/ additions in bay equipment of Maithon 400/220 kV substation of POWERGRID and generation switchyard of Maithon-RB.
4. Revised dedicated transmission system for Lanco Babandh Power Pvt. Ltd. (2x660 MW).
5. Evacuation of power from Patratu (3x800MW) TPS.
6. Perspective transmission plan of JUSNL up to 2021-22.
7. Transmission system for evacuation of power from Buxar Thermal Power Project (1320 MW).
8. Connectivity of Railway TSS with ISTS network for Mughal Sarai – Howrah route.
9. Modification in - Common Transmission System for Phase-II generation project in Odisha.
10. Termination of 220kV side of 400/220kV, 500MVA ICT-4 at Biharsharif (POWERGRID) substation under ERSS-XX.
11. Baharampur (India) – Bheramara (Bangladesh) 2<sup>nd</sup> 400kV D/c line.
12. High Capacity India-Bangladesh AC Corridor and Formation of 400kV nodes in NER-ER Corridor.
13. Additional power supply to Nepal through Muzaffarpur-Dhalkebar transmission line.
14. Modification in - Transmission System for Transfer of power from generation projects in Sikkim to NR/WR (Part-B1).
15. Interim connectivity to generation projects through LILO arrangement
16. Status of downstream 220kV or 132kV network by STUs from the various commissioned and under-construction ISTS substations.
17. Connectivity and LTA application of Odisha Integrated Power Ltd. (Odisha UMPP) and transmission system for power evacuation.
18. Additional feed to southern Odisha to improve power supply reliability and enable maximum utilisation of Guzuwaka Back-to-Back HVDC.
19. Proposal for stepwise completion of Rajarhat – New Purnea 400kV D/c line under ERSS-V scheme.
20. Programme for 11<sup>th</sup>/12<sup>th</sup> Plan augmentation of DVC System- Submission of revised plan for approval.
21. Installation of bus reactors at 400kV level at substations of STU.
22. Constraint in transportation of ICT to Farakka (NTPC) under ERSS-XII.
23. Conversion of 50MVAR (3x16.67MVAR) bus reactor at Farakka to switchable line reactor under the ERSS-XV due to space constraints in termination of Farakka – Baharampur 400kV D/c (Twin HTLS) line.
24. Modification in transmission system required for power evacuation from Sikkim IPPs and Operationalization of LTA.
25. Connectivity granted to Vedanta Ltd. (erstwhile Sterlite Energy Ltd).

26. Dropping of Banka (PG) – Deoghar 132kV D/c line which was proposed in 16<sup>th</sup> SCM-ER meeting.
27. Upgradation of 132kV bus arrangement at 400/220/132kV Malda S/s of POWERGRID
28. Modification under 13<sup>th</sup> Plan scheme: Agenda by BSPTCL.
29. To provide one additional 400/220kV, 500MVA ICT at Patna (POWERGRID)
30. Bus and Bay strengthening at Purnea (POWERGRID) S/s.
31. Limiting fault current level at 400kV bus at Farakka TPS (NTPC).
32. Commissioning of Rajarhat S/s and terminating lines proposed under ERSS-V scheme
33. Evacuation system for Talcher-III (2x660MW) project of NTPC
34. Approval for construction of 2 nos. 400/220kV substation at Bhadrak and Paradip by OPTCL with revised connectivity
35. Approval for connectivity of 400/220kV sub-station at Narendrapur to 400/220kV Jaynagar/ Jeypore (PG) with a 400kV D/c line in place of 400kV Angul –Narendrapur – Gazuwaka D/c line
36. Proposed evacuation plan of 3x800MW Power Plant of M/s OTPCL (Odisha Thermal Power Corporation Ltd.) at Kamakshyanagar, Odisha: Agenda by OPTCL
37. Evacuation of power from 2x660MW project of OPGC
38. Connectivity of Railways TSS with ISTS network for Ludhiana-DelhiSonenagar routes
39. Additional outlets from Darlipalli STPP and North Karanpura STPP for mining activities
40. Interim arrangement for power evacuation from Nabinagar TPP (3X660MW)
41. Revision in capacity of 4<sup>th</sup> 220/132kV ICT at Rangpo S/s under ERSS-XX
42. Bus splitting of POWERGRID sub-stations
43. LILO Connection of 132kV Sonenagar-Rihand (UP, NR) Circuit-I at NPGC, Nabinagar for providing startup power to NPGC
44. OPGW and Communication System for new ISTS system.

#### **D. 41<sup>st</sup> Meeting of the Standing Committee on Power System Planning in Southern Region**

1. Transmission system for evacuation of power from Uppur TPS (2x800 MW) of TNEB in Tamil Nadu
2. Evacuation scheme for SEPC (1X525 MW).
3. Provision of exclusive 220kV feeder to CPRI, Hyderabad for their online 350 MVA short circuit test facility
4. Establishment of Konthagai 400/230kV, 2x500 ICT S/S with following Connectivity:

##### **400kV Connectivity:**

- a) LILO of one of the Kaythar - Karaikudi 400kV D/C quad line at Konthagai.
- b) 400kV D/C line from the proposed Virudhnagar 765/400kV substation to Konthagai.

##### **230kV Connectivity:**

- a) LILO of Pasumalai-Anupankulam 230kV line at Konthagai
- b) LILO of Samayanllur-alagarkoil 230kV line at Konthagai

- c) 230kV S/C line to the sanctioned K.Pudur 230kV S/S from Konthagai.
- d) 230kV S/C line to the proposed Thummakundu 230/110kV S/S from Konthagai.
5. Implementation of Kadaladi – Kamuthi 400kV D/C line by TANTRANSCO
  6. Commissioning of 400/110kV 2nd ICT at Alamathy 400/230-110kV substation in Chennai
  7. Establishment of Koyambedu 400/230 kV substation
  8. Establishment of Manalmedu 400/230/110kV substation.
  9. Establishment of Neyveli 400/230 kV Substation - By Upgradation of the Neyveli (TNEB) 230 kV SS.
  10. Enhancement of transformation capacity of 400/230kV transformer from 2 x 315 MVA to 2 X 500 MVA and that of 400/110 kV transformer from 2 x 200 MVA to 3 X 200 MVA at K.R.Thoppur (Salem-TNEB) 400/230 kV SS
  11. LILO of 220 kV Nannur (AP) – Regumanugadda (TL) 220kV S/C line at 220/11 kV Brahmanakotkur (AP)
  12. Extension of 398.7 MW of power supply to Chintalapudi Lift Irrigation Scheme at 220 kV and 132 kV level in three stages in West Godavari district
  13. Replacement of Twin Moose conductor with high capacity conductor on existing VTS-IV – Sattenapalli 400kV D/C line (in place of proposed 2nd 400kV VTS-IV- Sattenapalli D/C line with Quad Moose conductor).
  14. Cochin East (Pallikkara) - Aluva 220kV D/C line (In the scope of KSEB)
  15. 400kV Udipi (UPCL)-Kasargode D/C line and Kasargode-Kozhikode 400 kV D/C line along with Kasargode 400/220 kV, 2x500MVA substation under ISTS
  16. Installation of 400kV 2x125 MVAR bus reactor at UPCL switchyard
  17. Establishing 2 X 500 MVA, 400/220 kV sub-station at Huliurdurga in Tumkur district
  18. Establishing 400/220kV, 4x167 MVA sub-station near Hebbanahalli substation.
  19. Additional reactors of 1x125 MVAR (400kV) each at Talaguppa and Devangere 400/220kV Substations
  20. Upgradation of existing 220kV Substation to 400/220kV GIS Substation (2x500MVA) at Peenya in Bengaluru city
  21. Revised proposal for connectivity of Telangana STPP (2x800 MW),
    - (a) LILO of both circuits of 400kV Mamidipalli-Dindi D/C line at upcoming 400kV Maheshwaram SS and
    - (b) Dichpally - Nirmal 400kV D/C line (with Quad Moose ACSR Conductor).
  22. Augmentation of Power Transformer at existing 400/220/132 kV Malkaram SS and 400/220 kV Shankarpally SS with 400/220 kV, 500 MVA transformer (4th ICT)
  23. Establishment of 400/220kV Asupaka S/S with 2x315 MVA and LILO of one circuit of 400kV Kalpaka –Khammam D/C Line at Asupaka
  24. Sita Rama Lift Irrigation Scheme – Erection of Substations for extension of power supply to (a) Pump House – 1 (6x25 MW) at B.G. Kothur (V) Ashwapuram(M) (b) Pump House - 2 (6x40 MW) at V.K. Ramavaram (V) Mulakalapally (M) and (c) Pump House 3 (5x40+2x30MW) at Kamalapuram(V) Chandrugonda(M) in Bhadradi Kothagudem District.
  25. Extension of Power supply under Phase-III, J.Chokka Rao Devadula Godavari Lift Irrigation Scheme – Construction of 220/11kV Substation Devannapet at Warangal Urban District and 220 kV D/C line (with Single Moose ACSR conductor from 400/220KV Oglapur (PGCIL) SS to proposed 220/11kV Devannapet LI SS
  26. Additional 400/220kV, 1x500 MVA ICT at Gazuwaka substation as ISTS.

## **Details of the Schemes notified through Tariff Based Competitive Bidding (TBCB)**

### **(a) Schemes under implementation by the Transmission Service Providers:**

1. Transmission system associated with IPPs of Nagapattinam / Cuddalore Area- Package A.
2. Transmission System associated with Gadarwara STPS (2x800 MW) of NTPC (Part-A)
3. Transmission System associated with Gadarwara STPS (2x800 MW) of NTPC (Part-B)
4. Transmission System Strengthening associated with Vindhyachal- V
5. Strengthening of Transmission system beyond Vemagiri
6. 765 kV System Strengthening Scheme in Eastern Region. ERSS-XVIII
7. Eastern Region Strengthening Scheme XXI (ERSS-XXI)
8. New WR-NR 765 kV Inter-Regional Corridor
9. Northern Regional System Strengthening Scheme, NRSS-XXIX
10. Common Transmission system for phase-II generation projects in Orissa and immediate evacuation system for OPGC project (Orissa)
11. Creation of new 400 kV GIS substations in Gurgaon area and Palwal as a part of ISTS
12. Connectivity system for Khargone TPP (2x660MW)
13. NER System Strengthening Scheme II
14. (A) Additional 400kV Feed to Goa and  
(B) Additional System for Power Evacuation from Generation Projects pooled at Raigarh (Tamnar) Pool
15. Additional inter regional AC link for import into southern region i.e Warora-Warangal and Chilakaluripeta – Hyderabad – Kurnool 765 kV link
16. System strengthening in northern region (NRSS XXXVI) along with LILO of Sikar-Neemrana 400 kV D/C line at Babai(RVPNL)
17. Additional system strengthening for Sipat STPS
18. Additional system strengthening for Chhattisgarh (B)
19. System strengthening for IPPs in Chhattisgarh and other generation projects in western region
20. Immediate evacuation for North Karanpura (3x660MW) generation project of NTPC(ERSS XIX)
21. Transmission System for Ultra Mega Solar Park in Fatehgarh, Distt. Jaisalmer Rajasthan
22. Transmission system strengthening in Indian system for transfer of power from new HEP's in Butan
23. North Eastern Region Strengthening Scheme (NERSS-VI)

### **(b) Schemes under bidding process by the Bid Process Coordinators:**

1. Connectivity and Long Term Access (LTA) to HPPCL 450 MW from Shongtong Karcham HEP

2. Transmission System for “Connectivity System for LancoVidarbha Thermal Power Pvt. Ltd. (LVTPPL) and Inter State Transmission system strengthening in Chhatarpur area in Madhya Pradesh”

**(c) Schemes commissioned by the Transmission Service Providers:**

1. Transmission system for Strengthening in SR for Import of Power from ER.
2. ATS of Unchahar TPS
3. NR System strengthening Scheme-NRSS-XXXI(Part-A)
4. System strengthening for WR
5. System strengthening common for WR and NR
6. Scheme for enabling import of NER/ER surplus by NR
7. Part ATS for RAPP U-7&8 in Rajasthan
8. Eastern Region System Strengthening Scheme-VII
9. Connectivity lines for Maheshwaram 765/400 kV S/S
10. Northern Region System Strengthening Scheme, NRSS-XXXI (Part-B)
11. Transmission System required for evacuation of power from Kudgi TPS (3x800 MW in Phase-I) of NTPC Ltd.
12. Transmission System for Patran 400kV S/S
13. Transmission System Associated with Krishnapattnam UMPP- Synchronous interconnection between SR and WR (Part-B)
14. Eastern Region System Strengthening Scheme-VI

## **ANNEXURE – 3D**

(Item 3.4.3)

### **Issues Pertaining to Transmission System Planning taken up in Empowered Committee on Transmission during 2017-18**

#### **37<sup>th</sup> Meeting of the Empowered Committee on Transmission**

1. Notification / approval of transmission schemes approved in 36th Empowered Committee (EC) on Transmission by MoP
2. De-notification of the Scheme ATS for Tanda Expansion TPS (2x660) MW
3. Issues raised by STUs in Standing Committees due to implementation of schemes through TBCB
4. Status of transmission schemes under bidding process - briefing by BPCs
5. New inter-state transmission schemes
6. Change / modification in the scope of works of transmission schemes under TBCB
7. Issues related to the providing of information to bidders for terminal bays at POWERGRID sub-stations:
8. Cost of the Project as per the Cost Committee
9. Constitution of the Bid Evaluation Committees (BEC's) for the new transmission schemes
10. Apportionment of transmission charges among individual transmission elements of Power Grid N M Transmission Limited (PNMTL) which was approved as an integrated system to be executed through TBCB.
11. Compensation to CTU for providing technical inputs to BPC.

**ANNEXURE-3E**  
(Item No. 3.4.4)

**The cost committee constituted for this purpose has estimated the cost of the following transmission schemes:**

| <b>Sl. No.</b> | <b>Independent Transmission Projects</b>   | <b>Estimated Cost of the Project as per Cost Committee (in Rs. Crore)</b> |
|----------------|--|---|
| 1.             | Additional 400kV Feed to Goa and Additional System for Power Evacuation from Generation Projects pooled at Raigarh (Tamnar) Pool | 1531.00   |
| 2.             | Connectivity and Long Term Access (LTA) to HPPCL 450 MW from Shongtong Karcham HEP   | 272.00  |
| 3.             | Transmission system for Ultra Mega Solar Park in Fatehgarh, distt. Jaisalmer, Rajasthan  | 624.00  |
| 4.             | Transmission System For Eastern Region Strengthening Scheme –XXI (ERSS-XXI)  | 1348.56   |
| 5.             | Transmission System For New WR- NR 765 kv Inter-Regional   | 1076.21   |

## Progress under Green Energy Corridor during 2017-18

### A. Inter State Transmission Schemes

| S.No. | GEC ISTS Scheme  | Estimated Cost (Rs. Crore) | NIT Status  | Target comm. Schedule |
|-------|--|----------------------------|-------------|-----------------------|
| 1     | GEC- Part A (KfW Tranche-I)  | 1479<br>(9 packages)       | All Awarded | 2017-18               |
| 2     | GEC- Part B (KfW Tranche-II)   | 3705<br>(22 Packages)      |             | 2017-18               |
| 3     | GEC- Part C ( KfW Tranche-III)   | 2247<br>(16 Packages)      |             | July' 18              |
| 4     | GEC- Part D (ADB)  | 3938<br>( 24 Packages)     |             | Dec' 18               |
|       | <b>Total ( Transmission Schemes)</b>   | <b>11,369</b>              |             |                       |
| 5     | Control Infrastructure <ul style="list-style-type: none"> <li>➤ Dynamic Compensation: Rs 1204 Cr</li> <li>➤ Real time monitoring: Rs. 473 Cr.</li> <li>➤ Energy Storage: Rs. 2000 Cr.</li> </ul> | 3677                       |             |                       |
| 6     | REMC ( in 11 locations)  | 409 (Revised)              | All awarded | Dec'18 – May 19       |
|       | <b>Aggregate</b>   | <b>15455<br/>(revised)</b> |             |                       |



## B. Intra – State Transmission Schemes

|   | Name of the State   | Current Estimated Cost (Rs. Crore) | NIT Status  | Award Status   | Target comm. Schedule |
|---|---|------------------------------------|---|--|-----------------------|
| 1 | Tamil Nadu<br>(for tranche – I)   | 1555.18                            | Done for all 5 packages (Rs. 1555.18 Cr)                        | Done for all 5 packages<br>DPR Cost: Rs. 1555.18 Cr.<br>Award Cost : Rs 1733.83 Cr   | 2018-19               |
| 2 | Rajasthan<br>(for tranche – I)<br><b>(Package 5-11 withdrawn. Only 4 packages left)</b> | 793.96                             | NIT published for 4 packages (Rs 532 Cr.)                       | Done for 6 packages.<br>However, 2 of the awarded packages withdrawn. So, DPR Cost of awarded 4 packages: Rs. 532 Cr<br>Award Cost: Rs. 439.92 Cr. | 2019-20               |
| 3 | Andhra Pradesh  | 1289                               | NIT for 4 packages published out of 6 packages ( Rs 1010.76 Cr) | Done for 3 packages.<br>However, it includes only Lot 2 of Package 2.<br>DPR Cost: Rs. 844 Cr.<br>Award Cost: Rs. 558.37 Cr.                       | 2019-20               |
| 4 | Himachal Pradesh  | 909.86                             | Done for 11 packages out of 17 packages (Rs 600.56 Cr.)         | Done for 6 packages. (HPPTCL) and sub-packages of 3 packages by HPSEBL.<br>DPR Cost: Rs. 312.89 Cr.<br>Award Cost: Rs. 220.12 Cr.                  | 2019-20               |
| 5 | Gujarat   | 1962.12                            | NIT for 25 packages out of 28 packages done. (Rs. 1857.42 Cr.)  | Done for 19 packages<br>DPR Cost: Rs. 1317.51 Cr.<br>Award Cost: Rs. 1051.5 Cr.  | 2019-20               |
| 6 | Karnataka   | 906                                | NIT for 6 packages done out of 7 packages ( Rs. 369.08 Cr.)     | Done for 6 packages<br>DPR Cost: Rs. 369.08 Cr.<br>Award Cost : Rs 472.37 Cr.  | 2019-20               |
| 7 | Madhya Pradesh  | 2026.92                            | NIT for 8 packages issued out of 8 packages (Rs. 1690.34)       | Done for 7 packages<br>DPR Cost: Rs.1690.34 Cr<br>Award Cost : Rs 1311.23 Cr.  | 2019-20               |

|    |                                |                 |   |   |         |
|----|--------------------------------|-----------------|---|---|---------|
| 8  | Maharashtra                    | 250.9           | NIT for package part of package 1 and package 2 published (Rs.130.15 Cr.) | Awarded for 1 package DPR and Award Cost : Rs.3.6 Cr. | 2019-20 |
| 9  | Rajasthan (for tranche – III)  | 2100            | Proposal yet to be submitted by RRVPNL for funding.                       | -   |         |
| 10 | Tamil Nadu (for tranche – III) | 900             | DPR not yet finalised   | -   |         |
|    | Total                          | <b>12693.94</b> | <b>7745.49</b>  | <b>DPR*: 6624.6</b><br><b>Awarded* : 5790.94</b>      |         |

**Details of Failed transmission lines reported to CEA**

| Sl. No. | Name of Transmission line                             | Date of occurrence Of Failure | No. of towers failed | Name of Utility           |
|---------|---|-------------------------------|----------------------|---------------------------|
| 1.      | 400 kV D/C Dadri - Panipath transmission line         | 26.02.2017                    | 5                    | PGCIL                     |
| 2       | 400 kV D/C Silchar-Purba Kanchan Bari transmission    | 2.04.2017                     | 8                    | PGCIL                     |
| 3.      | 765 kV D/C Wardha – Nizamabad transmission line       | 6.04.2017                     | 1                    | PGCIL                     |
| 4       | 400 kV D/C Koderma- Bokaro transmission line          | 13.5.2017                     | 3                    | PGCIL                     |
| 5.      | 400 kV D/C Farakka-Kahalgaon I & II transmission line | 15.5.2017                     | 4                    | PGCIL                     |
| 6.      | 765 kV S/C Gaya- Varanasi- I transmission line        | 17.05.2017                    | 5                    | PGCIL                     |
| 7.      | 765 kV S/C Jabalpur- Bina transmission line           | 5.06.2017                     | 5                    | M/s Sterlite (under TBCB) |
| 8.      | 765 kV S/C Bina - Gwalior transmission line           | 5.06.2017                     | 2                    | PGCIL                     |
| 9.      | 765 kV S/C Bina- Indore transmission line             | 14.06.2017                    | 6                    | PGCIL                     |
| 10.     | 765 kV S/C Agra- Jatikara transmission line           | 14.06.2017                    | 3                    | PGCIL                     |
| 11.     | 400 kV S/C Singrauli- Lucknow transmission line       | 16.06.2017                    | 1                    | PGCIL                     |
| 12.     | 765 kV S/C Bhiwani- Jhatikra transmission line        | 19.06.2017                    | 1                    | PGCIL                     |
| 13.     | 400 kV D/C Tikrikalan- Bawana transmission line       | 14.05.2017                    | 1                    | DTL                       |
| 14.     | + - 500 HVDC Mundra – Mohindergarh transmission line  | 24.07.2017                    | 1                    | Adani Power               |

**List of failures of Transformers and Reactors received in CEA in 2017-18**

|     |  |
|-----|--|
| 1.  | 80 MVAR, 400kV Shunt Reactor at Vizag substation of PGCIL                    |
| 2.  | 16.67 MVAR, 400kV Shunt Reactor at Bhiwardi-Agra substation of PGCIL         |
| 3.  | 80 MVAR, 765kV Shunt Reactor at Satna substation of PGCIL                    |
| 4.  | 315 MVA, 400kV ICT-II at Raigarh substation of PGCIL                         |
| 5.  | 315 MVA, 400kV ICT-I at Jalandhar substation of PGCIL                        |
| 6.  | 100MVA, 220/132/33kV Auto Transformer-III at Badrak Substation of OPTCL      |
| 7.  | 100 MVA, 220/110 kV Power Transformer at Bidnal substation of KPTCL          |
| 8.  | 160 MVA, 220/132/33kV Auto transformer-2 at New Bolangir substation of OPTCL |
| 9.  | 100 MVA, 220/66-33/11kV Power Transformer at Okhla substation of DTL         |
| 10. | 100MVA, 220/66-33/11kV Power Transformer at Geeta Colony substation of DTL   |
| 11. | 100MVA, 220/66-33/11kV Power Transformer at Naraina substation of DTL        |
| 12. | 50 MVA, 220/110/11kV Transformer at Esale, Sirsi substation of KPTCL         |
| 13. | 100MVA, 220/33/11kV Power Transformer at Lodhi Road substation of DTL.       |

**ANNEXURE-3I**

(Item 3.26)

As on 31-Mar-2018

**Transmission Lines Completed During FY- 2017-18**

| Voltage Level (kV)             | Name of Transmission Lines   | Circuit Type | Executing Agency | Line Length (cKM) | Month of Completion |
|--------------------------------|--|--------------|------------------|-------------------|---------------------|
| 1                              | 2  | 3            | 4                | 5                 | 6                   |
| <b>765 kV</b>                  |  |              |                  |                   |                     |
| <b><u>CENTRAL SECTOR</u></b>   |  |              |                  |                   |                     |
| 1                              | Darlipalli TPS - Jharsuguda (Sundergarh) PS line   | D/C          | PGCIL            | 41                | APR-17              |
| 2                              | Gadarwara - Jabalpor Pool line (Balance Portion from LILO of Seoni - Bina to Jabalpur) (PWTL-TBCB) | D/C          | PGCIL            | 187               | MAY-17              |
| 3                              | Nizamabad - Hyderabad line (Part of Wardha - Hyderabad line)                                       | D/C          | PGCIL            | 486               | JUL-17              |
| 4                              | Jabalpur PS - Orai Substation  | D/C          | PGCIL            | 714               | AUG-17              |
| 5                              | Aurangabad (PG) - Padghe (PG) line   | D/C          | PGCIL            | 570               | DEC-17              |
| 6                              | Chittorgarh - Ajmer line   | D/C          | PGCIL            | 422               | DEC-17              |
| 7                              | LILO of Agra - Meerut at Aligarh   | S/C          | PGCIL            | 22                | MAR-18              |
| 8                              | LILO of Kanpur - Jhatikara at Aligarh  | S/C          | PGCIL            | 22                | MAR-18              |
| 9                              | LILO of one ckt. of Satna- Gwalior 765KV 2xS/C line at Orai  | 2xS/C        | PGCIL            | 73                | MAR-18              |
| 10                             | Orai - Aligarh line  | D/C          | PGCIL            | 664               | MAR-18              |
| <b>Total of CENTRAL SECTOR</b> |  |              |                  | <b>3201</b>       |                     |
| <b><u>STATE SECTOR</u></b>     |  |              |                  |                   |                     |
| 11                             | Lalitpur TPS - Fatehabad (Agra (UP)) Ckt-II  | S/C          | UPPTCL           | 335               | APR-17              |
| <b>Total of STATE SECTOR</b>   |  |              |                  | <b>335</b>        |                     |
| <b><u>PRIVATE SECTOR</u></b>   |  |              |                  |                   |                     |
| 12                             | Hapur-Greater Noida line   | S/C          | WUPPTCL          | 66                | MAY-17              |
| 13                             | Mainpuri-Hapur line  | S/C          | WUPPTCL          | 217               | MAY-17              |
| <b>Total of PRIVATE SECTOR</b> |  |              |                  | <b>283</b>        |                     |
| <b>Total of 765 kV</b>         |  |              |                  | <b>3819</b>       |                     |
| <b>400 kV</b>                  |  |              |                  |                   |                     |
| <b><u>CENTRAL SECTOR</u></b>   |  |              |                  |                   |                     |
| 14                             | Kakarapar APP - Navsari line   | D/C          | PGCIL            | 77                | MAY-17              |
| 15                             | Kakarapar APP - Vapi line  | D/C          | PGCIL            | 234               | MAY-17              |
| 16                             | Lucknow - Kanpur line  | D/C          | PGCIL            | 320               | MAY-17              |
| 17                             | Lara STPS - Champa Pooling Station line (Q)  | D/C          | PGCIL            | 224               | JUN-17              |
| 18                             | Kishenpur - New Wanpoh line (132 KM D/C + 7 KM Multi Ckt)  | MC+D/C       | PGCIL            | 279               | JUL-17              |
| 19                             | Loop out (Kurnool - Maheshwaram portion of LILO of Hyderabad - Kurnool at Maheshwaram)             | S/C          | PGCIL            | 4                 | JUL-17              |
| 20                             | Mauda-II - Betul (Quad) line   | D/C          | PGCIL            | 393               | JUL-17              |

|    |  |     |       |     |        |
|----|--|-----|-------|-----|--------|
| 21 | RAPP - Kota line   | D/C | PGCIL | 90  | JUL-17 |
| 22 | LILLO of Karcham Wangtoo - Abdullapur at Kala Amb (PKATL-TBCB)   | D/C | PGCIL | 2   | AUG-17 |
| 23 | Raghunathpur TPS -Ranchi (PG)  | D/C | DVC   | 311 | SEP-17 |
| 24 | Allahabad - Kanpur line  | D/C | PGCIL | 481 | SEP-17 |
| 25 | Aurangabad - Boisar  | D/C | PGCIL | 690 | SEP-17 |
| 26 | Loop-In (Hyderabad-Maheshwaram) portion of LILLO of Hyderabad-Kurnool 400kV S/C line at Maheshwaram  | D/C | PGCIL | 3   | SEP-17 |
| 27 | Solapur STPP - Solapur line - II (Q)   | D/C | PGCIL | 25  | SEP-17 |
| 28 | LILLO of Both ckt. of Mundra UMPP - Limbdi at Bachau (Triple)  | D/C | PGCIL | 45  | OCT-17 |
| 29 | LILLO of one ckt. Gooty - Tumkur (Vasantnarsapur) at Tumkur line (Q) at Tumkur Pool  | D/C | PGCIL | 1   | OCT-17 |
| 30 | Chittorgarh (New) - Chittorgarh (RVPN) (Q)   | D/C | PGCIL | 97  | NOV-17 |
| 31 | Kurukshetra - Jind line (Q)  | D/C | PGCIL | 206 | NOV-17 |
| 32 | Ajmer (New) - Ajmer (RVPN) (Quad) line   | D/C | PGCIL | 131 | DEC-17 |
| 33 | Padghe (PG) - Padghe (Kudus) line (Q) line   | D/C | PGCIL | 32  | DEC-17 |
| 34 | Vapi (PG) - Kala - Kudus (balance Portion) line  | D/C | PGCIL | 149 | DEC-17 |
| 35 | Dulhasti - Kishenpur   | D/C | PGCIL | 115 | JAN-18 |
| 36 | LILLO of Both ckt. of Rourkela - Raigarh (2nd line) at Jharsaguda (Sundargarh)   | M/C | PGCIL | 130 | JAN-18 |
| 37 | Both ckts of IInd LILLO D/C portion of Simhadri - Vijayawada 400kV line at Vimagiri-i (AP) shall be LILLOed at Vimagiri-II (PG)  | D/C | PGCIL | 28  | FEB-18 |
| 38 | Both ckts of one LILLO D/C portion of Simhadri - Vijayawada line at Vimagiri -I (AP) shall be LILLOed at Vimagiri-II (PG) - (D/C)portion (1.8Km) and Multi Ckt. portion (13.2Km) | D/C | PGCIL | 61  | FEB-18 |
| 39 | Extn. Kudankulam APP - Tirunveli (Q)   | D/C | PGCIL | 132 | FEB-18 |
| 40 | LILLO of Bellary - Tumkur (Vasantnarsapur) line (Q) at Tumkur Pool.  | D/C | PGCIL | 220 | FEB-18 |
| 41 | LILLO of Both Ckt Cuddapah - Hindupur line (Q) at NP Kunta S/S   | D/C | PGCIL | 18  | FEB-18 |
| 42 | LILLO of Gooty - Tumkur (Vasantanarsapur) at Tumkur Pool (Ckt.-II)   | D/C | PGCIL | 2   | FEB-18 |
| 43 | LILLO of Vindhyachal - Jabalpur line (Q) (II Ckt.) at Rewa PS  | D/C | PGCIL | 116 | FEB-18 |
| 44 | Nabinagar-II - Gaya (Q)  | D/C | PGCIL | 184 | FEB-18 |
| 45 | Orai - Orai line (Q)   | D/C | PGCIL | 84  | FEB-18 |
| 46 | Punatsangchu-I - Alipurduar  | D/C | PGCIL | 128 | FEB-18 |
| 47 | Sasaram - Deltonganj line  | D/C | PGCIL | 392 | FEB-18 |
| 48 | Tirunelveli PS - Tuitcorin PS (Quad) 1and2 line  | D/C | PGCIL | 48  | MAR-18 |
| 49 | Dehradun - Abdullapur line (Q)   | D/C | PGCIL | 179 | MAR-18 |
| 50 | Kameng - Balipara line   | D/C | PGCIL | 114 | MAR-18 |

|                                |   |     |            |             |        |
|--------------------------------|---|-----|------------|-------------|--------|
| 51                             | LILO of Neelamangla - Hoddy 400 kV S/C LINE at Yelahanka              | D/C | PGCIL      | 20          | MAR-18 |
| <b>Total of CENTRAL SECTOR</b> |   |     |            | <b>5765</b> |        |
| <b>STATE SECTOR</b>            |   |     |            |             |        |
| 52                             | Bhadla-Bikaner  | D/C | RVPNL      | 379         | APR-17 |
| 53                             | Bhilwara TPS -Ajmer   | D/C | RVPNL      | 320         | APR-17 |
| 54                             | LILO of both ckt of Mamidipally - Srisailam at Dindi S/s              | D/C | TSTRANSCO  | 5           | APR-17 |
| 55                             | Fatehabad (Agra (UP)) - Maath ( Mathura) line                         | S/C | UPPTCL     | 142         | APR-17 |
| 56                             | LILO of Patran - Rajla at Patran (PGCIL) s/s                          | D/C | PSTCL      | 3           | MAY-17 |
| 57                             | Nandiwanaparathi - Shankarpally (part of Suryapet- Shankarpally line) | D/C | TSTRANSCO  | 222         | MAY-17 |
| 58                             | Aligarh - Sikandarabad line   | D/C | UPPTCL     | 190         | MAY-17 |
| 59                             | Allahabad - Banda Line  | D/C | UPPTCL     | 355         | MAY-17 |
| 60                             | Rayalaseema TPP - Chittoor line                                       | D/C | APTRANSCO  | 429         | JUN-17 |
| 61                             | Vizag TPP(HNPCL) - Kamavarapukota                                     | D/C | APTRANSCO  | 486         | JUN-17 |
| 62                             | Kirori - Jind line (Ckt-I)  | D/C | HVPNL      | 50          | JUN-17 |
| 63                             | Bellary (PS) - New Madhugiri (near Tumakur)                           | D/C | KPTCL      | 450         | JUN-17 |
| 64                             | Kanarpatti - Kayathar line  | D/C | TANTRANSCO | 25          | JUN-17 |
| 65                             | Maheshwaram (PGCIL) - Maheshwaram (TSTRANSCO)                         | D/C | TSTRANSCO  | 3           | JUN-17 |
| 66                             | Maheshwaram - Shankarpally S/s  | D/C | TSTRANSCO  | 12          | JUN-17 |
| 67                             | Agra(UP) - Agra (South)   | D/C | UPPTCL     | 139         | JUN-17 |
| 68                             | LILO of Agra - Muradnagar at Mathura                                  | D/C | UPPTCL     | 64          | JUN-17 |
| 69                             | LILO of NCTPS Stage-II - Alamathy line at Manali GIS                  | D/C | TANTRANSCO | 66          | JUL-17 |
| 70                             | Gr. Noida - Noida (Quad)  | D/C | UPPTCL     | 91          | JUL-17 |
| 71                             | Rasipalayam - Salem (Palavady)  | D/C | TANTRANSCO | 388         | AUG-17 |
| 72                             | LILO of one ckt. of 400kV Khammam -Gajwel Line at 400kV Asupaka S/s   | D/C | TSTRANSCO  | 34          | AUG-17 |
| 73                             | D/C LILO of PPSP - Arambagh 400 kV D/C line at New PPSP 400 kV GIS    | D/C | WBSETCL    | 1           | AUG-17 |
| 74                             | Kharagpur - N. Chanditala   | D/C | WBSETCL    | 277         | SEP-17 |
| 75                             | LILO of one ckt. of Vadavi-Zerda line at Veloda (Sankhari) S/s        | D/C | GETCO      | 31          | DEC-17 |
| 76                             | Ramgarh (Jaisalmer)-Akal (Jaisalmer )                                 | D/C | RVPNL      | 198         | DEC-17 |
| 77                             | Kalivanthapattu - Ottiyambakkam (Sholinganallur)                      | D/C | TANTRANSCO | 55          | DEC-17 |
| 78                             | LILO of Vadinar - Hadala at Kalawad                                   | D/C | GETCO      | 16          | JAN-18 |
| 79                             | LILO of Guddadahalli (Munirabad) - Guttur (Davangeere) at Dhoni       | D/C | KPTCL      | 54          | JAN-18 |
| 80                             | Julurupadu (QM) - Suryapet S/s  | D/C | TSTRANSCO  | 219         | JAN-18 |
| 81                             | LILO of one ckt. of KTPS - Khammam line at KTPS-VI                    | D/C | TSTRANSCO  | 1           | JAN-18 |
| 82                             | Jaipur STPP - Nirmal SS   | D/C | TSTRANSCO  | 289         | FEB-18 |
| 83                             | Julurupadu - KTPS (Stage-VII)   | D/C | TSTRANSCO  | 78          | FEB-18 |

|                              |   |       |            |             |        |
|------------------------------|---|-------|------------|-------------|--------|
| 84                           | LILO of Meja - Rewa Road at Masuli (Allahabad)  | D/C   | UPPTCL     | 65          | MAR-18 |
| 85                           | LILO of both ckt. 400kV RTPP - Chittoor TMDC line at 400kV Kalikiri S/S                           | D/C   | APTRANSCO  | 81          | MAR-18 |
| 86                           | Wanakbori S/y -Wanakbori S/y (existing)   | D/C   | GETCO      | 2           | MAR-18 |
| 87                           | LILO of Parbati - II HEP - Parbati-III Pooling station at Sainj                                   | D/C   | HPPTCL     | 1           | MAR-18 |
| 88                           | Yermarus TPS - Bellary Pooling Station (BPS)  | D/C   | KPTCL      | 285         | MAR-18 |
| 89                           | Bikaner -Sikar (PG)   | D/C   | RVPNL      | 420         | MAR-18 |
| 90                           | Phagi (Jaipur south-765 kV)-Ajmer (Ckt. - I)  | D/C   | RVPNL      | 106         | MAR-18 |
| 91                           | LILO in Ist and 2nd Ckt. of MTPS - III - Thiruvalem at Dharmapuri                                 | D/C   | TANTRANSCO | 2           | MAR-18 |
| 92                           | LILO of Chekkanurani - Kayather at Kinnimangalam  | D/C   | TANTRANSCO | 12          | MAR-18 |
| <b>Total of STATE SECTOR</b> |   |       |            | <b>6046</b> |        |
| <b>PRIVATE SECTOR</b>        |   |       |            |             |        |
| 93                           | Malerkotla - Amritsar line (NRSS-XXXI TL(B) - TBCB)   | D/C   | ESSEL      | 299         | APR-17 |
| 94                           | Muzaffarpur - Darbhanga line (DMTCL - TBCB)   | D/C   | ESSEL      | 126         | APR-17 |
| 95                           | Greater Noida-Noida Sec -148 line   | D/C   | WUPPTCL    | 94          | MAY-17 |
| 96                           | LILO of Rishikesh -Kashipur line at Nehtaur s/s   | D/C   | WUPPTCL    | 15          | MAY-17 |
| 97                           | JSW TPS - Bellary (PS)  | D/C   | JPL        | 19          | JUN-17 |
| 98                           | Hapur-Ataur   | D/C   | WUPPTCL    | 106         | JUN-17 |
| 99                           | Hapur-dasna   | D/C   | WUPPTCL    | 29          | JUN-17 |
| 100                          | LILO of Moradabad - Muradnagar TL at Ataur s/s  | D/C   | WUPPTCL    | 30          | JUN-17 |
| 101                          | LILO of Moradabad - Muradnagar TL at Hapur s/s  | D/C   | WUPPTCL    | 4           | JUN-17 |
| 102                          | LILO of Rishikesh - Kashipur line at Nehtaur (Balance portion)                                    | D/C   | WUPPTCL    | 15          | JUN-17 |
| 103                          | Mainpuri (765kV) - Aligarh line (Balance portion)   | D/C   | SEUPPTCL   | 54          | JUL-17 |
| 104                          | LILO of Barh - Gorakhpur 400 kV D/C Line at Motihari (DMTCL -TBCB)                                | 2xD/C | ESSEL      | 151         | AUG-17 |
| 105                          | Nizamabad - Yeddumailaram (Shankarpalli) (MTL - TBCB)   | D/C   | SGL        | 279         | AUG-17 |
| 106                          | OPGC - Jharsuguda (OGP-IITL - TBCB)   | D/C   | SGL        | 103         | AUG-17 |
| 107                          | LILO of Orai-Mainpuri at Mainpuri (Balance Portion)   | D/C   | SEUPPTCL   | 90          | SEP-17 |
| 108                          | LILO of one ckt. of Sikar- Neemrana line at Babai s/s (NRSS-XXXVITL - TBCB)                       | D/C   | ESSEL      | 3           | OCT-17 |
| 109                          | Ind - Barath (Power Plant (Shahjahal) - Jharsuguda (Sundargarh)line                               | D/C   | IBPIL      | 124         | OCT-17 |
| 110                          | Sterlite TPP (Vedanta)- Jharsuguda (Sundargarh) (Balance portion from LILO-I point to Jharsuguda) | D/C   | SEL        | 41          | OCT-17 |



|                                |  |     |                   |              |        |
|--------------------------------|--|-----|-------------------|--------------|--------|
| 111                            | Ataur-Indirapuram line   | D/C | WUPPTCL           | 31           | OCT-17 |
| 112                            | Maheshwaram(PG) - Mehboob Nagar (MTL - TBCB)   | D/C | SGL               | 197          | DEC-17 |
| 113                            | LILO of Orai - Mainpur at Bah  | D/C | SEUPPTCL          | 92           | FEB-18 |
| 114                            | LILO of one ckt. of Khandwa - Rajgarh at Khargone TPP (KTL - TBCB)                   | D/C | SGL               | 14           | FEB-18 |
| 115                            | LILO of Muradnagar -Muzzafarnagar at Ataur   | D/C | WUPPTCL           | 15           | FEB-18 |
| 116                            | Vindhyachal STPS - IV and V - Vindhyachal pool (Quad.) (C-WRTL-TBCB)                 | D/C | APL               | 57           | MAR-18 |
| 117                            | LILO of Both ckt Uri - Wagoora at Amargarh (NRSS-XXIX TL - TBCB)                     | M/C | SGL               | 14           | MAR-18 |
| <b>Total of PRIVATE SECTOR</b> |  |     |                   | <b>2002</b>  |        |
| <b>Total of 400 kV</b>         |  |     |                   | <b>13813</b> |        |
| <b>230 kV</b>                  |  |     |                   |              |        |
| <b>STATE SECTOR</b>            |  |     |                   |              |        |
| 118                            | PH Road - Koyambedu (UG Cable)   | D/C | TANTRANSCO        | 3            | MAY-17 |
| 119                            | Kamudhi - Kavanoor   | D/C | TANTRANSCO        | 56           | JUN-17 |
| 120                            | LILO of Alandur - Alagarkoil at Mondipatti 230 Kv S/S                                | D/C | TANTRANSCO        | 25           | JUN-17 |
| 121                            | Rohini theatre take off structure to CMRL Koyambedu 230kV GIS S/s (230 kV UG cable ) | S/C | TANTRANSCO        | 1            | JUN-17 |
| 122                            | Koladi - PH Road (Alamathy - Koyembedu)  | D/C | TANTRANSCO        | 27           | JUL-17 |
| 123                            | Thiruverkadu - Ambattur 3rd Main road S/S (UG Cable)                                 | D/C | TANTRANSCO        | 10           | AUG-17 |
| 124                            | Vyasarpadi - Pulianthoppe (UG Cable)   | D/C | TANTRANSCO        | 2            | AUG-17 |
| 125                            | Karuvalur - Shenbagapudur line   | S/C | TANTRANSCO        | 33           | OCT-17 |
| 126                            | LILO of Ulundurpet - Villupuram line at Cuddalore                                    | D/C | TANTRANSCO        | 69           | OCT-17 |
| 127                            | Veeranam - Abishekapatty (PGCIL)   | S/C | TANTRANSCO        | 31           | DEC-17 |
| 128                            | Veeranam - Kodikurichi   | S/C | TANTRANSCO        | 24           | MAR-18 |
| 129                            | Veeranam - Kodikurichi line at Kundah  | D/C | TANTRANSCO        | 24           | MAR-18 |
| <b>Total of STATE SECTOR</b>   |  |     |                   | <b>305</b>   |        |
| <b>Total of 230 kV</b>         |  |     |                   | <b>305</b>   |        |
| <b>220 kV</b>                  |  |     |                   |              |        |
| <b>CENTRAL SECTOR</b>          |  |     |                   |              |        |
| 130                            | Khalsti- Leh (Part of Alusteng - Drass - Kargil - Khalsti-Leh)                       | S/C | PGCONSULTA<br>NCY | 62           | NOV-17 |
| 131                            | Kargil - Khalsti Line  | S/C | PGCIL             | 97           | FEB-18 |
| 132                            | Kishanganga - Amargarh line  | D/C | PGCIL             | 85           | FEB-18 |
| <b>Total of CENTRAL SECTOR</b> |  |     |                   | <b>244</b>   |        |
| <b>STATE SECTOR</b>            |  |     |                   |              |        |
| 133                            | LILO of Atri-puri at Pandiabil S/s   | D/C | OPTCL             | 3            | APR-17 |
| 134                            | LILO of Mettur - Karimangalam at Dharmapuri S/s                                      | D/C | TANTRANSCO        | 6            | APR-17 |
| 135                            | Mylapore - Tharamani (UG Cable)  | D/C | TANTRANSCO        | 25           | APR-17 |
| 136                            | Maath (Mathura) -Chhata line   | D/C | UPPTCL            | 68           | APR-17 |

|     |   |            |            |     |        |
|-----|---|------------|------------|-----|--------|
| 137 | Sikandrabad (WUPPTCL) - Sikandrabad (ckt-I&II)                        | D/C        | UPPTCL     | 50  | APR-17 |
| 138 | LILO of 2nd ckt Bhigwan - Walchandnagar at Loni Deokar s/s (Ckt. -II) | S/C on D/C | MSETCL     | 19  | MAY-17 |
| 139 | LILO on Both circuits of Waluj - Jalna at Taptitanda s/s              | 2xD/C      | MSETCL     | 32  | MAY-17 |
| 140 | Warora - Wardha - II (Bhugaon)  | D/C        | MSETCL     | 165 | MAY-17 |
| 141 | LILO of Patran - Kakrala at Patran (PGCIL) s/s                        | D/C        | PSTCL      | 24  | MAY-17 |
| 142 | Uravakonda - Borampalli   | D/C        | APTRANSCO  | 72  | JUN-17 |
| 143 | LILO of 1st ckt. Darbhanga-MTPS(Kanti) at Motipur                     | D/C        | BSPTCL     | 72  | JUN-17 |
| 144 | LILO of 2nd ckt. Darbhanga-MTPS(Kanti) at Motipur                     | D/C        | BSPTCL     | 56  | JUN-17 |
| 145 | LILO of 2nd ckt Pusouli (PG) - Ara (PG) at Pusouli (New).             | D/C        | BSPTCL     | 5   | JUN-17 |
| 146 | LILO of Motipur - Darbhanga ckt-II at Musahari                        | D/C        | BSPTCL     | 41  | JUN-17 |
| 147 | Patna (PG) - Gourichak  | D/C        | BSPTCL     | 1   | JUN-17 |
| 148 | LILO of Chorania - Salejada at Bagodara S/s                           | D/C        | GETCO      | 4   | JUN-17 |
| 149 | Chandrapur MIDC - Ballarshah (Ckt- II)                                | D/C        | MSETCL     | 21  | JUN-17 |
| 150 | Indira Gandhi Nagar -Sitapur (Upgradation)                            | D/C        | RVPNL      | 8   | JUN-17 |
| 151 | Nimbahera - Pratapgarh (Part of Pratapgarh - Chittorgarh line)        | D/C        | RVPNL      | 181 | JUN-17 |
| 152 | LILO of Arasur - Palladam at Tiruppur                                 | D/C        | TANTRANSCO | 20  | JUN-17 |
| 153 | LILO of Chillakallu S/S - Narketpally line at Huzurnagar S/S          | D/C        | TSTRANSCO  | 24  | JUN-17 |
| 154 | LILO of Shadnagar - Yeddumailaram at Yeddumailaram                    | D/C        | TSTRANSCO  | 12  | JUN-17 |
| 155 | Mamidipally S/s-M/s K.S.K. Photo Voltaic near Fabcity Ravirala (V)    | D/C        | TSTRANSCO  | 11  | JUN-17 |
| 156 | Veltur-Thimmajipet  | D/C        | TSTRANSCO  | 80  | JUN-17 |
| 157 | Hapur (765) - Hapur   | S/C        | UPPTCL     | 8   | JUN-17 |
| 158 | LILO of Moradabad - Nehtaur at Amroha                                 | D/C        | UPPTCL     | 45  | JUN-17 |
| 159 | 400 kV Betul s/s - 220 kV Betul s/s                                   | D/C        | MPPTCL     | 4   | JUL-17 |
| 160 | Tondiarpet - Basin Bridge (UG Cable)                                  | D/C        | TANTRANSCO | 4   | JUL-17 |
| 161 | Morti (220kV) - Ataur (400kV)   | D/C        | UPPTCL     | 13  | JUL-17 |
| 162 | LILO of 2nd Ckt. Damoh - Sagar line at Damoh S/s                      | D/C        | MPPTCL     | 1   | AUG-17 |
| 163 | Balapur - Malegaon line Ckt.-I  | D/C        | MSETCL     | 71  | AUG-17 |
| 164 | Phaltan - Walchandnagar   | D/C        | MSETCL     | 114 | AUG-17 |
| 165 | LILO of Sankhari-Jangral at Veloda (Sankhari)                         | MC+D/C     | GETCO      | 61  | SEP-17 |
| 166 | LILO of Tappar-Hadala line at Vondh S/s                               | D/C        | GETCO      | 4   | SEP-17 |
| 167 | Jethana - Ajmer line  | D/C        | RVPNL      | 120 | SEP-17 |
| 168 | Jodhpur (New) - Jhalamand (TK)  | D/C        | RVPNL      | 40  | SEP-17 |
| 169 | Kalisindh TPS - Bhawanimandi  | S/C        | RVPNL      | 34  | SEP-17 |
| 170 | Dharmapuri (Palavady) - Gurubarapally                                 | S/C        | TANTRANSCO | 58  | SEP-17 |

|     |   |        |            |     |        |
|-----|---|--------|------------|-----|--------|
| 171 | LILO of Arasur - Karamadai at Shenbagapur S/S   | D/C    | TANTRANSCO | 75  | SEP-17 |
| 172 | LILO of Thiruvarur - Kadalangudi at Kumbakonam  | D/C    | TANTRANSCO | 46  | SEP-17 |
| 173 | Jajji - Rai line  | D/C    | HVPNL      | 102 | OCT-17 |
| 174 | LILO of 2nd Ckt. of Bansagar - Satna line at Kotar                                      | D/C    | MPPTCL     | 11  | OCT-17 |
| 175 | LILO of one ckt. of Satna (MPPTCL) - Chhaterpur line at Satna (PGCIL)                   | D/C    | MPPTCL     | 4   | OCT-17 |
| 176 | Shirpur Power Plant - Amalner line  | D/C    | MSETCL     | 70  | OCT-17 |
| 177 | Aligarh - Sikandra Rau line   | D/C    | UPPTCL     | 35  | OCT-17 |
| 178 | Jamnagar - Hadala   | D/C    | GETCO      | 139 | NOV-17 |
| 179 | LILO of both circuit Nyara-Thebda line at Kalawad S/s                                   | M/C    | GETCO      | 21  | NOV-17 |
| 180 | LILO of Haldarwa-Zaghadia Line to Jhanor  | D/C    | GETCO      | 14  | NOV-17 |
| 181 | LILO of both circuits of Madanpur - Baddi at Pinjore                                    | M/C    | HVPNL      | 23  | NOV-17 |
| 182 | Malegaon-Kalwan   | D/C    | MSETCL     | 98  | NOV-17 |
| 183 | LILO of Myvadi - Othakkalmandapam feeder at Anaikadavu 400 KV SS                        | D/C    | TANTRANSCO | 1   | NOV-17 |
| 184 | Bareilly (400) - Pilibhit   | S/C    | UPPTCL     | 39  | NOV-17 |
| 185 | LILO of Both ckt. of Biharsharif - Begusarai at BTPS Extn.                              | D/C    | BSPTCL     | 4   | DEC-17 |
| 186 | LILO of one ckt of Akrimota - Nakhatrana line at Bhachunda                              | D/C    | GETCO      | 53  | DEC-17 |
| 187 | Darbhanga - Samastipur (New)  | D/C    | BSPTCL     | 47  | DEC-17 |
| 188 | Motipur(BSPTCL) - Darbhanga(DMTCL)  | D/C    | BSPTCL     | 218 | DEC-17 |
| 189 | Chaibasa -Ramchandrapur   | D/C    | JUSNL      | 80  | DEC-17 |
| 190 | LILO of B.Bagewadi - Bijapur line at Kudgi 400kV STPP                                   | M/C    | KPTCL      | 80  | DEC-17 |
| 191 | Akola - Anjangaon line  | D/C    | MSETCL     | 106 | DEC-17 |
| 192 | LILO on Babhaleshwar - Alephata at UTSL C-Gen Plant line                                | D/C    | MSETCL     | 10  | DEC-17 |
| 193 | LILO on existing Phaltan - Walchandnagar at CSSK Bhavaninagar line                      | D/C    | MSETCL     | 2   | DEC-17 |
| 194 | LILO of Gadag - Lingapur at Gadag (Doni)  | D/C    | KPTCL      | 11  | JAN-18 |
| 195 | LILO of Somanahalli S/S-Yerandanahalli at Jigani 220kV s/s                              | MC+D/C | KPTCL      | 12  | JAN-18 |
| 196 | LILO of one ckt. 220KV Nakodar - Rehanajattan line at 220KV Hoshiarpur                  | D/C    | PSTCL      | 52  | JAN-18 |
| 197 | Jaipur North (400 kV GSS) - Manoharpur (Turnkey) and extended to LILO of S/C VKIA-Kukus | D/C    | RVPNL      | 80  | JAN-18 |
| 198 | Pratapgarh - Chittorgarh (Balance Portion)  | D/C    | RVPNL      | 61  | JAN-18 |
| 199 | Sarnath - Azamgarh - II   | S/C    | UPPTCL     | 60  | JAN-18 |
| 200 | LILO Urla - Khedamara (Bhilai) at Borjhara  | M/C    | CSPTCL     | 1   | FEB-18 |
| 201 | LILO of Bamnauli - Naraina at PPK-III   | D/C    | DTL        | 1   | FEB-18 |

|     |   |            |         |     |        |
|-----|---|------------|---------|-----|--------|
| 202 | Vyankatpura - Waghodia (765kV PGCIL) line                                       | D/C        | GETCO   | 29  | FEB-18 |
| 203 | LILO of RTPS - Lingasugur at Mallat (Manvi)                                     | D/C        | KPTCL   | 6   | FEB-18 |
| 204 | Vasanthanarasapura - Antharasanahally   | D/C        | KPTCL   | 38  | FEB-18 |
| 205 | Pothencode - Kattakkada   | D/C        | KSEB    | 57  | FEB-18 |
| 206 | LILO of Indore - Indore - II (Jaitpura) line at Mangliya S/s                    | D/C        | MPPTCL  | 1   | FEB-18 |
| 207 | LILO of one Ckt. Malanpur - Mehgaon line at CWRTL (Adani) S/s                   | D/C        | MPPTCL  | 26  | FEB-18 |
| 208 | Aurangabad-II - Jalna MIDC (Negewadi)   | D/C        | MSETCL  | 77  | FEB-18 |
| 209 | Kalwa - Borivali  | M/C        | MSETCL  | 63  | FEB-18 |
| 210 | LILO of Katapalli - Bolangir at Bargarh (New)                                   | D/C        | OPTCL   | 1   | FEB-18 |
| 211 | LILO of GHTP - Talwandi Sabo at Maur  | D/C        | PSTCL   | 18  | FEB-18 |
| 212 | Mukatsar - Kotkapura Ckt.-I   | S/C on D/C | PSTCL   | 39  | FEB-18 |
| 213 | Mukatsar - Malout   | D/C        | PSTCL   | 47  | FEB-18 |
| 214 | LILO of Howrah - Foundry Park at N. Chanditala.                                 | M/C        | WBSETCL | 36  | FEB-18 |
| 215 | LILO of Jeerat - Kasba at Barasat   | M/C        | WBSETCL | 10  | FEB-18 |
| 216 | LILO on Vita - Pandharpur line for Varkule - Malwadi Solar (M/s. Giriraj Solar) | D/C        | MSETCL  | 19  | MAR-18 |
| 217 | LILO of one ckt Samaguri - Sarusajai line at Sonapur S/S                        | D/C        | AEGCL   | 27  | MAR-18 |
| 218 | Darbhanga(DMTCL) - Supaul/Laukahi(BSPTCL)                                       | D/C        | BSPTCL  | 176 | MAR-18 |
| 219 | Magarwada (PG) - Magarwada  | D/C        | DANDD   | 2   | MAR-18 |
| 220 | Magarwada - Ringanwada  | D/C        | DANDD   | 12  | MAR-18 |
| 221 | LILO of both ckt. Tebhda - Rajkot line at Kalavad S/s                           | D/C        | GETCO   | 21  | MAR-18 |
| 222 | LILO of Jamnagar - Jetpur line-II at Sikka                                      | D/C        | GETCO   | 117 | MAR-18 |
| 223 | LILO of one ckt. Vyankatpura - Achhalia line at Kawant                          | D/C        | GETCO   | 167 | MAR-18 |
| 224 | Kairan-Chamera - II (PG)  | D/C        | HPPTCL  | 4   | MAR-18 |
| 225 | Amargarh (Delina) - Zainkote (2nd Ckt.)   | S/C        | JKPDD   | 43  | MAR-18 |
| 226 | LILO of Zainkote - Dalina at Amargarh   | 2xD/C      | JKPDD   | 12  | MAR-18 |
| 227 | Gwalior (PG) - Gwalior (MP) - 2nd circuiting                                    | D/C        | MPPTCL  | 3   | MAR-18 |
| 228 | Morena (Adani) - Morena (MP)  | D/C        | MPPTCL  | 49  | MAR-18 |
| 229 | Chandrapur - II - Chandrapur MIDC ( Tadali)                                     | D/C        | MSETCL  | 81  | MAR-18 |
| 230 | Kumbhargaoon - Krishnoor line ckt.-II   | D/C        | MSETCL  | 16  | MAR-18 |
| 231 | LILO on 220 kV Deepnagar - Amalner at Viroda                                    | D/C        | MSETCL  | 20  | MAR-18 |
| 232 | Partur - Nagewadi line  | D/C        | MSETCL  | 126 | MAR-18 |
| 233 | Ludhiana - Doraha   | D/C        | PSTCL   | 28  | MAR-18 |
| 234 | Nabha -Bhawanigarh  | S/C on D/C | PSTCL   | 40  | MAR-18 |
| 235 | Nakodar - Rehana  | D/C        | PSTCL   | 71  | MAR-18 |
| 236 | LILO of 1st ckt. Saharanpur - Khodri line at Sarsawa                            | D/C        | UPPTCL  | 14  | MAR-18 |

|                                |   |     |        |              |        |
|--------------------------------|---|-----|--------|--------------|--------|
| 237                            | LILO of 1st ckt. Sarojni Nagar - Unnao at Kanpur Road   | D/C | UPPTCL | 9            | MAR-18 |
| 238                            | LILO of Chinhat - Raebareli (PG) line at CG City Lko    | D/C | UPPTCL | 3            | MAR-18 |
| 239                            | LILO of Gorakhpur (PG) - Basti at Bansi                 | D/C | UPPTCL | 95           | MAR-18 |
| 240                            | LILO of Gr. Noida (400) - Sec.129 at Noida Sector - 148 | D/C | UPPTCL | 1            | MAR-18 |
| 241                            | Neebkarori - Mainpuri line                              | D/C | UPPTCL | 70           | MAR-18 |
| 242                            | Sitapur - Nighasan line                                 | S/C | UPPTCL | 109          | MAR-18 |
| <b>Total of STATE SECTOR</b>   |   |     |        | <b>4916</b>  |        |
| <b><u>PRIVATE SECTOR</u></b>   |   |     |        |              |        |
| 243                            | Haldia TPP (IPCL) - New Haldia (WBSETCL)                | D/C | IPCHL  | 5            | MAY-17 |
| 244                            | Tashiding - Legship                                     | D/C | SEPL   | 17           | MAR-18 |
| <b>Total of PRIVATE SECTOR</b> |   |     |        | <b>22</b>    |        |
| <b>Total of 220 kV</b>         |   |     |        | <b>5182</b>  |        |
| <b>Grand Total</b>             |   |     |        | <b>23119</b> |        |

**ANNEXURE-3J**  
(Item 3.26)

**As on 31-Mar-2018**

| <b>Sub-Stations Completed During FY - 2017-18</b> |   |                              |                         |                          |                            |
|---|---|------------------------------|-------------------------|--------------------------|----------------------------|
| <b>Sl No</b>                                      | <b>Name of Sub Stations</b>   | <b>Voltage Ratio (kV/kV)</b> | <b>Executing Agency</b> | <b>Capacity (MW/MVA)</b> | <b>Month of Completion</b> |
| <b>1</b>  | <b>2</b>  | <b>3</b>                     | <b>4</b>                | <b>5</b>                 | <b>6</b>                   |
| <b>800 kV</b>                                     |   |                              |                         |                          |                            |
| <b><u>CENTRAL SECTOR</u></b>                      |   |                              |                         |                          |                            |
| 1   | Champa and Kurukshetra HVDC S/S (Pole - II)                                     | 800                          | PGCIL                   | 1500                     | JUN-17                     |
| 2   | Alipurduar and Agra (Extn) HVDC S/S (Pole -4)                                   | 800                          | PGCIL                   | 1500                     | SEP-17                     |
| <b>TOTAL CENTRAL SECTOR</b>                       |   |                              |                         | <b>3000</b>              |                            |
| <b>TOTAL 800 kV</b>                               |   |                              |                         | <b>3000</b>              |                            |
| <b>765 kV</b>                                     |   |                              |                         |                          |                            |
| <b><u>CENTRAL SECTOR</u></b>                      |   |                              |                         |                          |                            |
| 3   | Nizamabad s/s (ICT-II)  | 765/400                      | PGCIL                   | 1500                     | APR-17                     |
| 4   | Bay Extn. at 765KV Jabalpur Pooling Station. (Gadarwara Part A)                 | 765/400                      | PGCIL                   | 0                        | MAY-17                     |
| 5   | Bay Extn. at 765/400/220KV KanpurS/stn.   | 765                          | PGCIL                   | 0                        | MAY-17                     |
| 6   | Bay Extn. at 765/400/220KV Lucknow S/stn.                                       | 765                          | PGCIL                   | 0                        | MAY-17                     |
| 7   | Hyderabad (Maheshwaram) (GIS) S/S - (ICT-I)                                     | 765/400                      | PGCIL                   | 1500                     | JUL-17                     |
| 8   | Bay Extn. at 765/400KV Hyderabad S/stn for 765KV D/C Nizamabad - Hyderabad line | 765/400                      | PGCIL                   | 0                        | JUL-17                     |
| 9   | Extn. Ranchi S/S  | 765/400                      | PGCIL                   | 0                        | JUL-17                     |
| 10  | Vindhyachal Pooling Station   | 765/400                      | PGCIL                   | 1500                     | JUL-17                     |
| 11  | Bay Extn. at 765/400KV Kanpur GIS   | 765/400                      | PGCIL                   | 0                        | SEP-17                     |
| 12  | Hyderabad (Maheshwaram) (GIS) S/S - (ICT-II)                                    | 765/400                      | PGCIL                   | 1500                     | SEP-17                     |
| 13  | Padghe S/S GIS  | 765/400                      | PGCIL                   | 3000                     | DEC-17                     |
| 14  | Ajmer S/S   | 765/400                      | PGCIL                   | 3000                     | DEC-17                     |
| 15  | Chittorgarh S/S   | 765/400                      | PGCIL                   | 3000                     | DEC-17                     |
| 16  | Orai (ICT-I)  | 765/400                      | PGCIL                   | 1000                     | MAR-18                     |
| <b>TOTAL CENTRAL SECTOR</b>                       |   |                              |                         | <b>16000</b>             |                            |
| <b><u>STATE SECTOR</u></b>                        |   |                              |                         |                          |                            |
| 17  | Anta GSS (ICT-3)  | 765/400                      | RVPNL                   | 1500                     | APR-17                     |
| 18  | Unnao (Addl ICT- III) s/s   | 765/400                      | UPPTCL                  | 1000                     | JUN-17                     |

|                              |   |         |         |              |        |
|------------------------------|---|---------|---------|--------------|--------|
| 19                           | 765 kV S/S Greater Noida (New) ICT-II                         | 765/400 | UPPTCL  | 1500         | FEB-18 |
|                              | <b>TOTAL STATE SECTOR</b>                                     |         |         | <b>4000</b>  |        |
| <b><u>PRIVATE SECTOR</u></b> |   |         |         |              |        |
| 20                           | Hapur AIS (ICT-II)  | 765/400 | WUPPTCL | 1500         | AUG-17 |
| 21                           | Hapur (New) ICT-I   | 765/400 | WUPPTCL | 1500         | JAN-18 |
|                              | <b>TOTAL PRIVATE SECTOR</b>                                   |         |         | <b>3000</b>  |        |
|                              | <b>TOTAL 765 kV</b>   |         |         | <b>23000</b> |        |
| <b>400 kV</b>                |   |         |         |              |        |
| <b><u>CENTRAL SECTOR</u></b> |   |         |         |              |        |
| 22                           | Extn. Vadodara S/S (GIS)                                      | 400/220 | PGCIL   | 1000         | APR-17 |
| 23                           | Agra (Extn.) s/s  | 400/220 | PGCIL   | 315          | JUN-17 |
| 24                           | Trichy (Extn.)  | 400/220 | PGCIL   | 500          | JUN-17 |
| 25                           | Ballabgarh S/S (Replacement of ICT-III and ICT-IV) ((500-315) | 400/220 | PGCIL   | 370          | JUN-17 |
| 26                           | Itarsi S/S  | 400/220 | PGCIL   | 500          | JUL-17 |
| 27                           | Gurgaon S/s 4th-ICT (Aug.) (under NRSS-XXXII)                 | 400/220 | PGCIL   | 500          | JUL-17 |
| 28                           | Betul (GIS) S/S   | 400/220 | PGCIL   | 630          | JUL-17 |
| 29                           | Mainpuri Extn.  | 400/220 | PGCIL   | 500          | AUG-17 |
| 30                           | Kala Amb S/S (PKATL-TBCB)                                     | 400/220 | PGCIL   | 630          | AUG-17 |
| 31                           | Bay Extn. at 400/220KV Sholapur S/stn.                        | 400     | PGCIL   | 0            | SEP-17 |
| 32                           | Maithon S/S (Replacement of ICT-II) (500-315)                 | 400/220 | PGCIL   | 185          | OCT-17 |
| 33                           | Kaithal s/s (Extn. )  | 400/220 | PGCIL   | 315          | OCT-17 |
| 34                           | Satna s/s (Extn.)   | 400/220 | PGCIL   | 500          | OCT-17 |
| 35                           | Tumkur (Pavagada) Pooling Station (ICT-I)                     | 400/220 | PGCIL   | 500          | OCT-17 |
| 36                           | Jamshedpur S/S  | 400/220 | PGCIL   | 315          | DEC-17 |
| 37                           | Narendra S/S - (ICT-I) Repl.                                  | 400/220 | PGCIL   | 185          | DEC-17 |
| 38                           | Parbati S/S (PS)  | 400/220 | PGCIL   | 630          | DEC-17 |
| 39                           | Gurgaon S/S - (ICT)   | 400/220 | PGCIL   | 500          | DEC-17 |
| 40                           | Bay Extn at 400KV Tuticorin Pooling Stn.                      | 400     | PGCIL   | 0            | DEC-17 |
| 41                           | Tumkur (Pavagada) PS (3x500) (ICT-II)                         | 400/220 | PGCIL   | 500          | FEB-18 |
| 42                           | 400/220kV Patna S/S   | 400/220 | PGCIL   | 500          | FEB-18 |
| 43                           | Extn. at Sikar S/S  | 400/220 | PGCIL   | 500          | MAR-18 |
| 44                           | Extn at Tirunelveli S/s                                       | 400/220 | PGCIL   | 500          | MAR-18 |
| 45                           | Rewa (ICT-I and II)   | 400/220 | PGCIL   | 1000         | MAR-18 |
| 46                           | Extn. at Karaikudi s/s  | 400/230 | PGCIL   | 500          | MAR-18 |
| 47                           | Daltonganj (ICT-I)  | 400/220 | PGCIL   | 315          | MAR-18 |
| 48                           | Extn.at Daltonganj S/S  | 400/220 | PGCIL   | 320          | MAR-18 |
| 49                           | Extn. at Kozhikode S/s  | 400/220 | PGCIL   | 500          | MAR-18 |
| 50                           | Yehlanka  | 400/220 | PGCIL   | 1000         | MAR-18 |
| 51                           | Extn. at Arasur S/s   | 400/230 | PGCIL   | 500          | MAR-18 |
|                              | <b>TOTAL CENTRAL SECTOR</b>                                   |         |         | <b>14210</b> |        |

**STATE SECTOR**

|    |   |                 |            |      |        |
|----|---|-----------------|------------|------|--------|
| 52 | Maath (Mathura) s/s (ICT-1)                 | 400/220         | UPPTCL     | 315  | APR-17 |
| 53 | Azamgarh (ICT-1) (Aug 500-315)              | 400/220         | UPPTCL     | 185  | APR-17 |
| 54 | Maath Mathura (New) (ICT-II)                | 400/220         | UPPTCL     | 315  | MAY-17 |
| 55 | Banda (New) (ICT-I)                         | 400/220         | UPPTCL     | 315  | MAY-17 |
| 56 | Agra (Aug) (500-315)                        | 400/220         | UPPTCL     | 185  | MAY-17 |
| 57 | Sultanpur (Additional) s/s                  | 400/220         | UPPTCL     | 315  | MAY-17 |
| 58 | Veltoor (Aug.)                              | 400/220         | TSTRANSCO  | 315  | JUN-17 |
| 59 | Thervaigandigai                             | 400/230/1<br>10 | TANTRANSCO | 830  | JUN-17 |
| 60 | Manali (GIS)                                | 400/230/1<br>10 | TANTRANSCO | 1030 | JUN-17 |
| 61 | Dindi S/S                                   | 400/220         | TSTRANSCO  | 630  | JUN-17 |
| 62 | Rasipalayam S/S                             | 400/230         | TANTRANSCO | 1030 | JUN-17 |
| 63 | Gani (3x500 - ICT-II)                       | 400/220         | APTRANSCO  | 500  | JUN-17 |
| 64 | Agra (South) S/S                            | 400/132         | UPPTCL     | 600  | JUN-17 |
| 65 | Kasara Mau (Addl ICT-III) S/s               | 400/132         | UPPTCL     | 200  | JUN-17 |
| 66 | Vemagiri (Aug) (ICT-III)                    | 400/220         | APTRANSCO  | 315  | JUN-17 |
| 67 | Jammalamudgu (ICT-II) (GEC-I)               | 400/220/1<br>32 | APTRANSCO  | 315  | JUN-17 |
| 68 | Uravakonda (Aug) (ICT-I)                    | 400/220         | APTRANSCO  | 500  | JUN-17 |
| 69 | Dhuri (New) (Addl.)                         | 400/220         | PSTCL      | 500  | JUL-17 |
| 70 | Gani (3x500 - ICT-III)                      | 400/220         | APTRANSCO  | 500  | JUL-17 |
| 71 | Maheswaram S/S                              | 400/220         | TSTRANSCO  | 500  | AUG-17 |
| 72 | Rasipalayam S/S (ICT-6)                     | 400/110         | TANTRANSCO | 200  | AUG-17 |
| 73 | Manali (Addl)                               | 400/110         | TANTRANSCO | 200  | AUG-17 |
| 74 | Alamathy                                    | 400/110         | TANTRANSCO | 200  | AUG-17 |
| 75 | Bhadla (Distt. Jodhpur)-ICT-1               | 400/220         | RVPNL      | 500  | AUG-17 |
| 76 | Asupaka S/S                                 | 400/220         | TSTRANSCO  | 315  | AUG-17 |
| 77 | New Chanditala 400kV S/s                    | 400/220         | WBSETCL    | 315  | AUG-17 |
| 78 | Dharmapuri (Palavady) 200MVA-<br>ICT-II     | 400/110         | TANTRANSCO | 200  | SEP-17 |
| 79 | Dharmapuri (Palavady)-ICT-II                | 400/230         | TANTRANSCO | 315  | SEP-17 |
| 80 | Narsapur (ICT-II)                           | 400/220         | TSTRANSCO  | 315  | SEP-17 |
| 81 | New Chanditala 400kV- (ICT-II)              | 400/220         | WBSETCL    | 315  | SEP-17 |
| 82 | Bhadla (Distt Jhodpur)-ICT-II               | 400/220         | RVPNL      | 500  | SEP-17 |
| 83 | Sultanpur (Aug.) (315-240)                  | 400/220         | UPPTCL     | 75   | OCT-17 |
| 84 | Jagdapur (ICT-I)                            | 400/220         | CSPTCL     | 315  | NOV-17 |
| 85 | Anaikadavu SS                               | 400/230/1<br>10 | TANTRANSCO | 1030 | NOV-17 |
| 86 | Chhegaon Addl. (Distt. Khandwa)<br>(Makhan) | 400/220         | MPPTCL     | 315  | NOV-17 |
| 87 | Orai (New) (ICT-II)                         | 400/220         | UPPTCL     | 315  | NOV-17 |
| 88 | Padhge ICT Repl(500-315)                    | 400/220         | MSETCL     | 185  | NOV-17 |
| 89 | Maheshwaram (2x500)-ICT-II                  | 400/220         | TSTRANSCO  | 500  | NOV-17 |
| 90 | Narsapur-ICT-III                            | 400/220         | TSTRANSCO  | 315  | NOV-17 |
| 91 | Sholinganallur (Ottinmbakkam)<br>S/S        | 400/230/1<br>10 | TANTRANSCO | 830  | DEC-17 |



|                              |   |                |            |              |        |
|------------------------------|---|----------------|------------|--------------|--------|
| 92                           | Moradabad (Aug.) S/S (500 - 315)            | 400/220        | UPPTCL     | 185          | DEC-17 |
| 93                           | Muradnagar -II (Aug.) S/S (315-240)         | 400/220        | UPPTCL     | 75           | DEC-17 |
| 94                           | Kudus New S/S - (ICT-I)                     | 400/220        | MSETCL     | 500          | DEC-17 |
| 95                           | Gorkhpur (Aug.) (500-240)                   | 400/220        | UPPTCL     | 260          | JAN-18 |
| 96                           | Hinjewadi II (GIS)                          | 400/220        | MSETCL     | 1000         | FEB-18 |
| 97                           | Jejuri (Addl.)                              | 400/220/3<br>3 | MSETCL     | 500          | MAR-18 |
| 98                           | Muradnagar-I (Aug.) (500-315)               | 400/220        | UPPTCL     | 185          | MAR-18 |
| 99                           | GSS Babai S/S                               | 400/220        | RVPNL      | 315          | MAR-18 |
| 100                          | Sanand                                      | 400/220        | GETCO      | 500          | MAR-18 |
| 101                          | Mardam                                      | 400/220        | APTRANSCO  | 630          | MAR-18 |
| 102                          | Kudus (ICT -II)                             | 400/220        | MSETCL     | 500          | MAR-18 |
| 103                          | Chandrapur-II (Addl.)                       | 400/220        | MSETCL     | 500          | MAR-18 |
| 104                          | Aurangabad-II (Thaptitanda) (Addl.)         | 400/220        | MSETCL     | 500          | MAR-18 |
| <b>TOTAL STATE SECTOR</b>    |   |                |            | <b>22300</b> |        |
| <b><u>PRIVATE SECTOR</u></b> |   |                |            |              |        |
| 105                          | Darbhanga (GIS) (DMTCL - TBCB)              | 400/220        | ESSEL      | 1000         | APR-17 |
| 106                          | Nehtaur (Bijnor) (New) AIS                  | 400/132        | WUPPTCL    | 200          | JUN-17 |
| 107                          | Gonda AIS                                   | 400/220        | SEUPPTCL   | 630          | JUL-17 |
| 108                          | Motihari (GIS) (DMTCL -TBCB)                | 400/132        | ESSEL      | 400          | AUG-17 |
| 109                          | Ataur                                       | 400/220        | WUPPTCL    | 500          | SEP-17 |
| 110                          | Indirapuram (New)                           | 400/220        | WUPPTCL    | 1000         | OCT-17 |
| 111                          | Dasna GIS                                   | 400/220        | WUPPTCL    | 630          | NOV-17 |
| 112                          | Ataur (New)- ICT-II                         | 400/220        | WUPPTCL    | 500          | NOV-17 |
| 113                          | Morena S/S (C-WRTL - TBCB)                  | 400/220        | APL        | 630          | FEB-18 |
| <b>TOTAL PRIVATE SECTOR</b>  |   |                |            | <b>5490</b>  |        |
| <b>TOTAL 400 kV</b>          |   |                |            | <b>42000</b> |        |
| <b>230 kV</b>                |   |                |            |              |        |
| <b><u>STATE SECTOR</u></b>   |   |                |            |              |        |
| 114                          | Oragadam (3rd Auto) s/s                     | 230/110        | TANTRANSCO | 100          | MAY-17 |
| 115                          | Kumbakkonam (JICA) S/S                      | 230/110        | TANTRANSCO | 200          | JUN-17 |
| 116                          | Central CMRL (GIS) (JICA)                   | 230/110        | TANTRANSCO | 200          | JUN-17 |
| 117                          | Eachangadu S/S                              | 230/110        | TANTRANSCO | 30           | JUL-17 |
| 118                          | Valayapatty                                 | 230/110        | TANTRANSCO | 80           | JUL-17 |
| 119                          | Mondipatty (1x80)                           | 230/110        | TANTRANSCO | 80           | SEP-17 |
| 120                          | Jambunathapuram                             | 230/110        | TANTRANSCO | 200          | NOV-17 |
| 121                          | Anuppankulam (Enhancement from 1x100- 1x60) | 230/110        | TANTRANSCO | 60           | FEB-18 |
| 122                          | Pudukkottai (Additional Transformer)        | 230/110        | TANTRANSCO | 160          | FEB-18 |
| 123                          | Savasapuram                                 | 230/110        | TANTRANSCO | 100          | MAR-18 |
| <b>TOTAL STATE SECTOR</b>    |   |                |            | <b>1210</b>  |        |
| <b>TOTAL 230 kV</b>          |   |                |            | <b>1210</b>  |        |
| <b>220 kV</b>                |   |                |            |              |        |
| <b><u>CENTRAL SECTOR</u></b> |   |                |            |              |        |

|                             |   |         |               |            |        |
|-----------------------------|---|---------|---------------|------------|--------|
| 124                         | Balipara S/S -ICT-I (Repl. 1x160-1x50)                | 220/132 | PGCIL         | 110        | SEP-17 |
| 125                         | (J and K) Khalsti S/S                                 | 220/66  | PGCONSULTANCY | 50         | NOV-17 |
| 126                         | (J and K) Leh S/S                                     | 220/66  | PGCONSULTANCY | 125        | NOV-17 |
| 127                         | Raebareli SS (Repl. of 100 MVA to 200MVA)- ICT-1      | 220/132 | PGCIL         | 100        | NOV-17 |
| 128                         | Raebareli SS )Repl. of 100 MVA - 200 MVA)- (ICT-II)   | 220/132 | PGCIL         | 100        | FEB-18 |
| <b>TOTAL CENTRAL SECTOR</b> |   |         |               | <b>485</b> |        |
| <b><u>STATE SECTOR</u></b>  |   |         |               |            |        |
| 129                         | Meerpur Kurali s/s (ICT-1)                            | 220/66  | HVPNL         | 100        | APR-17 |
| 130                         | Sec-1 IMT Manesar s/s                                 | 220/66  | HVPNL         | 60         | APR-17 |
| 131                         | Chandausi (Sambhal) (ICT-II)                          | 220/132 | UPPTCL        | 160        | APR-17 |
| 132                         | Chhata (Mathura ) s/s (ICT-1)                         | 220/132 | UPPTCL        | 160        | APR-17 |
| 133                         | Nanauta (ICT-I) (Aug200-100)                          | 220/132 | UPPTCL        | 100        | APR-17 |
| 134                         | Sadaipur s/s (ICT-1)                                  | 220/132 | WBSETCL       | 160        | APR-17 |
| 135                         | Omega Industrial Estate s/s                           | 220/110 | TANTRANSCO    | 200        | APR-17 |
| 136                         | Taramani (4th Auto Trf)                               | 220/110 | TANTRANSCO    | 100        | APR-17 |
| 137                         | Basti (ICT-1) (Aug 200-160)                           | 220/132 | UPPTCL        | 40         | APR-17 |
| 138                         | Bharthana (Etawah) (ICT-1)(Aug 160-100)               | 220/132 | UPPTCL        | 60         | APR-17 |
| 139                         | Morena (new) s/s                                      | 220/132 | MPPTCL        | 160        | APR-17 |
| 140                         | Vile Bhagad s/s (ICT-II)                              | 220/22  | MSETCL        | 25         | APR-17 |
| 141                         | Bonai S/S (ICT-1)                                     | 220/33  | OPTCL         | 20         | APR-17 |
| 142                         | RA Puram (GIS) UG (JICA)                              | 220/33  | TANTRANSCO    | 200        | APR-17 |
| 143                         | Allahabad (Rewa Road) (Augmentation of 160MVA ICT-II) | 220/132 | UPPTCL        | 40         | MAY-17 |
| 144                         | Gurugram Sec-20 (GIS)                                 | 220/66  | HVPNL         | 200        | MAY-17 |
| 145                         | Sonta s/s (2nd T/F)                                   | 220/66  | HVPNL         | 100        | MAY-17 |
| 146                         | Bhawanigarh s/s                                       | 220/66  | PSTCL         | 160        | MAY-17 |
| 147                         | Kotla Jagan s/s                                       | 220/66  | PSTCL         | 60         | MAY-17 |
| 148                         | Mhaisal s/s (Addl )                                   | 220/33  | MSETCL        | 25         | MAY-17 |
| 149                         | Airoli Knowledge Park s/s                             | 220/22  | MSETCL        | 50         | MAY-17 |
| 150                         | Bhelupur - (ICT -II)                                  | 220/132 | UPPTCL        | 60         | MAY-17 |
| 151                         | Chinchwad-II (Addl-ICT) s/s                           | 220/132 | MSETCL        | 200        | MAY-17 |
| 152                         | Kharghar S/s  | 220/33  | MSETCL        | 50         | JUN-17 |
| 153                         | Mandalgarh S/s  | 220/132 | RVPNL         | 100        | JUN-17 |
| 154                         | Warud S/S   | 220/132 | MSETCL        | 200        | JUN-17 |
| 155                         | Jorian (Aug) S/s                                      | 220/132 | HVPNL         | 60         | JUN-17 |
| 156                         | Bhestan S/S   | 220/66  | GETCO         | 300        | JUN-17 |
| 157                         | Bechraji S/S  | 220/66  | GETCO         | 200        | JUN-17 |
| 158                         | Dharamkot (Addl)                                      | 220/66  | PSTCL         | 100        | JUN-17 |
| 159                         | Bahadurgarh (Bhater) (Aug.)                           | 220/66  | PSTCL         | 100        | JUN-17 |
| 160                         | Bagha Purana (Addl)                                   | 220/66  | PSTCL         | 100        | JUN-17 |
| 161                         | Magadi  | 220/66  | KPTCL         | 200        | JUN-17 |

|     |                                       |                |           |     |        |
|-----|---------------------------------------|----------------|-----------|-----|--------|
| 162 | Chinthamani (Aug.)                    | 220/66         | KPTCL     | 100 | JUN-17 |
| 163 | Gurgaon Sector - 33 S/s               | 220/66         | HVPNL     | 160 | JUN-17 |
| 164 | Masjid Moth (Addl.)                   | 220/33         | DTL       | 100 | JUN-17 |
| 165 | Sector -6 Sonipat S/S                 | 220/33         | HVPNL     | 100 | JUN-17 |
| 166 | Bhokardhan (2nd Trf.)                 | 220/33         | MSETCL    | 50  | JUN-17 |
| 167 | Vallabhipur S/S                       | 220/66         | GETCO     | 100 | JUN-17 |
| 168 | Hapur (New)(ICT-II)                   | 220/132/3<br>3 | UPPTCL    | 180 | JUN-17 |
| 169 | Musahari S/S                          | 220/132/3<br>3 | BSPTCL    | 320 | JUN-17 |
| 170 | Motipur (GSS) (Bikhanpura new)<br>S/S | 220/132/3<br>3 | BSPTCL    | 320 | JUN-17 |
| 171 | Goddumarri                            | 220/11         | APTRANSCO | 100 | JUN-17 |
| 172 | Yellanur                              | 220/11         | APTRANSCO | 50  | JUN-17 |
| 173 | Barahua/ Gorakhpur (Aug)              | 220/132        | UPPTCL    | 60  | JUN-17 |
| 174 | Amroha (New) (ICT-I)                  | 220/132        | UPPTCL    | 160 | JUN-17 |
| 175 | Dichpally (Aug.)                      | 220/132        | TSTRANSCO | 315 | JUN-17 |
| 176 | Pratapgarh (Upgradation)(160-100)     | 220/132        | RVPNL     | 60  | JUN-17 |
| 177 | Peeragarhi (Addl.)                    | 220/33         | DTL       | 100 | JUL-17 |
| 178 | Karnal s/s                            | 220/33         | HVPNL     | 50  | JUL-17 |
| 179 | Panchgaon S/S                         | 220/33         | HVPNL     | 100 | JUL-17 |
| 180 | Mhaisal s/s (Addl-2)                  | 220/33         | MSETCL    | 25  | JUL-17 |
| 181 | Mahilpur (Addl)                       | 220/66         | PSTCL     | 100 | JUL-17 |
| 182 | Amroha (New)(ICT-II)                  | 220/132        | UPPTCL    | 160 | AUG-17 |
| 183 | Malegaon S/S                          | 220/132        | MSETCL    | 200 | AUG-17 |
| 184 | Lodhi Road GIS (Addl.)                | 220/33         | DTL       | 100 | AUG-17 |
| 185 | Jammalamadugu (220kV ICT-I)           | 220/132        | APTRANSCO | 160 | AUG-17 |
| 186 | Talwandi Bhai (Addl)                  | 220/66         | PSTCL     | 160 | AUG-17 |
| 187 | Gurgaon Sector - 20 (Aug.)            | 220/66         | HVPNL     | 100 | SEP-17 |
| 188 | Narsapur (ICT-II) (160 MVA)           | 220/132        | TSTRANSCO | 160 | SEP-17 |
| 189 | Narsapur (ICT-I) (100 MVA)            | 220/132        | TSTRANSCO | 100 | SEP-17 |
| 190 | Yawatmal (Addl ICT)                   | 220/132        | MSETCL    | 100 | SEP-17 |
| 191 | Jahangirabad (Aug.) (150-100)         | 220/132        | UPPTCL    | 50  | OCT-17 |
| 192 | Mangliya S/s                          | 220/132        | MPPTCL    | 160 | OCT-17 |
| 193 | Miraj (Aug.) (200-100)                | 220/132        | MSETCL    | 100 | OCT-17 |
| 194 | Balasore (3rd Trf.)                   | 220/132        | OPTCL     | 160 | OCT-17 |
| 195 | Sarnath (Aug.)                        | 220/132        | UPPTCL    | 200 | OCT-17 |
| 196 | Beed (Aug.)                           | 220/33         | MSETCL    | 25  | OCT-17 |
| 197 | Waluj (Aug.) (100-50)                 | 220/33         | MSETCL    | 50  | OCT-17 |
| 198 | Bonai (2nd Trf.)                      | 220/33         | OPTCL     | 20  | OCT-17 |
| 199 | Panchgaon                             | 220/66         | HVPNL     | 160 | OCT-17 |
| 200 | Kanjli (2nd Addl. Trf.)               | 220/66         | PSTCL     | 100 | OCT-17 |
| 201 | Bassi (Said Pura)- ICT-III            | 220/66         | PSTCL     | 100 | NOV-17 |
| 202 | Isherwal (Aug)                        | 220/132        | HVPNL     | 100 | NOV-17 |
| 203 | Pilibhit ICT-I                        | 220/132        | UPPTCL    | 100 | NOV-17 |
| 204 | Pandhurna S/S                         | 220/132        | MPPTCL    | 160 | NOV-17 |
| 205 | Pinjore s/s                           | 220/66         | HVPNL     | 100 | NOV-17 |
| 206 | Hinjewadi Trf repl. (100-50)          | 220/22         | MSETCL    | 50  | DEC-17 |

|     |   |         |         |     |        |
|-----|---|---------|---------|-----|--------|
| 207 | Pilibhit (New) S/S (ICT-II)             | 220/132 | UPPTCL  | 100 | DEC-17 |
| 208 | Noida Sec.-62 S/S (Aug.) (160-100)      | 220/132 | UPPTCL  | 60  | DEC-17 |
| 209 | Nanauta (Aug.) S/S (200-160)            | 220/132 | UPPTCL  | 40  | DEC-17 |
| 210 | Anjangaon S/S                           | 220/33  | MSETCL  | 50  | DEC-17 |
| 211 | Sarna S/S (ICT-II)                      | 220/66  | PSTCL   | 100 | DEC-17 |
| 212 | Panchkula Sector- 32 S/S                | 220/66  | HVPNL   | 200 | DEC-17 |
| 213 | Shatabdinagar (Aug.) S/S (200-160)      | 220/132 | UPPTCL  | 40  | DEC-17 |
| 214 | Sitapur (Aug.) S/S (200-100)            | 220/132 | UPPTCL  | 100 | DEC-17 |
| 215 | Shahdol (Upgradation)                   | 220/132 | MPPTCL  | 160 | JAN-18 |
| 216 | Khurja (Aug.) (200-160)-ICT-I           | 220/132 | UPPTCL  | 40  | JAN-18 |
| 217 | Gr. Noida (Aug) (200-160)-ICT-II        | 220/132 | UPPTCL  | 40  | JAN-18 |
| 218 | Bhugaon (Addl.)                         | 220/132 | MSETCL  | 100 | JAN-18 |
| 219 | Pappankalan-III                         | 220/66  | DTL     | 320 | FEB-18 |
| 220 | Karian S/S                              | 220/33  | HPPTCL  | 63  | FEB-18 |
| 221 | Sadaipur s/s (ICT-II)                   | 220/132 | WBSETCL | 160 | FEB-18 |
| 222 | Satgachia Aug.                          | 220/132 | WBSETCL | 160 | FEB-18 |
| 223 | New Chanditala ICT-III                  | 220/132 | WBSETCL | 315 | FEB-18 |
| 224 | Krishna nagar (Aug.)                    | 220/132 | WBSETCL | 160 | FEB-18 |
| 225 | Arambag (Aug.)                          | 220/132 | WBSETCL | 160 | FEB-18 |
| 226 | Alipurduar S/S                          | 220/132 | WBSETCL | 320 | FEB-18 |
| 227 | 220kV S/S Shahjahanpur (Aug.) (200-100) | 220/132 | UPPTCL  | 100 | FEB-18 |
| 228 | 220 kV S/S Sahupuri (Aug.) II (200-160) | 220/132 | UPPTCL  | 40  | FEB-18 |
| 229 | 220kV S/S Nara Mzn (Aug.)I (200-160)    | 220/132 | UPPTCL  | 40  | FEB-18 |
| 230 | 220kV S/S Modipuram (Aug.)II(200-160)   | 220/132 | UPPTCL  | 40  | FEB-18 |
| 231 | 220kV S/S Gonda (Aug.) II (160-100)     | 220/132 | UPPTCL  | 60  | FEB-18 |
| 232 | 220 kV S/S Gajokhar (Aug.) I (160-100)  | 220/132 | UPPTCL  | 60  | FEB-18 |
| 233 | 220kV S/S Fatehpur (Aug)(200-160)       | 220/132 | UPPTCL  | 40  | FEB-18 |
| 234 | 220 kV S/S Azamgarh-II (New)            | 220/132 | UPPTCL  | 320 | FEB-18 |
| 235 | Bhadrak (ICT Repl.)                     | 220/132 | OPTCL   | 60  | FEB-18 |
| 236 | Jalna MIDC (Nagewadi)                   | 220/132 | MSETCL  | 150 | FEB-18 |
| 237 | Mansa (ICT Repl.)                       | 220/66  | PSTCL   | 60  | FEB-18 |
| 238 | KIADB Hardware Park Devanahalli S/S     | 220/66  | KPTCL   | 200 | FEB-18 |
| 239 | Gururam Sec.-56                         | 220/66  | HVPNL   | 160 | FEB-18 |
| 240 | Kartarpur (160-100)                     | 220/132 | PSTCL   | 60  | MAR-18 |
| 241 | Meerpur Kurali s/s (ICT-2)              | 220/66  | HVPNL   | 100 | MAR-18 |
| 242 | Zagadia                                 | 220/66  | GETCO   | 160 | MAR-18 |
| 243 | Ukai (Hydro)                            | 220/66  | GETCO   | 160 | MAR-18 |
| 244 | Sanand                                  | 220/66  | GETCO   | 160 | MAR-18 |
| 245 | Sachin (Talangpore)                     | 220/66  | GETCO   | 60  | MAR-18 |

|     |  |                |                             |              |        |
|-----|--|----------------|-----------------------------|--------------|--------|
| 246 | Botad s/s  | 220/66         | GETCO                       | 160          | MAR-18 |
| 247 | CG City (AIS) Lucknow (New)                        | 220/33         | UPPTCL                      | 180          | MAR-18 |
| 248 | Malkangiri (ICT-II)                                | 220/33         | OPTCL                       | 40           | MAR-18 |
| 249 | Mendhegiri (Wind)                                  | 220/33         | MSETCL                      | 50           | MAR-18 |
| 250 | Krishnoor S/S                                      | 220/33         | MSETCL                      | 25           | MAR-18 |
| 251 | Theur s/s (Addl.)                                  | 220/22         | MSETCL                      | 50           | MAR-18 |
| 252 | Bargarh New (ICT-I)                                | 220/132/3<br>3 | OPTCL                       | 100          | MAR-18 |
| 253 | R.C. Green Gr. Noida (Aug.)                        | 220/132        | UPPTCL                      | 160          | MAR-18 |
| 254 | Noida Sec-148 (New)                                | 220/132        | UPPTCL                      | 160          | MAR-18 |
| 255 | Neebkarori Farrukhabad (New)                       | 220/132        | UPPTCL                      | 100          | MAR-18 |
| 256 | Motiran Adda Gorakhpur (Aug.)<br>(ICT-III (Addl.)) | 220/132        | UPPTCL                      | 160          | MAR-18 |
| 257 | Mirzapur (Aug.) (160-100)                          | 220/132        | UPPTCL                      | 60           | MAR-18 |
| 258 | Bansi Siddharth Nagar (New)                        | 220/132        | UPPTCL                      | 100          | MAR-18 |
| 259 | Agra (Aug.) (160-100)                              | 220/132        | UPPTCL                      | 60           | MAR-18 |
| 260 | Rajla (160-100)                                    | 220/132        | PSTCL                       | 60           | MAR-18 |
| 261 | Palwal (Aug.)                                      | 220/66         | HVPNL                       | 160          | MAR-18 |
| 262 | Ahemednagar (Kedgaon) (Addl.)                      | 220/132        | MSETCL                      | 200          | MAR-18 |
| 263 | Dadhibana (Aug.)                                   | 220/132        | HVPNL                       | 100          | MAR-18 |
| 264 | Shapur s/s   | 220/132        | GETCO                       | 100          | MAR-18 |
| 265 | Gotri  | 220/132        | GETCO                       | 300          | MAR-18 |
|     |  |                | <b>TOTAL STATE SECTOR</b>   | <b>16318</b> |        |
|     | <b><u>PRIVATE SECTOR</u></b>                       |                |                             |              |        |
| 266 | Ataur (3x60 MVA)                                   | 220/33         | WUPPTCL                     | 180          | SEP-17 |
|     |  |                | <b>TOTAL PRIVATE SECTOR</b> | <b>180</b>   |        |
|     |  |                | <b>TOTAL 220 kV</b>         | <b>16983</b> |        |
|     |  |                | <b>GRAND TOTAL</b>          | <b>86193</b> |        |

## ANNEXURE- 4A

## Power Supply Position for 2017-18

| State /<br>System /<br>Region | Energy                    |                 |                     |            | Peak                      |               |                |            |
|-------------------------------|---------------------------|-----------------|---------------------|------------|---------------------------|---------------|----------------|------------|
|                               | April, 2017 - March, 2018 |                 |                     |            | April, 2017 - March, 2018 |               |                |            |
|                               | Energy Requirement        | Energy Supplied | Energy not Supplied |            | Peak Demand               | Peak Met      | Demand not Met |            |
|                               | (MU)                      | (MU)            | (MU)                | (%)        | (MW)                      | (MW)          | (MW)           | (%)        |
| Chandigarh                    | 1,610                     | 1,601           | 9                   | 1.0        | 363                       | 363           | 0              | 0.0        |
| Delhi                         | 31,826                    | 31,806          | 19                  | 0.1        | 6,553                     | 6,526         | 27             | 0.4        |
| Haryana                       | 50,775                    | 50,775          | 0                   | 0.0        | 9,671                     | 9,539         | 132            | 1.4        |
| Himachal Pradesh              | 9,399                     | 9,346           | 53                  | 0.6        | 1,594                     | 1,594         | 0              | 0.0        |
| Jammu & Kashmir               | 18,808                    | 15,050          | 3,759               | 20.0       | 2,899                     | 2,319         | 580            | 20.0       |
| Punjab                        | 54,812                    | 54,812          | 0                   | 0.0        | 11,705                    | 11,705        | 0              | 0.0        |
| Rajasthan                     | 71,194                    | 70,603          | 591                 | 0.8        | 11,722                    | 11,564        | 158            | 1.3        |
| Uttar Pradesh                 | 120,052                   | 118,303         | 1,749               | 1.5        | 20,274                    | 18,061        | 2,213          | 10.9       |
| Uttarakhand                   | 13,457                    | 13,426          | 31                  | 0.2        | 2,149                     | 2,149         | 0              | 0.0        |
| <b>Northern Region</b>        | <b>371,934</b>            | <b>365,723</b>  | <b>6,211</b>        | <b>1.7</b> | <b>60,749</b>             | <b>58,448</b> | <b>2,301</b>   | <b>3.8</b> |
| Chattisgarh                   | 25,916                    | 25,832          | 84                  | 0.3        | 4,169                     | 3,887         | 282            | 6.8        |
| Gujarat                       | 109,984                   | 109,973         | 12                  | 0.0        | 16,590                    | 16,590        | 0              | 0.0        |
| Madhya Pradesh                | 69,925                    | 69,925          | 0                   | 0.0        | 12,338                    | 12,301        | 37             | 0.3        |
| Maharashtra                   | 149,761                   | 149,531         | 230                 | 0.2        | 22,542                    | 22,494        | 48             | 0.2        |
| Daman & Diu                   | 2,534                     | 2,534           | 0                   | 0.0        | 362                       | 362           | 0              | 0.0        |
| Dadar Nagar Haveli            | 6,168                     | 6,168           | 0                   | 0.0        | 790                       | 790           | 0              | 0.0        |
| Goa                           | 4,117                     | 4,117           | 0                   | 0.0        | 559                       | 558           | 1              | 0.2        |
| <b>Western Region</b>         | <b>368,405</b>            | <b>368,080</b>  | <b>326</b>          | <b>0.1</b> | <b>50,477</b>             | <b>50,085</b> | <b>392</b>     | <b>0.8</b> |
| Andhra Pradesh                | 58,384                    | 58,288          | 96                  | 0.2        | 8,993                     | 8,983         | 10             | 0.1        |
| Telangana                     | 60,319                    | 60,235          | 83                  | 0.1        | 10,298                    | 10,284        | 14             | 0.1        |
| Karnataka                     | 67,869                    | 67,701          | 168                 | 0.2        | 10,857                    | 10,802        | 56             | 0.5        |
| Kerala                        | 25,002                    | 24,917          | 85                  | 0.3        | 3,892                     | 3,870         | 22             | 0.6        |
| Tamil Nadu                    | 106,006                   | 105,839         | 166                 | 0.2        | 15,001                    | 14,975        | 26             | 0.2        |
| Puducherry                    | 2,668                     | 2,661           | 7                   | 0.3        | 390                       | 387           | 3              | 0.7        |
| Lakshadweep#                  | 47                        | 47              | 0                   | 0.0        | 9                         | 9             | 0              | 0.0        |
| <b>Southern Region</b>        | <b>320,248</b>            | <b>319,642</b>  | <b>606</b>          | <b>0.2</b> | <b>47,385</b>             | <b>47,210</b> | <b>175</b>     | <b>0.4</b> |
| Bihar                         | 27,019                    | 26,603          | 417                 | 1.5        | 4,521                     | 4,515         | 6              | 0.1        |
| DVC                           | 21,549                    | 21,373          | 176                 | 0.8        | 2,896                     | 2,896         | 0              | 0.0        |
| Jharkhand                     | 7,907                     | 7,753           | 154                 | 1.9        | 1,332                     | 1,260         | 72             | 5.4        |
| Odisha                        | 28,802                    | 28,706          | 96                  | 0.3        | 4,652                     | 4,402         | 250            | 5.4        |
| West Bengal                   | 50,760                    | 50,569          | 191                 | 0.4        | 8,137                     | 8,114         | 23             | 0.3        |
| Sikkim                        | 485                       | 484             | 0                   | 0.1        | 96                        | 96            | 0              | 0.0        |

|                       |           |           |       |     |         |         |       |     |
|-----------------------|-----------|-----------|-------|-----|---------|---------|-------|-----|
| Andaman- Nicobar #    | 328       | 299       | 29    | 9.0 | 58      | 54      | 4     | 7.0 |
| <b>Eastern Region</b> | 136,522   | 135,489   | 1,034 | 0.8 | 20,794  | 20,485  | 309   | 1.5 |
| Arunachal Pradesh     | 799       | 788       | 10    | 1.3 | 145     | 145     | 0     | 0.3 |
| Assam                 | 9,094     | 8,779     | 315   | 3.5 | 1,822   | 1,745   | 77    | 4.2 |
| Manipur               | 874       | 827       | 46    | 5.3 | 202     | 195     | 7     | 3.2 |
| Meghalaya             | 1,557     | 1,553     | 3     | 0.2 | 369     | 368     | 1     | 0.2 |
| Mizoram               | 497       | 488       | 9     | 1.7 | 105     | 96      | 9     | 8.4 |
| Nagaland              | 794       | 774       | 20    | 2.5 | 155     | 146     | 9     | 5.9 |
| Tripura               | 2,602     | 2,553     | 49    | 1.9 | 342     | 342     | 0     | 0.0 |
| <b>NE Region</b>      | 16,216    | 15,763    | 453   | 2.8 | 2,629   | 2,520   | 109   | 4.1 |
| <b>All India</b>      | 1,213,326 | 1,204,697 | 8,629 | 0.7 | 164,066 | 160,752 | 3,314 | 2.0 |

# Lakshadweep and Andaman & Nicobar Islands are stand- alone systems, power supply position of these doesn't form part of regional requirement and availability.

## ANNEXURE-4-B

### Details of Total Share of the States From Central Generating Stations

(As on 31-03-2018)

| S.No. | Region / State         | Firm power               | Unallocated Power                         |   |   |  |  | Total MW share from CGS | Total MW share from CGS as % of CGS in the country |
|-------|------------------------|--------------------------|---|---|---|--|--|-------------------------|--|
|       |                        | Firm Share from CGS (MW) | Unallocated power from regional pool (MW) | % of the regional pool of unallocated power | % of the national pool of unallocated power | Allocation from other Region / Bhutan (MW) | Total allocation of unallocated power (MW) |                         |  |
| 1     | Chandigarh             | 160                      | 106                                       | 4.7   | 1.4   | 14   | 120  | 280                     | 0.35   |
| 2     | Delhi                  | 4814                     | 0   | 0.0   | 0.0   | 30   | 30   | 4844                    | 6.04   |
| 3     | Haryana                | 2576                     | 0   | 0.0   | 0.0   | 15   | 15   | 2591                    | 3.23   |
| 4     | Himachal Pradesh       | 1489                     | 15  | 0.7   | 0.2   | 0  | 15   | 1504                    | 1.87   |
| 5     | Jammu & Kashmir        | 1688                     | 863                                       | 38.1  | 11.0  | 118  | 981  | 2669                    | 3.33   |
| 6     | Punjab                 | 2214                     | 37  | 1.6   | 0.5   | 30   | 67   | 2281                    | 2.84   |
| 7     | Rajasthan              | 2693                     | 635                                       | 28.0  | 8.1   | 52   | 687  | 3380                    | 4.21   |
| 8     | Uttar Pradesh          | 5845                     | 435                                       | 19.2  | 5.5   | 60   | 495  | 6340                    | 7.90   |
| 9     | Uttarakhand            | 907                      | 170                                       | 7.5   | 2.2   | 0  | 170  | 1077                    | 1.34   |
| 10    | Railways               | 0                        | 0   | 0.0   | 0.0   | 0  | 0  | 0                       | 0.00   |
| 11    | PowerGrid              | 5                        | 4   | 0.2   | 0.1   | 0  | 4  | 9                       | 0.01   |
|       | <b>Northern Region</b> | <b>22390</b>             | <b>2265</b>                               | <b>100.0</b>                                | <b>28.9</b>                                 | <b>319</b>                                 | <b>2584</b>                                | <b>24974</b>            | <b>31.12</b>                                       |
| 12    | Chhattisgarh           | 1322                     | 25  | 1.4   | 0.3   | 0  | 25   | 1347                    | 1.68   |
| 13    | Gujarat                | 3995                     | 0   | 0.0   | 0.0   | 0  | 0  | 3995                    | 4.98   |
| 14    | Madhya Pradesh         | 4768                     | 413                                       | 23.4  | 5.3   | 0  | 413  | 5181                    | 6.46   |
| 15    | Maharashtra            | 6641                     | 382                                       | 21.6  | 4.9   | 0  | 382  | 7023                    | 8.75   |
| 16    | Daman & Diu            | 174                      | 144                                       | 8.1   | 1.8   | 0  | 144  | 318                     | 0.40   |
| 17    | Dadar Nagar Haveli     | 244                      | 707                                       | 40.1  | 9.0   | 0  | 707  | 951                     | 1.18   |
| 18    | Goa                    | 497                      | 81  | 4.6   | 1.0   | 0  | 81   | 578                     | 0.72   |
| 19    | PowerGrid              | 2.72                     | 3   | 0.2   | 0.0   | 0  | 3  | 6.00                    | 0.01   |
| 20    | Railways WR            | 540                      | 0   | 0.0   | 0.0   | 0  | 0  | 540                     | 0.67   |
| 21    | HWP of DAE             | 0                        | 0   | 0.0   | 0.0   | 0  | 0  | 0                       | 0.00   |
| 22    | BARC Facilities        | 0                        | 10  | 0.6   | 0.1   | 0  | 10   | 10                      | 0.01   |
|       | <b>Western Region</b>  | <b>18184</b>             | <b>1765</b>                               | <b>100</b>                                  | <b>22.5</b>                                 | <b>0</b>                                   | <b>1765</b>                                | <b>19948</b>            | <b>24.86</b>                                       |
| 23    | Andhra Pradesh         | 1935                     | 586                                       | 22.4  | 7.5   | 0  | 586  | 2521                    | 3.14   |



|    |                             |              |             |       |        |     |      |       |        |
|----|-----------------------------|--------------|-------------|-------|--------|-----|------|-------|--------|
| 24 | Karnataka                   | 3127         | 801         | 30.6  | 10.2   | 0   | 801  | 3929  | 4.90   |
| 25 | Kerala                      | 1830         | 214         | 8.2   | 2.7    | 0   | 214  | 2045  | 2.55   |
| 26 | Tamil Nadu                  | 5838         | 481         | 18.4  | 6.1    | 0   | 481  | 6319  | 7.87   |
| 27 | Telangana                   | 2027         | 381         | 14.5  | 4.9    | 0   | 381  | 2408  | 3.00   |
| 28 | Pondicherry                 | 334          | 149         | 5.7   | 1.9    | 0   | 149  | 483   | 0.60   |
| 29 | NLC                         | 100          | 0           | 0.0   | 0.0    | 0   | 0    | 100   | 0.12   |
| 30 | PowerGrid                   | 0            | 6           | 0.2   | 0.1    | 0   | 6    | 6     | 0.01   |
|    | <b>Southern Region</b>      | <b>15191</b> | <b>2619</b> | 100.0 | 33.4   | 0   | 2619 | 17810 | 22.19  |
| 31 | Bihar                       | 2902         | 604         | 65.1  | 7.7    | 12  | 616  | 3518  | 4.38   |
| 32 | DVC                         | 6478         | 8           | 0.9   | 0.1    | 8   | 16   | 6494  | 8.09   |
| 33 | Jharkhand                   | 596          | 138         | 14.9  | 1.8    | 5   | 143  | 739   | 0.92   |
| 34 | Orissa                      | 1801         | 77          | 8.3   | 1.0    | 6   | 83   | 1884  | 2.35   |
| 35 | West Bengal                 | 1499         | 86          | 9.3   | 1.1    | 18  | 104  | 1603  | 2.00   |
| 36 | Sikkim                      | 156          | 12          | 1.2   | 0.1    | 1   | 13   | 169   | 0.21   |
| 37 | Railway                     | 450          | 0           | 0.0   | 0.0    | 0   | 0    | 450   | 0.56   |
| 37 | PowerGrid                   | 0            | 1           | 0.1   | 0.0    | 0   | 1    | 1     | 0.00   |
|    | <b>Eastern Region</b>       | <b>13882</b> | <b>927</b>  | 100.0 | 11.8   | 50  | 977  | 14859 | 18.52  |
| 38 | Arunachal Pradesh           | 169          | 3           | 1.3   | 0.0    | 9   | 12   | 181   | 0.23   |
| 39 | Assam                       | 1039         | 117         | 44.2  | 1.5    | 148 | 265  | 1304  | 1.62   |
| 40 | Manipur                     | 191          | 27          | 10.0  | 0.3    | 0   | 27   | 218   | 0.27   |
| 41 | Meghalaya                   | 207          | 82          | 30.9  | 1.0    | 0   | 82   | 289   | 0.36   |
| 42 | Mizoram                     | 95           | 23          | 8.5   | 0.3    | 8   | 31   | 126   | 0.16   |
| 43 | Nagaland                    | 123          | 11          | 4.3   | 0.1    | 1   | 12   | 136   | 0.17   |
| 44 | Tripura                     | 402          | 2           | 0.7   | 0.0    | 0   | 2    | 404   | 0.50   |
| 44 | PowerGrid                   | 2.5          | 0.0         | 0.0   | 0.0    | 0   | 0.0  | 2.5   | 0.00   |
|    | <b>North-Eastern Region</b> | <b>2229</b>  | <b>265</b>  | 100.0 | 3.4    | 166 | 431  | 2659  | 3.31   |
|    | <b>Grand Total</b>          | <b>71876</b> | <b>7840</b> |       | 100.00 | 535 | 8375 | 80251 | 100.00 |

**Note:-**

- 1 Firm share includes capacity of dedicated Central Sector stations, merchant power (75 MW each in ER and WR) and capacity allocated / diverted from other stations located within / outside the region.
- 2 Above allocation is for evening peak hours only. Allocation during off-peak hours may vary.
- 3 Grand Total power does not include power allocated to Bangladesh. Total Power allocated to Bangladesh = 250 MW (100 MW each from NR and WR unallocated power and 50 MW from ER NTPC stations' unallocated power.
- 4 Excludes capacity of central sector units which have been commissioned but yet to be declared under commercial operation.

## ANNEXURE - 5A

**PFRS under 50 000 MW Hydroelectric Initiative**  
**Statewise List of Schemes**

|  | Scheme       | Consultant | Installed Capacity |          |              | Head (m) | Annual Energy (GWh) | Tariff (Rs/kWh) |
|--|--------------|------------|--------------------|----------|--------------|----------|---------------------|-----------------|
|  |              |            | Nos of Units       | Size(MW) | Total (MW)   |          |                     |                 |
| <b>Andhra Pradesh</b>                    |              |            |                    |          |              |          |                     |                 |
| 1  | Pondugala    | WAPCOS     | 3                  | 27       | 81           | 18.67    | 399.36              | 3.48            |
| <b>Total (Andhra Pradesh ) 1 schemes</b> |              |            | <b>3</b>           |          | <b>81</b>    |          |                     |                 |
| <b>Arunachal Pradesh</b>                 |              |            |                    |          |              |          |                     |                 |
| 2  | Agoline      | NHPC       | 3                  | 125      | 375          | 163.00   | 1267.38             | 3.51            |
| 3  | Amulin       | NHPC       | 3                  | 140      | 420          | 132.00   | 1716.40             | 3.37            |
| 4  | Ashupani     | NHPC       | 2                  | 15       | 30           | 395.00   | 126.45              | 8.75            |
| 5  | Attunli      | NHPC       | 4                  | 125      | 500          | 264.00   | 2247.32             | 2.35            |
| 6  | Badao        | NEEPCO     | 4                  | 30       | 120          | 154.50   | 441.00              | 2.32            |
| 7  | Bhareli-I    | NEEPCO     | 8                  | 140      | 1120         | 97.00    | 4112.40             | 1.85            |
| 8  | Bhareli-II   | NEEPCO     | 5                  | 120      | 600          | 51.00    | 2345.00             | 1.67            |
| 9  | Chanda       | NEEPCO     | 4                  | 27.5     | 110          | 175.67   | 401.91              | 2.67            |
| 10                                       | Demwe        | NHPC       | 12                 | 250      | 3000         | 138.00   | 10823.82            | 1.97            |
| 11                                       | Dengser      | NHPC       | 4                  | 138      | 552          | 120.00   | 2666.71             | 3.26            |
| 12                                       | Dibbin       | NEEPCO     | 2                  | 50       | 100          | 151.24   | 335.72              | 2.23            |
| 13                                       | Duimukh      | NHPC       | 3                  | 50       | 150          | 65.00    | 551.48              | 8.50            |
| 14                                       | Elango       | NHPC       | 3                  | 50       | 150          | 363.00   | 583.14              | 5.00            |
| 15                                       | Emini        | NHPC       | 4                  | 125      | 500          | 125.00   | 1695.45             | 3.51            |
| 16                                       | Emra-II      | NHPC       | 3                  | 130      | 390          | 278.00   | 1648.09             | 3.02            |
| 17                                       | Etabue       | NHPC       | 3                  | 55       | 165          | 378.00   | 683.66              | 3.43            |
| 18                                       | Etalin       | NHPC       | 16                 | 250      | 4000         | 385.00   | 16071.60            | 1.70            |
| 19                                       | Hirong       | NHPC       | 4                  | 125      | 500          | 285.00   | 2535.80             | 1.62            |
| 20                                       | Hutong       | WAPCOS     | 12                 | 250      | 3000         | 166.77   | 9901.00             | 1.28            |
| 21                                       | Kalai        | WAPCOS     | 10                 | 260      | 2600         | 193.21   | 10608.64            | 1.01            |
| 22                                       | Kameng Dam   | NEEPCO     | 5                  | 120      | 600          | 65.00    | 2345.55             | 2.29            |
| 23                                       | Kapakleyak   | NEEPCO     | 4                  | 40       | 160          | 245.00   | 627.95              | 1.74            |
| 24                                       | Kurungl&II   | NHPC       | 3                  | 110      | 330          | 151.00   | 1435.40             | 4.04            |
| 25                                       | Mihumdon     | NHPC       | 4                  | 100      | 400          | 286.00   | 1451.75             | 3.60            |
| 26                                       | Mirak        | NHPC       | 3                  | 47       | 141          | 136.40   | 748.44              | 3.42            |
| 27                                       | Naba         | NHPC       | 4                  | 250      | 1000         | 221.00   | 3995.25             | 2.14            |
| 28                                       | Nalo         | NHPC       | 4                  | 90       | 360          | 221.00   | 1733.00             | 3.27            |
| 29                                       | Naying       | NHPC       | 4                  | 250      | 1000         | 245.00   | 5077.15             | 1.18            |
| 30                                       | Niare        | NHPC       | 4                  | 200      | 800          | 205.00   | 3356.62             | 2.02            |
| 31                                       | Oju-I        | NHPC       | 4                  | 175      | 700          | 257.00   | 3291.58             | 2.08            |
| 32                                       | Oju-II       | NHPC       | 4                  | 250      | 1000         | 322.00   | 4629.93             | 1.46            |
| 33                                       | Pakke        | NEEPCO     | 2                  | 55       | 110          | 452.50   | 335.26              | 3.33            |
| 34                                       | Papu         | NEEPCO     | 2                  | 100      | 200          | 238.00   | 505.00              | 2.94            |
| 35                                       | Phanchung    | NEEPCO     | 2                  | 30       | 60           | 157.13   | 174.83              | 3.24            |
| 36                                       | Ringong      | NHPC       | 3                  | 50       | 150          | 166.50   | 659.07              | 3.61            |
| 37                                       | Sebu         | NEEPCO     | 2                  | 40       | 80           | 123.00   | 227.53              | 3.71            |
| 38                                       | Simang       | NHPC       | 3                  | 30       | 90           | 125.00   | 417.82              | 5.43            |
| 39                                       | Talong       | NEEPCO     | 3                  | 100      | 300          | 171.67   | 915.50              | 2.24            |
| 40                                       | Tarangwarang | NEEPCO     | 2                  | 15       | 30           | 185.55   | 93.81               | 2.88            |
| 41                                       | Tato-II      | NHPC       | 4                  | 175      | 700          | 168.00   | 3465.90             | 1.48            |
| 42                                       | Tenga        | NEEPCO     | 4                  | 150      | 600          | 875.00   | 1046.50             | 3.52            |
| 43                                       | Utung        | NEEPCO     | 3                  | 33.3     | 100          | 291.00   | 359.13              | 3.10            |
| <b>Total (Arunachal Pr. ) 42 schemes</b> |              |            | <b>182</b>         |          | <b>27293</b> |          |                     |                 |

|  | Scheme                | Consultant | Installed Capacity |          |             | Head (m) | Annual Energy (GWh) | Tariff (Rs/kWh) |
|--|-----------------------|------------|--------------------|----------|-------------|----------|---------------------|-----------------|
|  |                       |            | Nos of Units       | Size(MW) | Total (MW)  |          |                     |                 |
| <b>Chhattisgarh</b>                        |                       |            |                    |          |             |          |                     |                 |
| 44   | Kotri                 | WAPCOS     | 3                  | 50       | 150         | 36.99    | 330.95              | 5.48            |
| 45   | Nugur-I               | WAPCOS     | 5                  | 34       | 170         | 24.54    | 316.13              | 4.89            |
| 46   | Nugur-II              | WAPCOS     | 5                  | 42       | 210         | 16.66    | 787.78              | 4.16            |
| 47   | Rehar-I               | WAPCOS     | 3                  | 57       | 171         | 46.84    | 264.38              | 8.70            |
| 48   | Rehar-II              | WAPCOS     | 3                  | 49       | 147         | 38.17    | 290.32              | 5.16            |
| <b>Total (Chhattisgarh ) - 5 schemes</b>   |                       |            | <b>19</b>          |          | <b>848</b>  |          |                     |                 |
| <b>Himachal Pradesh</b>                    |                       |            |                    |          |             |          |                     |                 |
| 49   | Bajoli Holi           | HPSEB      | 3                  | 60       | 180         | 278.00   | 762.98              | 2.03            |
| 50   | Bardang               | HPSEB      | 3                  | 38       | 114         | 55.00    | 438.41              | 2.91            |
| 51   | Chamba                | HPSEB      | 3                  | 42       | 126         | 110.00   | 646.82              | 1.48            |
| 52   | Chhatru               | HPSEB      | 3                  | 36       | 108         | 160.00   | 455.72              | 2.89            |
| 53   | Gharopa               | HPSEB      | 3                  | 38       | 114         | 169.00   | 534.25              | 2.09            |
| 54   | Gondhala              | HPSEB      | 3                  | 48       | 144         | 134.00   | 586.08              | 1.92            |
| 55   | Jangi Thopan          | HPSEB      | 3                  | 160      | 480         | 174.14   | 1779.45             | 2.00            |
| 56   | Khab-I                | SJVNL      | 3                  | 150      | 450         | 170.00   | 1551.00             | 2.24            |
| 57   | Khab-II               | SJVNL      | 3                  | 62       | 186         | 70.00    | 640.00              | 3.04            |
| 58   | Khoksar               | HPSEB      | 3                  | 30       | 90          | 99.00    | 351.91              | 2.46            |
| 59   | Luhri                 | HPSEB      | 3                  | 155      | 465         | 88.00    | 1825.13             | 2.41            |
| 60   | Thopan Powari         | HPSEB      | 3                  | 160      | 480         | 161.14   | 1786.26             | 1.81            |
| 61   | Tidong-I              | HPSEB      | 2                  | 30       | 60          | 511.50   | 211.65              | 2.71            |
| 62   | Tidong-II             | HPSEB      | 2                  | 35       | 70          | 575.00   | 256.18              | 2.02            |
| 63   | Yangthang             | HPSEB      | 3                  | 87       | 261         | 186.45   | 938.02              | 2.08            |
| <b>Total (Himachal Pr. ) 15 schemes</b>    |                       |            | <b>43</b>          |          | <b>3328</b> |          |                     |                 |
| <b>Jammu &amp; Kashmir</b>                 |                       |            |                    |          |             |          |                     |                 |
| 64   | Barinium              | WAPCOS     | 2                  | 120      | 240         | 117.77   | 1170.34             | 2.54            |
| 65   | Bichlari              | WAPCOS     | 2                  | 17.5     | 35          | 462.60   | 148.29              | 1.11            |
| 66   | Dumkhar               | NHPC       | 3                  | 15       | 45          | 27.80    | 219.18              | 4.66            |
| 67   | Kanyunche             | NHPC       | 3                  | 15       | 45          | 28.76    | 223.02              | 4.71            |
| 68   | Karkit                | NHPC       | 3                  | 10       | 30          | 26.90    | 153.11              | 5.40            |
| 69   | Kawar                 | WAPCOS     | 4                  | 80       | 320         | 74.00    | 1426.56             | 1.09            |
| 70   | Khalsi                | NHPC       | 3                  | 20       | 60          | 33.00    | 272.60              | 4.10            |
| 71   | Kiru                  | WAPCOS     | 4                  | 107.5    | 430         | 105.33   | 1935.77             | 0.77            |
| 72   | Ratle                 | WAPCOS     | 4                  | 140      | 560         | 92.33    | 2483.37             | 1.40            |
| 73   | Shamnot               | WAPCOS     | 4                  | 92.5     | 370         | 56.33    | 1650.19             | 1.69            |
| 74   | Shuas                 | WAPCOS     | 2                  | 115      | 230         | 115.70   | 1117.87             | 2.94            |
| 75   | Takmaching            | NHPC       | 3                  | 10       | 30          | 18.53    | 145.52              | 5.54            |
| 76   | Ujh                   | WAPCOS     | 4                  | 70       | 280         | 143.33   | 465.06              | 5.06            |
| <b>Total (J &amp; K ) - 13 schemes</b>     |                       |            | <b>41</b>          |          | <b>2675</b> |          |                     |                 |
| <b>Karnataka</b>                           |                       |            |                    |          |             |          |                     |                 |
| 77   | Agnashini             | KPCL       | 4                  | 150      | 600         | 427.00   | 1431.00             | 1.07            |
| 78   | Gangavali             | KPCL       | 2                  | 200      | 400         | 378.30   | 759.00              | 1.46            |
| 79   | Gundia                | KPCL       | 2                  | 150      | 300         | 600.00   | 616.00              | 1.41            |
| 80   | Kalinadi Stage-III    | KPCL       | 2                  | 150      | 300         | 407.67   | 610.00              | 1.67            |
| 81   | Tamankal              | KPCL       | 2                  | 150      | 300         | 87.29    | 401.00              | 3.32            |
| <b>Total (Karnataka ) - 5 schemes</b>      |                       |            | <b>12</b>          |          | <b>1900</b> |          |                     |                 |
| <b>Kerala</b>                              |                       |            |                    |          |             |          |                     |                 |
| 82   | Karappara Kuriarkutty | WAPCOS     | 2                  | 18       | 66          | 390.00   | 126.10              | 7.88            |
|  |                       |            | 2                  | 15       |             | 307.00   |                     |                 |
| 83   | Perianjakully         | WAPCOS     | 2                  | 30       | 60          | 282.90   | 86.30               | 6.25            |
| <b>Total (Kerala ) - 2 schemes</b>         |                       |            | <b>6</b>           |          | <b>126</b>  |          |                     |                 |
| <b>Madhya Pradesh</b>                      |                       |            |                    |          |             |          |                     |                 |
| 84   | Basania               | NHPC       | 3                  | 30       | 90          | 38.00    | 240.00              | 17.23           |
| 85   | Bauras                | NHPC       | 3                  | 18.33    | 55          | 17.50    | 248.43              | 3.96            |
| 86   | Hoshangabad           | NHPC       | 3                  | 20       | 60          | 16.50    | 288.21              | 4.10            |
| <b>Total (Madhya Pradesh ) - 3 schemes</b> |                       |            | <b>9</b>           |          | <b>205</b>  |          |                     |                 |

|  | Scheme                 | Consultant | Installed Capacity |          |             | Head (m) | Annual Energy (GWh) | Tariff (Rs/kWh) |
|--|------------------------|------------|--------------------|----------|-------------|----------|---------------------|-----------------|
|  |                        |            | Nos of Units       | Size(MW) | Total (MW)  |          |                     |                 |
| <b><u>Maharashtra</u></b>                  |                        |            |                    |          |             |          |                     |                 |
| 87   | Ghargaon               | WAPCOS     | 4                  | 13       | 52          | 9.84     | 74.47               | 15.50           |
| 88   | Hiranyakeshi           | WAPCOS     | 2                  | 9        | 18          | 36.10    | 23.76               | 20.26           |
| 89   | Kadvi                  | WAPCOS     | 2                  | 11       | 22          | 36.30    | 29.59               | 34.03           |
| 90   | Kasari                 | WAPCOS     | 2                  | 12.5     | 25          | 40.67    | 33.32               | 18.16           |
| 91   | Kumbhi                 | WAPCOS     | 2                  | 8.5      | 17          | 37.48    | 22.93               | 35.19           |
| 92   | Kunghara               | WAPCOS     | 4                  | 18       | 72          | 12.77    | 133.40              | 11.34           |
| 93   | Pranhita               | WAPCOS     | 2                  | 24       | 48          | 25.30    | 135.96              | 10.32           |
| 94   | Samda                  | WAPCOS     | 4                  | 13       | 52          | 10.64    | 83.40               | 14.11           |
| 95   | Wainganga              | WAPCOS     | 5                  | 21       | 105         | 19.74    | 246.15              | 3.86            |
| <b>Total (Maharashtra) - 9 schemes</b>     |                        |            | <b>27</b>          |          | <b>411</b>  |          |                     |                 |
| <b><u>Manipur</u></b>                      |                        |            |                    |          |             |          |                     |                 |
| 96   | Khongnum Chakka st.-II | WAPCOS     | 2                  | 33.5     | 67          | 281.25   | 192.84              | 4.59            |
| 97   | Nunglieban             | WAPCOS     | 2                  | 52.5     | 105         | 82.42    | 268.93              | 5.16            |
| 98   | Pabaram                | WAPCOS     | 2                  | 95       | 190         | 116.67   | 474.77              | 4.33            |
| <b>Total (Manipur) - 3 Nos. schemes</b>    |                        |            | <b>6</b>           |          | <b>362</b>  |          |                     |                 |
| <b><u>Meghalaya</u></b>                    |                        |            |                    |          |             |          |                     |                 |
| 99   | Mawblei                | WAPCOS     | 2                  | 70       | 140         | 400.33   | 303.66              | 4.44            |
| ####                                       | Mawhu                  | WAPCOS     | 3                  | 40       | 120         | 438.15   | 482.96              | 1.40            |
| ####                                       | Mawput                 | WAPCOS     | 3                  | 7        | 21          | 93.42    | 83.95               | 4.07            |
| ####                                       | Nongkolait             | WAPCOS     | 2                  | 60       | 120         | 463      | 332.87              | 1.97            |
| ####                                       | Nongnam                | WAPCOS     | 2                  | 25       | 50          | 215.17   | 212.59              | 2.44            |
| ####                                       | Rangmaw                | WAPCOS     | 2                  | 32.5     | 65          | 321.00   | 229.60              | 2.32            |
| ####                                       | Selim                  | WAPCOS     | 2                  | 85       | 170         | 433.67   | 534.68              | 2.02            |
| ####                                       | Sushen                 | WAPCOS     | 2                  | 32.5     | 65          | 114.58   | 220.6               | 3.85            |
| ####                                       | Umduna                 | WAPCOS     | 3                  | 19       | 57          | 253.17   | 231.24              | 1.68            |
| ####                                       | Umjaut                 | WAPCOS     | 3                  | 23       | 69          | 375.20   | 276.70              | 1.51            |
| ####                                       | Umngi                  | WAPCOS     | 2                  | 27       | 54          | 304.75   | 89.65               | 2.86            |
| <b>Total (Meghalaya) - 11 Nos. schemes</b> |                        |            | <b>26</b>          |          | <b>931</b>  |          |                     |                 |
| <b><u>Mizoram</u></b>                      |                        |            |                    |          |             |          |                     |                 |
| ####                                       | Boinu                  | WAPCOS     | 4                  | 160      | 640         | 158.67   | 1118.93             | 4.83            |
| ####                                       | Lungleng               | WAPCOS     | 5                  | 163      | 815         | 219.67   | 1169.06             | 4.17            |
| ####                                       | Tlawng                 | WAPCOS     | 2                  | 22.5     | 45          | 123.67   | 151.67              | 5.84            |
| <b>Total (Mizoram) - 3 Nos. schemes</b>    |                        |            | <b>11</b>          |          | <b>1500</b> |          |                     |                 |
| <b><u>Nagaland</u></b>                     |                        |            |                    |          |             |          |                     |                 |
| ####                                       | Dikhu                  | NEEPCO     | 4                  | 35       | 140         | 79.44    | 513.41              | 2.8             |
| ####                                       | Tizu                   | NEEPCO     | 3                  | 50       | 150         | 64.19    | 568.41              | 2.56            |
| ####                                       | Yangnyu                | NEEPCO     | 2                  | 20       | 40          | 115      | 176.45              | 4.48            |
| <b>Total (Nagaland) - 3 Nos. schemes</b>   |                        |            | <b>9</b>           |          | <b>330</b>  |          |                     |                 |
| <b><u>Orissa</u></b>                       |                        |            |                    |          |             |          |                     |                 |
| ####                                       | Baljori                | WAPCOS     | 2                  | 89       | 178         | 165.75   | 479.8               | 5.9             |
| ####                                       | Lower Kolab            | WAPCOS     | 3                  | 155      | 465         | 196.9    | 845.86              | 7.1             |
| ####                                       | Naraj                  | WAPCOS     | 7                  | 41       | 287         | 16.14    | 759.31              | 4.92            |
| ####                                       | Tikarpara              | WAPCOS     | 7                  | 37       | 259         | 16.97    | 828.37              | 3.69            |
| <b>Total (Orissa) - 4 Nos. schemes</b>     |                        |            | <b>19</b>          |          | <b>1189</b> |          |                     |                 |
| <b><u>Sikkim</u></b>                       |                        |            |                    |          |             |          |                     |                 |
| ####                                       | Dikchu                 | NHPC       | 3                  | 35       | 105         | 352      | 469                 | 2.15            |
| ####                                       | Lachen                 | NHPC       | 3                  | 70       | 210         | 350      | 865.94              | 2.35            |
| ####                                       | Lingza                 | NHPC       | 3                  | 40       | 120         | 736      | 477.51              | 2.85            |
| ####                                       | Panan                  | NHPC       | 4                  | 50       | 200         | 312      | 762                 | 2.15            |
| ####                                       | Rangyong               | NHPC       | 3                  | 47       | 141         | 723.18   | 639.52              | 2.7             |
| ####                                       | Ringpi                 | NHPC       | 2                  | 35       | 70          | 1106.4   | 317.41              | 3.17            |
| ####                                       | Rongni Storage         | NHPC       | 3                  | 65       | 195         | 442      | <b>510.35</b>       | 8.6             |
| ####                                       | Rukel                  | NHPC       | 3                  | 11       | 33          | 537.1    | 149.41              | 5.48            |
| ####                                       | Talem                  | NHPC       | 3                  | 25       | 75          | 393.19   | 305.48              | 4.34            |
| ####                                       | Teesta-I               | NHPC       | 4                  | 80       | 320         | 576.85   | 1298.12             | 1.8             |
| <b>Total (Sikkim) - 10 Nos. schemes</b>    |                        |            | <b>31</b>          |          | <b>1469</b> |          |                     |                 |

|                    | Scheme                                       | Consultant | Installed Capacity |          |              | Head (m)     | Annual Energy (GWh) | Tariff (Rs/kWh) |
|--------------------|--|------------|--------------------|----------|--------------|--------------|---------------------|-----------------|
|                    |  |            | Nos of Units       | Size(MW) | Total (MW)   |              |                     |                 |
| <b>Uttaranchal</b> |  |            |                    |          |              |              |                     |                 |
| ####               | Arakot Tiuni                                 | UJVNL      | 3                  | 24       | 72           | 250.2        | 382.9               | 1               |
| ####               | Badrinath                                    | WAPCOS     | 2                  | 70       | 140          | 459.67       | 702.7               | 0.81            |
| ####               | Bagoli Dam                                   | UJVNL      | 3                  | 24       | 72           | 139.5        | 340.7               | 4.1             |
| ####               | Bhaironghati                                 | WAPCOS     | 2                  | 32.5     | 65           | 108.9        | 293.18              | 1.8             |
| ####               | Bogudiyar - Sirkari Bhyal                    | WAPCOS     | 2                  | 85       | 170          | 344.47       | 744                 | 1.99            |
| ####               | Bokang Baling                                | WAPCOS     | 3                  | 110      | 330          | 455.2        | 1124.62             | 1.68            |
| ####               | Chhunger - Chal                              | WAPCOS     | 2                  | 120      | 240          | 292.83       | 853.28              | 1.13            |
| ####               | Deodi  | WAPCOS     | 2                  | 30       | 60           | 560.3        | 296.76              | 1.37            |
| ####               | Devsari                                      | WAPCOS     | 3                  | 100      | 300          | 227.5        | 878.5               | 2.77            |
| ####               | Gangotri                                     | WAPCOS     | 1                  | 55       | 55           | 336.33       | 264.76              | 1.62            |
| ####               | Garba Tawaghat                               | WAPCOS     | 3                  | 210      | 630          | 470.97       | 2483.11             | 0.9             |
| ####               | Gohana Tal                                   | WAPCOS     | 2                  | 30       | 60           | 584.52       | 269.35              | 1.64            |
| ####               | Harsil                                       | WAPCOS     | 3                  | 70       | 210          | 281.33       | 920.57              | 1.1             |
| ####               | Jadh Ganga                                   | WAPCOS     | 2                  | 25       | 50           | 142.6        | 220.88              | 2.19            |
| ####               | Jakhol Sankri                                | UJVNL      | 3                  | 11       | 33           | 364          | <b>144.24</b>       | 1.71            |
| ####               | Jelam Tamak                                  | WAPCOS     | 2                  | 30       | 60           | 195.58       | 268.12              | 1.71            |
| ####               | Kalika Dantu                                 | WAPCOS     | 2                  | 115      | 230          | <b>99.75</b> | 1067.3              | 2.95            |
| ####               | Karmoli                                      | WAPCOS     | 2                  | 70       | 140          | <b>419.7</b> | <b>621.31</b>       | 1.3             |
| ####               | Khartoi Lumti Talli                          | WAPCOS     | 2                  | 27.5     | 55           | 56.6         | 241.51              | 3               |
| ####               | Lata Tapovan                                 | UJVNL      | 4                  | 77.5     | 310          | 265          | 1123                | 2.21            |
| ####               | Maleri Jelam                                 | WAPCOS     | 2                  | 27.5     | 55           | 200.33       | 243.07              | 1.8             |
| ####               | Mapang - Bogudiyar                           | WAPCOS     | 2                  | 100      | 200          | 465.07       | 882.04              | 1.3             |
| ####               | Naitwar-Mori                                 | UJVNL      | 3                  | 11       | 33           | 76           | 151                 | 1.85            |
| ####               | Nand Prayag                                  | UJVNL      | 3                  | 47       | 141          | 72           | 794                 | 2.05            |
| ####               | Ramganga                                     | UJVNL      | 3                  | 22       | 66           | 100.1        | 327                 | 3.25            |
| ####               | Rishi Ganga - 1                              | WAPCOS     | 2                  | 35       | 70           | 536.17       | 327.3               | 1.18            |
| ####               | Rishi Ganga - II                             | WAPCOS     | 1                  | 35       | 35           | 236.96       | 164.64              | 2.22            |
| ####               | Rupsiabagar Khasiyabara                      | WAPCOS     | 2                  | 130      | 260          | 449.47       | 1195.63             | 1.59            |
| ####               | Sela Urthing                                 | WAPCOS     | 2                  | 115      | 230          | 255.5        | 816.73              | 1.4             |
| ####               | Sirkari Bhyol Rupsiabagar                    | WAPCOS     | 3                  | 70       | 210          | 388.97       | 967.97              | 1.55            |
| ####               | Taluka Sankri                                | UJVNL      | 2                  | 70       | 140          | 564.9        | 559.47              | 1.33            |
| ####               | Tamak Lata                                   | UJVNL      | 4                  | 70       | 280          | 291.4        | 1040.7              | 2.3             |
| ####               | Urthing Sobla                                | UJVNL      | 4                  | 70       | 280          | 414.96       | <b>1360.2</b>       | 1.49            |
|                    | <b>Total (Uttaranchal) - 33 Nos. schemes</b> |            | <b>81</b>          |          | <b>5282</b>  |              |                     |                 |
|                    | <b>Grand Total - 162 Nos. schemes</b>        |            | <b>525</b>         |          | <b>47930</b> |              |                     |                 |

**Hydro Capacity addition during 2017-18**

| Sl. No.   | Particular  | Unit Nos.                       | Cap. (MW)               | Commissioning as programmed | Actual(A)/ Anticipated  | Remarks   |
|-----------|---|---------------------------------|-------------------------|-----------------------------|---|---|
| <b>A.</b> | <b>Central Sector</b>   |                                 |                         |                             |   |   |
| 1         | <b>Tuirial</b><br>NEEPCO, Mizoram<br>2x30 = 60 MW                           | Unit # 1<br>Unit # 2            | 30<br>30                | Jun.17<br>Sep.17            | <b>25.08.2017 (A)</b><br><b>28.11.2017 (A)</b>                          | <b>Commissioned</b><br><b>Commissioned</b>                        |
| 2         | <b>Kishanganga</b><br>NHPC, J&K<br>3x110 = 330 MW                           | Unit #1<br>Unit # 2<br>Unit # 3 | 110<br>110<br>110       | Jan.18<br>Feb.18<br>Mar.18  | <b>13.03.2018 (A)</b><br><b>21.03.2018 (A)</b><br><b>30.03.2018 (A)</b> | <b>Commissioned</b><br><b>Commissioned</b><br><b>Commissioned</b> |
| 3         | <b>Pare</b><br>NEEPCO, Arunachal Pradesh<br>2x55=110 MW                     | Unit # 1<br>Unit # 2            | 55<br>55                | Feb.18<br>Mar.18            | Slipped (2018-19)<br>Slipped (2018-19)                                  | Leakage observed in Diversion Tunnel during water filling.        |
| 4         | <b>Kameng</b><br>NEEPCO, Arunachal Pradesh<br>4x150=600 MW                  | Unit # 1<br>Unit # 2            | 150<br>150              | Mar.18<br>Mar.18            | Slipped (2018-19)<br>Slipped (2018-19)                                  | Leakage observed in penstocks during water filling.               |
|           | <b>Sub- total (A):</b>  |                                 | <b>800</b>              |                             | <b>390 MW</b>   |   |
| <b>B.</b> | <b>State Sector</b>   |                                 |                         |                             |   |   |
| 1         | <b>Sainj</b><br>HPPCL, H.P.<br>2x50= 100 MW                                 | Unit # 1<br>Unit # 2            | 50<br>50                | May.17<br>Jun.17            | <b>04.09.2017 (A)</b><br><b>04.09.2017 (A)</b>                          | <b>Commissioned</b><br><b>Commissioned</b>                        |
| 2         | <b>Uhl - III</b><br>BVPCL, H.P.<br>3x33.33=100 MW                           | Unit #1<br>Unit # 2<br>Unit # 3 | 33.33<br>33.33<br>33.33 | Jan.18<br>Feb.18<br>Mar.18  | Slipped (2018-19)<br>Slipped (2018-19)<br>Slipped (2018-19)             | Delay in completion of HRT lining.                                |
| 3         | <b>Pulichintala</b><br>TSGENCO, Telangana<br>4x30=120 MW                    | Unit # 2<br>Unit # 3            | 30<br>30                | Aug.17<br>Oct.17            | <b>26.10.2017 (A)</b><br><b>01.11.2017 (A)</b>                          | <b>Commissioned</b><br><b>Commissioned</b>                        |
| 4         | <b>New Umtru</b><br>MePGCL, Meghalaya<br>2x20=40 MW                         | Unit # 1<br>Unit # 2            | 20<br>20                | Apr.17<br>Jul.17            | <b>22.04.2017 (A)</b><br><b>30.06.2017 (A)</b>                          | <b>Commissioned</b><br><b>Commissioned</b>                        |
|           | <b>Sub- total (B):</b>  |                                 | <b>300</b>              |                             | <b>200 MW</b>   |   |
| <b>C.</b> | <b>Private Sector</b>   |                                 |                         |                             |   |   |
| 1         | <b>Chanju-I</b><br>IA Energy, H.P.<br>3x12 = 36 MW                          | Unit # 3                        | 12                      | May.17                      | <b>26.07.2017 (A)</b>   | <b>Commissioned</b>   |
| 2         | <b>Dikchu</b><br>Sneha Kinetic Power Projects Pvt. Ltd., Sikkim, 2x48MW= 96 | Unit # 1<br>Unit # 2            | 48<br>48                | Apr.17<br>May.17            | <b>11.04.2017 (A)</b><br><b>12.04.2017 (A)</b>                          | <b>Commissioned</b><br><b>Commissioned</b>                        |
| 3         | <b>Tashiding</b><br>Shiga Energy Pvt. Ltd. Sikkim<br>2x48.5= 97 MW          | Unit # 1<br>Unit # 2            | 48.5<br>48.5            | Jul.17<br>Aug.17            | <b>06.11.2017 (A)</b><br><b>06.11.2017 (A)</b>                          | <b>Commissioned</b><br><b>Commissioned</b>                        |
|           | <b>Sub- total (C):</b>  |                                 | <b>205</b>              |                             | <b>205 MW</b>   |   |
|           | <b>Total (A+B+C)</b>  |                                 | <b>1305</b>             |                             | <b>795 MW</b>   |   |

**Tentative Programme for Hydro Capacity addition for 2018-19**

| <b>Sl. No.</b> | <b>Particular</b>  | <b>Unit Nos.</b>                             | <b>Capacity (MW)</b>     | <b>Commissioning as programmed</b>         | <b>COD as programmed</b>                   |
|----------------|--|--|--------------------------|--|--|
| <b>A.</b>      | <b>Central Sector</b>  |  |                          |  |  |
| 1              | <b>Pare</b><br>NEEPCO, Arunachal Pradesh<br>2x55=110 MW          | Unit # 1<br>Unit # 2                         | 55<br>55                 | May 18<br>May 18                           | June 18<br>June 18                         |
| 2              | <b>Kameng</b><br>NEEPCO, Arunachal Pradesh<br>4x150=600 MW       | Unit # 1<br>Unit # 2<br>Unit # 3<br>Unit # 4 | 150<br>150<br>150<br>150 | Aug. 18<br>Aug. 18<br>Sept. 18<br>Sept. 18 | Sept. 18<br>Sept. 18<br>Oct. 18<br>Oct. 18 |
|                | <b>Sub- total (A):</b>   |  | <b>710 MW</b>            |  |  |
| <b>B.</b>      | <b>State Sector</b>  |  |                          |  |  |
| 1              | <b>Sawara Kuddu</b><br>HPPCL, H.P.<br>3x37= 111 MW               | Unit # 1                                     | 37                       | Mar.19                                     | Mar. 19                                    |
| 2              | <b>Uhl - III</b><br>BVPCL, H.P.<br>3x33.33=100 MW                | Unit #1<br>Unit # 2<br>Unit # 3              | 33.33<br>33.33<br>33.33  | June 18<br>July.18<br>July.18              | July 18<br>Aug. 18<br>Aug. 18              |
| 3              | <b>Pulichintala</b><br>TSGENCO,Telangana<br>4x30=120 MW          | Unit # 4                                     | 30                       | Sept. 18                                   | Sept. 18                                   |
|                | <b>Sub- total (B):</b>   |  | <b>167</b>               |  |  |
| <b>C.</b>      | <b>Private Sector</b>  |  |                          |  |  |
| 1              | <b>Singoli Bhatwari</b><br>L&T UHPL, Uttarakhand<br>3x33 = 99 MW | Unit # 1                                     | 33                       | Mar.19                                     | Mar.19                                     |
|                | <b>Sub- total (C):</b>   |  | <b>33</b>                |  |  |
|                | <b>Total (A+B+C)</b>   |  | <b>910 MW</b>            |  |  |

**ANNEXURE-6A**

**THERMAL CAPACITY ADDITION TARGET/ACHIEVEMENT (RFD) FOR THE YEAR 2017-18**

|   | State        | Project                      | Imp Agency                              | Equip. Supplier | Fuel | Unit | Targeted Capacity (MW) | Capacity Achieved (MW) | Actual date of comm. | Comm. Target as per RFD |
|---|--------------|------------------------------|---|-----------------|------|------|------------------------|------------------------|----------------------|-------------------------|
|   |              | <b><u>CENTRAL SECTOR</u></b> |   |                 |      |      |                        |                        |                      |                         |
| 1 | Assam        | Bongaigaon TPP               | NTPC                                    | BHEL            | Coal | U-3  | 250                    |                        |                      | Dec-17                  |
| 2 | Bihar        | Nabi Nagar TPP               | JV of NTPC & Rly                        | BHEL            | Coal | U-2  | 250                    | 250                    | 03.04.17             | Apr-17                  |
| 3 | Bihar        | New Nabi Nagar TPP           | JV of NTPC & BSPGCL                     | NON BHEL        | Coal | U-1  | 660                    |                        |                      | Aug-17                  |
| 4 | Chhattisgarh | Lara TPP                     | NTPC                                    | NON BHEL        | Coal | U-1  | 800                    | 800                    |                      | Oct-17                  |
| 5 | Karnataka    | Kudgi STPP Ph-I              | NTPC                                    | NON BHEL        | Coal | U-3  | 800                    | 800                    | 12.03.18             | Aug-17                  |
| 6 | MP           | Gadarwara STPP, St-I         | NTPC                                    | BHEL            | Coal | U-1  | 800                    |                        |                      | Jan-18                  |
|   | Maharashtra  | Solapur STPP                 | NTPC                                    | NON BHEL        | Coal | U-1  | 660                    | 660                    | 07.04.17             | Apr-17                  |
|   | UP           | Meja STPP                    | JV of NTPC & UPRVUNL                    | NON BHEL        | Coal | U-1  | 660                    | 660                    | 31.03.18             | Oct-17                  |
|   |              |                              | <b>Total Central Sector</b>             |                 |      |      | <b>4880</b>            | <b>3170</b>            |                      |                         |
|   |              | <b><u>STATE SECTOR</u></b>   |   |                 |      |      |                        |                        |                      |                         |
| 1 | AP           | Royal seema TPP              | APGENCO                                 | BHEL            | Coal | U-6  | 600                    | 600.00                 | 12.03.18             | Aug-17                  |
| 2 | Assam        | Namrup                       | APGCL                                   | BHEL            | Gas  | ST   | 36.15                  |                        |                      | Feb-18                  |
| 3 | MP           | Shree Singaji TPP, St-II     | MPPGCL                                  | NON BHEL        | Coal | U-3  | 660                    |                        |                      | Dec-17                  |
| 4 | Rajasthan    | Suratgarh TPS                | RRVUNL                                  | BHEL            | Coal | U-7  | 660                    |                        |                      | Nov-17                  |
| 5 | Rajasthan    | Chhabra SCTPP                | RRVUNL                                  | L&T & MHI       | Coal | U-5  | 660                    | 660.00                 | 04.04.17             | Apr-17                  |
| 6 | Rajasthan    | Chhabra SCTPP                | RRVUNL                                  | L&T & MHI       | Coal | U-6  | 660                    |                        |                      | Jan-18                  |
| 7 | Telangana    | Bhadradri TPP                | TGENCO                                  | BHEL            | Coal | U-1  | 270                    |                        |                      | Mar-18                  |
|   |              |                              | <b>Total State Sector</b>               |                 |      |      | <b>3546.15</b>         | <b>1260.00</b>         |                      |                         |
|   |              | <b><u>PRIVATE SECTOR</u></b> |   |                 |      |      |                        |                        |                      |                         |
| 1 | Chhattisgarh | Akaltara (Naiyara) TPP       | KSK Mahandi Power Company Ltd           | CHINESE         | Coal | U-3  | 600                    | 600.00                 | 18.01.18             | Nov-17                  |
| 2 | Chhattisgarh | Binjkote TPP                 | SKS Power Generation (Chhattisgarh) Ltd | CHINESE         | Coal | U-1  | 300                    | 300.00                 | 25.04.17             | May-17                  |
| 3 | Chhattisgarh | Nawapara TPP                 | TRN Energy                              | CHINESE         | Coal | U-2  | 300                    | 300.00                 | 18.04.17             | May-17                  |
| 4 | Chhattisgarh | Lanco Amarkantak TPS-II      | LAP Pvt. Ltd.                           | CHINESE         | Coal | U-3  | 660                    |                        |                      | Nov-17                  |
| 5 | Maharashtra  | Nasik TPP Ph-I               | RattanIndia Nasik Power Ltd             | BHEL            | Coal | U-3  | 270                    | 270.00                 | 14.04.17             | May-17                  |



|   |              |                          |   |         |      |     |                 |                |          |        |
|---|--------------|--------------------------|---|---------|------|-----|-----------------|----------------|----------|--------|
| 6                                       | UP           | Bara TPP                 | Prayagraj Power Generation Co.Ltd.      | BHEL    | Coal | U-3 | 660             | 660.00         | 22.05.17 | Aug-17 |
| 7                                       | WB           | India Power TPP (Haldia) | Indian Energy Ltd (Haldia)              | BHEL    | Coal | U-1 | 150             | 150.00         | 07.06.17 | Apr-17 |
| <b>Total Private Sector</b>             |              |                          |   |         |      |     | <b>2940</b>     | <b>2280.0</b>  |          |        |
| <b>Total Target during 2016-17</b>      |              |                          |   |         |      |     | <b>11366.15</b> | <b>6710.00</b> |          |        |
| <b>ADDITIONAL CAPACITY COMMISSIONED</b> |              |                          |   |         |      |     |                 |                |          |        |
| <b><u>STATE SECTOR</u></b>              |              |                          |   |         |      |     |                 |                |          |        |
| 1                                       | Bihar        | Barauni Ext.             | BSEB                                    | BHEL    | Coal | U-8 |                 | 250.0          | 11.01.18 |        |
| 2                                       | Bihar        | Barauni Ext.             | BSEB                                    | BHEL    | Coal | U-9 |                 | 250.0          | 31.03.18 |        |
| <b><u>PRIVATE SECTOR</u></b>            |              |                          |   |         |      |     |                 |                |          |        |
| 1                                       | Maharashtra  | Nasik TPP Ph-I           | RattanIndia Nasik Power Ltd             | BHEL    | Coal | U-4 |                 | 270.00         | 19.05.17 |        |
| 2                                       | Maharashtra  | Nasik TPP Ph-I           | RattanIndia Nasik Power Ltd             | BHEL    | Coal | U-5 |                 | 270.00         | 30.05.17 |        |
| 3                                       | Chhattisgarh | Uchpinda TPP             | RKM Powergen Pvt.Ltd.                   | Chinese | Coal | U-3 |                 | 360.00         | 12.09.17 |        |
| 4                                       | Maharashtra  | Shirpur TPP              | Shirpur Power Pvt. Ltd.                 | BHEL    | Coal | U-1 |                 | 150.00         | 28.09.17 |        |
| 5                                       | WB           | India Power TPP (Haldia) | Indian Energy Ltd (Haldia)              | BHEL    | Coal | U-2 |                 | 150.00         | 31.12.17 |        |
| 6                                       | Chhattisgarh | Binjkote TPP             | SKS Power Generation (Chhattisgarh) Ltd | CHINESE | Coal | U-2 |                 | 300.00         | 28.03.18 |        |
| <b>Total Additional Capacity</b>        |              |                          |   |         |      |     |                 | <b>2000.0</b>  |          |        |
| <b>Grand Total 2017-18</b>              |              |                          |   |         |      |     | <b>13440.5</b>  | <b>8710.00</b> |          |        |

**ANNEXURE-6B**

**THERMAL CAPACIYT ADDITION TARGET FOR THE YEAR 2018-19**

|   | State                 | Project Name                 | Impl Agency                   | Equipmen t Supplier | Fuel | Unit No. | Targeted Cap. (MW) | Comm. Cap. (MW) | Actual Comm Date | Comm. Target as per RFD |
|---|-----------------------|------------------------------|-------------------------------|---------------------|------|----------|--------------------|-----------------|------------------|-------------------------|
|   | <b>CENTRAL SECTOR</b> |                              |                               |                     |      |          |                    |                 |                  |                         |
| 1 | Assam                 | Bongaigaon TPP               | NTPC                          | BHEL                | Coal | U-3      | 250                |                 |                  | Sep-18                  |
| 2 | Bihar                 | Nabi Nagar TPP               | JV of NTPC & Rly              | BHEL                | Coal | U-3      | 250                |                 |                  | Dec-18                  |
| 3 | Bihar                 | New Nabi Nagar TPP           | JV of NTPC & BSPGCL           | NON BHEL            | Coal | U-1      | 660                |                 |                  | Jan-19                  |
| 4 | MP                    | Gadarwara TPP                | NTPC                          | BHEL                | Coal | U-1      | 800                |                 |                  | Nov-18                  |
| 5 | Odisha                | Darlipalli STPP              | NTPC                          | NON BHEL            | Coal | U-1      | 800                |                 |                  | Mar/<br>Apr-19          |
|   |                       | TOTAL CENTRAL SECTOR         |                               |                     |      |          | <b>2760</b>        |                 |                  |                         |
|   | <b>STATE SECTOR</b>   |                              |                               |                     |      |          |                    |                 |                  |                         |
| 1 | Assam                 | Namrup CCGT                  | APGCL                         | BHEL                | Gas  | ST       | 36.15              |                 |                  | Feb-19                  |
| 2 | MP                    | Shri Singhaji TPP St-II      | MPGENC O                      | NON BHEL            | Coal | U-3      | 660                |                 |                  | Sep-18                  |
| 3 | MP                    | Shri Singhaji TPP St-II      | MPGENC O                      | NON BHEL            | Coal | U-4      | 660                |                 |                  | Feb-19                  |
| 4 | Odisha                | Ib valley TPP                | OPGCL                         | BHEL                | Coal | U-3      | 660                |                 |                  | Mar-19                  |
| 5 | Rajasthan             | Chhabra TPP Extn             | RRVUNL                        | NON BHEL            | Coal | U-6      | 660                |                 |                  | Dec-18                  |
| 6 | Rajasthan             | Suratgarh SCTPP              | RRVUNL                        | BHEL                | Gas  | U-7      | 660                |                 |                  | Dec-18                  |
| 7 | Karnataka             | Yelahanka CCPP               | KPCL                          | BHEL                | Coal | GT+ ST   | 370                |                 |                  | Oct-18                  |
| 8 | Telangana             | Kothagudem TPS St-VII        | TSGENC O                      | BHEL                | Coal | U-1      | 800                |                 |                  | Dec-18                  |
|   |                       | TOTAL STATE SECTOR           |                               |                     |      |          | <b>4506.15</b>     |                 |                  |                         |
|   | <b>PRIVATE SECTOR</b> |                              |                               |                     |      |          |                    |                 |                  |                         |
| 1 | AP                    | Thamminapatnam TPP stage -II | Meenakshi Energy Pvt. Ltd.    | CHINESE             | Coal | 4        | 350                |                 |                  | Mar-19                  |
| 2 | Chhattisgarh          | Akaltara TPP (Naiyara)       | KSK Mahandi Power Company Ltd | CHINESE             | Coal | 4        | 600                |                 |                  | Mar-19                  |
|   |                       | TOTAL PRIVATE SECTOR         |                               |                     |      |          | <b>950</b>         |                 |                  |                         |
|   |                       | TOTAL THERMAL CAPACITY       |                               |                     |      |          | <b>8216.15</b>     |                 |                  |                         |

**Details of Tours performed attended by CEA officer(s) during April, 2017 to March, 2018:-**

| Sl. No. | Name & Designation S/Sh.                | Duration              | Venue  | Name of the Programme                                |
|---------|---|-----------------------|--------|--|
| 1.      | Sh. Gorakh Thakur, Chief Engineer (TCD) | 16.01.2018-19.01.2018 | Bhutan | Visit of CEA Officers to Punatsangchhu-II at Bhutan. |
| 2.      | Sh. Neeraj Kumar, Dir. (TCD)            | 16.01.2018-19.01.2018 | Bhutan | Visit of CEA Officers to Punatsangchhu-II at Bhutan. |

**OUTSTANDING DUES OF POWER UTILITIES PAYABLE TO CENTRAL PUBLIC SECTOR UNDERTAKINGS (CPSUs)**  
(Dues of Principal and Surcharge outstanding for more than 60 days)

based upon the information received from CPSUs upto 31st March, 2018

All Figures in Rs Crores

| Sl. No. | STATE / UTILITY                | NTPC   |      | NHPC   |        | PGCIL  |      | NEEPCO |      | NPCIL  |        | DVC    |      | NLC   |       | SVJNL  |        | BBMB   |      | THDC    |      | NHDC  |      | TOTAL   |
|---------|--------------------------------|--------|------|--------|--------|--------|------|--------|------|--------|--------|--------|------|-------|-------|--------|--------|--------|------|---------|------|-------|------|---------|
|         |                                | PRIN   | SUR  | PRIN   | SUR    | PRIN   | SUR  | PRIN   | SUR  | PRIN   | SUR    | PRIN   | SUR  | PRIN  | SUR   | PRIN   | SUR    | PRIN   | SUR  | PRIN    | SUR  | PRIN  | SUR  |         |
| 1       | 2                              | 3      |      | 4      |        | 5      |      | 6      |      | 7      |        | 8      |      | 9     |       | 10     |        | 11     |      | 12      |      | 13    |      | 14      |
|         | <b>NORTHERN REGION</b>         |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
|         | <b>HARYANA</b>                 |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 1       | HVPNL                          |        |      |        |        | 14     |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      | 14.00   |
|         | <b>TOTAL (Haryana)</b>         | 0.00   | 0.00 | 0.00   | 0.00   | 14.00  | 0.00 | 0.00   | 0.00 | 0.00   | 0.00   | 0.00   | 0.00 | 0.00  | 0.00  | 0.00   | 0.00   | 0.00   | 0.00 | 0.00    | 0.00 | 0.00  | 0.00 | 14.00   |
|         | <b>HIMACHAL</b>                |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 2       | HPSEB                          |        |      |        | 0.65   |        |      |        |      |        | 0.14   |        |      |       |       |        | 10.34  | 0.63   |      | -3.57   |      |       |      | 8.19    |
| 3       | Govt.of HP                     |        |      |        |        |        |      |        |      |        |        |        |      |       |       | 8.75   | 311.61 |        |      |         |      |       |      | 320.36  |
|         | <b>TOTAL (Himachal)</b>        | 0.00   | 0.00 | 0.00   | 0.65   | 0.00   | 0.00 | 0.00   | 0.00 | 0.00   | 0.14   |        |      | 0.00  | 0.00  | 8.75   | 321.95 | 0.63   | 0.00 | -3.57   | 0.00 | 0.00  | 0.00 | 328.55  |
|         | <b>DELHI</b>                   |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 4       | DTL                            |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        | 11.54  |        |      |         |      |       |      | 11.54   |
| 5       | BYPL /BSES YAMUNA              |        |      | 182.91 | 154.42 |        |      |        |      | 212.88 | 124.87 |        |      |       |       | 42.14  | 71.26  |        |      | 281.40  |      |       |      | 1069.88 |
| 6       | BRPL/BSES RAJDHANI             |        |      |        |        |        |      |        |      | 117.38 | 87.96  |        |      |       |       |        |        |        |      | 257.51  |      |       |      | 462.85  |
|         | <b>TOTAL (Delhi)</b>           | 0.00   | 0.00 | 182.91 | 154.42 | 0.00   | 0.00 | 0.00   | 0.00 | 330.26 | 212.83 | 0.00   | 0.00 | 0.00  | 0.00  | 42.14  | 82.80  | 0.00   | 0.00 | 538.91  | 0.00 | 0.00  | 0.00 | 1544.27 |
|         | <b>JAMMU &amp; KASHMIR</b>     |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 7       | J&K PDD                        | 823.55 |      |        |        | 102.00 |      |        |      | 196.06 | 2.60   |        |      |       |       | 94.56  | 12.03  | 6.80   |      | 68.44   |      |       |      | 1306.04 |
| 8       | J&K PDCL                       |        |      | 514.02 | 50.09  |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      | 564.11  |
|         | <b>TOTAL (J&amp;K)</b>         | 823.55 | 0.00 | 514.02 | 50.09  | 102.00 | 0.00 | 0.00   | 0.00 | 196.06 | 2.60   |        |      | 0.00  | 0.00  | 94.56  | 12.03  | 6.80   | 0.00 | 68.44   | 0.00 | 0.00  | 0.00 | 1870.15 |
|         | <b>PUNJAB</b>                  |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 9       | PSEB                           |        |      |        |        |        |      |        |      |        | 0.11   |        |      |       |       |        |        |        |      |         |      |       |      | 0.11    |
| 10      | PSPCL                          |        |      |        | 19.58  | 28.00  |      |        |      |        |        | 91.62  |      |       |       | 0.17   | 1.60   |        |      | 1.90    |      |       |      | 142.87  |
|         | <b>TOTAL (Punjab)</b>          | 0.00   | 0.00 | 0.00   | 19.58  | 28.00  | 0.00 | 0.00   | 0.00 | 0.00   | 0.11   | 91.62  | 0.00 | 0.00  | 0.00  | 0.17   | 1.60   | 0.00   | 0.00 | 1.90    | 0.00 | 0.00  | 0.00 | 142.98  |
|         | <b>RAJASTHAN</b>               |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 11      | RRVUNL /RSEB                   |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        | 213.86 |      |         |      |       |      | 213.86  |
| 12      | JVVNL                          |        |      | 0.12   | 0.01   |        |      |        |      | 6.28   |        |        |      |       |       |        |        |        |      | 0.18    |      |       |      | 78.61   |
| 13      | AVVNL                          |        |      | 0.13   | 0.02   |        |      |        |      | 4.39   |        |        |      |       |       |        |        |        |      | 0.11    |      |       |      | 4.65    |
| 14      | JDVVNL                         |        |      | 9.34   | 0.91   |        |      |        |      | 3.13   | 0.05   |        |      |       | 72.02 |        |        |        |      | 0.05    |      |       |      | 13.48   |
|         | <b>TOTAL (Rajasthan)</b>       | 0.00   | 0.00 | 9.59   | 0.94   | 0.00   | 0.00 | 0.00   | 0.00 | 13.80  | 0.05   |        |      | 72.02 | 0.00  | 0.00   | 0.00   | 213.86 | 0.00 | 0.34    | 0.00 | 0.00  | 0.00 | 310.60  |
|         | <b>OTHERS</b>                  |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 15      | HWB (KOTA)                     |        |      |        |        |        |      |        |      | 23.23  | 0.02   |        |      |       |       |        |        |        |      |         |      |       |      | 23.25   |
|         | <b>UTTAR PRADESH</b>           |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 16      | UPPCL                          |        |      |        | 59.10  |        |      |        |      | 5.27   | 159.14 |        |      |       |       |        | 128.13 |        |      | 570.88  |      |       |      | 922.52  |
|         | <b>TOTAL (Uttar Pradesh)</b>   | 0.00   | 0.00 | 0.00   | 59.10  | 0.00   | 0.00 | 0.00   | 0.00 | 5.27   | 159.14 | 0.00   | 0.00 | 0.00  | 0.00  | 0.00   | 128.13 | 0.00   | 0.00 | 570.88  | 0.00 | 0.00  | 0.00 | 922.52  |
|         | <b>UTTARAKHAND</b>             |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 17      | UPCL                           |        |      |        |        |        |      |        |      |        | 0.90   |        |      |       |       |        |        |        |      |         |      |       |      | 0.90    |
|         | <b>CHANDIGARH</b>              |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 18      | CPDD                           |        |      | 0.02   | 2.00   |        |      |        |      |        |        |        |      |       |       |        |        | 140.14 |      | 8.72    |      |       |      | 150.88  |
|         | <b>OTHERS</b>                  |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 19      | M/s N.F.L. Nangal              |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        | 0.01   |      |         |      |       |      | 0.01    |
| 20      | B.S.L. Project S/Naqar         |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        | 0.20   |      |         |      |       |      | 0.20    |
| 21      | Beas Project talwara           |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        | 0.03   |      |         |      |       |      | 0.03    |
|         | <b>TOTAL (Others)</b>          | 0.00   | 0.00 | 0.00   | 0.00   | 0.00   | 0.00 | 0.00   | 0.00 | 0.00   | 0.00   | 0.00   | 0.00 | 0.00  | 0.00  | 0.00   | 0.24   | 0.00   | 0.00 | 0.00    | 0.00 | 0.00  | 0.00 | 0.00    |
|         | <b>TOTAL (Northern Region)</b> | 823.55 | 0.00 | 706.52 | 284.80 | 146.00 | 0.00 | 0.00   | 0.00 | 568.62 | 375.79 | 91.62  | 0.00 | 72.02 | 0.00  | 145.62 | 546.51 | 361.67 | 0.00 | 1185.62 | 0.00 | 0.00  | 0.00 | 5308.34 |
|         | <b>WESTERN REGION</b>          |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
|         | <b>GUJARAT</b>                 |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 22      | GUVNL                          |        |      |        |        |        |      |        |      | 3.17   |        |        |      |       |       |        |        |        |      |         |      |       |      | 3.17    |
|         | <b>MADHYA PRADESH</b>          |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 23      | MPPCL                          |        |      | 0.60   | 0.33   | 14.00  |      |        |      | 0.24   |        |        |      |       |       |        |        |        |      |         |      |       |      | 15.17   |
| 24      | MPPMCL Jabalpur                |        |      |        |        |        |      |        |      |        |        | 134.01 |      |       |       |        |        |        |      | -0.30   |      | 47.07 |      | 180.78  |
|         | <b>TOTAL (Madhya Pradesh)</b>  | 0.00   | 0.00 | 0.60   | 0.33   | 14.00  | 0.00 | 0.00   | 0.00 | 0.24   | 0.00   | 134.01 | 0.00 | 0.00  | 0.00  | 0.00   | 0.00   | 0.00   | 0.00 | -0.30   | 0.00 | 47.07 | 0.00 | 195.95  |
|         | <b>CHHATTISGARH</b>            |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 25      | CSEB/CSPDCL                    |        |      |        |        |        |      |        |      |        | 0.04   |        |      |       |       |        |        |        |      |         |      |       |      | 0.04    |
|         | <b>TOTAL(CHHATTISGARH)</b>     | 0.00   |      |        |        | 0.00   |      |        |      | 0.00   | 0.04   |        |      |       |       |        |        |        |      |         |      |       |      | 0.04    |
|         | <b>MAHARASHTRA</b>             |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 26      | MSEDCL                         |        |      |        |        |        |      |        |      | 0.09   | 0.11   |        |      |       |       | 28.21  | 6.16   |        |      |         |      |       |      | 34.57   |
|         | <b>OTHERS</b>                  |        |      |        |        |        |      |        |      |        |        |        |      |       |       |        |        |        |      |         |      |       |      |         |
| 27      | BARC                           |        |      |        |        |        |      |        |      |        | 0.16   |        |      |       |       |        |        |        |      |         |      |       |      | 0.16    |
|         | <b>TOTAL (Western Region)</b>  | 0.00   | 0.00 | 0.60   | 0.33   | 14.00  | 0.00 | 0.00   | 0.00 | 3.50   | 0.31   | 134.01 | 0.00 | 0.00  | 0.00  | 28.21  | 6.16   | 0.00   | 0.00 | -0.30   | 0.00 | 47.07 | 0.00 | 233.89  |

| Sl. No. | STATE / UTILITY                | NTPC    |      | NHPC   |        | PGCIL  |       | NEEPCO |      | NPCIL   |        | DVC     |      | NLC     |      | SVJNL  |        | BBMB   |      | THDC    |      | NHDC  |      | TOTAL    |
|---------|--------------------------------|---------|------|--------|--------|--------|-------|--------|------|---------|--------|---------|------|---------|------|--------|--------|--------|------|---------|------|-------|------|----------|
|         |                                | PRIN    | SUR  | PRIN   | SUR    | PRIN   | SUR   | PRIN   | SUR  | PRIN    | SUR    | PRIN    | SUR  | PRIN    | SUR  | PRIN   | SUR    | PRIN   | SUR  | PRIN    | SUR  | PRIN  | SUR  | 13       |
| 1       | 2                              | 3       |      | 4      |        | 5      |       | 6      |      | 7       |        | 8       |      | 9       |      | 10     |        | 11     |      | 12      |      | 13    |      | 14       |
|         | <b>SOUTHERN REGION</b>         |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
|         | <b>ANDHRA PRADESH</b>          |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 28      | APEPDC/ANPCL/APTRANSCO         | 1342.76 |      |        |        | 19.00  |       |        |      | 8.70    | 11.08  |         |      | 89.21   |      |        |        |        |      |         |      |       |      | 1470.75  |
|         | <b>TOTAL (Andhra Pradesh)</b>  | 1342.76 |      |        |        | 19.00  |       |        |      | 8.70    | 11.08  |         |      | 89.21   | 0.00 |        |        |        |      |         |      |       |      | 1470.75  |
|         | <b>KARNATAKA</b>               |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 29      | BESCOM                         |         |      |        |        |        |       |        |      | 0.73    |        | 126.00  |      |         |      |        |        |        |      |         |      |       |      | 411.29   |
| 30      | MESCOM                         |         |      |        |        |        |       |        |      | 0.40    |        |         |      |         |      |        |        |        |      |         |      |       |      | 0.40     |
| 31      | CESCOM                         | 17.38   |      |        |        |        |       |        |      | 15.74   | 4.23   |         |      |         |      |        |        |        |      |         |      |       |      | 37.35    |
| 32      | HESCOM                         | 13.56   |      |        |        |        |       |        |      | 277.14  | 74.79  |         |      |         |      |        |        |        |      |         |      |       |      | 365.49   |
| 33      | GESCOM                         |         |      |        |        |        |       |        |      | 63.68   | 4.86   |         |      |         |      |        |        |        |      |         |      |       |      | 68.54    |
| 34      | ESCOMS                         |         |      |        |        |        |       |        |      |         |        |         |      | 284.56  |      |        |        |        |      |         |      |       |      |          |
|         | <b>TOTAL (Karnataka)</b>       | 30.94   |      |        | 0.00   | 0.00   |       |        |      | 357.69  | 83.88  | 126.00  | 0.00 | 284.56  |      |        |        |        |      |         |      |       |      | 883.07   |
|         | <b>TELANGANA</b>               |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 35      | TELANGANA DISCOMS              | 118.72  |      |        |        |        |       |        |      | 0.74    | 4.72   |         |      | 75.33   |      |        |        |        |      |         |      |       |      | 199.51   |
|         | <b>KERALA</b>                  |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 36      | KSEB                           |         |      |        |        |        |       |        |      | 6.82    | 0.09   | 30.56   |      | 57.16   |      |        |        |        |      |         |      |       |      | 94.63    |
|         | <b>TAMILNADU</b>               |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 37      | TNEB/TANGEDCO                  | 12.16   |      |        |        |        |       |        |      | 698.18  | 269.80 |         |      | 1500.89 |      |        |        |        |      |         |      |       |      | 2481.03  |
|         | <b>Puducherry</b>              |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 38      | PED                            |         |      |        |        |        |       |        |      |         | 1.10   |         |      | 71.11   |      |        |        |        |      |         |      |       |      | 72.21    |
|         | <b>TOTAL (Southern Region)</b> | 1504.58 | 0.00 | 0.00   | 0.00   | 19.00  | 0.00  | 0.00   | 0.00 | 1072.13 | 370.67 | 156.56  | 0.00 | 2078.26 | 0.00 | 0.00   | 0.00   | 0.00   | 0.00 | 0.00    | 0.00 | 0.00  | 0.00 | 5201.20  |
|         | <b>EASTERN REGION</b>          |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 39      | DVC                            |         |      |        | 0.02   | 113.00 |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      | 113.02   |
|         | <b>BIHAR</b>                   |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 40      | BIHAR(NBPDCL/SBPCL)            |         |      | 0.25   | 0.03   |        |       |        |      |         |        | 11.53   |      |         |      |        |        |        |      |         |      |       |      | 11.81    |
|         | <b>WEST BENGAL</b>             |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 41      | WBSEB                          |         |      | 29.92  |        | 7.00   |       |        |      |         |        | 415.26  |      |         |      |        |        |        |      |         |      |       |      | 452.18   |
|         | <b>JHARKHAND</b>               |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 42      | JBVNL                          |         |      |        |        |        |       |        |      |         |        | 2066.68 |      |         |      |        |        |        |      |         |      |       |      | 2066.68  |
|         | <b>ORISSA</b>                  |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 43      | GRIDCO                         |         |      |        |        | 21.00  |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      | 21.00    |
|         | <b>Andaman &amp; Nicobar</b>   |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 44      | Electricity Deptt              | 5.55    |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      | 5.55     |
|         | <b>TOTAL (Eastern Region)</b>  | 5.55    | 0.00 | 0.25   | 29.97  | 113.00 | 28.00 | 0.00   | 0.00 | 0.00    | 0.00   | 2493.47 | 0.00 | 0.00    | 0.00 | 0.00   | 0.00   | 0.00   | 0.00 | 0.00    | 0.00 | 0.00  | 0.00 | 2670.24  |
|         | <b>NORTH EASTERN REGION</b>    |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
|         | <b>ARUNACHAL PRADESH</b>       |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 45      | Department of Power            |         |      |        | 0.01   |        |       | 0.84   |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      | 0.85     |
|         | <b>MANIPUR</b>                 |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 46      | Electricity Department         |         |      | 0.02   | 1.47   |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      | 1.49     |
|         | <b>MEGHALAYA</b>               |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 47      | MeEcl/MeSEB                    | 123.87  |      | 12.53  | 13.97  | 1.00   |       | 218.54 |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      | 369.91   |
|         | <b>MIZORAM</b>                 |         |      |        |        |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      |          |
| 48      | Electricity Department         |         |      |        | 0.05   |        |       |        |      |         |        |         |      |         |      |        |        |        |      |         |      |       |      | 0.05     |
|         | <b>TOTAL (NE Region)</b>       | 123.87  | 0.00 | 12.55  | 15.50  | 1.00   | 0.00  | 219.38 | 0.00 | 0.00    | 0.00   | 0.00    | 0.00 | 0.00    | 0.00 | 0.00   | 0.00   | 0.00   | 0.00 | 0.00    | 0.00 | 0.00  | 0.00 | 372.30   |
|         | <b>GRAND-TOTAL</b>             | 2457.55 | 0.00 | 719.92 | 330.60 | 293.00 | 28.00 | 219.38 | 0.00 | 1644.25 | 746.77 | 2875.66 | 0.00 | 2150.28 | 0.00 | 173.83 | 552.67 | 361.67 | 0.00 | 1185.32 | 0.00 | 47.07 | 0.00 | 13785.97 |

Note : The Negative values Rs. -3.57 cr and Rs. -0.30 cr under THDC column implies that THDC will have to return the amount to HPSEB and MPPMCL respectively as per the Revised Estimate

| SI. No.          | STATE / UTILITY | NTPC  |     | NHPC |     | PGCIL |     | NEEPCO |     | NPCIL |     | DVC         |     | NLC  |     | SJVNL   |     | BBMB |     | THDC |     | NHDC |     | TOTAL |
|------------------|-----------------|---|-----|------|-----|-------|-----|--------|-----|-------|-----|-------------|-----|------|-----|---|-----|------|-----|------|-----|------|-----|-------|
|                  |                 | PRIN  | SUR | PRIN | SUR | PRIN  | SUR | PRIN   | SUR | PRIN  | SUR | PRIN        | SUR | PRIN | SUR | PRIN  | SUR | PRIN | SUR | PRIN | SUR | PRIN | SUR |       |
| 1                | 2               | 3   |     | 4    |     | 5     |     | 6      |     | 7     |     | 8           |     | 9    |     | 10  |     | 11   |     | 12   |     | 13   |     | 14    |
| <b>Utilities</b> |                 |   |     |      |     |       |     |        |     |       |     |             |     |      |     |   |     |      |     |      |     |      |     |       |
| 1                | APCPDCL         | Andhra Pradesh Cenral Power Distribution Company Ltd. |     |      |     |       |     |        |     |       |     | 22 J&K PDCL |     |      |     | Jammu & Kashmir Power Development Corporation Ltd.  |     |      |     |      |     |      |     |       |
| 2                | APEPDCL         | Andhra Pradesh Eastern Power Distribution Co. Ltd.    |     |      |     |       |     |        |     |       |     | 23 J&K PDD  |     |      |     | Jammu & Kashmir Power Development Department        |     |      |     |      |     |      |     |       |
| 3                | APNPDCL         | Andhra Pradesh Northern Power Distribution Co. Ltd.   |     |      |     |       |     |        |     |       |     | 24 JDVVNL   |     |      |     | Jodhpur Vidyut Vitran Nigam Ltd.                    |     |      |     |      |     |      |     |       |
| 4                | APSPDCL         | Andhra Pradesh Southern Power Distribution Co. Ltd.   |     |      |     |       |     |        |     |       |     | 25 JVVNL    |     |      |     | Jaipur Vidyut Vitran Nigam Ltd.                     |     |      |     |      |     |      |     |       |
| 5                | APTRANSCO       | Andhra Pradesh Transmission Corporation Ltd.          |     |      |     |       |     |        |     |       |     | 26 MESCOM   |     |      |     | Mangalore Electricity Supply Company Ltd.           |     |      |     |      |     |      |     |       |
| 6                | AVVNL           | Ajmer Vidyut Vitran Nigam Ltd.                        |     |      |     |       |     |        |     |       |     | 27 MPPMCL   |     |      |     | Madya Pradesh Power Management company Ltd.         |     |      |     |      |     |      |     |       |
| 7                | BBMB            | Bhakra Beas Management Board                          |     |      |     |       |     |        |     |       |     | 28 MSEDCL   |     |      |     | Maharashtra State Electricity Distribution Co. Ltd. |     |      |     |      |     |      |     |       |
| 8                | BESCOM          | Bangalore Electricity Supply Company Ltd.             |     |      |     |       |     |        |     |       |     | 29 NEEPCO   |     |      |     | North Eastern Electric Power Corporation Ltd.       |     |      |     |      |     |      |     |       |
| 9                | BRPL            | BSES Rajdhani Power Ltd.                              |     |      |     |       |     |        |     |       |     | 30 NHDC     |     |      |     | Narmada Hydro Development Corporation               |     |      |     |      |     |      |     |       |
| 10               | BYPL            | BSES Yamuna Power Ltd.                                |     |      |     |       |     |        |     |       |     | 31 NHPC     |     |      |     | National Hydro Power Corporation                    |     |      |     |      |     |      |     |       |
| 11               | CESCOM          | Chamundeshwari Electricity Supply Company Ltd.        |     |      |     |       |     |        |     |       |     | 32 NLC      |     |      |     | Nyveli Lignite Corporation                          |     |      |     |      |     |      |     |       |
| 12               | CPDD            | Chandigarh Power Development Department.              |     |      |     |       |     |        |     |       |     | 33 NPCIL    |     |      |     | Nuclear Power Corporation of India Ltd.             |     |      |     |      |     |      |     |       |
| 13               | DTL             | Delhi Transco Ltd.                                    |     |      |     |       |     |        |     |       |     | 34 NTPC     |     |      |     | National Thermal Power Corporation                  |     |      |     |      |     |      |     |       |
| 14               | DVC             | Damodar Valley Corporation                            |     |      |     |       |     |        |     |       |     | 35 PED      |     |      |     | Pondicherry Electricity Department                  |     |      |     |      |     |      |     |       |
| 15               | ESCOMS          | Electricity Supply Company (Karnataka)                |     |      |     |       |     |        |     |       |     | 36 PGCIL    |     |      |     | Power Grid Corporation of India Ltd.                |     |      |     |      |     |      |     |       |
| 16               | GESCOM          | Gulbarga Electricity Supply Company Ltd.              |     |      |     |       |     |        |     |       |     | 37 PSPCL    |     |      |     | Punjab State Power Corporation Ltd.                 |     |      |     |      |     |      |     |       |
| 17               | GUVNL           | Gujarat Urja Vikas Nigam Limited                      |     |      |     |       |     |        |     |       |     | 38 RRVUNL   |     |      |     | Rajasthan Rajya Vidyut Utpadan Nigam Ltd.           |     |      |     |      |     |      |     |       |
| 18               | HESCOM          | Hubli Electricity Supply Company Ltd.                 |     |      |     |       |     |        |     |       |     | 39 SJVNL    |     |      |     | Satluj Jal Vidyut Nigam Ltd.                        |     |      |     |      |     |      |     |       |
| 19               | HVPNL           | Haryana Vidyut Prasaran Nigam Ltd.                    |     |      |     |       |     |        |     |       |     | 40 THDC     |     |      |     | Tehri Hydro Development Corporation                 |     |      |     |      |     |      |     |       |
| 20               | HPSEB           | Himachal Pradesh State Electricity Board              |     |      |     |       |     |        |     |       |     | 41 UPCL     |     |      |     | Uttarakhand Power Corporation Ltd.                  |     |      |     |      |     |      |     |       |
| 21               | HWB             | Heavy Water Board (Kota)                              |     |      |     |       |     |        |     |       |     | 42 UPPCL    |     |      |     | Uttar Pradesh Power Corporation Ltd.                |     |      |     |      |     |      |     |       |

## Utilities

|    |           |  |    |          |   |
|----|-----------|--|----|----------|---|
| 1  | APCPDCL   | Andhra Pradesh Central Power Distribution Company Ltd. | 22 | J&K PDCL | Jammu & Kashmir Power Development Corporation Ltd.  |
| 2  | APEPDCL   | Andhra Pradesh Eastern Power Distribution Co. Ltd.     | 23 | J&K PDD  | Jammu & Kashmir Power Development Department        |
| 3  | APNPDCL   | Andhra Pradesh Northern Power Distribution Co. Ltd.    | 24 | JDVVNL   | Jodhpur Vidyut Vitran Nigam Ltd.                    |
| 4  | APSPDCL   | Andhra Pradesh Southern Power Distribution Co. Ltd.    | 25 | JVVNL    | Jaipur Vidyut Vitran Nigam Ltd.                     |
| 5  | APTRANSCO | Andhra Pradesh Transmission Corporation Ltd.           | 26 | MESCOM   | Mangalore Electricity Supply Company Ltd.           |
| 6  | AVVNL     | Ajmer Vidyut Vitran Nigam Ltd.                         | 27 | MPPMCL   | Madya Pradesh Power Management company Ltd.         |
| 7  | BBMB      | Bhakra Beas Management Board                           | 28 | MSEDCL   | Maharashtra State Electricity Distribution Co. Ltd. |
| 8  | BESCOM    | Bangalore Electricity Supply Company Ltd.              | 29 | NEEPCO   | North Eastern Electric Power Corporation Ltd.       |
| 9  | BRPL      | BSES Rajdhani Power Ltd.                               | 30 | NHDC     | Narmada Hydro Development Corporation               |
| 10 | BYPL      | BSES Yamuna Power Ltd.                                 | 31 | NHPC     | National Hydro Power Corporation                    |
| 11 | CESCOM    | Chamundeshwari Electricity Supply Company Ltd.         | 32 | NLC      | Nyveli Lignite Corporation                          |
| 12 | CPDD      | Chandigarh Power Development Department.               | 33 | NPCIL    | Nuclear Power Corporation of India Ltd.             |
| 13 | DTL       | Delhi Transco Ltd.                                     | 34 | NTPC     | National Thermal Power Corporation                  |
| 14 | DVC       | Damodar Valley Corporation                             | 35 | PED      | Pondicherry Electricity Department                  |
| 15 | ESCOMS    | Electricity Supply Company (Karnataka)                 | 36 | PGCIL    | Power Grid Corporation of India Ltd.                |
| 16 | GESCOM    | Gulbarga Electricity Supply Company Ltd.               | 37 | PSPCL    | Punjab State Power Corporation Ltd.                 |
| 17 | GUVNL     | Gujarat Urja Vikas Nigam Limited                       | 38 | RRVUNL   | Rajasthan Rajya Vidyut Utpadan Nigam Ltd.           |
| 18 | HESCOM    | Hubli Electricity Supply Company Ltd.                  | 39 | SJVNL    | Satluj Jal Vidyut Nigam Ltd.                        |
| 19 | HVPL      | Haryana Vidyut Prasaran Nigam Ltd.                     | 40 | THDC     | Tehri Hydro Development Corporation                 |
| 20 | HPSEB     | Himachal Pradesh State Electricity Board               | 41 | UPCL     | Uttarakhand Power Corporation Ltd.                  |
| 21 | HWB       | Heavy Water Board (Kota)                               | 42 | UPPCL    | Uttar Pradesh Power Corporation Ltd.                |

**CENTRAL ELECTRICITY AUTHORITY  
FINANCIAL STUDIES & ASSISTANCE DIVISION  
STATEMENT SHOWING ESTIMATED AVERAGE RATES OF ELECTRICITY (upto 01.04.2017) (Provisional)**

(Rates in Paise/KWh)

| SL No.                   | Name of Utility                                | Tariff effective from    | Domestic 1KW (100 KWh/ Month) | Domestic 4KW (400 KWh/ Month) | Domestic 10KW (1000 KWh/ Month) | Commercial 2KW (300 KWh/ Month) | Commercial 10KW (1500 KWh/ Month) | Commercial 30KW (4500 KWh/ Month) | Commercial 50KW (7500 KWh/ Month) | Agriculture e 2HP (400 KWh/ Month) | Agriculture 5HP (1000 KWh/ Month) | Agriculture 10HP (2000 KWh/ Month) | Small Industry 10KW (1500 KWh/ Month) | Medium Industry 50KW (7500 KWh/ Month) | Large Industry (11KV) 1000KW 60%L.F. (438000 KWh/ Month) | Heavy Industry (11KV) 10000KW 60%L.F. 20000KW | Heavy Industry (33KV) 20000KW | Railway Traction 12500KW (25000000 KWh/ Month) |          |
|--------------------------|--|--------------------------|-------------------------------|-------------------------------|---------------------------------|---------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|------------------------------------|-----------------------------------|------------------------------------|---------------------------------------|--|--|---|-------------------------------|--|----------|
| <b>States</b>            |  |                          |                               |                               |                                 |                                 |                                   |                                   |                                   |                                    |                                   |                                    |                                       |  |  |   |                               |  |          |
| 1                        | Andhra Pradesh                                 | 01.04.2016               | 208.50                        | 491.63                        | 679.50                          | 856.91                          | 980.78                            | 1007.42                           | 1012.75                           | 71.88                              | 71.88                             | 71.88                              | 693.75                                | 693.75                                 | 745.04   | 745.04  | 696.62                        | 703.16   |          |
| 2                        | Arunachal Pradesh                              | 01.04.2016               | 400.00                        | 400.00                        | 400.00                          | 500.00                          | 500.00                            | 500.00                            | 500.00                            | 310.00                             | 310.00                            | 310.00                             | 430.00                                | 430.00                                 | 385.00   | 385.00  | 350.00                        | -  |          |
| 3                        | Assam  | 01.08.2015               | 434.00                        | 635.70                        | 713.28                          | 814.33                          | 833.53                            | 853.60                            | 854.24                            | 451.19                             | 451.19                            | 612.55                             | 515.67                                | 712.43                                 | 679.68   | 679.54  | 679.53                        | -  |          |
| 4                        | Bihar  | 01.04.2016               | 376.30<br>238.50<br>R         | 462.43                        | 555.44                          | 644.83<br>296.80<br>R           | 788.99                            | 794.18                            | 795.21                            | 174.00<br>114.00<br>R              | 174.00<br>114.00<br>R             | 174.00<br>114.00<br>R              | 663.52                                | 785.87                                 | 634.40   | -   | 602.60<br>132k<br>V           | 687.23<br>at 25KV<br>at 132KV                  |          |
| 5                        | Chhattishgarh                                  | 01.04.2016               | 397.44                        | 523.26                        | 735.26                          | 701.87                          | 866.13                            | 903.47                            | 910.93                            | 450.00                             | 450.00                            | 450.00                             | 573.96                                | 693.05                                 | 807.84   | 807.84  | 759.84                        | 711.11   |          |
| 6                        | Goa  | 01.04.2016               | 170.00                        | 242.50                        | 325.00                          | 468.33                          | 523.00                            | 534.33                            | 536.60                            | 156.00                             | 156.00                            | 156.00                             | 433.48                                | 444.14                                 | 563.42   | 563.42  | 563.42                        | -  |          |
| 7                        | Gujarat  | 01.04.2016               | 405.38<br>335.94<br>R         | 517.50<br>119.59<br>R         | 577.88<br>540.19<br>R           | 615.00                          | 685.00                            | 738.33                            | 738.33                            | 10.00                              | 10.00                             | 10.00                              | 605.00                                | 716.67                                 | 578.41   | 578.41  | 559.91                        | 612.62<br>at 11KV                              |          |
| 8                        | Haryana  | 01.04.2016               | 370.00                        | 530.63                        | 685.00                          | 615.00                          | 685.00                            | 738.33                            | 738.33                            | 10.00                              | 10.00                             | 10.00                              | 605.00                                | 716.67                                 | 578.41   | 578.41  | 559.91                        | 587.12<br>at 220KV                             |          |
| 9                        | Himachal Pradesh                               | 01.04.2016               | 206.00                        | 303.85                        | 390.37                          | 581.40                          | 552.60                            | 554.56                            | 554.56                            | 129.25                             | 117.70                            | 113.85                             | 520.29                                | 665.44                                 | 624.95   | 624.95  | 619.71                        | -  |          |
| 10                       | Jammu & Kashmir                                | 01.10.2016               | 191.40                        | 293.98                        | 353.21                          | 401.50                          | 627.73                            | 627.73                            | 627.73                            | 80.85                              | 80.85                             | 80.85                              | 399.67                                | 397.47                                 | 422.10   | 422.10  | 410.45                        | -  |          |
| 11                       | Jharkhand                                      | 01.01.2016               | 323.00<br>197.00<br>R         | 322.75                        | 334.00                          | 716.67<br>215.00<br>R           | 720.67                            | 721.33                            | 721.47                            | 67.00                              | 67.00                             | 67.00                              | 660.11                                | 660.11                                 | 473.18   | 473.18  | 459.14                        | 738.24<br>at 25 KV                             |          |
| 12                       | Karnataka                                      | 01.04.2016               | 453.68<br>417.64<br>F         | 667.27<br>615.86<br>F         | 731.19<br>672.46<br>F           | 881.57<br>821.50<br>F           | 895.70<br>835.63<br>F             | 898.06<br>837.99<br>F             | 898.53<br>838.46<br>F             | 0.00                               | 0.00                              | 0.00                               | 658.55<br>617.92<br>F                 | 763.52<br>720.48<br>F                  | 754.49<br>738.32<br>F                                    | 765.38<br>747.03<br>F                         | 763.87<br>745.40<br>F         | 737.29   |          |
| 13                       | Kerala   | 16.08.2014               | 350.00                        | 691.00                        | 845.00                          | 854.00                          | 1063.00                           | 1103.00                           | 1103.00                           | 222.98                             | 222.98                            | 222.98                             | 638.67                                | 655.33                                 | 606.10   | 606.10  | 606.10                        | 618.89   | at 110KV |
| 14                       | Madhya Pradesh                                 | 01.04.2016               | 523.20<br>495.95<br>R         | 803.78<br>792.66<br>R         | 858.97<br>847.80<br>R           | 739.10<br>716.30<br>R           | 744.29<br>721.33<br>R             | 879.24<br>860.28<br>R             | 879.44<br>860.28<br>R             | 407.50                             | 445.25                            | 465.13                             | 855.65<br>775.72<br>R                 | 855.65<br>752.46<br>R                  | 788.06   | 788.06  | 723.61                        | 742.22<br>132/220KV                            |          |
| 15                       | Maharashtra                                    | 01.11.2016               | 553.45                        | 965.54                        | 1271.14                         | 1019.93                         | 1227.62                           | 1360.67                           | 1360.65                           | 304.50                             | 304.50                            | 304.50                             | 852.92                                | 978.00                                 | 943.13<br>1019.64<br>B                                   | 943.13<br>1019.64<br>C                        | 863.34                        | 781.56   |          |
| 16                       | Manipur  | 01.04.2016               | 380.00                        | 470.00                        | 506.00                          | 556.67                          | 626.00                            | -                                 | -                                 | 347.38                             | 347.38                            | 347.38                             | 368.33                                | 504.07                                 | 525.37   | 525.37  | -                             | -  |          |
| 17                       | Meghalaya                                      | 01.04.2016               | 370.00                        | 477.50                        | 524.00                          | 699.33                          | 738.00                            | 744.44                            | 745.73                            | 278.38                             | 278.38                            | 278.38                             | 616.67                                | 616.67                                 | 640.35   | 640.35  | 616.21                        | -  |          |
| 18                       | Mizoram  | 01.04.2016               | 315.00                        | 450.00                        | 489.00                          | 500.00                          | 574.67                            | 587.11                            | 589.60                            | 198.06                             | 198.06                            | 198.06                             | 469.67                                | 484.60                                 | 447.46   | 447.46  | -                             | -  |          |
| 19                       | Nagaland                                       | 01.04.2016               | 434.00                        | 566.00                        | 616.40                          | 758.00                          | 847.60                            | 862.53                            | 865.52                            | 300.00                             | 300.00                            | 300.00                             | 566.67                                | 623.33                                 | 688.89   | 688.89  | -                             | -  |          |
| 20                       | Odisha   | 01.04.2016               | 369.20                        | 487.50                        | 556.92                          | 627.47                          | 707.89                            | 721.30                            | 723.98                            | 153.00                             | 153.00                            | 153.00                             | 588.00                                | 600.00                                 | 649.64   | 649.63  | 627.04                        | 655.88<br>640.90<br>at 25/33KV<br>at 132KV     |          |
| 21                       | Punjab   | 01.04.2016               | 510.76                        | 659.92                        | 708.74                          | 754.46                          | 761.09                            | 762.20                            | 762.42                            | 517.54<br>0.00<br>WS<br>S          | 517.54<br>0.00<br>WS<br>S         | 517.54<br>0.00<br>WS<br>S          | 618.11                                | 681.39                                 | 681.39   | 681.39  | 681.39                        | 740.15<br>at 132KV                             |          |
| 22                       | Rajasthan                                      | 01.09.2016               | 737.50                        | 729.38                        | 751.25                          | 953.33                          | 985.67                            | 1078.19                           | 1081.21                           | 486.50                             | 486.50                            | 486.50                             | 768.09                                | 832.02                                 | 841.93   | -   | 818.62                        | 832.78   |          |
| 23                       | Sikkim   | 01.04.2016               | 172.00                        | 362.75                        | 440.90                          | 533.50                          | 611.97                            | 627.32                            | 630.39                            | -                                  | -                                 | -                                  | 619.00                                | 476.86                                 | 619.73   | 619.73  | -                             | -  |          |
| 24                       | Tamil Nadu                                     | 23.05.2016               | 85.00                         | 470.00                        | 584.00                          | 836.50                          | 932.58                            | 939.69                            | 941.12                            | 0.00                               | 0.00                              | 0.00                               | 691.25                                | 691.25                                 | 713.36   | 770.48  | 713.36                        | 718.33   |          |
| 25                       | Telangana                                      | 01.07.2016               | 238.50                        | 668.50                        | 821.00                          | 891.00                          | 975.00                            | 995.67                            | 999.80                            | 79.38                              | 74.88                             | 73.38                              | 721.00                                | 731.00                                 | 800.11   | 799.77  | 747.12                        | -  |          |
| 26                       | Tripura  | 01.04.2014               | 521.50                        | 755.00                        | 755.00                          | 691.50                          | 768.33                            | 768.33                            | 768.33                            | 366.19                             | 366.19                            | 477.38                             | 740.00                                | 764.00                                 | -  | -   | -                             | -  |          |
| 27                       | Uttar Pradesh                                  | 01.08.2016               | 535.00                        | 585.63                        | 657.25                          | 827.50                          | 1004.83                           | 1027.72                           | 1032.30                           | 565.00                             | 565.00                            | 565.00                             | 925.83                                | 950.83                                 | 857.00   | 857.00  | 819.02                        | 1052.94<br>132KV & above                       |          |
| 28                       | Uttarakhand                                    | 01.04.2016               | 300.00                        | 386.25                        | 440.00                          | 561.67                          | 561.67                            | 646.37                            | 646.37                            | 170.00                             | 170.00                            | 170.00                             | 511.67                                | 557.25                                 | 588.89   | 588.89  | 588.89                        | 597.06   |          |
| 29                       | West Bengal                                    | 01.04.2016               | 630.89<br>617.07<br>R         | 843.94<br>830.79<br>R         | 941.92<br>936.66<br>R           | 880.79<br>880.06<br>R           | 1027.09<br>1026.94<br>R           | 1044.80<br>1044.75<br>R           | 1048.34<br>1048.31<br>R           | 487.43                             | 487.43                            | 487.43                             | 758.88<br>739.06<br>R                 | 895.17<br>867.79<br>R                  | 937.72   | 937.72  | 933.12                        | 913.00<br>at 25KV<br>at 132KV                  |          |
| <b>Union Territories</b> |  |                          |                               |                               |                                 |                                 |                                   |                                   |                                   |                                    |                                   |                                    |                                       |  |  |   |                               |  |          |
| 30                       | A & N Islands                                  | 01.04.2016               | 200.00                        | 456.25                        | 542.50                          | 678.33                          | 840.33                            | 880.11                            | 888.07                            | 150.00                             | 150.00                            | 150.00                             | 591.67                                | 618.33                                 | -  | -   | -                             | -  |          |
| 31                       | Chandigarh                                     | 01.04.2016               | 274.00                        | 414.63                        | 477.25                          | 587.67                          | 614.00                            | 619.78                            | 620.93                            | 290.00                             | 290.00                            | 290.00                             | 554.33                                | 612.67                                 | 598.83   | 598.83  | 598.83                        | -  |          |
| 32                       | Dadra & Nagar Haveli                           | 01.04.2016               | 150.00                        | 192.50                        | 230.00                          | 308.33                          | 329.67                            | 333.22                            | 333.93                            | 70.00                              | 70.00                             | 70.00                              | 367.34                                | 367.34                                 | 409.76   | 409.76  | -                             | -  |          |
| 33                       | Daman & Diu                                    | 01.04.2016               | 150.00                        | 192.50                        | 230.00                          | 331.67                          | 358.33                            | 362.78                            | 363.67                            | 70.00                              | 70.00                             | 70.00                              | 372.34                                | 372.34                                 | 496.64   | 496.64  | -                             | -  |          |
| 34                       | (BYPL/BRPL/NDPL)                               | 01.10.2015               | 462.00                        | 548.63                        | 711.90                          | 994.00                          | 994.00                            | 1081.11                           | 1081.11                           | 296.58                             | 296.58                            | 296.58                             | 943.25                                | 991.67                                 | 896.63   | 896.63  | 875.05                        | 841.22   |          |
| 35                       | Delhi (NDMC)                                   | 01.10.2015               | 362.25                        | 433.13                        | 579.60                          | 850.50                          | 850.50                            | 1068.53                           | 1068.53                           | -                                  | -                                 | -                                  | 893.53                                | 893.53                                 | 918.49   | 918.49  | 896.41                        | 911.65<br>at 33KV                              |          |
| 36                       | Lakshadweep                                    | 01.04.2016               | 140.00                        | 356.25                        | 484.50                          | 668.33                          | 749.67                            | 763.22                            | 765.93                            | -                                  | -                                 | -                                  | 550.93                                | 550.93                                 | 725.37   | 725.37  | -                             | -  |          |
| 37                       | Puducherry                                     | 01.04.2016               | 150.00                        | 283.75                        | 389.50                          | 601.21                          | 645.24                            | 652.58                            | 654.05                            | -                                  | -                                 | -                                  | 541.23                                | 536.65                                 | 614.67   | -   | 591.31                        | -  |          |
| <b>Private Companies</b> |  |                          |                               |                               |                                 |                                 |                                   |                                   |                                   |                                    |                                   |                                    |                                       |  |  |   |                               |  |          |
| 38                       | CESE Ltd. (Kolkata)                            | 28.10.2016               | 584.32                        | 820.55                        | 927.94                          | 850.72                          | 1019.47                           | 1041.15                           | 1045.49                           | -                                  | -                                 | -                                  | 750.00                                | 889.17                                 | 853.77   | 853.77  | 826.17                        | 746.33   |          |
| 39                       | DPSC Ltd. (West Bengal)                        | 17.02.2017               | 550.21                        | 707.63                        | 746.15                          | 726.83                          | 807.22                            | 809.86                            | 809.86                            | 252.95                             | 252.95                            | 252.95                             | 672.29                                | 793.75                                 | 738.77   | 738.77  | 512.22                        | 790.33   |          |
| 40                       | Durgapur Projects Ltd. (West Bengal)           | 01.04.2016               | 425.42                        | 530.04                        | 552.36                          | 549.29                          | 599.90                            | 604.17                            | 605.02                            | 179.29                             | 179.29                            | 179.29                             | 533.38                                | 588.72                                 | 592.45   | 592.45  | 574.05                        | 647.78<br>642.78<br>at 25KV<br>at 132KV        |          |
| 41                       | D.V.C. (A) Jharkhand Area (B) West Bengal Area | 01.09.2014<br>01.04.2016 | -<br>-                        | -<br>-                        | -<br>-                          | -<br>-                          | -<br>-                            | -<br>-                            | -<br>-                            | -<br>-                             | -<br>-                            | -<br>-                             | -<br>-                                | -<br>-                                 | -<br>-   | -<br>-  | 520.13<br>616.56              | 481.18<br>645.88<br>at 132KV                   |          |
| 42                       | Mumbai (Reliance Energy)                       | 01.10.2016               | 470.76                        | 731.76                        | 1028.14                         | 1228.39                         | 1267.11                           | 1370.01                           | 1370.01                           | -                                  | -                                 | -                                  | 1055.83                               | 1119.63                                | 1073.70  | 1073.70                                       | -                             | -  |          |
| 43                       | Mumbai (TATA'S)                                | 01.10.2016               | 492.80                        | 851.82                        | 1095.54                         | 1284.05                         | 1193.71                           | 1463.18                           | 1463.18                           | 481.00                             | 481.00                            | 481.00                             | 1024.86                               | 1234.40                                | 1185.18  | 1185.18                                       | -                             | at 100/33/22/11/6.6kV                          |          |
| 44                       | Torrent Power Ltd. (Ahmedabad)                 | 01.04.2016               | 410.44                        | 700.73                        | 1090.55                         | 1325.19                         | 1234.85                           | 1205.45                           | 1205.45                           | -                                  | -                                 | -                                  | 1035.79                               | 1145.86                                | 1069.33  | 1069.33                                       | -                             | 849.78<br>33/22kV                              |          |
| 45                       | Torrent Power Ltd. (Surat)                     | 01.04.2016               | 437.00                        | 503.13                        | 543.95                          | 620.83                          | 637.50                            | 733.33                            | 733.33                            | 330.00                             | 330.00                            | 330.00                             | 561.00                                | 645.33                                 | 514.14   | 514.14  | -                             | -  |          |
| 46                       | Torrent Power Ltd. (Surat)                     | 01.04.2016               | 422.63                        | 508.16                        | 556.31                          | 602.08                          | 602.08                            | 749.77                            | 749.77                            | 70.00                              | 70.00                             | 70.00                              | 529.83                                | 659.80                                 | 623.65   | 623.64  | -                             | -  |          |

B : Continuous Supply Areas C : Non-Continuous Supply Areas D : Bangalore, Davangere & Other City Municipal Corp. F : Areas under Village Panchayats U : Urban R : Rural O : Other Areas  
S : With Govt. Subsidy WS : Without Govt. Subsidy

\* : With Demand Side Management Measures - for dry land farmers(Connection>3 Nos) and wet land farmers(Holding>2.5 Acres) and

Without Demand Side Management Measures - for dry land farmers(Connection<=3 Nos) and wet land farmers(Holding<=2.5 Acres)

^ TOD tariff from 23:00 hrs to 06:00 hrs for DPSC Ltd. & Durgapur Projects Ltd. respectively in West Bengal.

Tariffs notified have varying parameters for various categories of consumers. The above comparison is based on certain assumed loads and electricity consumption levels in a month.



## ANNEXURE-10A

Item 10.2

**All India Sector wise/Organisation wise Target, Actual Generation & PLF (%) for the year 2017-18**

| Fuel, Sector/Organisation   | Target (MU)   | Actual (MU)      | PLF (%)      |
|-----------------------------|---------------|------------------|--------------|
| <b>THERMAL</b>              |               |                  |              |
| <b>CENTRAL SECTOR</b>       |               |                  |              |
| APCPL                       | 5500          | 7734.53          | 58.86        |
| BRBCL                       | 2500          | 1060.94          | 29.16        |
| DVC                         | 34475         | 35694.21         | 55.19        |
| K.B.U.N.L                   | 1500          | 1750.61          | 35.1         |
| MUNPL                       | 0             | 8.22             | *            |
| NEEPCO.                     | 2710          | 2958.05          | **           |
| NLC                         | 20848         | 20548.15         | 72.4         |
| NPGCPL                      | 100           | 0                | 0            |
| NSPCL                       | 3746          | 3877.77          | 88.53        |
| NTECL                       | 9201          | 7167.72          | 54.55        |
| NTPC Ltd.                   | 242571        | 261362.83        | 78.87        |
| NTPL                        | 6570          | 5412.83          | 61.79        |
| ONGC                        | 4500          | 4053.16          | **           |
| PVUNL                       | 1280          | 0                | 0            |
| RGPPPL                      | 4248          | 4501.03          | **           |
| <b>TOTAL CENTRAL SECTOR</b> | <b>339749</b> | <b>356130.05</b> | <b>72.38</b> |
| <b>STATE SECTOR</b>         |               |                  |              |
| HPGCL                       | 10200         | 10708.59         | 44.94        |
| IPGPCL                      | 700           | 578.8            | **           |
| JKSPDC                      | 0             | 0                | **           |
| PRAGATI                     | 4198          | 4912.93          | **           |
| PSPCL                       | 8380          | 5520.19          | 24.05        |
| RRVUNL                      | 32188         | 28195.43         | 55.25        |
| UPRVUNL                     | 34399         | 31548.71         | 62.04        |
| BECL                        | 200           | 480.15           | *            |
| CSPGCL                      | 19115         | 20834.05         | 72.51        |
| GMDCL                       | 1480          | 1357.12          | 61.97        |
| GPPCL                       | 500           | 168.06           | **           |
| GSECL                       | 15197         | 23044.31         | 60.89        |
| GSEGL                       | 345           | 195.81           | **           |
| MAHAGENCO                   | 53201         | 49271.57         | 51.35        |
| MPPGCL                      | 18500         | 18246.17         | 51.48        |
| APEPDCL                     | 722           | 1065.12          | **           |
| APGENCO                     | 20000         | 17746.25         | 71.59        |
| APPDCL                      | 9200          | 4939.92          | 35.24        |
| KPCL                        | 20880         | 14855.66         | 58.88        |
| KSEB                        | 54            | 1.92             | #            |

|                                  |               |                  |              |
|----------------------------------|---------------|------------------|--------------|
| P&ED, Pudu.                      | 223           | 226.45           | #            |
| RPCL                             | 4000          | 997.45           | *            |
| SCCL                             | 5500          | 9575.16          | 91.09        |
| TNGDCL                           | 27516         | 24785.15         | 60.43        |
| TSGENCO                          | 18437         | 18869.41         | 74.73        |
| A&N ADM                          | 200           | 258.79           | #            |
| BSEB                             | 400           | 39.48            | 2.14         |
| DPL                              | 2400          | 2524.46          | 43.66        |
| OPGC                             | 3050          | 2840.33          | 77.2         |
| TVNL                             | 2200          | 1933.31          | 52.55        |
| WBPDC                            | 24300         | 23445.98         | 59.44        |
| APGPCL                           | 1215          | 983.89           | **           |
| ED, Manipur                      | 0             | 0                | #            |
| TSECL                            | 594           | 586.31           | **           |
| <b>TOTAL STATE SECTOR</b>        | <b>339494</b> | <b>320736.93</b> | <b>56.9</b>  |
| <b>PVT. SEC. UTILITY</b>         |               |                  |              |
| CESC                             | 6050          | 6337.15          | 64.3         |
| RIL (DAHANU)                     | 3800          | 3534.27          | 80.69        |
| TATA PCL                         | 6384          | 6294.16          | 45.12        |
| TOR. POW. (UNOSUGEN)             | 2312          | 2638.78          | 71.38        |
| <b>TOTAL PVT. UTILITY SECTOR</b> | <b>18546</b>  | <b>18804.36</b>  | <b>60.42</b> |
| <b>PVT. SEC. IPP</b>             |               |                  |              |
| ABAN POWR                        | 491           | 480.13           | **           |
| ACB                              | 2000          | 2174.11          | 81.05        |
| ADHUNIK                          | 3400          | 2909.92          | 61.52        |
| AMNEPL                           | 0             | 0                | 0            |
| APGPCL                           | 600           | 1192.04          | **           |
| APL                              | 56000         | 44571.34         | 55.07        |
| BALCO                            | 3000          | 2313.07          | 44.01        |
| BELLARY                          | 0             | 0                | #            |
| BEPL                             | 2250          | 924.4            | 23.45        |
| BLAPPL                           | 250           | 87.88            | 22.29        |
| BSES(C)                          | 0             | 42.65            | **           |
| BSES(P)                          | 0             | 0                | **           |
| CEPL                             | 4500          | 3906.24          | 37.16        |
| CGPL                             | 26620         | 26514.87         | 75.67        |
| CIPL                             | 300           | 434.57           | **           |
| DBPCL                            | 6500          | 6536.81          | 62.18        |
| DIPL                             | 1500          | 2393.27          | 45.53        |
| EPGL                             | 5600          | 2682.42          | 25.52        |
| ESSAR                            | 0             | 0                | **           |
| ESSARPMPL                        | 3000          | 2918.23          | 55.52        |
| GAUTAMI                          | 0             | 0                | **           |
| GCEL                             | 1600          | 1367.92          | 6.14         |
| GEPL                             | 0             | 0                | 0            |
| GIPCL                            | 3747          | 3307.28          | 74.7         |
| GIPL                             | 400           | 560.66           | **           |
| GMR ENERG                        | 9500          | 9330.09          | 64.55        |

|                |       |          |       |
|----------------|-------|----------|-------|
| GPGSL (GVK)    | 1500  | 1541     | 32.58 |
| GREL           | 625   | 0        | **    |
| GVKP&IL        | 100   | 0        | **    |
| HEL            | 4200  | 4525.89  | 86.11 |
| HNPC           | 4100  | 3326.14  | 36.51 |
| HYEL           | 0     | 27.48    | *     |
| IBPIL          | 0     | 0        | 0     |
| IEPL           | 0     | 80.51    | 3.4   |
| ITPCL          | 3590  | 5724.29  | 54.45 |
| JHAPL          | 1500  | 1666.87  | 31.71 |
| JITPL          | 6600  | 3657.42  | 34.79 |
| JPL            | 8870  | 10905.76 | 42.29 |
| JPPVL          | 9500  | 10154.21 | 63.69 |
| JSWEL          | 11200 | 10744.42 | 59.54 |
| JhPL(HR)       | 4000  | 7325.47  | 63.35 |
| KONA           | 0     | 0        | **    |
| KONDAPALI      | 2200  | 660.7    | **    |
| KWPCL          | 2500  | 572.13   | 10.89 |
| LANCO          | 4100  | 4139.42  | 78.76 |
| LAPPL          | 8000  | 8397.1   | 79.88 |
| LPGCL          | 8001  | 8565.92  | 49.39 |
| LVS POWER      | 0     | 0        | #     |
| MADURAI P      | 0     | 0        | **    |
| MBPMPL         | 4500  | 6225.05  | 59.22 |
| MCCPL          | 1500  | 2223.84  | 84.62 |
| MEL            | 1200  | 587.3    | 22.35 |
| MPL            | 7376  | 7345.34  | 79.86 |
| NDPL           | 0     | 0        | **    |
| NPL            | 8400  | 9110.04  | 74.28 |
| PENNA          | 300   | 371.45   | **    |
| PGPL           | 500   | 0        | **    |
| PPGCL (Jaypee) | 4500  | 5635.06  | 33.74 |
| PPNPGCL        | 200   | 0        | **    |
| RELIANCE       | 0     | 0        | **    |
| RKMPPL         | 1833  | 1438.78  | 22.01 |
| RPSCCL         | 7200  | 7718.8   | 73.43 |
| RWPL (JSW)     | 6800  | 6855.95  | 72.47 |
| RattanIndia    | 2500  | 4773.07  | 33.62 |
| SAMALPATI      | 0     | 0        | #     |
| SCPL           | 400   | 743.06   | 73.2  |
| SEIL           | 8200  | 9833.58  | 85.04 |
| SEL            | 3000  | 1074.47  | 12.27 |
| SEPL           | 2000  | 25.02    | 0.48  |
| SGPL           | 3800  | 8970.59  | 77.58 |
| SKS            | 200   | 673.97   | *     |
| SPGL           | 1000  | 572.4    | **    |
| SPL            | 30000 | 31792.52 | 91.65 |
| SPPL           |       | 4.74     | *     |
| ST-CMSECP      | 1500  | 1025.27  | 46.82 |

|                               |                |                  |              |
|-------------------------------|----------------|------------------|--------------|
| SVPPPL                        | 300            | 27.13            | 4.92         |
| SrEPL                         | 400            | 1062.33          | **           |
| TATA PCL                      | 1666           | 1618.38          | 76.98        |
| TOR. POW. (SUGEN)             | 4200           | 6522.62          | **           |
| TOR. POW. (UNOSUGEN)          | 0              | 0                | **           |
| TRNE                          | 1900           | 2741.13          | 54.39        |
| TSPL                          | 6600           | 8556.82          | 49.33        |
| UPCL                          | 8000           | 6181.32          | 58.8         |
| VASAVI                        | 0              | 0                | #            |
| VEMAGIRI                      | 400            | 0                | **           |
| VESPL                         | 0              | 0                | 0            |
| VIP                           | 3800           | 3306.31          | 62.91        |
| VVL                           | 0              | 0                | 0            |
| WPCL                          | 7500           | 6936.68          | 44.21        |
| <b>Total PVT. SEC. IPP</b>    | <b>343519</b>  | <b>340615.65</b> | <b>55.09</b> |
| <b>PVT. SEC. IMP</b>          |                |                  |              |
| GIPCL                         | 180            | 196.18           | -            |
| ICCL                          | 290            | 296.5            | -            |
| NALCO                         | 250            | 279.43           | -            |
| <b>Total PVT. SEC. IMP</b>    | <b>720</b>     | <b>772.11</b>    |              |
| <b>Total IPP &amp; Import</b> | <b>344239</b>  | <b>341387.76</b> | <b>55.09</b> |
| <b>Total PVT. Sector</b>      | <b>362785</b>  | <b>360192.12</b> | <b>55.34</b> |
| <b>THERMAL Total</b>          | <b>1042028</b> | <b>1037059.1</b> | <b>60.72</b> |
| <b>NUCLEAR</b>                |                |                  |              |
| <b>CENTRAL</b>                |                |                  |              |
| DAE                           | 0              | 0                | 0            |
| NPCIL                         | 40972          | 38346.12         | 65.53        |
| <b>CENTRAL Total</b>          | <b>40972</b>   | <b>38346.12</b>  | <b>64.56</b> |
| <b>NUCLEAR Total</b>          | <b>40972</b>   | <b>38346.12</b>  | <b>64.56</b> |
| <b>HYDRO</b>                  |                |                  |              |
| <b>CENTRAL</b>                |                |                  |              |
| BBMB                          | 9360           | 10864.14         |              |
| DVC                           | 235            | 256.35           |              |
| NEEPCO.                       | 3492           | 3203.1           |              |
| NHDC                          | 3100           | 1325.36          |              |
| NHPC                          | 23046          | 22549.52         |              |
| NTPC Ltd.                     | 3055           | 3313.62          |              |
| SJVNL                         | 8625           | 9222.73          |              |
| THDC                          | 4115           | 4301.27          |              |
| <b>CENTRAL Total</b>          | <b>55028</b>   | <b>55036.09</b>  |              |
| <b>STATE</b>                  |                |                  |              |
| HPPCL                         | 568            | 332.12           |              |
| HPSEB                         | 1647           | 1590.86          |              |
| JKSPDC                        | 4599           | 5136.89          |              |
| PSPCL                         | 4021           | 4230.51          |              |
| RRVUNL                        | 720            | 819.53           |              |
| UJVNL                         | 4688           | 4526             |              |
| UPJVNL                        | 1170           | 1486.69          |              |
| CSPGCL                        | 250            | 178.07           |              |

|                           |               |                 |  |
|---------------------------|---------------|-----------------|--|
| GSECL                     | 857           | 612.45          |  |
| MAHAGENCO                 | 4296          | 3143.16         |  |
| MPPGCL                    | 2625          | 1420.98         |  |
| SSNNL                     | 4460          | 939.47          |  |
| APGENCO                   | 2400          | 1760.7          |  |
| KPCL                      | 11687         | 7008.65         |  |
| KSEB                      | 6221          | 5199.26         |  |
| TNGDCL                    | 4415          | 2919.6          |  |
| TSGENCO                   | 4440          | 2601.75         |  |
| JSEB                      | 150           | 190.38          |  |
| OHPC                      | 5672          | 5555.29         |  |
| TUL                       | 5214          | 4429.33         |  |
| WBSEDCL                   | 1596          | 1282.02         |  |
| APGPCL                    | 390           | 484.98          |  |
| MeECL                     | 919           | 1140.26         |  |
| <b>STATE Total</b>        | <b>73005</b>  | <b>56988.95</b> |  |
| <b>PVT SEC. UTL</b>       |               |                 |  |
| <b>HYDRO</b>              |               |                 |  |
| BHIRA HPS                 | 883           | 341.17          |  |
| BHIRA PSS HPS             | 0             | 551.13          |  |
| BHIVPURI HPS              | 297           | 307.2           |  |
| KHOPOLI HPS               | 270           | 316.38          |  |
| <b>TOTAL PVT SEC. UTL</b> | <b>1450</b>   | <b>1515.88</b>  |  |
| <b>PVT SEC. IPP</b>       |               |                 |  |
| <b>HYDRO</b>              |               |                 |  |
| ALLAIN DUHANGAN HPS       | 700           | 683.01          |  |
| BASPA HPS                 | 1250          | 1336.65         |  |
| BHANDARDHARA HPS          |               |                 |  |
| ST-                       | 37            | 42.55           |  |
| BUDHIL HPS                | 282           | 317.63          |  |
| CHANJU-I HPS              |               | 79.42           |  |
| CHUZACHEN HPS             | 495           | 444.79          |  |
| DIKCHU HPS                |               | 370.1           |  |
| JORETHANG LOOP            | 459           | 406.01          |  |
| KARCHAM WANGTOO HPS       |               |                 |  |
|                           | 4250          | 4569.93         |  |
| MALANA HPS                | 344           | 346.29          |  |
| MALANA-II HPS             | 360           | 368.89          |  |
| SRINAGAR HPS              | 1340          | 1382.54         |  |
| TASHIDING HPS             | 400           | 73.07           |  |
| TIDONG HPS                | 200           | 0               |  |
| VISHNU PRAYAG HPS         | 1800          | 2160.9          |  |
| <b>TOTAL PVT SEC. IPP</b> | <b>11917</b>  | <b>12581.78</b> |  |
| <b>TOTAL PVT. SEC.</b>    | <b>13367</b>  | <b>14097.66</b> |  |
| <b>HYDRO Total</b>        | <b>141400</b> | <b>126122.7</b> |  |

Based on March 2018 Final report  
Generation from conventional sources (Thermal/Hydro/Nuclear) with station capacity > 25 MW

- **PLF is calculated for Coal & Lignite based power station only.**
- **\* Unit Not Stabilized**
- **\*\* Gas Based Station**
- **# diesel Based Station**

**ALL INDIA INSTALLED CAPACITY (IN MW) OF POWER STATIONS  
LOCATED IN THE REGIONS OF MAIN LAND AND ISLANDS**

**(As on 31.03.2018)**

**(UTILITIES)**

| Region                     | Ownership/<br>Sector | Mode wise breakup |                 |               |                 |                |                 |                 | Grand Total      |
|----------------------------|----------------------|-------------------|-----------------|---------------|-----------------|----------------|-----------------|-----------------|------------------|
|                            |                      | Thermal           |                 |               |                 | Nuclear        | Hydro           | RES *<br>(MNRE) |                  |
|                            |                      | Coal              | Gas             | Diesel        | Total           |                |                 |                 |                  |
| <b>Northern<br/>Region</b> | State                | 16888.00          | 2879.20         | 0.00          | 19767.20        | 0.00           | 8643.55         | 689.56          | 29100.31         |
|                            | Private              | 22760.83          | 558.00          | 0.00          | 23318.83        | 0.00           | 2514.00         | 11854.66        | 37687.49         |
|                            | Central              | 13290.37          | 2344.06         | 0.00          | 15634.43        | 1620.00        | 8596.22         | 329.00          | 26179.65         |
|                            | <b>Sub Total</b>     | <b>52939.20</b>   | <b>5781.26</b>  | <b>0.00</b>   | <b>58720.46</b> | <b>1620.00</b> | <b>19753.77</b> | <b>12873.22</b> | <b>92967.45</b>  |
| <b>Western<br/>Region</b>  | State                | 21280.00          | 2849.82         | 0.00          | 24129.82        | 0.00           | 5446.50         | 311.19          | 29887.51         |
|                            | Private              | 34285.67          | 4676.00         | 0.00          | 38961.67        | 0.00           | 481.00          | 19473.89        | 58916.56         |
|                            | Central              | 15042.95          | 3280.67         | 0.00          | 18323.62        | 1840.00        | 1520.00         | 661.30          | 22344.92         |
|                            | <b>Sub Total</b>     | <b>70608.62</b>   | <b>10806.49</b> | <b>0.00</b>   | <b>81415.11</b> | <b>1840.00</b> | <b>7447.50</b>  | <b>20446.38</b> | <b>111148.99</b> |
| <b>Southern<br/>Region</b> | State                | 19432.50          | 791.98          | 287.88        | 20512.36        | 0.00           | 11808.03        | 518.02          | 32838.41         |
|                            | Private              | 12124.50          | 5322.10         | 473.70        | 17920.30        | 0.00           | 0.00            | 33359.36        | 51279.66         |
|                            | Central              | 14225.02          | 359.58          | 0.00          | 14584.60        | 3320.00        | 0.00            | 491.90          | 18396.50         |
|                            | <b>Sub Total</b>     | <b>45782.02</b>   | <b>6473.66</b>  | <b>761.58</b> | <b>53017.26</b> | <b>3320.00</b> | <b>11808.03</b> | <b>34369.28</b> | <b>102514.57</b> |
| <b>Eastern<br/>Region</b>  | State                | 7070.00           | 100.00          | 0.00          | 7170.00         | 0.00           | 3537.92         | 225.11          | 10933.03         |
|                            | Private              | 6375.00           | 0.00            | 0.00          | 6375.00         | 0.00           | 399.00          | 803.29          | 7577.29          |
|                            | Central              | 13876.64          | 0.00            | 0.00          | 13876.64        | 0.00           | 1005.20         | 10.00           | 14891.84         |

|                             |                  |                  |                 |               |                  |                |                 |                 |                  |
|-----------------------------|------------------|------------------|-----------------|---------------|------------------|----------------|-----------------|-----------------|------------------|
|                             | <b>Sub Total</b> | <b>27321.64</b>  | <b>100.00</b>   | <b>0.00</b>   | <b>27421.64</b>  | <b>0.00</b>    | <b>4942.12</b>  | <b>1038.40</b>  | <b>33402.16</b>  |
| <b>North Eastern Region</b> | State            | 0.00             | 457.95          | 36.00         | 493.95           | 0.00           | 422.00          | 254.25          | 1170.20          |
|                             | Private          | 0.00             | 24.50           | 0.00          | 24.50            | 0.00           | 0.00            | 23.31           | 47.81            |
|                             | Central          | 520.02           | 1253.60         | 0.00          | 1773.62          | 0.00           | 920.00          | 5.00            | 2698.62          |
|                             | <b>Sub Total</b> | <b>520.02</b>    | <b>1736.05</b>  | <b>36.00</b>  | <b>2292.07</b>   | <b>0.00</b>    | <b>1342.00</b>  | <b>282.56</b>   | <b>3916.63</b>   |
| <b>Islands</b>              | State            | 0.00             | 0.00            | 40.05         | 40.05            | 0.00           | 0.00            | 5.25            | 45.30            |
|                             | Private          | 0.00             | 0.00            | 0.00          | 0.00             | 0.00           | 0.00            | 2.21            | 2.21             |
|                             | Central          | 0.00             | 0.00            | 0.00          | 0.00             | 0.00           | 0.00            | 5.10            | 5.10             |
|                             | <b>Sub Total</b> | <b>0.00</b>      | <b>0.00</b>     | <b>40.05</b>  | <b>40.05</b>     | <b>0.00</b>    | <b>0.00</b>     | <b>12.56</b>    | <b>52.61</b>     |
| <b>ALL INDIA</b>            | State            | 64670.50         | 7078.95         | 363.93        | 72113.38         | 0.00           | 29858.00        | 2003.37         | 103974.75        |
|                             | Private          | 75546.00         | 10580.60        | 473.70        | 86600.30         | 0.00           | 3394.00         | 65516.72        | 155511.02        |
|                             | Central          | 56955.00         | 7237.91         | 0.00          | 64192.91         | 6780.00        | 12041.42        | 1502.30         | 84516.63         |
|                             | <b>Total</b>     | <b>197171.50</b> | <b>24897.46</b> | <b>837.63</b> | <b>222906.59</b> | <b>6780.00</b> | <b>45293.42</b> | <b>69022.39</b> | <b>344002.39</b> |

Figures at decimal may not tally due to rounding off

**Abbreviation:-** SHP=Small Hydro Project ( $\leq 25$  MW), BP=Biomass Power, U&I=Urban & Industrial Waste Power, RES=Renewable Energy Sources

**Note :-** 1. RES include SHP, BP, U&I, Solar and Wind Energy. Installed capacity in respect of RES (MNRE) as on 31.03.2018

(As per latest information available with MNRE)

**\*Break up of RES all India as on 31.03.2018 is given below (in MW) :**

| Small Hydro Power | Wind Power      | Bio-Power       |                 | Solar Power     | Total Capacity  |
|-------------------|-----------------|-----------------|-----------------|-----------------|-----------------|
|                   |                 | BM Power/Cogen. | Waste to Energy |                 |                 |
| <b>4485.81</b>    | <b>34046.00</b> | <b>8700.80</b>  | <b>138.30</b>   | <b>21651.48</b> | <b>69022.39</b> |



|           |   |                |
|-----------|---|----------------|
| <b>A.</b> | <b>Capacity Added during March., 2018</b> | <b>3890 MW</b> |
|-----------|---|----------------|

1. U-1 of MEJA STPP (660 MW) has been commissioned and added to the Central Sector of NR states as per their allocation..
2. U-1 of LARA TPP (800 MW) has been commissioned and added to the Central Sector of WR states as per their allocation..
3. U-3 of KUDGI STPP (800 MW) has been commissioned and added to the Central Sector of SR states as per their allocation.
4. U-1,2&3 of KISHANGANGA HPS (3\*110=330 MW) has been commissioned and added to the Central Sector of NR states as per their tentative allocation.
5. U-6 of RAYALASEEMA TPS (600 MW) has been commissioned and added to the State Sector of Andhra Pradesh.
6. U-9 of BARAUNI TPS (250 MW) has been commissioned and added to the State Sector of Bihar.
7. U-2 of BINJKOTE TPP (300 MW) has been commissioned and added to the Private Sector of Chhattisgarh.
8. U-2 of Hiranmaye TPP (150 MW) has been commissioned and added to the Private Sector of West Bengal.

|           |   |               |
|-----------|---|---------------|
| <b>B.</b> | <b>Capacity Retired during March., 2018</b> | <b>210 MW</b> |
|-----------|---|---------------|

1. PANKI TPS U-3&4 (2\*105=210 MW) has been retired from the State Sector of Uttar Pradesh.

|           |                         |                     |             |
|-----------|-------------------------|---------------------|-------------|
| <b>C.</b> | <b>Capacity Derated</b> | <b>March., 2018</b> | <b>0 MW</b> |
|-----------|-------------------------|---------------------|-------------|

|           |   |              |                |
|-----------|---|--------------|----------------|
| <b>D.</b> | <b>Net Capacity Added during March., 2018</b> | <b>A-B-C</b> | <b>3680 MW</b> |
|-----------|---|--------------|----------------|

**INSTALLED CAPACITY (IN MW) OF POWER UTILITIES IN THE STATES/UTS LOCATED IN  
NORTHERN REGION**

**INCLUDING ALLOCATED SHARES IN JOINT & CENTRAL SECTOR UTILITIES**

**(As on 31.03.2018)**

| State                   | Ownership/<br>Sector | Modewise breakup |                |             |                |               |                      |               | Grand Total     |
|-------------------------|----------------------|------------------|----------------|-------------|----------------|---------------|----------------------|---------------|-----------------|
|                         |                      | Thermal          |                |             |                | Nuclear       | Hydro<br>(Renewable) | RES<br>(MNRE) |                 |
|                         |                      | Coal             | Gas            | Diesel      | Total          |               |                      |               |                 |
| <b>Delhi</b>            | State                | 135.00           | 1800.40        | 0.00        | 1935.40        | 0.00          | 0.00                 | 0.00          | 1935.40         |
|                         | Private              | 869.22           | 108.00         | 0.00        | 977.22         | 0.00          | 0.00                 | 121.57        | 1098.79         |
|                         | Central              | 3817.72          | 207.01         | 0.00        | 4024.73        | 102.83        | 723.09               | 0.00          | 4850.65         |
|                         | <b>Sub-Total</b>     | <b>4821.94</b>   | <b>2115.41</b> | <b>0.00</b> | <b>6937.35</b> | <b>102.83</b> | <b>723.09</b>        | <b>121.57</b> | <b>7884.84</b>  |
| <b>Haryana</b>          | State                | 2720.00          | 150.00         | 0.00        | 2870.00        | 0.00          | 1084.51              | 59.30         | 4013.81         |
|                         | Private              | 4080.78          | 0.00           | 0.00        | 4080.78        | 0.00          | 200.00               | 347.45        | 4628.23         |
|                         | Central              | 1294.72          | 535.61         | 0.00        | 1830.34        | 100.94        | 663.70181            | 5.00          | 2599.98         |
|                         | <b>Sub-Total</b>     | <b>8095.50</b>   | <b>685.61</b>  | <b>0.00</b> | <b>8781.12</b> | <b>100.94</b> | <b>1948.21</b>       | <b>411.75</b> | <b>11242.01</b> |
| <b>Himachal Pradesh</b> | State                | 0.00             | 0.00           | 0.00        | 0.00           | 0.00          | 694.60               | 256.61        | 951.21          |
|                         | Private              | 0.00             | 0.00           | 0.00        | 0.00           | 0.00          | 992.00               | 597.23        | 1589.23         |
|                         | Central              | 183.40           | 62.01          | 0.00        | 245.41         | 28.95         | 1223.88              | 0.00          | 1498.24         |
|                         | <b>Sub-Total</b>     | <b>183.40</b>    | <b>62.01</b>   | <b>0.00</b> | <b>245.41</b>  | <b>28.95</b>  | <b>2910.48</b>       | <b>853.84</b> | <b>4038.68</b>  |

|                            |                  |                 |               |             |                 |               |                |                |                 |
|----------------------------|------------------|-----------------|---------------|-------------|-----------------|---------------|----------------|----------------|-----------------|
| <b>Jammu &amp; Kashmir</b> | State            | 0.00            | 175.00        | 0.00        | 175.00          | 0.00          | 1230.00        | 129.03         | 1534.03         |
|                            | Private          | 0.00            | 0.00          | 0.00        | 0.00            | 0.00          | 0.00           | 51.36          | 51.36           |
|                            | Central          | 506.39          | 129.07        | 0.00        | 635.47          | 67.98         | 1139.48        | 0.00           | 1842.93         |
|                            | <b>Sub-Total</b> | <b>506.39</b>   | <b>304.07</b> | <b>0.00</b> | <b>810.47</b>   | <b>67.98</b>  | <b>2369.48</b> | <b>180.39</b>  | <b>3428.32</b>  |
| <b>Punjab</b>              | State            | 2620.00         | 150.00        | 0.00        | 2770.00         | 0.00          | 2570.23        | 127.80         | 5468.03         |
|                            | Private          | 5115.50         | 0.00          | 0.00        | 5115.50         | 0.00          | 288.00         | 1154.62        | 6558.12         |
|                            | Central          | 854.58          | 264.01        | 0.00        | 1118.59         | 196.81        | 923.42         | 0.00           | 2238.82         |
|                            | <b>Sub-Total</b> | <b>8590.08</b>  | <b>414.01</b> | <b>0.00</b> | <b>9004.09</b>  | <b>196.81</b> | <b>3781.65</b> | <b>1282.42</b> | <b>14264.97</b> |
| <b>Rajasthan</b>           | State            | 5850.00         | 603.80        | 0.00        | 6453.80         | 0.00          | 1087.96        | 23.85          | 7565.61         |
|                            | Private          | 3882.00         | 0.00          | 0.00        | 3882.00         | 0.00          | 104.00         | 6455.79        | 10441.79        |
|                            | Central          | 1206.25         | 221.10        | 0.00        | 1427.35         | 556.74        | 739.01         | 294.00         | 3017.10         |
|                            | <b>Sub-Total</b> | <b>10938.25</b> | <b>824.90</b> | <b>0.00</b> | <b>11763.15</b> | <b>556.74</b> | <b>1930.97</b> | <b>6773.64</b> | <b>21024.50</b> |
| <b>Uttar Pradesh</b>       | State            | 5563.00         | 0.00          | 0.00        | 5563.00         | 0.00          | 724.10         | 25.10          | 6312.20         |
|                            | Private          | 8714.33         | 0.00          | 0.00        | 8714.33         | 0.00          | 842.00         | 2621.91        | 12178.24        |
|                            | Central          | 3796.39         | 549.49        | 0.00        | 4345.88         | 289.48        | 1854.93        | 30.00          | 6520.29         |
|                            | <b>Sub-Total</b> | <b>18073.72</b> | <b>549.49</b> | <b>0.00</b> | <b>18623.21</b> | <b>289.48</b> | <b>3421.03</b> | <b>2677.01</b> | <b>25010.73</b> |
| <b>Uttarakhand</b>         | State            | 0.00            | 0.00          | 0.00        | 0.00            | 0.00          | 1252.15        | 67.87          | 1320.02         |
|                            | Private          | 99.00           | 450.00        | 0.00        | 549.00          | 0.00          | 88.00          | 479.53         | 1116.53         |
|                            | Central          | 343.24          | 69.66         | 0.00        | 412.90          | 31.24         | 475.54         | 0.00           | 919.68          |
|                            | <b>Sub-Total</b> | <b>442.24</b>   | <b>519.66</b> | <b>0.00</b> | <b>961.90</b>   | <b>31.24</b>  | <b>1815.69</b> | <b>547.40</b>  | <b>3356.23</b>  |
| <b>Chandigarh</b>          | State            | 0.00            | 0.00          | 0.00        | 0.00            | 0.00          | 0.00           | 0.00           | 0.00            |
|                            | Private          | 0.00            | 0.00          | 0.00        | 0.00            | 0.00          | 0.00           | 25.20          | 25.20           |
|                            | Central          | 38.15           | 15.03         | 0.00        | 53.17           | 8.01          | 101.71         | 0.00           | 162.89          |
|                            | <b>Sub-Total</b> | <b>38.15</b>    | <b>15.03</b>  | <b>0.00</b> | <b>53.17</b>    | <b>8.01</b>   | <b>101.71</b>  | <b>25.20</b>   | <b>188.09</b>   |

|  |                        |                 |                |             |                 |                |                 |                 |                 |
|--|------------------------|-----------------|----------------|-------------|-----------------|----------------|-----------------|-----------------|-----------------|
| <b>Central - Unallocated</b>           |                        | 1249.53         | 291.05         | 0.00        | 1540.58         | 237.03         | 751.45          | 0.00            | 2529.07         |
| <b>Total<br/>(Northern<br/>Region)</b> | State                  | 16888.00        | 2879.20        | 0.00        | 19767.20        | 0.00           | 8643.55         | 689.56          | 29100.31        |
|  | Private                | 22760.83        | 558.00         | 0.00        | 23318.83        | 0.00           | 2514.00         | 11854.66        | 37687.49        |
|  | Central                | 13290.37        | 2344.06        | 0.00        | 15634.43        | 1620.00        | 8596.22         | 329.00          | 26179.65        |
|  | <b>Grand<br/>Total</b> | <b>52939.20</b> | <b>5781.26</b> | <b>0.00</b> | <b>58720.46</b> | <b>1620.00</b> | <b>19753.77</b> | <b>12873.22</b> | <b>92967.45</b> |

**INSTALLED CAPACITY (IN MW) OF POWER UTILITIES IN THE STATES/UTS LOCATED IN  
WESTERN REGION**

**INCLUDING ALLOCATED SHARES IN JOINT & CENTRAL SECTOR UTILITIES**

(As on 31.03.2018)

| State          | Ownership/<br>Sector | Modewise breakup |                |             |                 |               |                      |                | Grand Total     |
|----------------|----------------------|------------------|----------------|-------------|-----------------|---------------|----------------------|----------------|-----------------|
|                |                      | Thermal          |                |             |                 | Nuclear       | Hydro<br>(Renewable) | RES<br>(MNRE)  |                 |
|                |                      | Coal             | Gas            | Diesel      | Total           |               |                      |                |                 |
| Goa            | State                | 0.00             | 0.00           | 0.00        | 0.00            | 0.00          | 0.00                 | 0.05           | 0.05            |
|                | Private              | 0.00             | 48.00          | 0.00        | 48.00           | 0.00          | 0.00                 | 0.91           | 48.91           |
|                | Central              | 454.78           | 19.67          | 0.00        | 474.45          | 26.00         | 0.00                 | 0.00           | 500.45          |
|                | <b>Sub-Total</b>     | <b>454.78</b>    | <b>67.67</b>   | <b>0.00</b> | <b>522.45</b>   | <b>26.00</b>  | <b>0.00</b>          | <b>0.96</b>    | <b>549.41</b>   |
| Daman & Diu    | State                | 0.00             | 0.00           | 0.00        | 0.00            | 0.00          | 0.00                 | 0.00           | 0.00            |
|                | Private              | 0.00             | 0.00           | 0.00        | 0.00            | 0.00          | 0.00                 | 10.61          | 10.61           |
|                | Central              | 126.63           | 43.34          | 0.00        | 169.97          | 7.00          | 0.00                 | 0.00           | 176.97          |
|                | <b>Sub-Total</b>     | <b>126.63</b>    | <b>43.34</b>   | <b>0.00</b> | <b>169.97</b>   | <b>7.00</b>   | <b>0.00</b>          | <b>10.61</b>   | <b>187.58</b>   |
| Gujarat        | State                | 4750.00          | 2177.82        | 0.00        | 6927.82         | 0.00          | 772.00               | 8.00           | 7707.82         |
|                | Private              | 7765.67          | 3960.00        | 0.00        | 11725.67        | 0.00          | 0.00                 | 7049.02        | 18774.69        |
|                | Central              | 3090.51          | 424.00         | 0.00        | 3514.51         | 559.00        | 0.00                 | 238.30         | 4311.81         |
|                | <b>Sub-Total</b>     | <b>15606.18</b>  | <b>6561.82</b> | <b>0.00</b> | <b>22168.00</b> | <b>559.00</b> | <b>772.00</b>        | <b>7295.32</b> | <b>30794.32</b> |
| Madhya Pradesh | State                | 4080.00          | 0.00           | 0.00        | 4080.00         | 0.00          | 1703.66              | 83.96          | 5867.62         |
|                | Private              | 5574.00          | 100.00         | 0.00        | 5674.00         | 0.00          | 0.00                 | 3635.84        | 9309.84         |
|                | Central              | 2794.41          | 257.00         | 0.00        | 3051.41         | 273.00        | 1520.00              | 300.00         | 5144.41         |

|                                 |                    |                 |                 |             |                 |                |                |                 |                  |
|---------------------------------|--------------------|-----------------|-----------------|-------------|-----------------|----------------|----------------|-----------------|------------------|
|                                 | <b>Sub-Total</b>   | <b>12448.41</b> | <b>357.00</b>   | <b>0.00</b> | <b>12805.41</b> | <b>273.00</b>  | <b>3223.66</b> | <b>4019.80</b>  | <b>20321.87</b>  |
| <b>Chhattisgarh</b>             | State              | 2280.00         | 0.00            | 0.00        | 2280.00         | 0.00           | 120.00         | 11.05           | 2411.05          |
|                                 | Private            | 8490.00         | 0.00            | 0.00        | 8490.00         | 0.00           | 0.00           | 524.30          | 9014.30          |
|                                 | Central            | 1953.44         | 0.00            | 0.00        | 1953.44         | 48.00          | 0.00           | 0.00            | 2001.44          |
|                                 | <b>Sub-Total</b>   | <b>12723.44</b> | <b>0.00</b>     | <b>0.00</b> | <b>12723.44</b> | <b>48.00</b>   | <b>120.00</b>  | <b>535.35</b>   | <b>13426.79</b>  |
| <b>Maharashtra</b>              | State              | 10170.00        | 672.00          | 0.00        | 10842.00        | 0.00           | 2850.84        | 208.13          | 13900.97         |
|                                 | Private            | 12456.00        | 568.00          | 0.00        | 13024.00        | 0.00           | 481.00         | 8247.75         | 21752.75         |
|                                 | Central            | 4334.75         | 2272.73         | 0.00        | 6607.48         | 690.00         | 0.00           | 123.00          | 7420.48          |
|                                 | <b>Sub-Total</b>   | <b>26960.75</b> | <b>3512.73</b>  | <b>0.00</b> | <b>30473.48</b> | <b>690.00</b>  | <b>3331.84</b> | <b>8578.88</b>  | <b>43074.19</b>  |
| <b>Dadra &amp; Nagar Naveli</b> | State              | 0.00            | 0.00            | 0.00        | 0.00            | 0.00           | 0.00           | 0.00            | 0.00             |
|                                 | Private            | 0.00            | 0.00            | 0.00        | 0.00            | 0.00           | 0.00           | 5.46            | 5.46             |
|                                 | Central            | 174.44          | 66.34           | 0.00        | 240.78          | 9.00           | 0.00           | 0.00            | 249.78           |
|                                 | <b>Sub-Total</b>   | <b>174.44</b>   | <b>66.34</b>    | <b>0.00</b> | <b>240.78</b>   | <b>9.00</b>    | <b>0.00</b>    | <b>5.46</b>     | <b>255.24</b>    |
| <b>Central - Unallocated</b>    |                    | 2114.00         | 197.59          | 0.00        | 2311.59         | 228.00         | 0.00           | 0.00            | 2539.59          |
| <b>Total (Western Region)</b>   | State              | 21280.00        | 2849.82         | 0.00        | 24129.82        | 0.00           | 5446.50        | 311.19          | 29887.51         |
|                                 | Private            | 34285.67        | 4676.00         | 0.00        | 38961.67        | 0.00           | 481.00         | 19473.89        | 58916.56         |
|                                 | Central            | 15042.95        | 3280.67         | 0.00        | 18323.62        | 1840.00        | 1520.00        | 661.30          | 22344.92         |
|                                 | <b>Grand Total</b> | <b>70608.62</b> | <b>10806.49</b> | <b>0.00</b> | <b>81415.11</b> | <b>1840.00</b> | <b>7447.50</b> | <b>20446.38</b> | <b>111148.99</b> |

**INSTALLED CAPACITY (IN MW) OF POWER UTILITIES IN THE STATES/UTS LOCATED IN  
SOUTHERN REGION**

**INCLUDING ALLOCATED SHARES IN JOINT & CENTRAL SECTOR UTILITIES**

(As on 31.03.2018)

| State                 | Ownership/<br>Sector | Modewise breakup |                |               |                 |               |                      |                 | Grand Total     |
|-----------------------|----------------------|------------------|----------------|---------------|-----------------|---------------|----------------------|-----------------|-----------------|
|                       |                      | Thermal          |                |               |                 | Nuclear       | Hydro<br>(Renewable) | RES<br>(MNRE)   |                 |
|                       |                      | Coal             | Gas            | Diesel        | Total           |               |                      |                 |                 |
| <b>Andhra Pradesh</b> | State                | 5010.00          | 235.40         | 0.00          | 5245.40         | 0.00          | 1673.60              | 48.75           | 6967.75         |
|                       | Private              | 3873.88          | 3694.12        | 36.80         | 7604.80         | 0.00          | 0.00                 | 6427.13         | 14031.93        |
|                       | Central              | 1674.56          | 0.00           | 0.00          | 1674.56         | 127.27        | 0.00                 | 250.00          | 2051.83         |
|                       | <b>Sub-Total</b>     | <b>10558.44</b>  | <b>3929.52</b> | <b>36.80</b>  | <b>14524.76</b> | <b>127.27</b> | <b>1673.60</b>       | <b>6725.88</b>  | <b>23051.51</b> |
| <b>Telangana</b>      | State                | 5082.50          | 0.00           | 0.00          | 5082.50         | 0.00          | 2449.93              | 40.22           | 7572.65         |
|                       | Private              | 839.45           | 950.88         | 0.00          | 1790.33         | 0.00          | 0.00                 | 3609.30         | 5399.63         |
|                       | Central              | 1956.12          | 0.00           | 0.00          | 1956.12         | 148.73        | 0.00                 | 10.00           | 2114.85         |
|                       | <b>Sub-Total</b>     | <b>7878.07</b>   | <b>950.88</b>  | <b>0.00</b>   | <b>8828.95</b>  | <b>148.73</b> | <b>2449.93</b>       | <b>3659.52</b>  | <b>15087.13</b> |
| <b>Karnataka</b>      | State                | 5020.00          | 0.00           | 127.92        | 5147.92         | 0.00          | 3599.80              | 155.33          | 8903.05         |
|                       | Private              | 1958.50          | 0.00           | 25.20         | 1983.70         | 0.00          | 0.00                 | 12283.52        | 14267.22        |
|                       | Central              | 2829.20          | 0.00           | 0.00          | 2829.20         | 698.00        | 0.00                 | 0.00            | 3527.20         |
|                       | <b>Sub-Total</b>     | <b>9807.70</b>   | <b>0.00</b>    | <b>153.12</b> | <b>9960.82</b>  | <b>698.00</b> | <b>3599.80</b>       | <b>12438.85</b> | <b>26697.47</b> |
| <b>Kerala</b>         | State                | 0.00             | 0.00           | 159.96        | 159.96          | 0.00          | 1881.50              | 151.02          | 2192.48         |
|                       | Private              | 615.00           | 174.00         | 0.00          | 789.00          | 0.00          | 0.00                 | 178.44          | 967.44          |
|                       | Central              | 1143.22          | 359.58         | 0.00          | 1502.80         | 362.00        | 0.00                 | 50.00           | 1914.80         |
|                       | <b>Sub-Total</b>     | <b>1758.22</b>   | <b>533.58</b>  | <b>159.96</b> | <b>2451.76</b>  | <b>362.00</b> | <b>1881.50</b>       | <b>379.46</b>   | <b>5074.72</b>  |

|  |                        |                 |                |               |                 |                |                 |                 |                  |
|--|------------------------|-----------------|----------------|---------------|-----------------|----------------|-----------------|-----------------|------------------|
| <b>Tamil Nadu</b>                      | State                  | 4320.00         | 524.08         | 0.00          | 4844.08         | 0.00           | 2203.20         | 122.70          | 7169.98          |
|  | Private                | 4837.67         | 503.10         | 411.70        | 5752.47         | 0.00           | 0.00            | 10860.81        | 16613.28         |
|  | Central                | 4489.52         | 0.00           | 0.00          | 4489.52         | 1448.00        | 0.00            | 181.90          | 6119.42          |
|  | <b>Sub-Total</b>       | <b>13647.19</b> | <b>1027.18</b> | <b>411.70</b> | <b>15086.07</b> | <b>1448.00</b> | <b>2203.20</b>  | <b>11165.41</b> | <b>29902.68</b>  |
| <b>NLC</b>                             | State                  | 0.00            | 0.00           | 0.00          | 0.00            | 0.00           | 0.00            | 0.00            | 0.00             |
|  | Private                | 0.00            | 0.00           | 0.00          | 0.00            | 0.00           | 0.00            | 0.00            | 0.00             |
|  | Central                | 100.00          | 0.00           | 0.00          | 100.00          | 0.00           | 0.00            | 0.00            | 100.00           |
|  | <b>Sub-Total</b>       | <b>100.00</b>   | <b>0.00</b>    | <b>0.00</b>   | <b>100.00</b>   | <b>0.00</b>    | <b>0.00</b>     | <b>0.00</b>     | <b>100.00</b>    |
| <b>Puducherry</b>                      | State                  | 0.00            | 32.50          | 0.00          | 32.50           | 0.00           | 0.00            | 0.00            | 32.50            |
|  | Private                | 0.00            | 0.00           | 0.00          | 0.00            | 0.00           | 0.00            | 0.16            | 0.16             |
|  | Central                | 248.40          | 0.00           | 0.00          | 248.40          | 86.00          | 0.00            | 0.00            | 334.40           |
|  | <b>Sub-Total</b>       | <b>248.40</b>   | <b>32.50</b>   | <b>0.00</b>   | <b>280.90</b>   | <b>86.00</b>   | <b>0.00</b>     | <b>0.16</b>     | <b>367.06</b>    |
| <b>Central - Unallocated</b>           |                        | 1784.00         | 0.00           | 0.00          | 1784.00         | 450.00         | 0.00            | 0.00            | 2234.00          |
| <b>Total<br/>(Southern<br/>Region)</b> | State                  | 19432.50        | 791.98         | 287.88        | 20512.36        | 0.00           | 11808.03        | 518.02          | 32838.41         |
|  | Private                | 12124.50        | 5322.10        | 473.70        | 17920.30        | 0.00           | 0.00            | 33359.36        | 51279.66         |
|  | Central                | 14225.02        | 359.58         | 0.00          | 14584.60        | 3320.00        | 0.00            | 491.90          | 18396.50         |
|  | <b>Grand<br/>Total</b> | <b>45782.02</b> | <b>6473.66</b> | <b>761.58</b> | <b>53017.26</b> | <b>3320.00</b> | <b>11808.03</b> | <b>34369.28</b> | <b>102514.57</b> |



**INSTALLED CAPACITY (IN MW) OF POWER UTILITIES IN THE STATES/UTS LOCATED IN  
EASTERN REGION**

**INCLUDING ALLOCATED SHARES IN JOINT & CENTRAL SECTOR UTILITIES**

(As on 31.03.2018)

| State              | Ownership/<br>Sector | Modewise breakup |               |             |                |             |                      |               | Grand Total     |
|--------------------|----------------------|------------------|---------------|-------------|----------------|-------------|----------------------|---------------|-----------------|
|                    |                      | Thermal          |               |             |                | Nuclear     | Hydro<br>(Renewable) | RES<br>(MNRE) |                 |
|                    |                      | Coal             | Gas           | Diesel      | Total          |             |                      |               |                 |
| <b>Bihar</b>       | State                | 710.00           | 0.00          | 0.00        | 710.00         | 0.00        | 0.00                 | 70.70         | 780.70          |
|                    | Private              | 281.00           | 0.00          | 0.00        | 281.00         | 0.00        | 0.00                 | 255.45        | 536.45          |
|                    | Central              | 2914.33          | 0.00          | 0.00        | 2914.33        | 0.00        | 110.00               | 0.00          | 3024.32         |
|                    | <b>Sub-Total</b>     | <b>3905.33</b>   | <b>0.00</b>   | <b>0.00</b> | <b>3905.33</b> | <b>0.00</b> | <b>110.00</b>        | <b>326.15</b> | <b>4341.47</b>  |
| <b>Jharkhand</b>   | State                | 420.00           | 0.00          | 0.00        | 420.00         | 0.00        | 130.00               | 4.05          | 554.05          |
|                    | Private              | 730.00           | 0.00          | 0.00        | 730.00         | 0.00        | 0.00                 | 25.67         | 755.67          |
|                    | Central              | 393.74           | 0.00          | 0.00        | 393.74         | 0.00        | 61.00                | 0.00          | 454.74          |
|                    | <b>Sub-Total</b>     | <b>1543.74</b>   | <b>0.00</b>   | <b>0.00</b> | <b>1543.74</b> | <b>0.00</b> | <b>191.00</b>        | <b>29.72</b>  | <b>1764.46</b>  |
| <b>West Bengal</b> | State                | 5520.00          | 100.00        | 0.00        | 5620.00        | 0.00        | 986.00               | 91.95         | 6697.95         |
|                    | Private              | 2425.00          | 0.00          | 0.00        | 2425.00        | 0.00        | 0.00                 | 343.87        | 2768.87         |
|                    | Central              | 760.77           | 0.00          | 0.00        | 760.77         | 0.00        | 410.00               | 0.00          | 1170.77         |
|                    | <b>Sub-Total</b>     | <b>8705.77</b>   | <b>100.00</b> | <b>0.00</b> | <b>8805.77</b> | <b>0.00</b> | <b>1396.00</b>       | <b>435.82</b> | <b>10637.59</b> |
| <b>DVC</b>         | State                | 0.00             | 0.00          | 0.00        | 0.00           | 0.00        | 0.00                 | 0.00          | 0.00            |
|                    | Private              | 0.00             | 0.00          | 0.00        | 0.00           | 0.00        | 0.00                 | 0.00          | 0.00            |

|                               |                    |                 |               |             |                 |             |                |                |                 |
|-------------------------------|--------------------|-----------------|---------------|-------------|-----------------|-------------|----------------|----------------|-----------------|
|                               | Central            | 6985.04         | 0.00          | 0.00        | 6985.04         | 0.00        | 186.20         | 0.00           | 7171.24         |
|                               | <b>Sub-Total</b>   | <b>6985.04</b>  | <b>0.00</b>   | <b>0.00</b> | <b>6985.04</b>  | <b>0.00</b> | <b>186.20</b>  | <b>0.00</b>    | <b>7171.24</b>  |
| <b>Odisha</b>                 | State              | 420.00          | 0.00          | 0.00        | 420.00          | 0.00        | 2061.92        | 6.30           | 2488.22         |
|                               | Private            | 2939.00         | 0.00          | 0.00        | 2939.00         | 0.00        | 0.00           | 178.30         | 3117.30         |
|                               | Central            | 1633.90         | 0.00          | 0.00        | 1633.90         | 0.00        | 89.00          | 10.00          | 1732.90         |
|                               | <b>Sub-Total</b>   | <b>4992.90</b>  | <b>0.00</b>   | <b>0.00</b> | <b>4992.90</b>  | <b>0.00</b> | <b>2150.92</b> | <b>194.60</b>  | <b>7338.42</b>  |
| <b>Sikkim</b>                 | State              | 0.00            | 0.00          | 0.00        | 0.00            | 0.00        | 360.00         | 52.11          | 412.11          |
|                               | Private            | 0.00            | 0.00          | 0.00        | 0.00            | 0.00        | 399.00         | 0.00           | 399.00          |
|                               | Central            | 87.03           | 0.00          | 0.00        | 87.03           | 0.00        | 64.00          | 0.00           | 151.03          |
|                               | <b>Sub-Total</b>   | <b>87.03</b>    | <b>0.00</b>   | <b>0.00</b> | <b>87.03</b>    | <b>0.00</b> | <b>823.00</b>  | <b>52.11</b>   | <b>962.14</b>   |
| <b>Central - Unallocated</b>  |                    | 1101.83         | 0.00          | 0.00        | 1101.83         | 0.00        | 85.01          | 0.00           | 1186.84         |
| <b>Total (Eastern Region)</b> | State              | 7070.00         | 100.00        | 0.00        | 7170.00         | 0.00        | 3537.92        | 225.11         | 10933.03        |
|                               | Private            | 6375.00         | 0.00          | 0.00        | 6375.00         | 0.00        | 399.00         | 803.29         | 7577.29         |
|                               | Central            | 13876.64        | 0.00          | 0.00        | 13876.64        | 0.00        | 1005.20        | 10.00          | 14891.84        |
|                               | <b>Grand Total</b> | <b>27321.64</b> | <b>100.00</b> | <b>0.00</b> | <b>27421.64</b> | <b>0.00</b> | <b>4942.12</b> | <b>1038.40</b> | <b>33402.16</b> |

**INSTALLED CAPACITY (IN MW) OF POWER UTILITIES IN THE STATES/UTS LOCATED IN  
NORTH-EASTERN REGION**

**INCLUDING ALLOCATED SHARES IN JOINT & CENTRAL SECTOR UTILITIES**

**(As on 31.03.2018)**

| State             | Ownership/<br>Sector | Modewise breakup |               |             |                |             |                      |               | Grand Total    |
|-------------------|----------------------|------------------|---------------|-------------|----------------|-------------|----------------------|---------------|----------------|
|                   |                      | Thermal          |               |             |                | Nuclear     | Hydro<br>(Renewable) | RES<br>(MNRE) |                |
|                   |                      | Coal             | Gas           | Diesel      | Total          |             |                      |               |                |
| Assam             | State                | 0.00             | 288.45        | 0.00        | 288.45         | 0.00        | 100.00               | 30.01         | 418.46         |
|                   | Private              | 0.00             | 24.50         | 0.00        | 24.50          | 0.00        | 0.00                 | 16.55         | 41.05          |
|                   | Central              | 279.02           | 435.56        | 0.00        | 714.58         | <b>0.00</b> | 331.23               | 0.00          | 1045.81        |
|                   | <b>Sub-Total</b>     | <b>279.02</b>    | <b>748.51</b> | <b>0.00</b> | <b>1027.53</b> | <b>0.00</b> | <b>431.23</b>        | <b>46.56</b>  | <b>1505.32</b> |
| Arunachal Pradesh | State                | 0.00             | 0.00          | 0.00        | 0.00           | 0.00        | 0.00                 | 104.61        | 104.61         |
|                   | Private              | 0.00             | 0.00          | 0.00        | 0.00           | 0.00        | 0.00                 | 5.39          | 5.39           |
|                   | Central              | 24.70            | 46.82         | 0.00        | 71.52          | 0.00        | 97.45                | 0.00          | 168.97         |
|                   | <b>Sub-Total</b>     | <b>24.70</b>     | <b>46.82</b>  | <b>0.00</b> | <b>71.52</b>   | <b>0.00</b> | <b>97.45</b>         | <b>110.00</b> | <b>278.97</b>  |
| Meghalaya         | State                | 0.00             | 0.00          | 0.00        | 0.00           | 0.00        | 322.00               | 31.03         | 353.03         |
|                   | Private              | 0.00             | 0.00          | 0.00        | 0.00           | 0.00        | 0.00                 | 0.02          | 0.02           |
|                   | Central              | 30.40            | 109.69        | 0.00        | 140.09         | 0.00        | 65.19                | 0.00          | 205.28         |
|                   | <b>Sub-Total</b>     | <b>30.40</b>     | <b>109.69</b> | <b>0.00</b> | <b>140.09</b>  | <b>0.00</b> | <b>387.19</b>        | <b>31.05</b>  | <b>558.33</b>  |
| Tripura           | State                | 0.00             | 169.50        | 0.00        | 169.50         | 0.00        | 0.00                 | 16.01         | 185.51         |

|                                     |                    |               |                |              |                |             |                |               |                |
|-------------------------------------|--------------------|---------------|----------------|--------------|----------------|-------------|----------------|---------------|----------------|
|                                     | Private            | 0.00          | 0.00           | 0.00         | 0.00           | 0.00        | 0.00           | 0.09          | 0.09           |
|                                     | Central            | 37.40         | 436.95         | 0.00         | 474.35         | 0.00        | 62.38          | 5.00          | 541.73         |
|                                     | <b>Sub-Total</b>   | <b>37.40</b>  | <b>606.45</b>  | <b>0.00</b>  | <b>643.85</b>  | <b>0.00</b> | <b>62.38</b>   | <b>21.10</b>  | <b>727.33</b>  |
| <b>Manipur</b>                      | State              | 0.00          | 0.00           | 36.00        | 36.00          | 0.00        | 0.00           | 5.45          | 41.45          |
|                                     | Private            | 0.00          | 0.00           | 0.00         | 0.00           | 0.00        | 0.00           | 0.06          | 0.06           |
|                                     | Central            | 31.40         | 71.57          | 0.00         | 102.97         | 0.00        | 88.93          | 0.00          | 191.90         |
|                                     | <b>Sub-Total</b>   | <b>31.40</b>  | <b>71.57</b>   | <b>36.00</b> | <b>138.97</b>  | <b>0.00</b> | <b>88.93</b>   | <b>5.51</b>   | <b>233.41</b>  |
| <b>Nagaland</b>                     | State              | 0.00          | 0.00           | 0.00         | 0.00           | 0.00        | 0.00           | 30.67         | 30.67          |
|                                     | Private            | 0.00          | 0.00           | 0.00         | 0.00           | 0.00        | 0.00           | 1.00          | 1.00           |
|                                     | Central            | 21.40         | 48.93          | 0.00         | 70.33          | 0.00        | 53.37          | 0.00          | 123.70         |
|                                     | <b>Sub-Total</b>   | <b>21.40</b>  | <b>48.93</b>   | <b>0.00</b>  | <b>70.33</b>   | <b>0.00</b> | <b>53.37</b>   | <b>31.67</b>  | <b>155.37</b>  |
| <b>Mizoram</b>                      | State              | 0.00          | 0.00           | 0.00         | 0.00           | 0.00        | 0.00           | 36.47         | 36.47          |
|                                     | Private            | 0.00          | 0.00           | 0.00         | 0.00           | 0.00        | 0.00           | 0.20          | 0.20           |
|                                     | Central            | 20.70         | 40.46          | 0.00         | 61.16          | 0.00        | 94.19          | 0.00          | 155.35         |
|                                     | <b>Sub-Total</b>   | <b>20.70</b>  | <b>40.46</b>   | <b>0.00</b>  | <b>61.16</b>   | <b>0.00</b> | <b>94.19</b>   | <b>36.67</b>  | <b>192.02</b>  |
| <b>Central - Unallocated</b>        |                    | 75.00         | 63.62          | 0.00         | 138.62         | 0.00        | 127.26         | 0.00          | 265.88         |
| <b>Total (North-Eastern Region)</b> | State              | 0.00          | 457.95         | 36.00        | 493.95         | 0.00        | 422.00         | 254.25        | 1170.20        |
|                                     | Private            | 0.00          | 24.50          | 0.00         | 24.50          | 0.00        | 0.00           | 23.31         | 47.81          |
|                                     | Central            | 520.02        | 1253.60        | 0.00         | 1773.62        | 0.00        | 920.00         | 5.00          | 2698.62        |
|                                     | <b>Grand Total</b> | <b>520.02</b> | <b>1736.05</b> | <b>36.00</b> | <b>2292.07</b> | <b>0.00</b> | <b>1342.00</b> | <b>282.56</b> | <b>3916.63</b> |

**INSTALLED CAPACITY (IN MW) OF POWER UTILITIES IN THE STATES/UTS LOCATED IN ISLANDS**

**INCLUDING ALLOCATED SHARES IN JOINT & CENTRAL SECTOR UTILITIES**

**(As on 31.03.2018)**

| State                            | Ownership/<br>Sector | Modewise breakup |             |              |              |             |                      |               | Grand Total  |
|----------------------------------|----------------------|------------------|-------------|--------------|--------------|-------------|----------------------|---------------|--------------|
|                                  |                      | Thermal          |             |              |              | Nuclear     | Hydro<br>(Renewable) | RES<br>(MNRE) |              |
|                                  |                      | Coal             | Gas         | Diesel       | Total        |             |                      |               |              |
| <b>Andaman &amp;<br/>Nicobar</b> | State                | 0.00             | 0.00        | 40.05        | 40.05        | 0.00        | 0.00                 | 5.25          | 45.30        |
|                                  | Private              | 0.00             | 0.00        | 0.00         | 0.00         | 0.00        | 0.00                 | 1.46          | 1.46         |
|                                  | Central              | 0.00             | 0.00        | 0.00         | 0.00         | 0.00        | 0.00                 | 5.10          | 5.10         |
|                                  | <b>Sub-Total</b>     | <b>0.00</b>      | <b>0.00</b> | <b>40.05</b> | <b>40.05</b> | <b>0.00</b> | <b>0.00</b>          | <b>11.81</b>  | <b>51.86</b> |
| <b>lakshadweep</b>               | State                | 0.00             | 0.00        | 0.00         | 0.00         | 0.00        | 0.00                 | 0.00          | 0.00         |
|                                  | Private              | 0.00             | 0.00        | 0.00         | 0.00         | 0.00        | 0.00                 | 0.75          | 0.75         |
|                                  | Central              | 0.00             | 0.00        | 0.00         | 0.00         | 0.00        | 0.00                 | 0.00          | 0.00         |
|                                  | <b>Sub-Total</b>     | <b>0.00</b>      | <b>0.00</b> | <b>0.00</b>  | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>          | <b>0.75</b>   | <b>0.75</b>  |
| <b>Total (Islands)</b>           | State                | 0.00             | 0.00        | 40.05        | 40.05        | 0.00        | 0.00                 | 5.25          | 45.30        |
|                                  | Private              | 0.00             | 0.00        | 0.00         | 0.00         | 0.00        | 0.00                 | 2.21          | 2.21         |
|                                  | Central              | 0.00             | 0.00        | 0.00         | 0.00         | 0.00        | 0.00                 | 5.10          | 5.10         |
|                                  | <b>Grand Total</b>   | <b>0.00</b>      | <b>0.00</b> | <b>40.05</b> | <b>40.05</b> | <b>0.00</b> | <b>0.00</b>          | <b>12.56</b>  | <b>52.61</b> |

### Details of Foreign Tours performed during 2017-18

| Sl.No. | Participant(Shri/Smt/Ms)                     | Country           | Purpose of the visit  | Duration/Year                    |
|--------|--|-------------------|---|----------------------------------|
| 1.     | Shri Deepak Choudhary,<br>Assistant Director | Germany           | Inspection of 400kv XLPE cable for contract package MEM-, Punatsangchhu HPA-I   | 25 April, 2017                   |
| 2.     | Shri Vivek Goyal,<br>Director                | Germany & Spain   | Study Tour to Spain & Germany on "Integration of Renewable Energy Resources into the grid"  | 31 May, 2017 to 10 June, 2017    |
| 3.     | Shri Asit Singh,<br>Superintending Engineer  | Germany & Spain   | Study Tour to Spain & Germany on "Integration of Renewable Energy Resources into the grid"  | 15 June, 2017 to 30 June, 2017   |
| 4.     | Shri Irfan Ahmed,<br>Director                | Germany & Spain   | Study Tour to Spain & Germany on "Integration of Renewable Energy Resources into the grid"  | 17 June, 2017 to 30 June, 2017   |
|        | Shri Annepu Suresh,<br>Dy. Director          |                   |   |                                  |
| 5.     | Shri Shantanu Biswas,<br>Dy Director         | Spain,<br>Germany | Study Tour to Spain & Germany on "Integration of Renewable Energy Resources into the grid"  | 14 June, 2017 to 01 July, 2017   |
| 6.     | Shri Anil Thomas, Director                   | Germany & Spain   | Study Tour to Spain & Germany on "Integration of Renewable Energy Resources into the grid"  | 6 July, 2017 to 14 July, 2017    |
|        | Smt. N S Malini,<br>Dy .Director             |                   |   |                                  |
| 7.     | Shri M M Dhakate,<br>Director                | Spain,<br>Germany | Study Tour to Spain & Germany on "Integration of Renewable Energy Resources into the grid"  | 27 July, 2017 to 04 August, 2017 |
|        | Shri N R L K Prasad,<br>Executive Engineer   |                   |   |                                  |
|        | Smt. Anusha Das,<br>Asst. Executive Engineer |                   |   |                                  |
| 8.     | Shri Brieflee Lyngkhai,<br>Director          | Spain,<br>Germany | Capacity Building Programme on Integration of Renewable Energy Sources  | 02 July, 2017 to 14 July, 2017   |
|        | D K Srivastava<br>Director                   |                   |   |                                  |
| 9.     | Shri Vikram Singh,<br>Director (GM)          | Bhutan            | Workshop on Identification, Comparison & Scenario Based Application of Power Demand/ Load Forecasting tools                                   | 04 July 2017 to 05 July 2017     |
|        | Shri Ishan Sharan,<br>Director (PSLF)        |                   |   |                                  |
| 10.    | Shri Deepak Sharma,<br>Dy Director           | Bhutan            | Inspection of the ongoing Assembly/ erection works and witnessing of Hydro Testing of Spiral Casing Unit V of Punatsangchhu- I HEP (6*200 MW) | 15 June, 2017 to 17 June, 2017   |

|     |  |            |  |  |
|-----|--|------------|--|--|
| 11. | Shri Shravan Kumar,<br>Director          | Maruitius  | To assess energy requirements and develop a road map for Mauritius   | 24 July, 2017 to<br>30 July, 2017              |
| 12. | Shri K K Arya,<br>Member                 | Bhutan     | To attend TCC Meeting of Punatsangchhu HEP-I &II HEP   | 20 July, 2017 to<br>22 July, 2017              |
|     | Shri P C Kureel<br>Chief Engineer        |            |  |  |
| 13. | Shri J S Bawa,<br>Chief Engineer         | Nepal      | Meeting on DPR finalization of Pancheshwar, Multipurpose Project   | 21 August 2017 to<br>22 August 2017            |
| 14. | Shri K K Arya<br>Member                  | Germany    | To witness inspection of generator Transformer Bushing of Punatsangchhu-I HEP  | 22 August, 2017 to<br>24 August, 2017          |
| 15. | Shri Ravinder Gupta,<br>Chief Engineer   | Pakistan   | workshop on “Growth of Indian Power Infrastructure and Lessons Learnt”   | 13 September 2017<br>to 14 September<br>2017   |
|     | Shri Ghanshyam Prasad,<br>Chief Engineer |            |  |  |
| 16. | Shri J S Bawa,<br>Chief Engineer         | Washington | 2 <sup>nd</sup> Meeting of World bank with Senior representative of India and Pakistan in Washington, USA on issue relating to Kishenganga and Ratle HEPs under Indus Water Treaty | 14 September, 2017<br>to<br>15 September, 2017 |
| 17. | Shri. P S Mhaske,<br>Member              | Bangladesh | 13 <sup>th</sup> Meeting of Indo-Bangladesh Joint working Group (JWG) and Joint Steering Committee (JSC) on Cooperation in Power Sector  | 27 September<br>2017 to 28<br>September 2017   |
| 18. | Shri Pankaj Batra,<br>Member             | Australia  | Participation in Second Lateral Learning Programme on Smart Grid Technologies and Implications for Inclusive Development   | 02 October, 2017 to<br>06 October, 2017        |
| 19. | Shri Rakesh Kumar,<br>Director           | Nepal      | Preparation of Detailed Project Report of Kuri-Gongri Hydro Electric Project (2640 MW)   | 25 October, 2017 to<br>27 August, 2017         |
|     | Shri Mukesh Kumar,<br>Dy. Director       |            |  |  |
|     | Shri Suyash Verma,<br>Asst. Director     |            |  |  |
|     | Shri Shrey Kumar,<br>Asst. Director      |            |  |  |
| 20. | Smt. Rishika Sharan,<br>Director         | Bangladesh | workshop on system operation and settlement mechanism for cross border trade/regional power market   | 10 December 2017<br>to 11 December<br>2017     |
|     | Shri. Irfan Ahmad,<br>Director           |            |  |  |

|     |  |             |   |   |
|-----|--|-------------|---|---|
| 21. | Shri M A K P Singh,<br>Member Secretary  | Australia   | Executive Exchange on<br>“Electricity Markets and<br>Renawable Grid Integration”  | 11 December 2017<br>to 15 December<br>2017  |
| 22. | Shri Goutam Roy,<br>Chief Engineer       | Nepal       | Inspection of transmission<br>line for strengthening of<br>132kV Power Transmission<br>Interconnection between India<br>and Nepal | 21 November 2017<br>to 24 November,<br>2017 |
| 23. | Shri Ramesh Kumar,<br>Director           | Japan       | Workshop on Energy<br>Conservation  | 15 January, 2018 to<br>19 January, 2018     |
|     | Shri Bhailal,<br>Chief Engineer          | South Korea | Training on 420kV Gas<br>Insulated Switchgears &<br>Associated Equipments   | 29 January, 2018 to<br>09 February, 2018    |
|     | Shri Amit Roy Singhal,<br>Asst. Director |             |   |   |
| 24. | Shri Gorakh Thakur,<br>Chief Engineer    | Bhutan      | Visit of CEA Officers to<br>Punatsangchhu-II at Bhutal  | 16 January, 2018 to<br>19 January, 2018     |
|     | Shri Neeraj Kumar,<br>Director           | Bhutan      |   |   |
| 24. | Shri Rakesh Kumar,<br>Director           | China       | 11 <sup>th</sup> Expert Level Mechanism<br>(ELM) meeting  | 26 March, 2018 to<br>29 March, 2018         |