





#### भारत सरकार Government of India विद्युत मंत्रालय Ministry of Power केन्द्रीय विद्युत प्राधिकरण Central Electricity Authority विद्युत संचार विकास प्रभाग

#### **Power Communication Development Division**

\*\*\*\*\*

CEA Case No.: MRA-1211						
PTCC approval for 220 kV S/C line on D/C tower UTCL Awarpur – Manikgarh Cement Gadchandur (3.436 km) – Regd.						
S. No	Reference No.	Dated				
(i)	UTCL: UTCL/MCW/220kV-Projt/1122	11.11.2022				
(ii)	UTCL: UTCL/MCW/220kV-Projt/786	29.12.2022				
(iii)	BSNL: IC/MBI/PTCC/MRA-2575/02	30.12.2022				
(iv)	South Central Railway: SG.85/4/3/PTCC/SCR/2022-23/MH-8 RTD	29.11.2022				

The PTCC proposal submitted vide reference (i) has been examined. The LF induction on communication circuits of BSNL and South Central Railway with respect to details furnished vide above reference (iii) & (iv) respectively have been computed. The voltages likely to be induced on paralleling communication cables of BSNL and South Central Railway under Single Line to Ground fault conditions are enclosed at Annexure-I & II respectively. The screening factors as applicable have been considered.

EPR Zones for proposed substation are mentioned below.

Name of the	Half	Fault	Resistance of	d (mts)	d (mts)	d (mts)	d (mts)
proposed SS	Diagonal	Current,	earth mat, R	at 430 V	at 650	at 7 kV	at 10
	Distance,	I (kA)	(Ohms)		V		kV
	D/2 (mts)						
220 k	V 43	20	0.16	277	168.7	NIL	NIL
Manikgarh							
Cement							
Gadchandur							

Telecommunication details from DG Signals, MoD are awaited however, vide reference (ii) above, M/s UTCL have informed that erection and testing of the subject line is completed and Final Charging Permission from Electrical Inspector Office, Nagpur region has also been received. M/s UTCL have requested for provisional PTCC clearance so that the line can be charged.

Taking above into consideration, necessary action for issuance of provsional PTCC route approval may be taken under intimation to this office. LF induction on telecommunication circuits of Defense will be communicated after the receipt of details from DG Signals, MoD. Encl.: As above

**Chief Engineer** 

#### To,

- ,		
1.	Divisional	QA & Inspection circle, 1 <sup>st</sup> floor, D- wing,
	Engineer (PTCC),	BSNL Admin Bldg., Junu Tara Road,
	Western Zone	Santacruz (West), Mumbai-400054

# 1/25503/2023

2.			South Central Railway, Office of PCSTE,	Annex-II
		GM/Tele	7 <sup>th</sup> floor, Rail Nilayam, Secunderabad -	
			500025	
3.	2	Senior Manager	UTCL, P.O. Gadchandur, Tah. Korpana,	Copy for information
	э.	(E&I)	Dist. Chandrapur, Maharashtra - 442908	Copy for information
		Director General	General Staff Branch, Integrated HQ,	With a request to provide
		of Signals	MoD (army), Sena Bhawan, DHQ,	details of Telecom assets/
4	4.		PO, New Delhi- 110 105	NOC at the earliest for IV
				calculation and issuance of
				final RAC.

# ANNEXURE-I

Name of	CEA Case No.: MRA-1211  Name of the Power line: 220 kV S/C line on D/C tower UTCL Awarpur – Manikgarh Cement Gadchandur			Map Scale : 1 cm= 500 m  Total Length : 3.436 km  S.R. Value : 5000 Ohm-cm			
S.No.	Telecom. Details	Length of Parallelis m in Km.	Mutual Coupling in Ohms.	Effective Fault current in Amps.	I.V in Volts.		
BSNL Letter No: IC/MBI/PTCC/MRA-2575/02 Date: 30.12.2022							
1	200Pr UG cable b/w Gadchandur Exch and Axis  Bank ATM	0.3	0.0095	20000	190		

# **ANNEXURE-II**

CEA Case No.: MRA-1211  Name of the Power line: 220 kV S/C line on D/C tower UTCL Awarpur –  Manikgarh Cement Gadchandur			Map Scale : 1 cm= 500 m  Total Length : 3.436 km  S.R. Value : 5000 Ohm-cm					
S.No.	Telecom. Details	Length of Parallelis m in Km.	Mutual Coupling in Ohms.	Effective Fault current in Amps.	I.V in Volts.			
	SOUTH CENTRAL RAILWAY: SG.85/4/3/PTCC/SCR/2022-23/MH-8 RTD Date: 29.11.2022							
1	Gadchandur (GDCR) – Maratha Cement Works (MCW)	1.3	0.0005	24800	12			
	Maratha Cement Works (MCW) – Pandar Pawani (PRPI)		Out of parallelis	sm	0			