



सत्यमेव जयते



भारत सरकार
Government of India
विद्युत मंत्रालय
Ministry of Power
केन्द्रीय विद्युत प्राधिकरण
Central Electricity Authority
विद्युत प्रणाली संचार विकास प्रभाग
Power System Communication Development Division

On behalf of
Central Level Power & Telecommunication Co-ordination Committee

No: As assigned

Date: As assigned

CEA Case No.: AND-782

Certificate of Approval for the Route of Extra High Tension (EHT) Power Line / Telecommunication Line

Approval of the Central Level Power & Telecommunication Co-ordination Committee is hereby conveyed to the route of 33 kV cable feeder from **33/0.8 kV IDT-3, IDT-4 & IDT-5 for Plot No. 3 at Pinnapuram, Nandyal to 400/33 kV Pooling SS at Pinnapuram, Nandyal (Length: 1.915 kms)** particulars of which are given in Annexure I.

The approval is for the route only and is subject to the following conditions.

1. The approval is based on the Power system/ Telecom system conditions' details as reported by the Power supply authority/ Telecom authority at present. Any changes either to Transmission line or the Power system or the paralleling telecommunication lines which are likely to alter the low frequency induction from the estimated at present should be reported to PTCC for its prior approval.
2. The Power and Telecommunication authorities shall be required to adopt such measures as may be recommended by PTCC for counteracting any interference that might arise when the EHT line is in normal operation.
3. Each crossing should satisfy the conditions as laid down in Para 6 -10 of PTCC Code of Practice for crossings.
4. The angle of crossing shall be 90 degrees but in no case less than 60 degrees.
5. The power line shall be equipped with protective switchgear such that the duration of earth current shall be as short as possible but never exceeding 0.5 seconds.
6. The power line shall be energized within a mutually acceptable time limit after obtaining a Certificate from the concerned Telecom and/or Railway authority regarding completion of provision of all protective measures as recommended by PTCC and also under specific clearance from the Telecom and/or Railway authority maintaining the Telecom system.

7. The energization of Extra High Tension power lines would not be held up for want of installation of GD tubes on telecom lines when the induced voltages are in the range of 430 to 650 V.
8. The telecom line shall be commissioned within a mutually acceptable time after completing provision of all protective measures as recommended by PTCC and also after obtaining specific clearance from the Power authority, if certain measures as recommended by PTCC are to be carried out on power system.
9. The later entrant in the field shall bear the entire cost of providing GD tubes and their fitting as recommended by PTCC, including 15% spares and/or any other protective measures as recommended by PTCC.
10. The route approval shall be subject to special conditions as laid down under Annexure II.

Chief Engineer

1.	M/s Greenko AP01 IREP Private Limited	Second Floor, Block D, Plot No. 13, SY No. 64, Hitech City Layout, Madhapur Village, Hyderabad – 500 081
----	--	---

Annexure I

1

- | | | |
|-----|---|---|
| (a) | Name of the Power Supply authority seeking approval | M/s Greenko AP01 IREP Private Limited |
| (b) | Reference number & date: | Greenko AP01/PTCC/8/2025 dated 20.03.2025 |
| (c) | Name of the Power line | 33 kV cable feeder from 33/0.8 kV IDT-3, IDT-4 & IDT-5 for Plot No. 3 at Pinnapuram, Nandyal to 400/33 kV Pooling SS at Pinnapuram, Nandyal (Length: 1.915 kms) |
| (d) | Length of Power line: | 1.915 kms |
| (e) | Operating Voltage | 33 kV |
| (f) | Number of circuits | 2 |

2

- | | | |
|-----|----------------------------------|--------------------|
| (a) | Names of parallel telecom lines: | As per Annexure-II |
| (b) | Length of parallelism: | As per Annexure-II |

3 Average value of earth resistivity in the region: 50,000 ohm-cms

4 Whether LF test necessary: No

5 Special conditions subject to which this certificate will be effective: As per Annexure-II

Annexure II

Name of the Power Line: 33 kV cable feeder from 33/0.8 kV IDT-3, IDT-4 & IDT-5 for Plot No. 3 at Pinnapuram, Nandyal to 400/33 kV Pooling SS at Pinnapuram, Nandyal (Length: 1.915 kms)

1. BSNL Telecom Details:

DET (PTCC), SZ, BSNL vide letter SR-PTCC/AND131020250006(AND-782)/06 dated 15.10.2025, given their NOC.

2. Railway Telecom Details:

CCE/SC, South Central Railway vide letter SG.85/4/3/PTCC/2025-26/SCRAP 09 RC dated 21.04.2025 has issued their NOC.

3. Defense Telecom Details:

ADG (telecom) vide letter B/46937/Sigs-7(b)/4849 dated 27.07.2025 has issued their NOC.

4. EPR zone for the proposed substation is mentioned below:

Name of the proposed SS	Half Diagonal Distance, D/2 (mts)	Fault Current, I (kA)	Resistance of earthmat, R (Ohms)	d (mts) at 430 V	d (mts) at 650 V	d (mts) at 7 kV	d (mts) at 10 kV
0.8/33 kV IDT-3	7.56	19.81	5.18	1797	1186	103	70
0.8/33 kV IDT-4	7.56	19.81	3.22	1114	734	61	41
0.8/33 kV IDT-5	7.56	19.81	7.41	2573	1700	151	103

Telecom authorities to ensure the protection of telecom equipment and personnel within the EPR zone of the proposed substation at the cost of the later entrant.

5. As per the decision taken in the 111th and 112th CLPTCC meeting, since NOC has been obtained from all the stakeholders concerned, this Route Approval Certificate (RAC) shall serve as Deemed Energization Approval.