



सत्यमेव जयते



भारत सरकार
Government of India
विद्युत मंत्रालय
Ministry of Power
केन्द्रीय विद्युत प्राधिकरण
Central Electricity Authority
विद्युत प्रणाली संचार विकास प्रभाग
Power System Communication Development Division

On behalf of
Central Level Power & Telecommunication Co-ordination Committee

No: As assigned

Date: As assigned

CEA Case No.: GUJ-1012

Certificate of Approval for the Route of Extra High Tension (EHT) Power Line / Telecommunication Line

Approval of the Central Level Power & Telecommunication Co-ordination Committee is hereby conveyed to the route of 33 KV SC ISTS line on 33 KV SPSC Pole from INOX Green Energy Services Ltd 220/33 PSS WTG located at Village Samanda, Ta. Abadasa Dist. Bhuj (Kutch) to NTPC REL Wind Turbine Generator Feeder-02 (Length: 63.541 km) particulars of which are given in Annexure I.

The approval is for the route only and is subject to the following conditions.

1. The approval is based on the Power system/ Telecom system conditions' details as reported by the Power supply authority/ Telecom authority at present. Any changes either to Transmission line or the Power system or the paralleling telecommunication lines which are likely to alter the low frequency induction from the estimated at present should be reported to PTCC for its prior approval.
2. The Power and Telecommunication authorities shall be required to adopt such measures as may be recommended by PTCC for counteracting any interference that might arise when the EHT line is in normal operation.
3. Each crossing should satisfy the conditions as laid down in Para 6 -10 of PTCC Code of Practice for crossings.
4. The angle of crossing shall be 90 degrees but in no case less than 60 degrees.
5. The power line shall be equipped with protective switchgear such that the duration of earth current shall be as short as possible but never exceeding 0.5 seconds.
6. The power line shall be energized within a mutually acceptable time limit after obtaining a Certificate from the concerned Telecom and/or Railway authority regarding completion of provision of all protective measures as recommended by PTCC and also under specific clearance from the Telecom and/or Railway authority maintaining the Telecom system.

सेवा भवन, रामाकृष्ण पुरम, सेक्टर -1, नई दिल्ली -110 066 टेलीफोन: 011-26736706 ईमेल: cepcd.cea@gov.in वेबसाइट: www.cea.nic.in

Sewa Bhawan, R.K.Puram, Sector-1, New Delhi-110 066 Telephone: 011-26736706 Email: cepcd.cea@gov.in Website: www.cea.nic.in

7. The energization of Extra High Tension power lines would not be held up for want of installation of GD tubes on telecom lines when the induced voltages are in the range of 430 to 650 V.
8. The telecom line shall be commissioned within a mutually acceptable time after completing provision of all protective measures as recommended by PTCC and also after obtaining specific clearance from the Power authority, if certain measures as recommended by PTCC are to be carried out on power system.
9. The later entrant in the field shall bear the entire cost of providing GD tubes and their fitting as recommended by PTCC, including 15% spares and/or any other protective measures as recommended by PTCC.
10. The route approval shall be subject to special conditions as laid down under Annexure II.

Chief Engineer

1.	M/s INOX Green Energy Services Limited	INOX Towers, Plot No. 17, Sector-16A, Noida -201301, UP
----	--	---

Annexure I

1

- | | | |
|-----|---|--|
| (a) | Name of the Power Supply authority seeking approval | M/s INOX Green Energy Services Limited |
| (b) | Reference number & date: | (i) INOX/SolarLine/PTCC/2025-26/002
dated 28.06.2025 |
| (c) | Name of the Power line | 33 KV SC ISTS line on 33 KV SPSC Pole from INOX Green Energy Services Ltd 220/33 PSS WTG located at Village Samanda, Ta. Abadasa Dist. Bhuj (Kutch) to NTPC REL Wind Turbine Generator Feeder-02 |
| (d) | Length of Power line: | 63.541 km |
| (e) | Operating Voltage | 33 kV |
| (f) | Number of circuits | Single Circuit |

2

- | | | |
|-----|----------------------------------|--------------------|
| (a) | Names of parallel telecom lines: | As per Annexure-II |
| (b) | Length of parallelism: | As per Annexure-II |

3	Average value of earth resistivity in the region:	3,000 ohm-cm
---	---	--------------

4	Whether LF test necessary:	No
---	----------------------------	----

5	Special conditions subject to which this certificate will be effective:	As per Annexure-II
---	---	--------------------

Annexure II

Name of the Power Line: 33 KV SC ISTS line on 33 KV SPSC Pole from INOX Green Energy Services Ltd 220/33 PSS WTG located at Village Samanda, Ta. Abadasa Dist. Bhuj (Kutch) to NTPC REL Wind Turbine Generator Feeder-02. (Length: 63.541km)

BSNL Telecom Details:

DET (PTCC), WZ, BSNL vide letter: IC/MBI/PTCC/Offline/GUJ-3104 dated 13.10.2025 has given their NOC.

1. Railway Telecom Details:

General Manager (S&T), Western Railway vide letter SG.158/28/12/1589 dated 15.12.2025 has issued their NOC.

2. Defense Telecom Details:

ADG (Telecom) vide letter B/46937/Sigs-7(b)/5031 dated 23.10.2025 has issued their NOC.

3. EPR zone for the proposed substation is mentioned below:

Name of the proposed Substation	Half diagonal distance, D/2 (mts)	Fault Current I (KA)	Resistance of Earth Mat, R (ohms)	d (mts) at 430 V	d (mts) at 650 V	d (mts) at 7kV	d (mts) at 10kV
220/33 kV PSS SS of INOX Green Energy Services Limited	96	40	0.315	2718	1766	77	25
33 kV Unit NTPC REL Wind Turbine Generator Feeder -02	14.32	32.5	0.19	187	119	NA	NA

Telecom authorities to ensure the protection of telecom equipment and personnel within the EPR zone of the proposed substation at the cost of the later entrant.

4. As per the decision taken in the 111th and 112th CLPTCC meeting, since NOC has been obtained from all the stakeholders concerned, this Route Approval Certificate (RAC) shall serve as Deemed Energization Approval.