



सत्यमेव जयते



भारत सरकार
Government of India
विद्युत मंत्रालय
Ministry of Power
केन्द्रीय विद्युत प्राधिकरण
Central Electricity Authority
विद्युत प्रणाली संचार विकास प्रभाग
Power System Communication Development Division

On behalf of
 Central Level Power & Telecommunication Co-ordination Committee

No: As assigned

Date: As assigned

Subject: Certificate of Approval for the Route of Power Line of M/s Green Infra Wind Energy Limited.

Route Approval Certificate for the following listed lines of M/s Green Infra Wind Energy Limited is annexed to this letter:

S. No.	Name
1	33 kV S/C line on S/C and D/C RSJ poles for Feeder-08 from 220/33 kV 300 MW Wind Energy PSS of M/s Green Infra Wind Energy Limited at Hire Mannapur, Kushtagi to 33 kV Unit Substation of WTG at Advibhavi, Saswihal, Ainapur & Mandapur of Kushtagi (Length: 18.153 kms)

Chief Engineer

1.	M/s Green Infra Wind Energy Limited	5th Floor, Tower C, Building No 8, DLF Cybercity, Gurugram – 122002
----	-------------------------------------	---

CEA Case No.: KNK - 1202**Approval for the Route of Extra High Tension (EHT) Power Line / Telecommunication Line**

Approval of the Central Level Power & Telecommunication Co-ordination Committee is hereby conveyed for **33 kV S/C line on S/C and D/C RSJ poles for Feeder-08 from 220/33 kV 300 MW Wind Energy PSS of M/s Green Infra Wind Energy Limited at Hire Mannapur, Kushtagi to 33 kV Unit Substation of WTG at Advibhavi, Saswihal, Ainapur & Mandapur of Kushtagi (Length: 18.153 kms)** particulars of which are given in Annexure I.

The approval is for the route only and is subject to the following conditions.

1. The approval is based on the Power system/ Telecom system conditions' details as reported by the Power supply authority/ Telecom authority at present. Any changes either to Transmission line or the Power system or the paralleling telecommunication lines which are likely to alter the low frequency induction from the estimated at present should be reported to PTCC for its prior approval.
2. The Power and Telecommunication authorities shall be required to adopt such measures as may be recommended by PTCC for counteracting any interference that might arise when the EHT line is in normal operation.
3. Each crossing should satisfy the conditions as laid down in Para 6 -10 of PTCC Code of Practice for crossings.
4. The angle of crossing shall be 90 degrees but in no case less than 60 degrees.
5. The power line shall be equipped with protective switchgear such that the duration of earth current shall be as short as possible but never exceeding 0.5 seconds.
6. The power line shall be energized within a mutually acceptable time limit after obtaining a Certificate from the concerned Telecom and/or Railway authority regarding completion of provision of all protective measures as recommended by PTCC and also under specific clearance from the Telecom and/or Railway authority maintaining the Telecom system.
7. The energization of Extra High Tension power lines would not be held up for want of installation of GD tubes on telecom lines when the induced voltages are in the range of 430 to 650 V.
8. The telecom line shall be commissioned within a mutually acceptable time after completing provision of all protective measures as recommended by PTCC and also after obtaining specific clearance from the Power authority, if certain measures as recommended by PTCC are to be carried out on power system.
9. The later entrant in the field shall bear the entire cost of providing GD tubes and their fitting as recommended by PTCC, including 15% spares and/or any other protective measures as recommended by PTCC.
10. The route approval shall be subject to special conditions as laid down under Annexure II.

Annexure I

1

- | | | |
|-----|---|---|
| (a) | Name of the Power Supply authority seeking approval | M/s Green Infra Wind Energy Limited |
| (b) | Reference number & date: | SEMBCORP/GIWEL/33kVPTCC/F-8 dated 30.09.2025 |
| (c) | Name of the Power line | 33 kV S/C line on S/C and D/C RSJ poles for Feeder-08 from 220/33 kV 300 MW Wind Energy PSS of M/s Green Infra Wind Energy Limited at Hire Mannapur, Kushtagi to 33 kV Unit Sunstation of WTG at Advibhavi, Saswihal, Ainapur & Mandapur of Kushtagi (Length: 18.153 kms) |
| (d) | Length of Power line: | 18.153 kms |
| (e) | Operating Voltage | 33 kV |
| (f) | Number of circuits | S/C |

2

- | | | |
|-----|----------------------------------|--------------------|
| (a) | Names of parallel telecom lines: | As per Annexure-II |
| (b) | Length of parallelism: | As per Annexure-II |
- 3 Average value of earth resistivity in the region: 25000 ohm-cms
- 4 Whether LF test necessary: No
- 5 Special conditions subject to which this certificate will be effective: As per Annexure-II

Annexure II

Name of the Power Line: 33 kV S/C line on S/C and D/C RSJ poles for Feeder-08 from 220/33 kV 300 MW Wind Energy PSS of M/s Green Infra Wind Energy Limited at Hire Mannapur, Kushtagi to 33 kV Unit Substation of WTG at Advibhavi, Saswihal, Ainapur & Mandapur of Kushtagi (Length: 18.153 kms)

1. BSNL Telecom Details:

DET (PTCC), Southern Region, Bangalore vide Letter No: SR-PTCCIKNK-1202/5 dated 10.12.2025 has given NOC for charging of the line.

2. Railway Telecom Details:

PCSTE, SOUTH WESTERN RAILWAY vide letter SG/SWR/PTCC/Corres/E: 2-12 dated 31.03.2026 has given NOC for charging of the line.

3. Defense Telecom Details:

ADG(Telecom) , Ministry of Defence vide letter B/46937/Sigs-7(b)/5279 dated 24.12.2025 has accorded NOC for charging of the line.

4. EPR zone for the proposed substation is mentioned below:

Name of the proposed Substation	Half diagonal distance, D/2 (mts)	Fault Current I (KA)	Resistance of Earth Mat, R (ohms)	d (mts) at 430 V	d (mts) at 650 V	d (mts) at 7kV	d (mts) at 10kV
M/s Green Infra Wind Energy Limited 33kV/690V 2.4 MVA WTG S/S situated near Benchmatti, Kushtagi, Koppal	15.68	18	0.353	216	138	N.A	N.A

Telecom authorities to ensure the protection of telecom equipment and personnel within the EPR zone of the proposed substation at the cost of the later entrant.